



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.- भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर-04/2022-23/9736-41 दिनांक:- 27/07/2023

सेवा में,

मैसर्स अनिल कुमार शर्मा,
548/2 कोलोनेल कॉलोनी,
नरवाल पेन, सतवारी,
जम्मू कैंट., जम्मू और कश्मीर-180003
ई-मेल: anilkumar.sharma344@gmail.com
मो.- 9419189631

M/s Anil Kumar Sharma,
548/2 Colonel Colony,
Narwal Pain, Satwari,
Jammu Cant., Jammu and Kashmir-180003
E-mail: anilkumar.sharma344@gmail.com
Mob - 9419189631

विषय :- कंस्ट्रक्शन ऑफ लिंक टैक्सी ट्रैक फॉर प्रपोज्ड एफ.टी.ओ. एट किशनगढ़ एअरपोर्ट। सब हेड :- इलेक्ट्रिकल वर्क.

Subject :- Construction of Link Taxi Track for proposed FTO at Kishangarh Airport. SH-Electrical work.

संदर्भ:- दिनांक 21/07/2023 को खोली गई आपकी ई-निविदा (वित्तिय बिड)।

Ref:- Your E-Tender (Financial Bid) opened on dated 21/07/2023.

महोदय,

1. उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल रु. 73,00,250.00 (अक्षरे तिहत्तर लाख दो सौ पचास रुपये मात्र) (जी.एस.टी. रहित) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत रु. 1,12,97,620.00 (जी.एस.टी. रहित) से 35.38% नीचे हैं।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 73,00,250** (Rupees Seventy Three Lakh Two Hundred Fifty only) **(Excluding GST)** which is **35.38 % below** the estimated cost of **Rs. 1,12,97,620.00 (Excluding GST)**.

2. सहायक महाप्रबंधक (अभियांत्रिकी-विधुत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु 25/08/2023 तक सहायक महाप्रबंधक (अभियांत्रिकी-विधुत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हो। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन-ज्युडिशियल) स्टांप पेपर पर बनाया जाएगा तथा स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-E) AAI, Kishangarh Airport, Ajmer by 25/08/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. सुरक्षा राशि रु. 7,30,025.00 (अक्षरे सात लाख तीस हजार पच्चीस रुपये मात्र) को 10 दिन के भीतर जमा करें अन्यथा इस राशि की कटौति संविदा कागजात के पृष्ठ 33 पर खण्ड-1 ए के अनुसार आपके चालू बिलों से की जाएगी।

Security deposit **Rs. 7,30,025.00 (Rupees Seven Lakh Thirty Thousand Twenty Five only)** within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no.- 1A, page no. -33 of tender/contract document.

4. आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970, संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध एवं उन्मूलन) अधिनियम 1986, निमार्ण श्रमिकों (सेवा के शर्त और नियमन) अधिनियम 1986 और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जो कि निविदा दस्तावेज के जी.सी.सी. के प्रावधानों का और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970, Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.

5. आपको प्रबन्धक (अभियांत्रिकी-विद्युत), भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।

You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको **03 माह** का समय प्रदान किया जाता है जो कि इस पत्र के जारी होने की तिथि से 10 दिन बाद से प्रभावी होंगी।

Please note that the time allowed for carrying out the work shall be **03 Months** & shall be reckoned from 10th day after the date of issue this letter

7. दोष दायित्व अवधि एक (01) वर्ष होगी, जो कार्य के पूरा होने की वास्तविक दर्ज तिथि से प्रभावी होगी।

The defects liability period shall be **One (01) Year**, which will be effective from the actual recorded date of completion of the work.

8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-इन-चार्ज के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In case any discrepancy is found, then English version will be taken as correct.

Enclosure :- BOQ Page 01 to 06.

भवदीय / Yours Faithfully,

सहायक महाप्रबंधक (अभि०-वि०) / Asstt. Gen. Mgr. (Engg.-E)
कृते तथा ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

प्रतिलिपि / Copy to :

1. महाप्रबंधक (वित्त), भा.वि.प्रा., क्षेत्रीय मुख्यालय, उत्तरी क्षेत्र, रंगपुरी, नई दिल्ली।
2. निदेशक विमानपत्तन, भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर।
3. प्रबंधक (अभि.-विद्युत), भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर।
4. करारनामा।
5. सम्बन्धित फाईल।

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work: Construction of Link Taxi Track for proposed FTO at Kishangarh Airport. SH-Electrical work.

Contract No: 2022_AAI_158364_1

Name of the Bidder/ Bidding Firm / Company :	ANIL KUMAR SHARMA
--	-------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of Medium Intensity Elevated type omni directional LED Taxiway edge Light fitting (LED type) for aviation visual aids requirements complete with LEDs, optic lens, power converter, two pin secondary lead, central column assembly, breakable coupling, base plate, gaskets, bolts etc. and all other standard accessories required as per ICAO and conforming to technical specifications.	91	Each	3500.00	318500.00	INR Three Lakh Eighteen Thousand Five Hundred Only
2	Supply of omni directional Inset Type Taxi way Light Fitting complete with shallow base, matching body made of die cast aluminium, pre-focused LED lamp and driver units suitable to work on 15 w 6.6/6.6 amps Isolating transformer with all accessories confirming to ICAO requirement complete as required.	14	Each	34000.00	476000.00	INR Four Lakh Seventy Six Thousand Only
3	Supply of 2 core 4 sqmm 600 V grade, copper conductor, EPR insulated, PCP sheathed, underground secondary cable complete as specified complete as required and conforming to technical specifications.	260	Mtr	140.00	36400.00	INR Thirty Six Thousand Four Hundred Only
4	Supply of Single core, 06 Sqmm, 5 KV, XLPE insulated & PVC sheathed stranded copper conductor, antitermite & antirodent, Airport lighting cable confirming to IS 7098 (Part-II) with up to date ammendment and as per technical specification specified in tender documents.	5557	Mtr	80.00	444560.00	INR Four Lakh Forty Four Thousand Five Hundred & Sixty Only
5	Supply of Single core, 16 Sqmm, 5 KV, XLPE insulated & PVC sheathed stranded copper conductor, antitermite & antirodent, Airport lighting cable confirming to IS 7098 (Part-II) with up to date ammendment and as per technical specification specified in tender documents.	1430	Mtr	198.00	283140.00	INR Two Lakh Eighty Three Thousand One Hundred & Forty Only
6	Supply of following type, 5 KV grade, 50 Hz, series Isolating Transformer encapsulated in polyester resin, finally moulded in neoprene type rubber with primary and secondary connectors etc and all other standard accessories required as per ICAO and conforming to technical specifications.					
6.1	15 W, 6.6/6.6 Amps.	91	Each	2600.00	236600.00	INR Two Lakh Thirty Six Thousand Six Hundred Only
6.2	45 W, 6.6/6.6 Amps.	12	Each	3000.00	36000.00	INR Thirty Six Thousand Only
6.3	100 W, 6.6/6.6 Amps.	3	Each	4000.00	12000.00	INR Twelve Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
7	Supply of 5 KV grade plug & receptacle (Essna Connector) of type I class B connector & suitable for field attachment with 5 KV grade PVC insulated and PVC sheathed single core 6 sqmm copper conductor cable as etc complete as required and conforming to technical specifications.	151	Set	600.00	90600.00	INR Ninety Thousand Six Hundred Only
8	Supply of 5 KV grade plug & receptacle (Essna Connector) of type I class B connector & suitable for field attachment with 5 KV grade PVC insulated and PVC sheathed single core 16 sqmm copper conductor cable as etc complete as required and conforming to technical specifications.	15	Set	600.00	9000.00	INR Nine Thousand Only
9	Supply, installation, testing and commissioning of 4.0 KW Indoor type air cooled constant current regulator of microprocessor controlled, thyristor type suitable for operation on 230 Volts + 10%, 50 Hz input AC supply with 5 steps variation of current output, suitable for local and remote control operation with suitable control supply and able to communicate with PC or PLC controlled system, with output current indicated on multifunction digital display, overcurrent, over voltage, open circuit and earth fault protection and earthleakage meter, positive back indication equipments, hours run counter, complete as required, confirming to ICAO requirements and as per technical specifications.	1	Job	180000.00	180000.00	INR One Lakh Eighty Thousand Only
10	Design, Manufacturing, Supply, installation, connection, testing and commissioning of illuminated taxiway/ runway guidance signages of various sizes made of anodized 2 mm (nominal) thick extruded aluminum profile frame with suitable stiffening supports for structural rigidity, 1.5 mm thick aluminum back cover, 4 mm thick poly carbonate sheet with glare free face, supporting legs, breakable coupling etc. The letters and symbols shall be internally pasted/ screen printed with required coloring. The sign boards shall be uniformly internally illuminated with required number of LEDs strips to achieve required illumination level, alongwith drivers, internal control circuit, automatic changeover to function on both main & standby (runway/ taxiway) circuits etc. and shall operate without any flickering when operated on input source of 2.8 Amps. to 6.6 amps. series current. The suitable arrangement shall be made for water tightness and locking arrangement. The signages shall be installed on 1:2:4 grade cement concrete of size 400x400x500 mm for each leg and total base of 150 mm thick for the distance of 1.5 mtr. all around the board including installation of isolating transformer, crimping/ jointing of plug & receptacles, laying of secondary leads, connections, earthing etc. complete as required. The taxiway guidance signages shall be as per ICAO and confirming to technical specifications. (legends shall be as approved by Engineer-in-charge).	12	Sqm	35000.00	420000.00	INR Four Lakh Twenty Thousand Only
11	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 90 mm dia (OD-90 mm & ID-76 mm nominal)	4741.00	Mtr	150.00	711150.00	INR Seven Lakh Eleven Thousand One Hundred & Fifty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
12	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 160 mm dia (OD-160 mm & ID-135 mm nominal)	1815	Meter	220.00	399300.00	INR Three Lakh Ninety Nine Thousand Three Hundred Only
13	Supply of cast iron isolating Transformer housing box, water tight round type, metal container of outside size 330 mm dia, height 450 mm made of 10 mm thick cast iron moulding all round, except the top surface, which is 15 mm thick , cast iron moulding suitable to receive a light fitting base plate/ cover plate on the top and underground for housing transformer, power cable and having one/two/ three nos holes as per site requirement on the periphery centre, 75 mm above bottom surface suitable to receive of 50 mm and 15mm dia GI/DWC HDPE/HDPE pipe as required. The box should have two SS earth bolts of M10x40 mm tapped inside near the hole (4" away from the hole centre) and having drain hole at the bottom suitably tapped to receive 15mm dia GI pipe and having clear opening of 220 mm at the top surface and 06 Nos. M10 tapped hole having centre to centre distance of 260mm to receive fittings/base plate and bolts, etc complete as required.	106	Each	5000.00	530000.00	INR Five Lakh Thirty Thousand Only
14	Installation of CI isolating transformer housing boxes with a base concrete of 1:3:6 of size 630x630x100mm thick all round concrete of 1:2:4, 150mm thick top sloped with 1:2:4 cement including providing and fixing 300mm long 15mm dia "B" class GI pipe with check nut for drainage of water including excavation of soil and refilling, adjustment of CI boxes etc. complete as required.	106	Job	2500.00	265000.00	INR Two Lakh Sixty Five Thousand Only
15	Installation, testing and commissioning of medium intensity LED type taxiway edge light fitting on the existing CI isolating transformer housing box including installation of isolating transformer, crimping/jointing of plug & receptacles, laying of secondary leads, connections, earthing etc. complete as required and includes supply of all materials excluding fixture, secondary lead, isolating transformer and plug & receptacles.	91	Job	200.00	18200.00	INR Eighteen Thousand Two Hundred Only
16	Laying one number 5 KV grade Airfield lighting cable of size single core 6 / 16 Sqmm, 2 Core 4 Sqmm secondary cable in the existing RCC/ HUME/ STONEWARE/ METAL/ HDPE/DWC pipe as required.	7122	Mtr	15.00	106830.00	INR One Lakh Six Thousand Eight Hundred & Thirty Only
17	Laying of one number 5 KV grade Airfield lighting cable of size single core 6/16 Sqmm in the existing masonry duct as required.	100	Mtr	15.00	1500.00	INR One Thousand Five Hundred Only
18	Excavation of the trench in the hard rock not exceeding 1.5 metres in width, and lift upto 1.5 meters, including getting out the excavated soil and disposal of excavated soil as directed with in a lead of 50 mtrs.	221	Cu Mtr.	200.00	44200.00	INR Forty Four Thousand Two Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
19	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	7	Set	5000.00	35000.00	INR Thirty Five Thousand Only
20	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	105	Mtr.	150.00	15750.00	INR Fifteen Thousand Seven Hundred & Fifty Only
21	Providing and fixing 6 SWG dia G.I. wire on surface or in recess or in HDPE/metal pipe for loop earthing along with cable as required.	6987	Mtr.	20.00	139740.00	INR One Lakh Thirty Nine Thousand Seven Hundred & Forty Only
22	Upgradation and integration of existing Electro System make Airfield lighting control and monitoring system (ALCMS) for newly added taxi-C lighting facilities including taxiway edge lights, guard lights, Signages etc complete with all required upgradation/enhancement of software and hardware for the units installed in ATC and CCR hall meeting ICAO/FAA.	1	Job	50000.00	50000.00	INR Fifty Thousand Only
23	Supply of 4C x 25 Sqmm, 1.1 KV grade, ARMOURED, XLPE insulated PVC sheathed, FRLS, Aluminium conductor cable confirming to IS: 7098 part -I amended upto date.	1070	Mtr	150.00	160500.00	INR One Lakh Sixty Thousand Five Hundred Only
24	Supply of 19 core, 2.5 Sqmm, 1100 V grade, PVC insulated and PVC sheathed FRLS, multistrand bare copper conductor flexible control cable confirming to IS: 694 amended upto date.	100	Mtr	550.00	55000.00	INR Fifty Five Thousand Only
25	Laying of one number 19 core, 2.5 Sqmm, 1100 V grade, PVC insulated and PVC sheathed, FRLS control cable . in the existing masonry duct as required.	100	Mtr	30.00	3000.00	INR Three Thousand Only
26	Supply of 3.5 Core x 240 Sq.mm size 1.1 kv grade, XLPE insulated and PVC inner sheathed, FRLS, Aluminium conductor armoured power cable conforming to IS: 7098(Part 1)1988/ IS: 7098 (Part 1) with up to date amendments etc. complete as required.	1125	Mtr	930.00	1046250.00	INR Ten Lakh Forty Six Thousand Two Hundred & Fifty Only
27	Supply of 3.5 Core x 150 Sq.mm size 1.1 kv grade, XLPE insulated and PVC inner sheathed, FRLS, Aluminium conductor armoured power cable conforming to IS: 7098(Part 1)1988/ IS: 7098 (Part 1) with up to date amendments etc. complete as required.	990	Mtr	572.00	566280.00	INR Five Lakh Sixty Six Thousand Two Hundred & Eighty Only
28	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade size of above 185 Sqmm and up to 400 Sqmm cable in the existing RCC/ HUME/ STONEWARE/ METAL/ HDPE/DWC pipe as required.	1225	Mtr	50.00	61250.00	INR Sixty One Thousand Two Hundred & Fifty Only
29	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade size of above 95 Sqmm and up to 185 Sqmm cable in the existing RCC/ HUME/ STONEWARE/ METAL/ HDPE/DWC pipe as required.	990	Mtr	50.00	49500.00	INR Forty Nine Thousand Five Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) In Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
30	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of Upto 35 sq. mm size in the existing RCC/ HUME/ METAL/DWCHDPE pipe as required.	950	Mtr	25.00	23750.00	INR Twenty Three Thousand Seven Hundred & Fifty Only
31	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.(i).4C X 25 sq. mm	3	Job	500.00	1500.00	INR One Thousand Five Hundred Only
32	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5 x 150 Sqmm, PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade complete as required.	7	Job	500.00	3500.00	INR Three Thousand Five Hundred Only
33	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5 x 240 Sqmm, PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade complete as required.	4	Job	500.00	2000.00	INR Two Thousand Only
34	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for size of 4 x 25 Sqmm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	8	Job	2000.00	16000.00	INR Sixteen Thousand Only
35	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for size of 3.5 x 150 Sqmm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	5	Job	2500.00	12500.00	INR Twelve Thousand Five Hundred Only
36	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for size of 3.5 x 240 Sqmm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	13	Job	3000.00	39000.00	INR Thirty Nine Thousand Only
37	Supply & laying of double wall high density polyethylene (HDPE pipe) pipe of size- 90/76mm (PN 6), PE-80 conforming to IS:14930 (part-2) with latest amendment, complete with accessories like couplers, bends, tee etc in the shoulder/runway/taxiway by horizontal trenchless boring as per the site requirement.	260	Mtr	600.00	156000.00	INR One Lakh Fifty Six Thousand Only
38	Supply and fixing of 03 phase, 250A, TPN Aluminium bus bar LT Panel made of 2.00 mm thick CRCA Sheet and having double door with lockable arrangement, one no 200 A MCCB at input side and two nos 100A MCCB at output. Panel should also have provision of digital Ampere meter, Voltmeter, energy meter, indication lamp (R/Y/B/ON/OFF), four legs for installation etc. including making connection and fixing the panel in cement foundation etc. complete as required.	1	Each	30000.00	30000.00	INR Thirty Thousand Only

[Handwritten signature]

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
39	Supply of 200 Watt LED type out door lighting luminaire (flood light) ,with high pressure die cast aluminium/standard alloy housing, having uniform lighting distribution with luminaire efficiency of more than 110 lumen per watt, CRI more than 70, THD less than 10%, IP 66 protection, with 5 Year warrenty on complete luminaire including driver/control gear & LED, more than 50,000 burning hours, as per technical specifications complete as required. Make/Model:- Bajaj/ GLEAM or Make/Model:- Havells/ JETA ADORN or equivalent.	8	Each	5500.00	44000.00	INR Forty Four Thousand Only
40	Installation, testing and commissioning of inset type taxiway light by core cutting in the runway pavement, fixing the shallow base with dobefil and hardener, installation of isolating transformer, crimping/jointing of plug & receptacles, laying of secondary leads, connections, earthing etc. complete as required and includes supply of all materials excluding fixture, secondary lead, isolating transformer and plug & receptacles.	13	Job	6000.00	78000.00	INR Seventy Eight Thousand Only
41	Kerfs cutting with machine in taxiway/runway of PQC/bituminous surface of suitable depth and width for 1 or 2 nos secondary lead along with earth cables and laying of secondary lead and earth cable by wrapping cotton tape i/c refilling the same by suitable sealing material (PIDILITE) etc. complete as required and as per instruction of EIC.	125	Mtr	700.00	87500.00	INR Eighty Seven Thousand Five Hundred Only
42	Numbering of GLF fittings with letters in yellow on black back ground as per inscription approved of Engineer in charge as required.	105	Job	50.00	5250.00	INR Five Thousand Two Hundred & Fifty Only
Total in Figures					7300250.00	INR Seventy Three Lakh Two Hundred & Fifty Only
Quoted Rate in Words		INR Seventy Three Lakh Two Hundred & Fifty Only				


 27/09/23
 AGM C-S

Signature Not Verified

Digitally signed by TANSUKH RAM
 Date: 2023.09.06 17:18:20 IST
 Location: eProcurement System for
 Central PSUs