



भारतीय विमानपत्तन प्राधिकरण
नागर विमानक्षेत्र, वडोदरा
Airports Authority of India,
Civil Aerodrome, Vadodara

भाविप्रा/वडोदरा/सयुक्त.महा.प्र(अभि-सि)/डब्ल्यू-258/2023-24/
AAI/VAD/Jt. GM (Engg-C)/W-258/2023-24/924CH15

दिनांक: 22/11/2023
Date: 22/11/2023

सेवा मे,
मेसर्स जे.के.जी इन्फ्राटेक प्राइवेट लिमिटेड,
ई - 33, फेस - 1, अशोक विहार,
दिल्ली - 110 052.
Email : jkginfra@gmail.com

To,
M/s JKG INFRATECH PRIVATE LTD,
E-33, Phase - I, Ashok Vihar,
Delhi - 110 052.
Email : jkginfra@gmail.com

कार्य का नाम : नागर विमानक्षेत्र वडोदरा पर रात के पार्किंग (अप्रोन -2) एवं अलगाव बे की मरम्मत
ओर स्तर मे सुधार का कार्य ।
(निविदा आई. डी. - 2023_AAI_160727_1)

Name of Work: Repair and Level correction of Night parking (Apron-2) and
Isolation bay at C.A. Vadodara.
(Tender ID - 2023_AAI_160727_1)

संदर्भ:- दिनांक 25/09/2023 को खोला गया आपका ई-टेंडर । (वित्तीय बोली)
Ref: Your e-tender opened on 25/09/2023 (Financial Bid)


महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताए गये मद मूल्यों पर निविदा की राशि कुल रु. 5,09,24,522.00 (रुपये पांच करोड़ नौ लाख चौबीस हजार पांच सौ बाईस मात्र) स्वीकृत किया जाता है, जो कि निविदा की अनुमानित लागत राशि रु. 590.42 Lakh (Excluding GST) से 13.75 % नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 5,09,24,522.00 (Rupees Five Crore Nine Lakh Twenty Four Thousand Five Hundred Twenty Two only), which is 13.75 % below the estimated cost put to tender of Rs. 590.42 Lakh (Excluding GST).

- सयुक्त. महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा कार्य प्रभारी अभियंता होंगे । आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 08/12/2023 तक सयुक्त. महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र के कार्यालय मे उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु.300/- (रु. तीन सो मात्र) के नोन ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा ।

Jt. General Manager (Engg- Civil), Vadodara Airport, Vadodara shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Jt. General Manager (Engg- Civil), Vadodara Airport by 08/12/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.


22.11.2023



भारतीय विमानपत्तन प्राधिकरण

नागर विमानक्षेत्र, वडोदरा

Airports Authority of India,
Civil Aerodrome, Vadodara

3. निविदा के साथ बैंक गारंटी के रूप में प्राप्त अग्रिम धन राशि रु. 11, 80,840.00 (रु. ग्यारह लाख अस्सी हजार आठ सौ चालीस मात्र) को संविदा के GCC पृष्ठ संख्या 16 के अनुच्छेद संख्या 1"ए" के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रु. 13,65,387.00 (रु. तेरह लाख पैंसठ हजार तीन सौ सत्तासी मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

The earnest money amount of Rs. 11, 80,840.00 (Rupees Eleven Lakh Eighty Thousand Eight Hundred Forty Only) received along with your tender in form of bank guarantee will be treated and converted as a part of security deposit as per clause 1A on GCC page 16 of the tender document. Please deposit Rs. 13,65,387.00 (Rupees Thirteen Lakh Sixty Five Thousand Three Hundred Eighty Seven Only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition referred above of the contract document.

4. इस स्वीकृति पत्र के जारी होने के 30 दिनों के भीतर, आप भा.वि.प्रा. को निविदा दस्तावेज़ GCC पृष्ठ संख्या - 15, अनुच्छेद 1 की शर्त के अनुसार निष्पादन गारंटी रुपये 25,46,227/- (रुपये पच्चीस लाख छियालीस हजार दो सौ सत्ताईस मात्र) निविदा दस्तावेज़ में दिए गये प्रोफॉर्मा जीसीसी पृष्ठ संख्या 108-109 के अनुसार बैंक गारंटी के रूप में जमा करें।


Within 30 days of issue of this letter, you shall submit to AAI, a Performance Guarantee as per condition of GCC clause 1 at Page GCC -22 of tender document for an amount of Rs. 25,46,227/- (Rupees Twenty Five Lakh Forty Six Thousand Two Hundred Twenty Seven only) in the form of Bank guarantee on the performa appended at page no GCC 108 – 109 of tender document.

5. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करें, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.


6. आपको निर्देश दिया जाता है कि आप तुरंत सहा. महा. प्रबंधक (अभि-सिविल) / वरिष्ठ प्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र से मिलें वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर लें कि काम करने का अनुमत समय 10 (दस) महीना दो माह वर्षा ऋतु के साथ है जोकि इस पत्र के जारी होने के दस दिन बाद से गिना जाएगा।

You are also directed to contact Asst. Gen. Manager (Engg-Civil) / Senior Manager (Engg – Civil) Vadodara Airport immediately who will arrange to hand over site to you. Please note that the time allowed for carrying out the work is 10 (Ten) Months i/c two month rainy seasons which shall be reckoned from 10th days after the issuance of this letter.


22.11.2023

7. इस ठेके के संबंध में आगे की कोई भी पत्राचार सयुक्त. महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा 390022 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the **Jt. General Manager (Engg-Civil)**, Vadodara Airport, Vadodara -390022.
8. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
All the letters referred above shall form part of contract.
9. उपर्युक्त कार्य के लिए त्रुटि दायित्व की अवधि **12 (बारह)** महीने होगी।
The defects liability period for the above-mentioned work is **12 (Twelve)** months.
10. यदि ठेकेदार सुरक्षा नियमों का भंग करेगा तो उनका कालियादी में सम्मिलित किया जाएगा एवं उचित कानूनी कार्यवाही के लिए भी जिम्मेदार होगा।
If Contractor is found Violate any of Security Regulations, he shall be Black listed and will be subjected to other Legal Proceedings.
11. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
12. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा ,
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully



22.11.2023

सयुक्त. महाप्रबंधक (अभि-सिविल),
वडोदरा हवाईअड्डा
कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
Jt.GM (Engg. -Civil), Vadodara Airport
For and on behalf of Chairman
Airports Authority of India



भारतीय विमानपत्तन प्राधिकरण
नागर विमानक्षेत्र, वडोदरा
Airports Authority of India,
Civil Aerodrome, Vadodara

प्रतिलिपि /Copy to :-

1. क्षेत्रीय कार्यपालक निदेशक, पश्चिमी क्षेत्र, भाविप्रा, पारसीवाड़ा के सामने सहार रोड, विले पार्ले (पूर्व) मुंबई-400099
The Regional Executive Director, WR AAI, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
2. महा प्रबंधक (अभियांत्रिकी), भाविप्रा, पारसीवाड़ा के सामने सहार रोड, विले पार्ले (पूर्व) मुंबई-400099
General Manager (Engg) WR, AAI, Office of the RED, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
3. विभागाध्यक्ष (सतर्कता), भाविप्रा, क्षेत्रीय कार्यपालक निदेशक, पारसीवाड़ा के सामने सहार रोड, विलेपार्ले (पूर्व) मुंबई-400099
HOD (Vigilance), AAI, Office of the RED, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
4. श्रम आयुक्त, 5, देबर सोसायटी, बगीखाना रोड, बरोडा हाई स्कूल के पास, बरोडा-390001
Labour Commissioner, 5, Dhebar society, Bagikhana Road, Near Baroda High school, Baroda-390001
5. भविष्यनिधि कमिशनर, "भविष्य निधि भवन", वडोदरा सेवासदन कार्यालय नं-6 के पीछे, अकोटा स्टेडियम रोड, अकोटा, वडोदरा-390020
Provident Fund Commissioner, "Bhavishya Nidhi Bhavan", B/H VMC Seva Sadan Office No-6 Akota Stadium Road, Akota, Vadodara-390020

आंतरिक /Internal :-

1. विमानपत्तन निदेशक, भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Airport Director, AAI, C.A. Vadodara.
2. संयुक्त महाप्रबंधक (वायु यातायात प्रबंधन), भाविप्रा, नागर विमानक्षेत्र, वडोदरा |
Jt.GM (ATM), भाविप्रा, नागर विमानक्षेत्र, वडोदरा |
3. संयुक्त. महाप्रबंधक (अभि-विधायुत), भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Jt. General Manager (Engg-E), AAI, C.A. Vadodara
4. सहा महाप्रबंधक (वित्त), भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Asst. General Manager (Finance), AAI, C.A. Vadodara
5. सहा. महाप्रबंधक (अभि-सिविल) / वरिष्ठ प्रबंधक (अभि-सिविल), भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Asst. General Manager (Engg-C) / Senior Manager (Engg - Civil), AAI, C.A. Vadodara
6. मुख्य सुरक्षा अधिकारी, भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Chief Security officer / Terminal Manager AAI, C.A. Vadodara.
7. टर्मिनल प्रबंधक भाविप्रा, नागर विमानक्षेत्र, वडोदरा
Terminal Manager AAI, C.A. Vadodara.
8. करारनामा प्रतिलिपि
Agreement Copy.
9. राजभाषा धारा 3
10. कार्यफाइल / Work file

भवदीय /Yours faithfully

संयुक्त महाप्रबंधक
22.11.2023

संयुक्त. महाप्रबंधक (अभि-सिविल),
वडोदरा हवाईअड्डा
कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
Jt.GM (Engg. -Civil), Vadodara Airport
For and on behalf of Chairman
Airports Authority of India

Tender Inviting Authority: AGM (Engg - Civil), AAI, Vadodara Airport

Name of Work: Repair and Level correction of Night parking (Apron-2) and Isolation bay at C.A. Vadodara. (SH: Civil and Electrical works)"

Contract No: 2023_AAI_160727_1

Name of the	JKG INFRA TECH PRIVATE LIMITED
-------------	--------------------------------

Firm /

Company :

Company :

Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)	TEXT #
1	2	4	5	13	53	55	
1	Civil Works Providing, laying and fixing of self adhesive composite biaxial glass fibre geogrid of 100 KN/M tensile strength as Asphalt reinforcement of High modulus fibre glass of mesh size not exceeding 12.5mm * 12.5mm (Miscellaneous or equivalent make). The grid shall be pressed down fully with a rubber tired roller and glued to pavement surface. The longitudinal overlap should not be less than 150 mm and transverse overlap i.e. at the end of the roll should not be less than 250 mm. Over self adhesive glass fibre reinforcement, stress absorbing membrane inter layer (SAMIL) shall be provided which shall comprise of a membrane of hot sprayed bitumen VG30 grade (supplied in BULK) @ 1.4kg/sqm and then treated with approximately 7.5 kg/sqm stone aggregate of 6 to 10 mm size. The stones will be spread in such a manner that 50% of the surface is covered. The item should be completed in all respect to the satisfaction of Engineer-in-Charge.	36351.000	Sqm	250.00	9087750.00	INR Ninety Lakh Eighty Seven Thousand Seven Hundred & Fifty Only	
2	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and cement filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG -30 bitumen of grade shall be taken as 110 kg/m³ of mix supplied in bulk produced by Govt. Refineries and 2 % cement by weight of aggregates as filler material.	1818.000	Cum	8850.00	16089300.00	INR One Crore Sixty Lakh Eighty Nine Thousand Three Hundred Only	
3	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30] content shall be taken as 120 kg/m³ of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material.	313.000	Cum	9250.00	2895250.00	INR Twenty Eight Lakh Ninety Five Thousand Two Hundred & Fifty Only	
4	Providing and laying of Hot Mix Dense Asphaltic Concrete (DAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 135 kg/m³ of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material.	1505.000	Cum	9800.00	14749000.00	INR One Crore Forty Seven Lakh Forty Nine Thousand Only	
5	Providing and applying tack coat using Bitumen Emulsion (Rapid Setting) complying with IS:3887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-in-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment.	36351.000	Sqm	12.00	436212.00	INR Four Lakh Thirty Six Thousand Two Hundred & Twelve Only	

Handwritten notes on the right margin:
 22.1.2023
 JFM (E-c)
 Aff: Kaddana

6	Providing and applying tack coat using Bitumen Emulsion(Rapid Setting) complying with IS-8887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment. 0.30kg/ Sqm on existing Concrete surface.	36351.000	Sqm	15.00	545265.00	INR Five Lakh Forty Five Thousand Two Hundred & Sixty Five Only
7	Demolishing cement concrete manually/ by mechanical means including disposal of material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground or any other area for lead upto 2 km for all lifts, complete as per direction of Engineer - in - charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	403.000	Cum	1000.00	403000.00	INR Four Lakh Three Thousand Only
8	Providing and laying Pavement Quality Concrete (PQC) produced in a batching & mixing plant having a Characteristic flexural strength i.e. minimum flexural strength of 4.1 MPa at 28 days using 360 Kg of Ordinary Portland cement of 43/53 grade, super plasticizer by mass of cement, fine aggregate, graded stone aggregates of 40 mm nominal size in appropriate proportion as per specification and job mix formula, laid in panels as per drawings/design as approved by the Engineer-In-Charge using slip form paver or fixed form paver, screed, float finish, texture etc. including anti friction layer, joint filler board, making necessary provision for expansion, construction, dummy joints, including filling with polysulphide sealant of approved make, curing, making profile etc, complete as per direction of Engineer-in-Charge and particular specifications. The item for execution shall also include the following operations: i) polyethylene sheet (Black in color) of thickness 400 micron conforming to IS: 2508 with 6mm thick fine sand layer. ii) Providing and laying in position for expansion joint, 25mm thick pre-cut Synthetic joint filler board of approved make conforming to IS:1838 (part-3)-2011, 45 mm from top (to be removed at the time of filling of Polysulphide sealant). iii) Mechanically cutting dummy joints 3mm wide x 1/3rd thickness of slab which is subsequently widened to 10mm for the top 25mm depth and construction joints 10mm wide X 25mm deep as per specification. iv) Providing and filling in position Polysulphide sealant of approved make conforming to BS-5212-1900 or IS:11433-1995 in expansion/ construction/ dummy joints including rounding off edges, applying two coats approved primer compatible with the brand of Polysulphide and preparing the surface and applying masking tape along the edge of joint to prevent accidental spillage of sealant on top surface and to give neat finish to the sealant and removing the masking tape after application of Sealant etc. as per the details below: (a) Expansion Joints of size 25mm wide and 10mm deep over 30mm dia expanded closed-cell polyethylene foam back-up/backer rod of minimum density 22 Kg/Cum, as per manufacturer's specifications. (b) Construction joints of size 10mm wide and 10mm deep over 12 mm dia expanded closed-cell Polyethylene foam back-up/ backer rod of minimum density 22 kg/Cum, as per manufacturer's specification. (c) Dummy joints of size 10mm wide and 10 mm deep over 12 mm dia expanded closed-cell Polyethylene foam back-up/ backer rod of minimum density 22 Kg/Cum, as per manufacturer's specifications. Note: Cement content considered in this item is @ 360 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately.	403.000	Cum	8500.00	3425500.00	INR Thirty Four Lakh Twenty Five Thousand Five Hundred Only
9	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete.New work (Two or more coats)	1359.000	Sqm	200.00	271800.00	INR Two Lakh Seventy One Thousand Eight Hundred Only
10	Painting Letters with road marking paint using skilled Art Painter on concrete surface, of approved brand and manufacture etc complete as per direction of Engineer in Charge.	11404.000	Per Letter Per cm Height	30.00	342120.00	INR Three Lakh Forty Two Thousand One Hundred & Twenty Only
11	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	19665.000	KG	125.00	2458125.00	INR Twenty Four Lakh Fifty Eight Thousand One Hundred & Twenty Five Only
12	Electrical Works Supply & fixing of CI collar round type of outside dia 330 mm of 100mm height made of 10 mm thick cast iron moulding all round except on top surface which is 15 mm thick cast iron moulding suitable to receive a light fitting base plate on the top and existing CI transformer housing box at the bottom. The CI collar shall have a clear opening of 220 mm at the top and bottom surface and 6 nos M-10 tapped holes at the hole centre of 260 mm at top and bottom to fix the collar on the existing CI box including providing 6 nos. M-10 bolts (SS), and a base plate gasket for each collar etc. complete as per site requirement.	56.000	EACH	3200.00	179200.00	INR One Lakh Seventy Nine Thousand Two Hundred Only
13	Dismantling and Reinstallation of existing elevated fitting complete as per site requirement.	56.000	JOB	750.00	42000.00	INR Forty Two Thousand Only
Total in Figures					50924522.00	INR Five Crore Nine Lakh Twenty Four Thousand Five Hundred & Twenty Two Only
Quoted Rate in Words		INR Five Crore Nine Lakh Twenty Four Thousand Five Hundred & Twenty Two Only				

22.11.2023
 H. GM (G-e),
 AAI, Vadodara.