




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



No:AAI/TRY/ENGG(C)/WIDEN PM ROAD/23-24/126

Date: 12-10-2023

To

M/s.V Meenal & Co.,

18, Corporation Road, Devakottai, Sivagangai - 630 302.

Email: meenalveluchamy@gmail.com, Phone: 99403 06593.

Name of work: Works in Operational area for improving the operational requirement.

S.H: Widening of existing perimeter road and approach road to CAT-I approach lighting system at Trichy Airport - reg.


Ref: Your e-Bid Ref No.2023_AAI_160799_1, Tender Reference
No.AAI/TRY/ENGG(C)/WIDEN PM ROAD/23-24 opened on 11-09-2023.

Dear Sir,

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the Item Rates quoted by you totaling to **₹3,28,45,260.82** (Rupees Three Crore Twenty Eight Lakh Forty Five Thousand Two Hundred Sixty and Paise Eighty Two only) **including GST @ 18%.**
2. The Deputy General Manager (Engg-Civil), AAI, Trichy Airport shall be the Engineer-In-Charge of the work. You are requested to attend the office of Deputy General Manager (Engg-Civil) on (or) before 21-10-2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. Please deposit Rs.27,83,497/- (Rupees Twenty Seven Lakh Eighty Three Thousand Four Hundred and Ninety Seven Only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1 A of Clauses of Contract on Page No.72 of contract document.
4. You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on Page No.106 of GCC of tender and rules of Central and State Government.
5. You are requested to comply with all provisions of the Employees Provident Fund and miscellaneous provisions Act 1952 and Employees State Insurance Act 1948, amended from time to time and rule framed there under wherever applicable.




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



6. You are also directed to contact Senior Manager (Engg-Civil) immediately for the commencement of work. ✓
7. The letters under reference shall form part of Agreement. ✓
8. Please note that the time allowed for carrying out the work shall be **04 [Four] months including One month considered for monsoon period** and same shall be reckoned from **10th day after the issue of this letter**. ✓
9. Any further correspondence in connection with contract should normally be addressed to the Engineer-In-Charge. ✓
10. All Corrigendum, Queries, Clarification etc., raised during e-tendering process and replies thereof including the letter referred above shall also form part of the Agreement.
11. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Thanking you,

Yours faithfully,


(R. Ganesan),
Deputy General Manager (Engg-Civil),
For and On Behalf of Chairman,
Airports Authority of India.

Encl: Schedule of Quantities.

उप महाप्रबंधक (इंजीनियरिंग - सिविल) / DGM (Engg - Civil)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
तिरुचिरापल्ली अंतरराष्ट्रीय हवाई अड्डा / Tiruchirappalli International Airport
तिरुची - 620 007 / Trichy - 620 007.

Item Rate BoQ

Tender Inviting Authority: Deputy General Manager (Engg-Civil), AAI, Trichy International Airport, Trichy - 620 007.

Name of Work: Widening of existing perimeter road and approach road to CAT-I approach lighting system at Trichy Airport.

Contract No: Tender ID: 2023_AAI_160799_1, Tender Reference No.AAI/TRY/ENGG(C)/WIDEN PM ROAD/23-24

Name of the Bidder/ Bidding Firm / Company :	V MEENAL AND CO ,DEVAKKOTTAI					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1000m	2235.00	Cum	250.00	558750.00	INR Five Lakh Fifty Eight Thousand Seven Hundred & Fifty Only
2	Loosening, leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Table 300-2 for embankment construction.	2055.00	Sqm	157.00	322635.00	INR Three Lakh Twenty Two Thousand Six Hundred & Thirty Five Only
3	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 m : a)All kinds of soil	1210.00	Cum	206.00	249260.00	INR Two Lakh Forty Nine Thousand Two Hundred & Sixty Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a)1:2:4 (1 cement : 2 M Sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	70.00	Cum	4500.00	315000.00	INR Three Lakh Fifteen Thousand Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a)1:4:8 (1 Cement : 4 M Sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	440.00	Cum	4200.00	1848000.00	INR Eighteen Lakh Forty Eight Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
6	Centering and shuttering including strutting, propping etc. and removal of form for a) Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	235.00	Sqm	415.00	97525.00	INR Ninety Seven Thousand Five Hundred & Twenty Five Only
7	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. a) All kinds of soil.	12090.00	Sqm	18.00	217620.00	INR Two Lakh Seventeen Thousand Six Hundred & Twenty Only
8	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	930.00	Cum	1065.38	990803.40	INR Nine Lakh Ninety Thousand Eight Hundred & Three and Paise Forty Only
9	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion a) On W.B.M / W.M.M. @ 0.4kg/sqm	24180.00	Sqm	10.13	244943.40	INR Two Lakh Forty Four Thousand Nine Hundred & Forty Three and Paise Forty Only
10	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion a) On bituminous surface @ 0.25kg/sqm	24180.00	Sqm	8.00	193440.00	INR One Lakh Ninety Three Thousand Four Hundred & Forty Only
11	Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. a) 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	2280.00	Cum	7182.00	16374960.00	INR One Crore Sixty Three Lakh Seventy Four Thousand Nine Hundred & Sixty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
12	2.5 cm premix carpet surfacing with 2.25 cum and 1.12 cum of stone chippings of 13.2 mm and 11.2 mm size respectively per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). a) With paving Asphalt grade VG - 30 with no solvent.	24180.00	Sqm	157.00	3796260.00	INR Thirty Seven Lakh Ninety Six Thousand Two Hundred & Sixty Only
13	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator , vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-incharge. (The panel shuttering work shall be paid for separately).	285.00	Cum	5600.00	1596000.00	INR Fifteen Lakh Ninety Six Thousand Only
14	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. a)80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	1645.00	Sqm	626.00	1029770.00	INR Ten Lakh Twenty Nine Thousand Seven Hundred & Seventy Only
Total in Figures					27834966.80	INR Two Crore Seventy Eight Lakh Thirty Four Thousand Nine Hundred & Sixty Six and Paise Eighty Only
Quoted Rate in Words		INR Two Crore Seventy Eight Lakh Thirty Four Thousand Nine Hundred & Sixty Six and Paise Eighty Only				