



Work-order

संख्या: भा.वि.प्रा./मुंबई/एनएसी/अभि-सि//19/23-24/WO-32/40

दिनांक:-25/09/2023

No. AAI/MUM/NAC/E-C/19/23-24/WO-32/40

Date:- 25/09/2023

सेवा मे,

M/s. M.K. Construction

1/4, Segvan Chawl, L.B.S. Nagar,

90 Feet Road, Sakinaka,

Mumbai - 400 072.

Email id: munnarsingh9322@gmail.com

जीएसटी:- 27ANIPS6614F1ZS.

विषय : 2023 24 के दौरान न्यू एयरपोर्ट कॉलोनी मुंबई के लिए एआरएमओ का काम

उपशीर्ष : शौचालयों की मरम्मत, फर्श, रसोई, अन्य विविध चिनाई कार्य और आंतरिक रंग रोगन

Subject: ARMO work for New Airport Colony Mumbai during 2023 24.

SH: Repairs to washrooms, flooring, kitchen, other misc. masonry works and internal painting.

Tender id: 2022_AAI_161070_1 / बीड क्र°/ Bid No: 590118.

संदर्भ:- आपका दिनांक 18.08.2023 को खोला गया वित्तीय ई-निविदा।

Ref.:- Your e-tender Finance bid Opened on dated 18.08.2023.

महोदय/ Dear Sir (S),

- ऊपर उल्लेखित कार्य हेतु आपकी ई-निविदा, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है। आपके द्वारा बताए गए मद मूल्यों पर आपकी टेंडर राशि कुल रु. **55,72,675/-** (रुपये पचपन लाख बहत्तर हजार छह सौ पचहत्तर मात्र) (जीएसटी रहित) हैं, जो की टेंडर की अनुमानित लागत राशि रु. **96,47,260/-** (रुपये छियानवे लाख सैंतालीस हजार दो सौ साठ मात्र) (जीएसटी रहित) से **42.24** प्रतिशत नीचे हैं। आपकी उद्धृत गणना से लाई रकम पर 18% फीसदी जी.एस.टी. (यानि 9 फीसदी CGST और 9 फीसदी SGST) राशि का वैध टैक्स चालान का जमा करने पर भुगतान किया जाएगा।
- Your e-tender for the work mentioned above is hereby accepted on the behalf of the Chairman, Airports Authority of India at your quoted rate amounting to **Rs.55,72,675/-** (Rupees Fifty Five Lakh Seventy Two Thousand Six Hundred Seventy Five only) (excluding GST). Your bid quote is **42.24% below** the estimate cost put to tender of **Rs.96,47,260/-** (Rupees Ninety Six Lakh Forty Seven Thousand Two Hundred Sixty only) (The GST at 18 per cent (i.e. 9 per cent CGST plus 9 per cent SGST) will be paid over and above the amount calculated on your quoted rate on submission to valid tax invoice.

Work-order

2. वरिष्ठ प्रबंधक (अभि-सिविल), प.क्षे. मुंबई कार्य के अभियंता-प्रभारी होंगे। आपसे निवेदन है कि आप आपकी और से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक **05.11.2023** तक व. प्रबंधक (अभि-सिविल), ए.ए.आई. , सिविल मेंटेनेंस ऑफिस, एनएसी, मुंबई के कार्यालय में उपस्थित हो और करारनामे को पूरा करें। ठेके का करारनामा 100 / - रुपये के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर की लागत आपके द्वारा ली जाएगी।
2. Sr. Manager (Engg-Civil), Mumbai shall be Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the O/o. Sr. Manager (Engg-Civil), AAI, Civil Maintenance office, NAC, Mumbai by **05.11.2023** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- and the cost of the stamp paper shall be borne by you.
3. कृपया इस पत्र जारी होने की तारीख से 15 दिनों के भीतर सुरक्षा जमा रु. **3,64,321.50** (कुल रुपये तीन लाख चौंसठ हजार तीन सौ इक्कीस रुपये एवं पचास पैसा मात्र) जमा करें, असफल होने पर ठेके के दस्तावेज के पृष्ठ सं. 16 पर दी गयी शर्त 1 (ए) के अनुसार आपके चालू बिल से कटौती की जाएगी।
3. Please deposit **Rs. 3,64,321.50** (Rupees Three Lakh Sixty Four Thousand Three Hundred Twenty One and Fifty Paise Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per condition 1 (A) on page 16 of the contract document.
4. आपसे निवेदन है कि आप केन्द्रीय एवं राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और अन्य नियमों का अनुपालन किया जाए।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

25.09.23
SM/ET

Work-order

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (अभि-सिविल), सिविल रखरखाव कार्यालय, न्यू एयरपोर्ट कॉलोनी से तुरंत संपर्क करें, वह आपको साइट सौंपने की व्यवस्था करेंगे और कार्य के निष्पादन और निगरानी के लिए अपेक्षित दिशा-निर्देश जारी करने के लिए अधिकृत है। कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय **बारह (12) महीने है** जिसे इस पत्र जारी करने के बाद दसवे दिन या वास्तविक कार्य चालू करने पर, इनमे से जो भी पहले हो वह गिना जाएगा।
5. You are also directed to contact Manager (Engg-Civil), Civil Maintenance office, New Airport Colony immediately who will arrange to hand over the site to you and is authorised for issuing requisite directions for executing and monitoring the work. Please note that the time allowed for carrying out the work is **12 (Twelve) Months** which shall be reckoned from the 10th day after the date of issue of this letter or the day of actual start of work whichever is earlier.
6. अनुबंध दस्तावेज के पृष्ठ संख्या 47 और 48 पर खंड संख्या 17 में उल्लिखित दोष देयता अवधि बारह महीने है।
6. The defects liability period mentioned in clause No. 17 on page no.47 & 48 of the contract document is **Twelve Months**.
7. इस ठेके के सम्बंध मे आगे कोई भी पत्राचार व. प्रबंधक (अभि-सिविल), प.क्षे. भारतीय विमानपत्तन प्राधिकरण, सिविल मेटेनैस कार्यालय, न्यू एयरपोर्ट कॉलोनी, विले पार्ले (पूर्व), मुम्बई-400 099 के पते पर संदर्भ AAI/MUM/NAC/E-C/19/23-24/WO-32 से किया जाए।
7. Any further correspondence in connection with the contract should be addressed to the Sr. Manager (Engg-Civil), WR, Airports Authority of India, Civil maintenance office, New Airport Colony, Vile-Parle (East), Mumbai-400 099 and the reference number for this work is AAI/MUM/NAC/E-C/19/23-24/WO-32 .


25.09.23
SM (C)

Work-order


8. कृपया इस पत्र की प्रतिलिपि स्वीकृति के एक टोकन के रूप में हस्ताक्षर कर अधोहस्ताक्षरी को वापिस करें।

8. Please acknowledge the receipt and return the copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

धन्यवाद/ Thanking you,

संलग्न : BOQ-05 पृष्ठ

भवदीय / Yours faithfully,



अमित अवचार / Amit Avachar

वरिष्ठ प्रबन्धक अभि-सिविल ,

Sr. Manager (Engg-Civil)

कृते तथा ओर से, अध्यक्ष

For and on behalf of chairman,

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

Work-order

फॉर्म – V / Form V
नियम 21(2) देखें / See Rule 21(2)

मुख्य नियोक्ता द्वारा प्रमाण पत्र / Form of Certificate by Principal Employer

Certified that AAI have engaged the applicant M/s. M.K. Construction , Mumbai, as a contractor for the work of “ARMO work for New Airport Colony Mumbai during 2023 24. SH: Repairs to washrooms, flooring, kitchen, other misc. masonry works and internal painting” AAI undertakes to be bound by all the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996, in so far as the provisions are applicable to them in respect of the employment of contract labour by the applicant in this establishment.

प्रमाणित किया जाता है कि एएआई ने आवेदक **मेसर्स एम. के. कंस्ट्रक्शन** को 2023 24 के दौरान न्यू एयरपोर्ट कॉलोनी मुंबई के लिए एआरएमओ का काम उपशीर्ष : शौचालयों की मरम्मत, फर्श, रसोई, अन्य विविध चिनाई कार्य और आंतरिक रंग रोगन कार्य के लिए ठेकेदार के रूप में लगाया है। एएआई आवेदक को अनुबंध श्रम) विनियमन और उन्मूलन (अधिनियम 1970 और अनुबंध श्रम) विनियमन और उन्मूलन (केंद्रीय नियम 1971, बाल श्रम) निषेध और विनियमन (अधिनियम 1986 , निर्माण कार्यकर्ताओं) रोजगार और सेवा-की शर्तों का विनियमन (अधिनियम 1996 , भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, जहां तक इस प्रतिष्ठान में अनुबंध श्रम के रोजगार के संबंध में प्रावधान लागू होते हैं। आवेदक द्वारा के एएआई के सभी प्रावधानों से बंधेगा।


25.09.23

वरिष्ठ प्रबन्धक (अभि-सिविल)
Sr. Manager (Engg-Civil)

सेवामें / To,
M/s. M.K. Construction
1/4 , Segvan Chawl, L.B.S. Nagar,
90 Feet Road, Sakinaka,
Mumbai – 400 072.
Email id: munnarsingh9322@gmail.com
जीएसटी:- 27ANIPS6614F1ZS.

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Sr. Manager (Engg-Civil), NAC, Mumbai-99

Name of Work: ARMO work for New Airport Colony, Mumbai during 2023-24.
SH: Repairs to washrooms, flooring, kitchen, other misc. masonry works and internal painting

Contract No: AAI/MUM/NAC/E-C/19/23-24

Name of the Bidder/
Bidding Firm /

M.K.Construction

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words without Taxes INR
1	2	3	4	5	12	13	53	55
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.		500.00	sqm	INR	700.00	350000.00	INR Three Lakh Fifty Thousand Only
2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, on walls, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.		1750.00	sqm	INR	650.00	1137500.00	INR Eleven Lakh Thirty Seven Thousand Five Hundred Only
3	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3 kg/ sqm.		1750.00	sqm	INR	75.00	-131250.00	INR Minus One Lakh Thirty One Thousand Two Hundred & Fifty Only
4	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.		1750.00	sqm	INR	250.00	437500.00	INR Four Lakh Thirty Seven Thousand Five Hundred Only
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm		750.00	sqm	INR	1050.00	787500.00	INR Seven Lakh Eighty Seven Thousand Five Hundred Only

Handwritten signature and date: 25.04.24

6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	90.00	sqm	INR	1150.00	103500.00	INR One Lakh Three Thousand Five Hundred Only
7	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red Area of slab over 0.50 sqm	100.00	sqm	INR	2200.00	220000.00	INR Two Lakh Twenty Thousand Only
8	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work	20.00	m	INR	150.00	3000.00	INR Three Thousand Only
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	5.00	Cum	INR	5900.00	29500.00	INR Twenty Nine Thousand Five Hundred Only
10	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	300.00	sqm	INR	220.00	66000.00	INR Sixty Six Thousand Only
11	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	1250.00	sqm	INR	25.00	31250.00	INR Thirty One Thousand Two Hundred & Fifty Only
12	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	1250.00	sqm	INR	15.00	18750.00	INR Eighteen Thousand Seven Hundred & Fifty Only
13	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. 25 mm average thickness in 2 layers. (Note: Measurement and payment: The pre-measurement of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm2).	1250.00	sqm	INR	350.00	437500.00	INR Four Lakh Thirty Seven Thousand Five Hundred Only
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	10.00	cum	INR	4300.00	43000.00	INR Forty Three Thousand Only

Handwritten signature and initials in blue ink, including the word "Total" and some illegible scribbles.

15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	10.00	cum	INR	4600.00	46000.00	INR Forty Six Thousand Only
16	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	350.00	sqm	INR	690.00	241500.00	INR Two Lakh Forty One Thousand Five Hundred Only
17	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-In-Charge 50 mm average thickness	10.00	sqm	INR	180.00	1800.00	INR One Thousand Eight Hundred Only
18	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars upto 12 mm diameter	50.00	m	INR	4.00	200.00	INR Two Hundred Only
19	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars Above 12 mm diameter	50.00	m	INR	8.00	400.00	INR Four Hundred Only
20	Disposal of loose earth/ debris /stones /building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	550.00	cum	INR	115.00	63250.00	INR Sixty Three Thousand Two Hundred & Fifty Only
21	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	15000.00	Sqm	INR	3.00	45000.00	INR Forty Five Thousand Only
22	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. SBR Polymer (@10% of cement weight) modified cementitious bond coat @ 2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	500.00	Sqm	INR	90.00	45000.00	INR Forty Five Thousand Only

25.01.23
BML/ET

23	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. Note: Measurement and payment: The pre-measurement of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm2). 12 mm average thickness.	500.00	Sqm	INR	275.00	137500.00	INR One Lakh Thirty Seven Thousand Five Hundred Only
24	Supplying white cement based putty of approved brand and manufacturer as mentioned in list of approved make and technical specification.	5500.00	Kg	INR	25.00	137500.00	INR One Lakh Thirty Seven Thousand Five Hundred Only
25	Applying white cement based putty/ plaster of Paris putty / Acrylic putty of average thickness 1 mm in layers over the plastered wall surface to prepare the surface even and smooth complete. Note: Item will be supplied by AAI.	2500.00	Sqm	INR	30.00	75000.00	INR Seventy Five Thousand Only
26	Supplying plaster of paris putty of approved make and specification as per list of approved make and technical specification.	2500.00	Kg	INR	13.00	32500.00	INR Thirty Two Thousand Five Hundred Only
27	Supplying synthetic enamel paint of approved brand and manufacture as per list of approved make and technical specification.	300.00	Liter	INR	230.00	69000.00	INR Sixty Nine Thousand Only
28	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on all works. Note: Synthetic enamel paint will be provided by AAI.	2000.00	Sqm	INR	25.00	50000.00	INR Fifty Thousand Only
29	Supplying water thinnable cement primer of approved brand and manufacture as per list of approved make and technical specification .	500.00	Liter	INR	95.00	47500.00	INR Forty Seven Thousand Five Hundred Only
30	Applying required coats of water thinnable cement primer of approved brand and manufacture on wall surface. Note : Material will be provided by AAI.	5000.00	Sqm	INR	15.00	75000.00	INR Seventy Five Thousand Only
31	Supplying premium acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture as per list of approved make and technical specification.	2050.00	Liter	INR	128.00	262400.00	INR Two Lakh Sixty Two Thousand Four Hundred Only
32	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. A) One coat Note: Acrylic Emulsion paint will be provided by AAI.	20000.00	Sqm	INR	25.00	500000.00	INR Five Lakh Only
33	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. A) Two coats Note: Acrylic Emulsion paint will be provided by AAI.	5000.00	Sqm	INR	32.00	160000.00	INR One Lakh Sixty Thousand Only
34	Providing and applying crack sealant for joints, cracks, etc. by preparing groove and filling crack sealant of approved brand and manufacture as per list of approved make and technical specification.	125.00	Kg	INR	95.00	11875.00	INR Eleven Thousand Eight Hundred & Seventy Five Only

$\frac{50}{\cancel{20}} = \frac{5}{2}$

35	Supplying Acrylic wall putty of approved brand and manufacturer as mentioned in list of approved make and technical specification.		500.00	Kg	INR	75.00	37500.00	INR Thirty Seven Thousand Five Hundred Only
Total in Figures							5572675.00	INR Fifty Five Lakh Seventy Two Thousand Six Hundred & Seventy Five Only
Quoted Rate in Words		INR Fifty Five Lakh Seventy Two Thousand Six Hundred & Seventy Five Only						

25/05/23
 5:30 PM
 25/05/23
 5:30 PM