

संख्या:- भाविप्रा/जोध./अभि.(वि.)/बीकेएन/डब्ल्यू ई-09/2023-24/ 2172-81

दिनांक :- 14.09.2023

Ref. No: - AAI/JOD/ENGG (E)/BKN/WE-09/2023-24/

Date :- 14.09.2023

सेवामें,

मैसर्स सुपरटेक इंजीनियर्स,

गली नंबर 3, एसएसडी गर्ल्स कॉलेज के पास,

अमरीक सिंह रोड, बठिंडा,

पंजाब – 151001

To,

M/s Supertech Engineers,

Street No. 3, Near S.S.D. Girl's College

Amrik Singh road, Bathinda

Punjab – 151001

कार्य का नाम :- “सिविल एयरपोर्ट बीकानेर में विविध विद्युत कार्य का प्रावधान।

उपकार्य :- प्रोविजन ऑफ इलेक्ट्रिकल वर्क्स फॉर सिक्युरिटी वाच टॉवर/ हट ऐप्रन साइड & बूम बैरियर कैबिन सिटी साइड।

Name of Work: “Miscellaneous Electrical Works at Civil Airport, Bikaner.”

SH: - Provision of Electrical works for Security Watch Tower / Hut Apron Side & Boom Barrier Cabin City Side.

संदर्भ:- आपकी ई – निविदा (Tender ID- 2023_AAI_161796_1) की वित्तीय बिड दिनांक 28/08/2023 को खोली गयी।

Ref:- Financial Bid of your e-Tender (Tender ID-2023_AAI_161796_1) opened on dtd. 28/08/2023.

महोदय / Dear Sir (S),

1. उपरोक्त उल्लेखित कार्य के लिए आपका ई-टेंडर आपके द्वारा बताए गये मद मूल्यों पर कुल राशि ₹ 4,37,920/- (दर जीएसटी के बिना) (रूपये चार लाख सैंतीस हजार नौ सौ बीस मात्र) जो कि अनुमानित लागत ₹ 4,97,901.00 (जीएसटी रहित) टेण्डर के लिए रखी गई है, से 11.90% नीचे है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your e – Tender Bid for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to ₹ 4,37,920/- (Rates excluding of GST) (Rupees Four Lakh Thirty Seven Thousand Nine Hundred Twenty Only) which is 11.90% below the Estimated Cost put to bid of ₹ 4,97,901.00 (excluding GST).

2. सहायक महाप्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव, जोधपुर – 342011 इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है आप करारनामे पर हस्ताक्षर करने के लिए दिनांक 29/09/2023 तक सहा. महाप्रबंधक (अभि.-विद्युत), सिविल एन्क्लेव, जोधपुर – 342011 के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा ₹ 500/- (रु पाँच सौ मात्र) के नोन ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा जिसका खर्चा आपके द्वारा उठाया जाएगा।

Asst. Gen. Manager (E-E), Airports Authority of India, Civil Enclave, Jodhpur - 342011 shall be Engineer-in-Charge of the work. You are requested to attend the office of Asst. Gen. Manager (E-E), Airports Authority of India, Civil Enclave, Jodhpur - 342011 by 29/09/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of ₹500/- (Rs. Five Hundred only) and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूति राशि ₹ 43,792.00 (रूपये तैंतालीस हजार सात सौ बानबे मात्र) जमा कर दें, अन्यथा ठेके के करारनामे में GCC के पृष्ठ संख्या 17 पर क्लॉज नं.1A के अनुसार इतनी ही राशि आपके रनिंग बिल से काट ली जाएगी।

संयंक शाह
14/09/2023

लगातार – 2

कार्यालय निदेशक विमानपत्तन, सिविल एन्क्लेव, जोधपुर – 342011, फोन: 0291-2595201, निवास: 0291-16550727 फैक्स 0291-2512934

O/o Airport Director, Civil Enclave, Jodhpur -342011, Ph: – 0291-2595201 Residence: 0291-6550727 Fax: 0291-2512934

“हिन्दी पत्रों का स्वागत है।”

Please deposit ₹ 47,792.00 (Rs. Forty Three Thousand Seven Hundred Ninety Two Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause No. 1A on Page No. 17 of GCC of contract document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम के प्रावधान और अनुबंध श्रम (विनियमन और उन्मूलन) के केंद्रीय नियम 1971, बालश्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की शर्त का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 आदि जैसाकि बिड दस्तावेज और केंद्रीय एवं राज्य सरकार के नियमों में निर्दिष्ट प्रावधानों का अनुपालन करें।

You are requested to comply with the Provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in the bid document and rules of Central and State Government.

5. आपको निर्देशित किया जाता है कि तुरंत प्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, सिविल एयरपोर्ट, बीकानेर से मिले वह आप को साइट सौंपने की व्यवस्था करेंगे।

You are directed to contact Manager (Engg.-Elect), Airports Authority of India, Civil Airport, Bikaner immediately who will arrange to hand over the site to you.

6. कृपया नोट कर ले कि काम करने का निर्धारित समय **04 (चार) माह** है जोकि इस पत्र के जारी होने के बाद 10 वें दिन से गिना जाएगा।
Please note that the time allowed for carrying out the work shall be **04 (Four) Month** and same shall be reckoned from the 10th day after issue of this letter.

7. इस अनुबंध के संबंध में कोई और पत्राचार सामान्य रूप से प्रभारी अभियंता को संबोधित किया जाये।

Any further correspondence in connection with this contract should normally be addressed to Engg.-in-Charge.

8. कृपया पावती भेजें और इस पत्र की डुप्लिकेट कॉपी हस्ताक्षर करने के बाद स्वीकृति के टोकन के रूप में अधोहस्ताक्षरी को लौटाएं।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

नोट : हिंदी अथवा अंग्रेजी संस्करण में अंतर पाये जाने पर अंग्रेजी संस्करण मान्य होगा।

NOTE: If there any discrepancy is observed in Hindi and English version, the English version will be considered.

सत्येंद्र शास्त्री
14/09/2023

सहा. महाप्रबंधक (अभि.-विद्युत) /AGM (Engg. - E),

के लिए और ओर तरफ से - अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,

For and on behalf of the Chairman, Airports Authority of India,

संलग्न / Enclosed:- Bill of Quantities

प्रतिलिपि / Copy to :-

1. महाप्रबन्धक (अभि.) – उ.क्षे., भारतीय विमानपत्तन प्राधिकरण, प्रचालन काम्प्लेक्स, NATS बिल्डिंग, नई दिल्ली-37
General Manager (Engg.) – I, N.R., A.A.I., Operational Offices, NATS Building, New Delhi – 37
2. महाप्रबन्धक (वित्त), उ.क्षे., भारतीय विमानपत्तन प्राधिकरण, प्रचालन काम्प्लेक्स, NATS बिल्डिंग, नई दिल्ली-37
General Manager (Finance), N.R., A.A.I., Operational Offices, NATS Building, New Delhi – 37
3. निदेशक विमानपत्तन, भारतीय विमानपत्तन प्राधिकरण, सिविल एयरपोर्ट, बीकानेर – 334001
Airport Director, Airports Authority of India, Civil Airport, Bikaner – 334001
4. संयुक्त महाप्रबन्धक (अभि. - विद्युत) उ.क्षे., भारतीय विमानपत्तन प्राधिकरण, NATS बिल्डिंग, नई दिल्ली-37
Jt. General Manager (Engg. – E), N.R., A.A.I., Operational Offices, NATS Building, New Delhi – 37
5. वरिष्ठ प्रबन्धक (वित्त), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव, जोधपुर – 342011
Senior Manager (Finance), Airports Authority of India, Civil Enclave, Jodhpur – 342011
6. प्रबन्धक (अभि. - विद्युत), भारतीय विमानपत्तन प्राधिकरण, सिविल एयरपोर्ट, बीकानेर – 334001
Manager (Engg. – E), Airports Authority of India, Civil Airport, Bikaner – 334001
7. सहायक श्रम आयुक्त (केंद्रीय), ऑफिसर्स मैस के सामने, जोधपुर – 342011
Assistant Labor Commissioner (Central), Opposite Officers Mess, Jodhpur - 342011
8. करारनामा प्रतिलिपि /Agreement Copy
9. सम्बन्धित फाइल / Concerned File

संयुक्त महाप्रबन्धक
14/08/2023

सहा. महाप्रबन्धक (अभि.-विद्युत) /AGM (Engg. - E).

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

सिविल एन्क्लेव, जोधपुर – 342011 / Civil Enclave, Jodhpur – 342011



भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

सिविल एन्क्लेव, जोधपुर / Civil Enclave, Jodhpur

कार्यसूची / BILL OF QUANTITIES

कार्य का नाम:- सिविल एयरपोर्ट बीकानेर में विविध विद्युत कार्य का प्रावधान।

उपकार्य :- प्रोविजन ऑफ इलेक्ट्रिकल वर्क्स फॉर सिक्युरिटी वाच टॉवर/ हट ऐप्रन साइड & बूम बैरियर कैबिन सिटी साइड।

Name of Work:- Miscellaneous Electrical Works at Civil Airport, Bikaner.


SH:- Provision of Electrical works for Security Watch Tower / Hut Apron Side & Boom Barrier Cabin City Side.

BILL OF QUANTITIES

Sr. No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. (Group - C)	Point	28	1600.00	44800.00
2	Wiring for Circuit wiring alongwith earth wire with the 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required	Meter	100	310.00	31000.00
3	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	Meter	100	350.00	35000.00
4	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as	Each	7	450.00	3150.00
5	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	Each	7	600.00	4200.00
6	Supply of 20 watt LED tube light surface mounted suitable for operation on 230 volt,50Hz AC supply, complete etc as required.	Each	14	300.00	4200.00
7	Supply of 1200mm sweep ceiling fan (5 Star rating) complete with downrod, fan blades and step type electronic regulator complete with all accessories as required.	Each	11	2400.00	26400.00
8	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.	Each	11	350.00	3850.00

Sr. No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
9	Supply of heavy duty exhaust fan of size 450mm (18 inch), 1400 RPM suitable for operation on 230V 50 Hz AC supply complete with louvers/shutters etc. as per site requirement.	Each	3	4000.00	12000.00
10	Installation of exhaust fan upto 450mm sweep in the existing opening, including making the hole to suit the size of the above fan, making good the damage, connections, testing, commissioning etc. as required.	Each	3	500.00	1500.00
11	Supplying and fixing, 4 way, single pole and neutral, sheet steel, MCB distribution board, double door, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar,	Each	8	1000.00	8000.00
12	Supplying and fixing 6 amps to 32 amps, Single pole, rating, 240 volts, 10 kA, "C" curve, miniature circuit breaker in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Each	16	180.00	2880.00
13	Supplying and fixing DP MCB 32 amps, Double pole, rating, 240 volts, 10 kA, "C" curve, miniature circuit breaker in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Each	8	1000.00	8000.00
14	Providing and fixing 6 SWG dia. G.I. wire on surface or in recess for loop earthing as required.	Meter	500	60.00	30000.00
15	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting / LED fittings of all types, complete with all accessories and tube etc. directly on ceiling/ wall, including connection	Each	14	200.00	2800.00
16	Supply, Installation, testing and commissioning of Desert cooler made of minimum 0.91 mm (20 SWG) thick steel steet body and 1.22 mm (18 SWG) GI sump tank of minimum 60 ltr with 450 mm sweep fan having speed	Each	5	8700.00	43500.00
17	Supply of 2 X 10 sq.mm size aluminium conductor armoured XLPE insulated PVC sheathed electric power cable for working voltage upto 1.1 KV. as per IS :7098 (Part-I) etc as required.	Mtr	500	120.00	60000.00
18	Laying of one number PVC insulated & PVC sheathed / XLPE power cable 1.1 KV grade of Upto 35 sq. mm size direct in ground i/c excavation and refilling the trench with 40 mm HDPE Pipe etc. as required.	Mtr.	420	198.00	83160.00
19	Laying of one number PVC insulated & PVC sheathed /XLPE power cable 1.1 KV grade of Upto 35 sq. Mm size in the existing RCC/ HUME/ METAL/HDPE pipe as required.	Mtr.	30	99.00	2970.00
20	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of Upto 35 sq. mm on wall surface as required.	Mtr.	50	99.00	4950.00

मथुरा शास्त्र
14/09/2023
स.प्र.प्र. (3/17/23)

Sr. No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
21	Supply and making end termination with brass compression gland and aluminium lugs for 2 x 10 sq mm size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required.	set	16	240.00	3840.00
22	Supplying of 40 mm outer dia DWC HDPE pipe as per specifications etc as required.	Mtr.	500	38.00	19000.00
23	Supplying of 75 mm outer dia DWC HDPE pipe as per specifications etc as required.	Mtr.	20	68.00	1360.00
24	Laying of 75 mm dia HDPE pipe for road crossing including coupling / jointing of pipe. Complete as	Mtr	20	68.00	1360.00
Total				₹ 437,920.00	
(Rs. Four Lakh Thirty Seven Thousand Nine Hundred Twenty Only)  सहा. महाप्रबंधक (अभि.-विद्युत) / AGM (Engg. - E) भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India सिविल एन्क्लेव, जोधपुर – 342011 / Civil Enclave, Jodhpur – 342011					