

By Hand/ E-mail

F.No. AAI/BLY/Engg. (C)/2023/Perimeterroad/ 157

Date: 04.10.2023

सेवा में,

मैसर्स आदित्य इंजीनियरिंग प्राइवेट लिमिटेड
35-ए/7, रामपुर गार्डन,
कुंवर भवन चंद्रा लेन,
बरेली, उत्तर प्रदेश-243001

M/s. ADITYA ENGGCON PRIVATE LIMITED
35-A/7, RAMPUR GARDEN,
KUNVAR BHUVAN CHANDRA LANE,
BAREILLY, UTTAR PRADESH-243001

Subject: Construction of balance portion of perimeter road and connecting road between car parking and new Terminal building at Bareilly Airport (E- Tender ID- 2023_162941_1)

संदर्भ: दिनांक 01.09.2023 को खोली गई आपकी वित्तीय ई.-निविदा।

Ref: Your financial e-bid Opened on Dated: 01.09.2023.

प्रिय महोदय/Dear sir,

- 1) आपके उपरोक्त कार्य की रू० 1,82,90,513/- (जीएसटी रहित) (रू० एक करोड़ व्यासी लाख नब्बे हजार पाँच सौ तेरह मात्र) की मदद से ई.-निविदा जो कि उक्त कार्य की अनुमानित लागत रू० 1,70,16,935/- (जीएसटी रहित) (रू० एक करोड़ सत्तर लाख सोलह हजार नौ सौ पैंतीस मात्र) से 7.48% अधिक है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।
Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling to Rs. 1,82,90,513/- (excluding GST) (Rupees one crore eighty-two lakhs ninety thousand five hundred thirteen only) which is 7.48% above the estimated cost put to tender of Rs. 1,70,16,935/- (excluding GST) (Rupees one crore seventy lakhs sixteen thousand nine hundred thirty-five only).

- 2) सहायक महाप्रबंधक (अभि-सिविल), भा०वि०प्रा०, सिविल एन्क्लेव, बरेली इस कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि दिनांक: 28.10.2023 तक सहायक महाप्रबंधक, (अभि-सिविल) भा०वि०प्रा०, सिविल एन्क्लेव, बरेली एयरपोर्ट के कार्यालय में उपस्थित होकर ठेका संविदा को हस्ताक्षरित कर पूर्ण करें। ठेका रू 100/- (रूपये एक सौ मात्र) के न्यायिकोत्तर मुद्रांक पत्र पर सम्पादित किया जाएगा एवं मुद्रांक पत्र की कीमत आपके द्वारा वहन की जाएगी।

Asst. General Manager (Engg.Civil), AAI, Civil Enclave, Bareilly shall be the Engineer-in-charge of this work. You are requested to attend the office of Asst. General Manager (Engg.Civil), AAI, Civil Enclave, Bareilly by dated: 28.10.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-Judicial stamp paper of value Rs. 100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

- 3) आपसे अनुरोध है कि संविदा मूल्य के 10% की दर से सुरक्षा जमा राशि जमा करें जो कि किसी भी अनुसूचित बैंक की बैंक गारंटी के रूप में हो सकता है लेकिन सहकारी या ग्रामीण बैंक नहीं हो। यदि आप जमानत राशि जमा करने में विफल रहते हैं, तो इसे प्रत्येक आर.ए. बिल से उक्त आर.ए. बिल राशि के 10% की दर से सुरक्षा जमा की पूरी राशि की वसूली तक परिस्थितियों के अनुसार एवं प्रभारी अभियन्ता से निकासी प्रमाण पत्र प्रदान करने उपरांत अंतिम बिल में समायोजित/निपटान करने के लिए वसूल किया जाएगा।

You are requested to deposit the security deposit @ 10% of the contract value which can be in the form of bank guarantee of any scheduled bank but not Co-Operative or Gramin Bank. If you fail to deposit security deposit, the same shall be recovered from each RA bill @ 10% of the said RA bill amount till realization of full amount of security deposit, to be adjusted/settled in the final bill as per the circumstances and on providing clearance certificate from Engineer-in-charge.

- 4) आपसे अनुरोध है कि 1970 के अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, भवन और अन्य निर्माण श्रमिकों (रोजगार का विनियमन) के प्रावधानों का अनुपालन करें। सेवा की शर्तें अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, न्यूनतम मजदूरी अधिनियम 1948, ईपीएफ अधिनियम -1952, ईएसआई अधिनियम -1948, और केंद्र और राज्य सरकार के अन्य नियम।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Building and other Construction Workers (Regulation of Employment of Conditions of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996,

सिविल एन्क्लेव, बरेली, पीलीभीत रोड, मुड़िया अहमद नगर (मयूर वन चेतना केन्द्र के पास), बरेली, उत्तर प्रदेश -243122

Civil Enclave, Bareilly, Pilibhit Road, Mudiya Ahmed Nagar (Near Mayur Van Chetna Kendra), Bareilly, Uttar Pradesh -243122


Minimum Wages Act 1948, EPF Act-1952, ESI Act-1948, and other rules there of central and state Government.

- 5) ठेकेदार नियमित तथा प्रभावी पर्यवेक्षण को सुनिश्चित करेगा और उनके द्वारा तैनात किये गये कार्मिक पर नियंत्रण एवं ठेके के दायित्वों को पूरा करने के लिए उपयुक्त निर्देश देगा।
The contractor shall ensure regular and effective supervision and control of the personnel deployed by him and gives suitable direction for undertaking the contractual obligations.
- 6) आपको निर्देशित किया जाता है कि तुरन्त प्रभाव से सहायक प्रबन्धक (इंजी-सिविल) सिविल एन्क्लेव, बरेली को संपर्क करें जो कि आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact Asstt Manager (Engg- Civil), Civil Enclave, Bareilly immediately who will arrange to hand over the site to you.
- 7) कार्य करने का निर्धारित समय **06 माह** है, जो कि इस पत्र के निर्गत होने की तिथि के **दसवें दिन** से माना जाएगा।
Please note that time allowed for carrying out the work shall be **06 Months** and same shall be reckoned from the **10th day** from the date of issue of this letter.
- 8) संविदा के संदर्भ में सामान्यतः कोई भी पत्राचार कार्य प्रभारी अभियन्ता को सम्बोधित करते हुए किया जाना चाहिए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.
- 9) नागरिक उड्डयन सुरक्षा ब्यूरो (बीसीएस) के निर्देशानुसार एयरोड्रम एंट्री परमिट (ईपी) जारी करने के लिए संबंधित एजेंसी के ई-सहज पोर्टल से सुरक्षा मंजूरी और बीसीएस द्वारा अनुमोदित सुरक्षा कार्यक्रम अनिवार्य है। अतः आपको निर्देशित किया जाता है कि उपरोक्त कार्य के लिए प्रतिनियुक्त केजुअल लेबर, प्रोपराइटर, इंजीनियर्स का सुरक्षा क्लीयरेंस एवं पुलिस वेरीफिकेशन प्राप्त करें।
Security Clearance from the e-Sahaj portal of the concerned agency and security programme approved by BCAS is mandatory for issuance of Aerodrome Entry Permit (AEP) as per the instruction of Civil Aviation Security Bureau (BCAS). Hence, you are directed to get security clearance and Police Verification of Casual Labours, Proprietor, Engineers deputed for the above-mentioned work.
- 10) ठेके की त्रुटि दायित्व अवधि **बारह महीने** है जो कि कार्य समाप्ति की तिथि से गिना जाएगा।
The defect liability period of the contract is **Twelve Months** which shall be reckoned from the actual date of completion of work.
- 11) कृपया प्राप्ति की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

नोट: यदि हिंदी और अंग्रेजी संस्करण में कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण का पालन किया जाएगा।

Note: If any discrepancy is observed in Hindi and English version, then English version will be followed.

भवदीय,
Yours faithfully,


04/10/23

(अवधेश अग्रवाल)

(Avdhesh Aggarwal)

सहायक महाप्रबन्धक (इंजी०-सि०)

Asst. General Manager (Engg. -Civil)

भा०वि०प्रा०, सिविल एन्क्लेव, बरेली

AAI, Civil Enclave, Bareilly

अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के लिए व उनकी तरफ से

For & on behalf of the Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

Encl: Price Schedule.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asstt. General Manager (Engg-Civil), AAI, Civil Enclave, Bareilly

Name of Work: Construction of balance portion of perimeter road and connecting road between car parking and new Terminal building at Bareilly Airport

Contract No: 2023_AAI_162941

Name of the Bidder/ Bidding Firm / Company :	ADITYA ENGGCON PRIVATE LIMITED
--	--------------------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder excluding GST Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Item No.1	1.00	cum	270.00	270.00	INR Two Hundred & Seventy Only
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	Item No.2	2.00	cum	270.00	540.00	INR Five Hundred & Forty Only
3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	Item No.3	2.00	cum	270.00	540.00	INR Five Hundred & Forty Only
4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	Item No.4	6.00	cum	270.00	1620.00	INR One Thousand Six Hundred & Twenty Only
5	Earthwork in excavation in all kinds of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections and transporting to embankment location with all lifts and leads within airport premises as per	Item No.5	4692.00	cum	180.00	844560.00	INR Eight Lakh Forty Four Thousand Five Hundred & Sixty Only
6	Consolidation of sub grade with power road roller of 8 to 12 tonne capacity including making good the undulations etc. with earth or quarry spoils etc. and rerolling the subgrade etc. as per the satisfaction and direction of Engineer-in-charge.	Item No.6	9224.00	sqm	12.00	110688.00	INR One Lakh Ten Thousand Six Hundred & Eighty Eight Only
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Item No.7	4692.00	cum	75.00	351900.00	INR Three Lakh Fifty One Thousand Nine Hundred Only
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded	Item No.8	34.00	cum	4500.00	153000.00	INR One Lakh Fifty Three Thousand Only
9	Providing and fixing stainless steel bollards (grade 304) made of hollow tubes, plates etc. including tig welding, grinding, buffing, polishing and making curvature, laser cutting (wherever required) and fitting the same with	Item No.9	60.00	kg	600.00	36000.00	INR Thirty Six Thousand Only
10	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 12.5mm nominal size derived from natural sources)	Item No.10	44.00	sqm	200.00	8800.00	INR Eight Thousand Eight Hundred Only
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	Item No.11	28.00	Cum	5400.00	151200.00	INR One Lakh Fifty One Thousand Two Hundred Only
12	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as	Item No.12	154.00	sqm	750.00	115500.00	INR One Lakh Fifteen Thousand Five Hundred Only
13	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete.	Item No.13	3000.00	sqm	540.00	1620000.00	INR Sixteen Lakh Twenty Thousand Only

Handwritten signature and date: 04/10/23

14	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	Item No.14	1384.00	cum	2700.00	3736800.00	INR Thirty Seven Lakh Thirty Six Thousand Eight Hundred Only
15	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	Item No.15	1109.00	cum	3006.00	3333654.00	INR Thirty Three Lakh Thirty Three Thousand Six Hundred & Fifty Four Only
16	Providing and applying primer coat with bitumen emulsion SS1 grade conforming to IS:8887 on prepared surface of Granular base including clearing of surface and spraying primer at the rate of 0.70 kg/sqm using mechanical means complete in all respects as per direction of Engineer-in-charge. The contractor shall quote his rates assuming quantity of bitumen emulsion as 0.70 kg/sqm. If the actual quantity of bitumen emulsion varies from the quantity assumed above, necessary cost adjustment for deviation in the quantity of bitumen emulsion shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen emulsion exclusive of GST shall only be considered for payment.	Item No.16	5544.00	sqm	27.00	149688.00	INR One Lakh Forty Nine Thousand Six Hundred & Eighty Eight Only
17	Providing and applying tack coat using suitable low viscosity paving bitumen of VG 10 grade conforming to IS:73), spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen emulsion varies from the quantity assumed above, necessary cost adjustment for deviation in the quantity of bitumen emulsion shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen emulsion exclusive of GST shall only be considered for payment. 0.20 Kg/Sqm on existing bituminous surface.	Item No.17	5544.00	sqm	12.00	66528.00	INR Sixty Six Thousand Five Hundred & Twenty Eight Only
18	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and cement as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in- Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 110 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	Item No.18	278.00	cum	8100.00	2251800.00	INR Twenty Two Lakh Fifty One Thousand Eight Hundred Only
19	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and cement as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in- Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 120 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	Item No.19	278.00	cum	9600.00	2668800.00	INR Twenty Six Lakh Sixty Eight Thousand Eight Hundred Only
20	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of oil dirt, scales, oil, grease and other foreign material etc. and lining out complete. New work (Two or more coats)	Item No.20	192.00	sqm	450.00	86400.00	INR Eighty Six Thousand Four Hundred Only
21	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Item No.21	11.00	cum	360.00	3960.00	INR Three Thousand Nine Hundred & Sixty Only
22	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Item No.22	13.00	m	600.00	7800.00	INR Seven Thousand Eight Hundred Only
23	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Item No.23	13.00	sqm	100.00	1300.00	INR One Thousand Three Hundred Only
24	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	Item No.24	40.00	sqm	72.00	2880.00	INR Two Thousand Eight Hundred & Eighty Only
25	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	Item No.25	13.00	m	600.00	7800.00	INR Seven Thousand Eight Hundred Only

4950
04/10/23

26	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	Item No.26	294.00	Sqm	6000.00	1764000.00	INR Seventeen Lakh Sixty Four Thousand Only
27	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Item No.27	50.00	sqm	7500.00	375000.00	INR Three Lakh Seventy Five Thousand Only
28	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work	Item No.28	144.00	m	3000.00	432000.00	INR Four Lakh Thirty Two Thousand Only
29	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 450 mm dia RCC pipes.	Item No.29	15.00	m	750.00	11250.00	INR Eleven Thousand Two Hundred & Fifty Only
30	Providing weep holes in Brick masonry/Plain/ Reinforced concrete with 75 mm dia unplasticised Rigid PVC pipe (working pressure 4 kg / cm ²) etc. all complete as per direction and satisfaction of Engineer-in-charge.	Item No.30	5.00	m	27.00	135.00	INR One Hundred & Thirty Five Only
31	Deduct for taking away of reinforced steel scrapped from dismantled RCC covers. The material so received shall be the property of contractor after dismantling, duly weighed/measured before removing from the site as per the satisfaction of Engineer-in-charge	Item No.31	130.00	kg	30.00	-3900.00	INR Minus Three Thousand Nine Hundred Only
Total in Figures						18290513.00	
Quoted Rate in Words		INR One Crore Eighty Two Lakh Ninety Thousand Five Hundred & Thirteen Only					

Handwritten signature
04/10/23
AS4 (F-9)

Signature Not Verified

Digitally signed by AVDHESH AGGARWAL
Date: 2025.01.03 13:20:01 IST
Location: eProcurement System for Central PSUs

