



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या: भा.वि.प्रा/क्षे.मु./उ.पू.क्षे./ईएनजीजी-सी/विविध सिविल/जीएचवाई/कार्य आदेश-02/23-24
Ref. No.: AAI/RHQ/NER/ENGG-C/Misc Civil/GHY/W.O-02/23-24 / 3516-22

दिनांक:

Date: 10.11.2023

सेवा मे, / To,

मेसर्स काजल दास

M/s Kajal Das

अझारा, मिर्जापुर

Azara, Mirzapur

गुवाहाटी /Guwahati-17

ईमेल / E-mail: kajal.das11@yahoo.com

संपर्क नंबर / Contact No. 8638119118

विषय:- "आरएचक्यू एनईआर गुवाहाटी में एएआई आवासीय कॉलोनी में विविध सिविल कार्य (2023-24)।"

Sub: - "Miscellaneous Civil Works in AAI Residential Colony at RHQ NER Guwahati (2023-24)."

निविदा आई.डी./ Tender ID: 2023_AAI_165434_1

संदर्भ : आपकी वित्तीय ई-बोली 06.10.2023 को CPP पोर्टल के माध्यम से खोली गई।

Reference: Your financial e-bid opened on 06.10.2023 through CPP Portal.

महोदय /Sir (s),

1. उपर्युक्त विषय से संबंधित कार्य के लिए आपकी ई-निविदा इस पत्र के तहत अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है, जिसकी कुल राशि रु 26,50,350/- (जी. एस. टी के बिना) (रुपये छब्बीस लाख पचास हजार तीन सौ पचास मात्र) जो कि अनुमानित लागत निविदा के लिए रखी गई राशि रु.37,86,000/- (जी. एस. टी के बिना) से 29.99% (प्रतिशत) कम है।

Your e-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 26,50,350/- (Excluding GST)** (Rupees Twenty Six Lakh Fifty Thousand Three Hundred Fifty only) which is **29.99% below** the estimated cost put to tender of **Rs. 37,86,000/- (Excluding GST)**.

2. **संयुक्त महाप्रबंधक (अभि-सि)**, भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू. क्षेत्र, इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **संयुक्त महाप्रबंधक (अभि-सि)**, भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र के कार्यालय में **03.12.2023** तक उपस्थित हों। संविदा करार रु.100/- (सौ रुपये मात्र) के गैर न्यायिक (नॉन ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Jt. Gen. Manager (E-C), AAI, RHQ, NER, shall be the Engineer-in-Charge of the work. You are requested to attend office of the Engineer-in-charge i.e. **Jt. Gen. Manager (E-C)**, AAI, RHQ, NER, by **03.12.2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके ई-निविदा के साथ प्राप्त 75,720/- रुपये (पचहतर हजार सात सौ बीस रुपये मात्र) की बयाना राशि को (जीसीसी के) अनुबंध दस्तावेज़ का पृष्ठ संख्या 18 पर खंड संख्या 1ए के अनुसार सुरक्षा जमा के हिस्से के रूप में माना जाएगा और परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के रूप में 1,89,315/- रुपये (एक लाख उनासी हजार तीन सौ पंद्रह रुपये मात्र) जमा करें, अन्यथा अनुबंध दस्तावेज़ के पृष्ठ संख्या 18 (जीसीसी के) पर खंड संख्या 1 ए की शर्त के अनुसार कटौती की जाएगी।

जगदीश-सिंह

10.11.23



IAS-ANZ



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

The earnest money amount of Rs 75,720/- (Rupees Seventy-Five Thousand Seven Hundred Twenty only) received along with your e-tender will be treated and converted as part of security deposit as per Clause No. 1A on page no. 18 (of GCC) Of contract document. Please deposit **Rs. 1,89,315.00** (Rupees **One Lakh Eighty Nine Thousand Three Hundred Fifteen only**) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A on page no.18 (of GCC) of contract document.


4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की स्थिति) के प्रावधानों का अनुपालन करें।) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ 52/53 पर खंड 19, 19ए और केंद्र और राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare cess Act 1996 as specified in Clause 19, 19A on Page 52/53 of GCC of tender and rules of Central and State Government.

5. आपको निर्देश दिए जाते हैं कि आप **संयुक्त महाप्रबंधक (अभि-सिविल)**, भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र से तत्काल सम्पर्क करें जो कि कार्यस्थल सुपद करने की व्यवस्था करेंगे।
You are also directed to contact **Jt. Gen. Manager (E-C)**, AAI, RHQ, NER immediately who will arrange to hand over the site to you.
6. कृपया यह नोट कर लें कि काम करने का समय **06 (छह) महीने**, जिसे **इस पत्र के जारी होने के 10वें दिन** से गिना जाएगा।
Please note that the time allowed for carrying out the work shall be **06 (Six) Months** and same shall be reckoned from **10th day after issue of this letter**.
7. संविदा के संबंध में आगे किया जाने वाला पत्राचार सामान्यतः इंजीनियर प्रभारी से किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. कृपया रसीद की पावती दें और इसके साथ संलग्न इस पत्र की डुप्लीकेट कॉपी को स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को विधिवत हस्ताक्षर करने के बाद लौटा दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
9. यदि कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण को सही माना जाएगा।
In case any discrepancy is found, then English version will be taken as correct.

धन्यवाद/ Thanking you.

भवदीय / Yours faithfully,


(जगबीर सिंह) / (Jagbir Singh)

संयुक्त महाप्रबंधक (अभि-सि) / Jt. GM (E-C)
भा. वि. प्रा., क्षे.मु. उ.पू.क्षे.गुवाहाटी
AAI, RHQ, NER, Guwahati.
For and on behalf of the Chairman,
Airports Authority of India

Encl:

सिस्टम जनित तुलनात्मक विवरण (05 पृष्ठ)
System Generated Comparative Statement (05 pages)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

मुलप्राप्ति पर नहीं/ N.O.O :


में प्रतिलिपि/Copy to:

आंतरिक वितरण/ Internal Distribution:

1. विमानपत्तन निदेशक ,भा.वि.प्रा .गुवाहाटी हवाई अड्डा, गुवाहाटी
Airport Director, AAI, Guwahati Airport, Guwahati
2. महाप्रबंधक (अभि), भा.वि.प्रा., क्षेत्र.मु., उ.पू.क्षेत्र, गुवाहाटी
General Manager (Engg), RHQ, NER, AAI Guwahati
3. सहायक महाप्रबंधक (सतर्कता), भा.वि.प्रा., क्षेत्र.मु., उ.पू.क्षेत्र, गुवाहाटी
Asst. General Manager (Vig.), AAI, RHQ, NER, Guwahati
4. सहायक महाप्रबंधक (वित्त), भा.वि.प्रा., क्षेत्र.मु., उ.पू.क्षेत्र, गुवाहाटी
Asst. General Manager (Fin.), AAI, RHQ, NER, Guwahati
5. वरिष्ठ प्रबंधक (अभि- सिविल), भा.वि.प्रा., क्षेत्र.मु., उ.पू.क्षेत्र, गुवाहाटी
Senior Manager (Engg-Civil), AAI, RHQ, NER, Guwahati
6. कार्यालय प्रतिलिपि
Office Copy.
7. अनुबंध प्रति
Agreement Copy

बाहरी वितरण/ External Distribution:


1. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि भवन, जी.एस. रोड, भंगगढ़, गुवाहाटी-781005, असम।
Regional Provident Fund Commissioner, Bhavishya Nidhi Bhawan, G.S Road, Bhangagarh, Guwahati-781005, Assam.
2. क्षेत्रीय निदेशक, ई.एस.आई निगम, पंचदीप भवन, पी. ओ. बामुनिमैदान, गुवाहाटी-781021, असम।
Regional Director, ESI corporation, Panchdeep Bhawan, P.O: Bamunimaidan, Guwahati-781021, Assam.
3. श्रम प्रवर्तन अधिकारी (केंद्रीय), भारत सरकार, श्रम रोजगार मंत्रालय, केन्द्रीय श्रम सदन, आर.के. मिशन रोड बीरुबारी, गुवाहाटी-781016, असम।
Labour Enforcement Officer (Central), Govt. of India, Ministry of Labour employment, Kendriya Shram Sadan, R.K. Mission road Birubari, Guwahati-781016, Assam.


(जगबीर सिंह) / (Jagbir Singh)

संयुक्त महाप्रबंधक (अभि-सि)/Jt. GM(E-C)
भा.वि.प्रा., क्षेत्र.मु. उ.पू.क्षेत्र, गुवाहाटी
AAI, RHQ, NER, Guwahati.
For and on behalf of the Chairman,
Airports Authority of India

BOQ Summary Details Tender Title: Miscellaneous Civil Works in AAI Residential Colony at RHQ, NER, Guwahati 2023 24 Tender ID: 2023_AAI_165434_1

Sheet Name	Sl.No	Bidder Name	Amount	Bid Rank
BoQ1	1	Sri Kajal Das	2650350.00	L1
	2	BINOD KUMAR PRASAD	2883250.00	L2


 जगबीर सिंह
 Jagbir Singh
 सपु. म. प्र. (अभि. नित.) 23

Tender Inviting Authority: Airports Authority of India

Name of Work: "Miscellaneous Civil Works in AAI Residential Colony at RHQ, NER, Guwahati (2023-24)."

Contract No: AAI/RHQ/NER/ENGGC/Misc Civil/GHY/23-24

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Sri Kajal Das(GSTN-18AILPD0306P1Z7)		BINOD KUMAR PRASAD(GSTN-NA)	
				Rate	Amount	Rate	Amount
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	5.00	Cum	400.00	2000.00	300.00	1500.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	5.00	Cum	400.00	2000.00	300.00	1500.00
3.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	200.00	Cum	200.00	40000.00	199.00	39800.00
4.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	36.00	Cum	6500.00	234000.00	6800.00	244800.00
5.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	39.00	Cum	5800.00	226200.00	5900.00	230100.00
6.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	4.00	Cum	8000.00	32000.00	8700.00	34800.00
7.00	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	50.00	Sqm	500.00	25000.00	600.00	30000.00
8.00	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but , excluding cost of reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	16.00	Cum	8000.00	128000.00	7700.00	123200.00
9.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars	2000.00	Kg	100.00	200000.00	89.00	178000.00

जगबीर सिंह
Jagbir Singh
11.11.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Sri Kajal Das(GSTN-18AILPD0306P1Z7)		BINOD KUMAR PRASAD(GSTN-NA)	
				Rate	Amount	Rate	Amount
10.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	12.00	Cum	8000.00	96000.00	6500.00	78000.00
11.00	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand)	95.00	Sqm	900.00	85500.00	950.00	90250.00
12.00	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 30 mm thick shutters With ISI marked stainless steel butt hinges of required size Second class teak wood	26.00	Sqm	3500.00	91000.00	2700.00	70200.00
13.00	Providing and fixing to existing door frames. 30 mm thick Fiberglass Reinforced Plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF)/Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856, complete as per direction of EIC.	20.00	sqm	3500.00	70000.00	4000.00	80000.00
14.00	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Two track two panels sliding window made of (small series) frame 52 x 44 mm & sash 32 x 60 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension. (Area of window upto 1.75 sqm)	21.00	Sqm	10500.00	220500.00	7200.00	151200.00
15.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	62.00	Sqm	400.00	24800.00	550.00	34100.00
16.00	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase	310.00	Mtr	250.00	77500.00	270.00	83700.00
17.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	150.00	Mtr	200.00	30000.00	160.00	24000.00

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Sri Kajal Das(GSTN-18AILPD0306P1Z7)		BINOD KUMAR PRASAD(GSTN-NA)	
				Rate	Amount	Rate	Amount
18.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	150.00	Mtr	300.00	45000.00	260.00	39000.00
19.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 75 mm	30.00	each	100.00	3000.00	50.00	1500.00
20.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 110 mm	30.00	each	150.00	4500.00	80.00	2400.00
21.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee with door 75x75x75 mm	30.00	each	150.00	4500.00	110.00	3300.00
22.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend	30.00	each	100.00	3000.00	50.00	1500.00
23.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 110 mm bend	30.00	each	150.00	4500.00	80.00	2400.00
24.00	Providing and fixing Heat Resistant Terrace Tiles (300 mm x 300 mm x 20 mm) with SRI (solar refractive index) > 78, solar reflection > 0.70 and initial emittance > 0.75 on waterproof and sloped surface of terrace, laid on 20 mm thick cement sand mortar in the ratio of 1:4 (1 cement : 4 coarse sand) and grouting the joints with mix of white cement & marble powder in ratio of 1:1, including rubbing and polishing of the surface upto 3 cuts complete, including providing skirting upto 150 mm height along the parapet walls in the same manner	565.00	Sqm	850.00	480250.00	1480.00	836200.00
25.00	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand)	190.00	Sqm	200.00	38000.00	250.00	47500.00
26.00	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : a. 1:4 (1 cement: 4 fine sand)	470.00	sqm	250.00	117500.00	350.00	164500.00
27.00	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	380.00	Sqm	120.00	45600.00	100.00	38000.00
28.00	Supplying and stacking at site. Good earth	240.00	Cum	500.00	120000.00	120.00	28800.00
29.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-In-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	200.00	sqm	850.00	170000.00	1000.00	200000.00

जगजीत सिंह
जगबीर सिंह
Jagbir Singh
संयु. म. प्र. (अति)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Sri Kajal Das(GSTN-18AILPD0306P1Z7)		BINOD KUMAR PRASAD(GSTN-NA)	
				Rate	Amount	Rate	Amount
30.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	20.00	sqm	1500.00	30000.00	1150.00	23000.00

Total in Figures

2650350.00

2883250.00

Lowest Amount Quoted BY: Sri Kajal Das(2650350.00)

जगदीश सिंह

जगदीश सिंह / (Jagbir Singh)

10.11.23

संयुक्त महाप्रबंधक इंजी. (सिविल) / Jt. General Manager Engg. (Civil)

क्षेत्रीय मुख्यालय, उत्तर पूर्वी क्षेत्र, मुंबई-400 001, महाराष्ट्र

संयु. म. प्र. (अभि.-सि.)

Jt. GM (E-C)