

भाविप्रा/कोल्हापुर/उप.म.(अभि.-सि)/डब्ल्यू-02/2023-24/ 192
AAI/Kolhapur/Dy.GM (Engg.-C)/W-02/2023-24/ 192

दिनांक: 22/11/2023
Date: 22/11/2023

सेवा मे,
मेसर्स श्रीकृष्ण कन्स्ट्रक्शन,
गाला नंबर 9, गुरुनानक शॉपिंग सेंटर,
गुरुनानक चौक, सोलापुर, महाराष्ट्र।

To,
M/s. Shrikrishna Construction,
Gala No. 9, Gurunanak Shopping Centre,
Gurunanak Chouk, Solapur, Maharashtra.

कार्य का नाम : - सोलापुर हवाई अड्डे पर एएआई भूमि की सुरक्षा के लिए सीमा दीवार का निर्माण।
Name of Work: Construction of Boundary Wall for Protection to AAI Land at Solapur Airport.

संदर्भ:- दिनांक 02/11/2023 को खोला गया आपका ई-टेंडर 2023_AAI_167233_1 (वित्तीय लिफाफा)।
Ref: Your e-tender no. 2023_AAI_167233_1 (Financial bid) opened on 02/11/2023.

महोदय/Sir,


1. उपरोक्त कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दर पर कुल रु. 2,79,70,353.00 (रु. दो करोड़ उनासी लाख सत्तर हजार तीन सौ तिरपन, मात्र) (GST के बगैर) पर स्वीकृत की जाती है जो की निविदा में रखी गयी अनुमानित लागत रु. 4,37,93,000/- (रु. चार करोड़ सैंतीस लाख तिरानबे हजार, मात्र) से 36.13% नीचे है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 2,79,70,353.00 (Rs. Two Crore Seventy-Nine Lakhs Seventy Thousand Three Hundred & Fifty-Three, only) (Excluding GST) which is 36.13% below the estimated cost put to tender of Rs. 4,37,93,000/- (Rs. Four Crore Thirty-Seven Lakhs & Ninety-Three Thousand, only).

2. उप महाप्रबंधक (इंजी.-सिविल), भारतीय विमानपत्तन प्राधिकरण, सोलापुर विमानक्षेत्र, सोलापुर कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 07/12/2023 तक उप महाप्रबंधक (इंजी.-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 300/- (रु. तीन सौ मात्र) के नोन-ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Deputy General Manager (Engg.- Civil), Airports Authority of India, Solapur Airport, Solapur shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Dy. General Manager (Engg.- Civil), AAI, Kolhapur Airport by 07/12/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

3. इस निविदा के साथ मांगी गयी अग्रिम धन राशि रु. 8,75,860.00/- (रु. आठ लाख पचहत्तर हजार आठ सौ साठ, मात्र) थी जो की आपके मूल खाते में प्राप्त हो जावेगी। कृपया, प्रतिभूति निक्षेप राशि रु. 27,97,035.00/- (रु. सत्ताईस लाख सत्तानबे हजार और पैंतीस, मात्र) इस पत्र के निर्गत दिनांक से दस


22/11/23

दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त 1A पृष्ठ क्रमांक GCC-16 के अनुसार की जाएगी।

The earnest money deposit of Rs. 8,75,860.00 (Rs. Eight Lakh Seventy-Five Thousand Eight Hundred and Sixty Only) will be refunded back to your original account. Please deposit Rs. 27,97,035.00/- (Rupees Twenty-Seven Lakh Ninety-Seven Thousand & Thirty-Five only), towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per condition of GCC Clause no. 1A at page 16 of GCC of tender document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

5. आपको निर्देश दिया जाता है कि आप तुरंत उप महाप्रबंधक (इंजी-सिविल), भाविप्रा, सोलापुर विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय 09 (नौ) महीना है जोकि दिनांक 02/12/2023 से गिना जायेगा।

You are also directed to contact Deputy General Manager (Engg.-Civil), AAI, Solapur Airport immediately who will arrange to hand over site to you. Please note that, the time allowed for carrying out the work is 09 (Nine) Months which shall be reckoned from the date 02/12/2023.

6. इस ठेके के संबंध में आगे की कोई भी पत्राचार उप महाप्रबंधक (इंजी-सिविल), भाविप्रा, सोलापुर विमानक्षेत्र, सोलापुर 413224 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Deputy General Manager (Engg.-Civil), AAI, Solapur Airport, Solapur-413224.

7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall form part of contract.

8. उपरोक्त कार्य के लिए त्रुटि दायित्व की अवधि 12 (बारह) महीने होगी।

The defects liability period for the above-mentioned work is 12 (Twelve) months.

9. यदि ठेकेदार को किसी भी सुरक्षा नियम का उल्लंघन करते हुए पाया जाता है, तो वह ब्लैक लिस्टेड हो जाएगा और अन्य कानूनी कार्यवाही के लिए जिम्मेदार होगा।

If Contractor is found violate any of Security Regulations, he shall be Black listed and will be responsible subjected to other Legal Proceedings.


DGMG
22/11/23


10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा.

In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully



उप महाप्रबंधक (अभि-सिविल),

भाविप्रा, कोल्हापुर हवाईअड्डा, कोल्हापुर

कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

Deputy General Manager (Engg.-Civil),

AAI, Kolhapur Airport, Kolhapur

For & on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <SM (Engg.-Civil), AAI, Kolhapur Airport >


Name of Work: <Construction of Boundary Wall for Protection to AAI Land at Solapur Airport>

Contract No: <2023_AAI_167233_1>

Name of the Bidder/ Bidding Firm / Company :		PRICE SCHEDULE									
Shrikrishna Construction		(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)									
NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	NUMBER #	NUMBER #	NUMBER #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words			
1	2	3	4	5	12	7	8	10			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	item1	2613.000	cum	INR	120.00	313560.00	INR Three Lakh Thirteen Thousand Five Hundred & Sixty Only			
2	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil end disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	item2	955.000	cum	INR	280.00	267400.00	INR Two Lakh Sixty Seven Thousand Four Hundred Only			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	item3	270.000	cum	INR	4000.00	1080000.00	INR Ten Lakh Eighty Thousand Only			

22/11/23
22/11/23
22/11/2322/11/23
22/11/23
22/11/23

4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	item4	600.000 cum	INR	5000.00	3000000.00	INR Thirty Lakh Only
5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	item5	98.000 cum	INR	6500.00	637000.00	INR Six Lakh Thirty Seven Thousand Only
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	item6	130.000 cum	INR	6500.00	845000.00	INR Eight Lakh Forty Five Thousand Only
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	item7	56790.000 kg	INR	70.00	3975300.00	INR Thirty Nine Lakh Seventy Five Thousand Three Hundred Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	item8	17251.000 kg	INR	70.00	1207570.00	INR Twelve Lakh Seven Thousand Five Hundred & Seventy Only
9	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	item9	1606.000 sqm	INR	180.00	289080.00	INR Two Lakh Eighty Nine Thousand & Eighty Only
10	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	item10	1653.000 sqm	INR	450.00	743850.00	INR Seven Lakh Forty Three Thousand Eight Hundred & Fifty Only
11	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	item11	3240.000 sqm	INR	550.00	1782000.00	INR Seventeen Lakh Eighty Two Thousand Only
12	Brick work with common burnt clay F.P.S. (non modular) brick of class designation 3.5 in foundation and plinth in : Cement Mortar 1:6 (1 cement : 6 coarse sand).	item12	949.000 cum	INR	5400.00	5124600.00	INR Fifty One Lakh Twenty Four Thousand Six Hundred Only


 22/11/23
 22/11/23


 22/11/23

13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	item13	710.000	cum	INR	5400.00	3834000.00	INR Thirty Eight Lakh Thirty Four Thousand Only
14	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	item14	15150.000	sqm	INR	142.00	2151300.00	INR Twenty One Lakh Fifty One Thousand Three Hundred Only
15	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	item15	10416.000	kg	INR	75.00	781200.00	INR Seven Lakh Eighty One Thousand Two Hundred Only
16	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	item16	523.000	sqm	INR	80.00	41840.00	INR Forty One Thousand Eight Hundred & Forty Only
17	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre operable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	item17	16150.000	sqm	INR	65.00	1049750.00	INR Ten Lakh Forty Nine Thousand Seven Hundred & Fifty Only
18	Pointing/Embossing AAI logo with cement mortar 1:3 (1 cement : 3 fine sand) projecting out by 12 mm raised on cement plastered walls as per drawing and directions of Engineer-in-Charge.	item18	2740.000	meter	INR	180.00	493200.00	INR Four Lakh Ninety Three Thousand Two Hundred Only
19	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	item19	100.000	nos	INR	1000.00	100000.00	INR One Lakh Only
20	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	item20	20.000	cum	INR	5000.00	100000.00	INR One Lakh Only
21		item21	20.000	cum	INR	800.00	16000.00	INR Sixteen Thousand Only

Handwritten signature and date: 25/08/23

Handwritten signature

22	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar	Item 22	15.000	cum	INR	1500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
23	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	Item 23	870.000	kg	INR	1.90	1653.00	INR One Thousand Six Hundred & Fifty Three Only
24	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.	Item 24	1035.000	meter	INR	130.00	134550.00	INR One Lakh Thirty Four Thousand Five Hundred & Fifty Only
25	Credit for taking away of PVC connections, pipes and fittings etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Item 25	200.000	kg	INR	15.00	-3000.00	INR Minus Three Thousand Only
26	Credit for taking away of aluminium sections and fittings like tee, channels, plates, etc. received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Item 26	200.000	kg	INR	15.00	-3000.00	INR Minus Three Thousand Only
27	Credit for taking away of M.S pipes, plates, angles etc. received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Item 27	1000.000	kg	INR	15.00	-15000.00	INR Minus Fifteen Thousand Only
Total in Figures							27970353.00	INR Two Crore Seventy Nine Lakh Seventy Thousand Three Hundred & Fifty Three Only
Quoted Rate in Words							INR Two Crore Seventy Nine Lakh Seventy Thousand Three Hundred & Fifty Three Only	

22/11/2023
S.M (C-2)
22/11/2023
22/11/2023