



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.स. : भाविप्रा/वारा/अभि/ बैगेज/डब्लू-86/1469-78/9004/3
Ref. No. AAI/VNS/ENGG/Baggage/W-86/...

दिनांक: 24.11.2023
Date: 24.11.2023

सेवा में,

मेसर्स राहुल कन्स्ट्रक्शन
401, टावर डी-1, के.एल.जे. प्लेटिनम प्लस
सेक्टर-77, फरिदाबाद-121004

M/s Rahul Constructions,
Flat No. 401, Tower D-1, KLJ Platinum Plus,
Sector-77, Faridabad-121004

विषय : एलबीएसआई हवाई अड्डे, वाराणसी पर बैगेज चेक टेबल, स्टैम्पिंग बोर्डिंग पास टेबल और फ्रिस्किंग स्टैंड के साथ-साथ ग्लास गेट के साथ ग्लास पार्टिशन का प्रावधान, मौजूदा स्टील रेलिंग पर मजबूत ग्लास लगाने के साथ-साथ फ्रेंजिबल बर्ड वॉच टॉवर और परिधि सड़क से उनके दृष्टिकोण मार्ग का प्रावधान।

Providing Baggage check table, stamping boarding pass table and frisking stand along with provision of Glass partition with glass gate contained in, fixing of toughened glass over existing steel railings as well as provision of frangible bird watch tower and their approach pathway from perimeter road at LBSI Airport, Varanasi (Tender ID : 2023_AAI_169054_1)

संदर्भ : ई-निविदा खुलने की तिथि : 06.11.2023

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपये 56,73,280.00 (रुपया छप्पन लाख तीहत्तर हजार दो सौ अस्सी मात्र) (जी.एस.टी. रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपये 83.46 लाख (जी.एस.टी. रहित) से 32.02% (बत्तीस दशमलव शून्य दो प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs.56,73,280.00 (Rupees Fifty Six Lakhs Seventy Three Thousand Two Hundred Eighty only) (excluding GST) which is 32.02% (Thirty Two point Zero Two percent) below to the estimated cost put to tender of Rs. 83.46 lakhs (excluding GST).

- 2) उपमहाप्रबन्धक (अभि0-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा सहायक महाप्रबन्धक अभि(सिविल) एवं प्रबन्धक (अभि0-सि0), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 19.12.2023 तक सहा0 महाप्रबन्धक (अभि0-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The DGM(Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and AGM (E-C)/Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the AGM(Engg-Civil) by 19.12.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपये 1,66,920.00 (रुपया एक लाख छह हजार नौ सौ बीस मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 4,00,408.00 (रुपया चार लाख चार हजार आठ मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

The earnest money amount of Rs. 1,66,920.00 (Rupees One Lakh Twenty Five Thousand Seven Hundred Sixty only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs.4,00,408.00 (Rupees Four Lakhs Four Hundred Eight only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

शेष पृष्ठ 2 पर....

014

-2-

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से प्रबन्धक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौपने की व्यवस्था करेंगे।
You are also directed to contact the Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 06(छः) महीने हैं जो कि दिनांक 04.12.2023 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 06 (Six) months and the same shall be reckoned from 04.12.2023
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः उपमहाप्रबन्धक (अभि-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 06 (सिविल कार्य रु. 56,73,280.00) संलग्न है।
Schedule 'A' (total page 06) (Civil works Rs.56,73,280.00) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।

In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

भवदीय

संलग्नक- यथोपरि
Encl:- As above

(Signature)
24-11-2023
उ.म.प्र.(अभि.-सिविल),
DGM (Engg-Civil)

अध्यक्ष, भा०वि०प्रा० के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI

उप महाप्रबन्धक (अभि-सिविल)
Deputy General Manager (Engg-Civil)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. संयुक्त महाप्रबन्धक (अभि)-उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ

ब. आंतरिक-

- | | | |
|---|---|------------------------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. प्रभारी (वित्त) | : | -तदैव- |
| 3. सं.म.प्र. (अभि-विद्युत) | : | -तदैव- |
| 4. स.म.प्र. (अभि-सिविल) | : | -तदैव- |
| 5. श्री अंकुर अग्रवाल, प्रबन्धक (अभि-सिविल) | : | आवश्यक कार्यवाही हेतु। |
| 6. कार्यादेश फाईल | : | |
| अनुबन्ध | | |

विशेष कुशल
22-11-2013
उ.म.प्र.(अभि.-सिविल),

O/C

उप महाप्रबन्धक (अभि-सिविल)
Deputy General Manager (Engr-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री अंतर्राष्ट्रीय हवाई अड्डा, वाराणसी
Lal Bahadur Shastri International Airport, Varanasi

Item Rate BoQ

Tender Inviting Authority: Airports Authority of India

Name of Work: Providing Baggage check table, stamping boarding pass table and firsking stand along with provision of Glass partition with glass gate contained in, fixing of toughened glass over existing steel railings as well as provision of frangible bird watch tower and their approach pathway from perimeter road at LBSI Airport, Varanasi

Contract No: 2023_AAI_169054_1

Name of the Bidder/ Bidding Firm / Company :	RAHUL CONSTRUCTIONS						
PRICE SCHEDULE							
Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
0.1	Civil Works						
1	Fabricating, providing and fixing in position Baggage Check Table each of Size (2390 X 830X 760) mm (LXWXH) as per drawing attached at DW-1 made out by 18mm thick ISI water proof ply (MR grade) confirming to IS 303 of approved make with top, 2 sides and front end surfaces finished with 12 mm thick solid acrylic of approved make and of Colour combination as approved by Engineer-in-Charge with necessary moulding edges and interior shelves finished with 1mm thick laminate of approved make (in approved colour and shade) complete in all respect with all necessary hardwares, adhesives, tools, etc as per satisfaction of Engineer In - Charge. The rate shall be inclusive of material, transportation and loading/unloading charges, fabrication and placing at desired place at security check area at Domestic and International departures (or at places as decided by Engineer-in-Charge) of the Airport, including all taxes (but excluding GST)/levies/transportation at concerned station, etc complete in all respect.	Item1	20.00	each	111000.00	2220000.00	INR Twenty Two Lakh Twenty Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
2	Fabricating, providing and placing in position Table for stamping boarding passes of size (740 x 300 x 1000) mm as per drawing attached at DW-2, made out by 18 mm thick Boiling water proof ply (MR ply) confirming to IS 303 of approved make with complete exterior finish surface of 12 mm thick solid acrylic of approved make and of Colour combination as approved by Engineer-in-Charge with all necessary frames works, screws, hinges, bottom support, etc all complete as per drawing and direction of engineer in charge. The cost of complete work includes construction of frame work of 18 mm ply, fixing of solid acrylic with necessary moulding edges with all necessary hardwares, tools, screws, adhesives, bottom and intermediate supports, etc and placing in position as directed by the Engineer-in-Charge within the Airport Terminal Building including transportation of all materials at the Airport, etc., including all taxes (but excluding GST)/levies/transportation at concerned station, etc complete in all respect.	Item2	15.00	each	39000.00	585000.00	INR Five Lakh Eighty Five Thousand Only
3	Fabricating , providing and placing in position (1050 x 650 x 150) mm Frisking stand as per attached drawing at DW-3 made of 18 mm thick Boiling water proof ply (MR ply) confirming to IS 303 of approved make with edges as per design with top layers of surrounding four sides covered with 6 mm thick solid acrylic of approved make and of Colour combination as approved by Engineer-in-Charge and top surface with 18 mm thick black pre-polished granite having round edges duly polished fixed on board with approved adhesive keeping 3mm x 3mm recessed groove around including all hardwares, tools, adhesives, fittings, etc complete as per design, drawing and directions of Engineer-in-Charge (Mild steel/Stainless steel/other iron containing materials are not to be used as screwing/clit members in order to avoid being detected while frisking). The rate shall be inclusive of material, transportation and loading/unloading charges, fabrication and placing at desired place at security check area at Domestic and International departures (or at places as decided by Engineer-in-Charge) of the Airport, including all taxes (but excluding GST)/levies/transportation at concerned station, etc complete in all respect.	Item3	15.00	each	13000.00	195000.00	INR One Lakh Ninety Five Thousand Only
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	Item4	300.00	kg	128.00	38400.00	INR Thirty Eight Thousand Four Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
5	Supplying, installation, testing and commissioning of automatic sliding door operator of AIDO XL-C 4150 DORMAKABA or HAFELE or equivalent brand as per approved dwg. Compliant with european standards and produced according to the guidelines for power-operated doors, The track profile should be separate from the main profile for enabling reduction in vibration insulation. Operator length = 4150 mm, clear passage opening = 2100 mm, clear passage height = 2400 mm, includes micro processor controlled drive unit, with self learning mechanism, program selector with knob, motion detector, mechanical components, toothed belt, cover profile, floor guide for frameless glass (02 nos), glass clamping rail (02 nos). Body finish : standard silver anodised operator profile, with Electromechanical lock with 12 mm plain toughened frameless glass and heavy duty aluminium profile to hang automatic track for complete elevation - 2 moving panels. UPS of 750 VA shall be provided by client, which will give power backup of 20 min. Only & if the duration of power cut to the operator is more than 30 min., then separate arrangement needs to be done for the same as automatic operator requires uninterrupted stabilized power supply. Also supplying and installation of fixed partition with toughened glass 12 mm with necessary hardwares including providing small L connetors to fix the glass with the existing frame and whenever required so as to make it monolithic and reduce gaps. The above work include supplying, installation, testing and commissioning of above with necessary transportation to site, all levis and taxes but excluding GST, complete in all respect as per approved drawings and to the satisfaction of engineer-in-charge. (Note: M. S. Frame to be paid separately)	Item5	36.00	sqm	9000.00	324000.00	INR Three Lakh Twenty Four Thousand Only
6	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double acting hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc.to be paid separately).	Item6	10.00	sqm	3950.00	39500.00	INR Thirty Nine Thousand Five Hundred Only
7	Providing and fixing stainless steel fancy handle of approved make fixed with SS screws etc. complete as per direction of Engineer-in-charge. 200 mm	Item7	8.00	each	150.00	1200.00	INR One Thousand Two Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
8	Providing and fixing 12 mm thick toughened glass over existing stainless steel frames using Stainless Steel brackets over floors/SS frames complete using SS screws, fittings, brackets, etc including making necessary holes for fixing of brackets, etc complete as per satisfaction and direction of Engineer-in-Charge. The rate should include providing of materials, fabrication/installation, placing at desired location as directed by EIC, all taxes (but excluding GST)/levies/transportation, etc complete in all respect.	Item8	22.00	sqm	7800.00	171600.00	INR One Lakh Seventy One Thousand Six Hundred Only
9	Fabricating, providing and fixing in position Security Restricted Items (SRI) Box with its stand having following specifications: a) SRI Box having size (600 x 600 x 900) mm (LXWXH) (as per drawing attached DW-4 (a)) made out by 12 mm thick solid acrylic (LG Hausys, Dupont, Merino Hanex or approved equivalent) of transparent in nature and approved by Engineer-in-Charge with necessary moulding edges with vertical sides fixed to each other firmly using necessary adhesives/SS bolts/SS screws and top surface (openable from one side using provided CP Brass Butt hinge at the other side) consisting of locking arrangement using CP brass cupboard lock and small opening at top cover, complete in all respect with all necessary hardwares, adhesives, tools, screws/bolts, clothes, etc as per satisfaction of Engineer In - Charge. b) Stand having size of (700 x 700 x 100) mm (LxWxH) (as per drawing attached DW-4 (b)) made out by 18 mm thick Boiling water proof ply (MR ply) confirming to IS 303 of approved make (Merino, Century, greenply or approved equivalent) as frame and top surface of vertical sides finished with 1mm thick laminate of approved make (merino/ green lam/century or equivalent in approved colour and shade) and top surface consisting of 18 mm thick black pre-polished granite firmly fixed to frame using approved adhesives.	Item9	4.00	each	23000.00	92000.00	INR Ninety Two Thousand Only
10	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	Item10	92.00	cum	105.00	9660.00	INR Nine Thousand Six Hundred & Sixty Only
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Item11	42.00	cum	5000.00	210000.00	INR Two Lakh Ten Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
12	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Item12	14.00	cum	6000.00	84000.00	INR Eighty Four Thousand Only
13	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	Item13	59.00	sqm	200.00	11800.00	INR Eleven Thousand Eight Hundred Only
14	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Item14	92.00	cum	150.00	13800.00	INR Thirteen Thousand Eight Hundred Only
15	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge	Item15	353.00	sqm	740.00	261220.00	INR Two Lakh Sixty One Thousand Two Hundred & Twenty Only
16	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Item16	17.00	sqm	710.00	12070.00	INR Twelve Thousand & Seventy Only
17	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Item17	6.00	sqm	750.00	4500.00	INR Four Thousand Five Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
18	Supplying, Fabricating and Erection of Pre-Fabricated PUF-Panelled frangible Bird watch tower of size 1.8 m(L)X 1.8 m(B)X2.4(H) M (Dimensions are external dimensions, 2.4M height - lower side of the roof to bottom of the flooring) with 2.7 meter height at the centre and 1 nos. main door of size 0.9m(B)X1.8m(H) made of sand witch panel of Wall and Roof 50mm thick with both sides 2mm thick FRP/ GRP sheet at the outer sides and middle part consists of PU foam of density 40 kg/m ³ , 3 nos of UPVC track sliding glass window size 0.9X 0.90 with loading, transporting, unloading and erection at site of work in all respect and complete. The prefabricated frangible hut shall consist of following - a) Provision of one number of main door with necessary locking arrangement. b) The roof is provided with 3° to 5° slope to enable easy drain of rain water. c) The PUF Panel shall be CFC free, Self-Extinguishing, and Fire Retardant having density of 40 kg /cum (± 2Kg tolerance limit) d) All necessary door fittings such as door hinges, handles and tower bolts shall also to be provided. e) The cost of the hut is inclusive of design, vetting of design by Govt. Engg. College, fragility certificate form manufacturer, fabrication, transportation, all taxes excluding GST and commissioning of the hut at the proposed site as per drawing and specification over a Cement Concrete platform.	Item18	5.00	each	278028.00	1390140.00	INR Thirteen Lakh Ninety Thousand One Hundred & Forty Only
19	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). Note: The design of white and red squares (2 feet X 2 feet) as per ICAO guidelines and direction of E-I-C.	Item19	84.00	sqm	100.00	8400.00	INR Eight Thousand Four Hundred Only
20	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Item20	10.00	sqm	99.00	990.00	INR Nine Hundred & Ninety Only
Total in Figures						5673280.00	INR Fifty Six Lakh Seventy Three Thousand Two Hundred & Eighty Only
Quoted Rate in Words		INR Fifty Six Lakh Seventy Three Thousand Two Hundred & Eighty Only					

Signature Not Verified

Digitally signed by VINOD KUMAR PANDEY

Date: .. :: IST

Location: eProcurement System for Central PSUs



26.11.2023
 Deputy General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री अंतर्राष्ट्रीय हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri International Airport, Varanasi