

Government eProcurement System Created By: Simerdeep Singh Created Date/Time: 02-Nov-2023 11:25 AM Tender Title: Special Repair Work of Apron at Srinagar International Airport Tender ID: 2023_AAI_169306_1

Tender Inviting Authority: Senor Manager (Engg-C), Airports Authority of India Srinagar International Airport Srinagar.

Name of Work: Special Repair Work of Apron at Srinagar International Airport

Contract No:

SCHEDULE OF WORK / ITEM(S)

SI.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	VINAYAK TECHNICO(GSTN-08AEXPB7330M1ZZ)		M/S KUCHAY CONSTRUCTION CORPORATION(GSTN-		BAKHTAWAR AHMAD RATHER(GSTN-NA)		M/S LUCKY BUILDERS(GSTN-NA)	
					Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1.00	Supplying of self levelling three component modified Elastomeric concrete compound (of preferred make mentioned in tender document) at site as per specifications and directions of Engineer-in-charge. The one pack of 10 kg Elastomeric concrete shall consist of three components viz. Component A - 3.0 to 3.6 Kg, Component B - 1.50 to 0.9 Kg, Component C (Aggregates) - 5.5 Kg.	5980.00	Kg		450.00	2691000.00	383.00	2290340.00	385.00	2302300.00	430.00	2571400.00
2.00	Supplying of primer (of preferred make mentioned in tender document) for Elastomeric compound at site as per specifications and directions of Engineer-in-charge.	140.00	Litre		400.00	56000.00	480.00	67200.00	320.00	44800.00	530.00	74200.00
3.00	Laying of self levelling modified Elastomeric concrete compound (of preferred make mentioned in tender document) in damaged portion of rigid pavement / potholes / surface spalls / cracks including demarcation, cutting, chipping the pavement up to required size by using mechanical cutters, side locking on the vertical face, preparing the area for application by removing all loose gravel, dirt, oil, grease and foreign matter, applying the primer, masking around the patch / crack / spall to avoid accidental spillage of compound, pouring the compound, finishing & texturing complete as per specifications and directions of Engineer-in-charge with required machines & tools. Note: The rate quoted shall be exclusive of cost of material which shall be paid separately in Item no. 1 and 2 respectively.	5980.00	Kg		80.00	478400.00	218.00	1303640.00	110.00	657800.00	150.00	897000.00
4.00	Repairing of existing expansion joints including cutting the edges in line with mechanical cutters as per requirement, removing loose/dust particles, cleaning the expansion joints, wherever required, providing & filling with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990) of preferred make mentioned in tender document including painting the sides of slab / joint with approved primer, providing and inserting the backup material of 30 mm dia conforming to IS code and of approved make in the joint to receive the specified sealing compound, providing and applying bond breaking tape on top edges of joint to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant, laying of polysulphide sealant, making groove on top of sealant / joint with adequate tool, finishing & texturing etc. all complete as per specifications and directions of Engineer-in-charge.	467500.00	Cucm		.80	374000.00	.81	378675.00	1.65	771375.00	1.00	467500.00

L1 Amount	L1 Vendor
2290340.00	M/S KUCHAY CONSTRUCTION CORPORATION
44800.00	BAKHTAWAR AHMAD RATHER
478400.00	VINAYAK TECHNICO
374000.00	VINAYAK TECHNICO

5.00	Repairing of existing construction / dummy joints including cutting the edges in line with mechanical cutters as per requirement, removing loose/dust particles, cleaning the construction / dummy joints, wherever required, providing & filling with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990) of preferred make mentioned in tender document including painting the sides of slab / joint with approved primer, providing and inserting the backup material of 12 mm dia conforming to IS code and of approved make in the joint to receive the specified sealing compound, providing and applying bond breaking tape on top edges of joint to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant, laying of polysulphide sealant, making groove on top of sealant / joint with adequate tool, finishing & texturing etc. all complete as per specifications and directions of Engineer-in-charge.	106000.00	Cum
6.00	Repairing of existing surface cracks in concrete panels including grinding / cutting the edges in line with mechanical cutters as per requirement to make a groove 25 mm wide and 20 mm deep, removing loose/dust particles, cleaning the groove, wherever required, providing & filling with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990) of preferred make mentioned in tender document including painting the sides of groove / crack with approved primer, providing and inserting the suitable backup material conforming to IS code and of approved make, providing and applying bond breaking tape on top edges of groove / crack to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant and filling the groove / crack with the specified sealing compound, finishing & texturing etc. all complete as per specifications and directions of Engineer-in-charge.	180.00	Mtr
7.00	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	2.00	Cum
8.10	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign material etc. and lining out complete. New work (Two or more coats)	34.00	Sqm
8.20	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign material etc. and lining out complete. Old work (One or more coats)	100.00	Sqm

.60	63600.00	.91	96460.00	3.00	318000.00	1.00	106000.00
600.00	108000.00	409.00	73620.00	100.00	18000.00	500.00	90000.00
9000.00	18000.00	3900.00	7800.00	8000.00	16000.00	6000.00	12000.00
150.00	5100.00	182.00	6188.00	150.00	5100.00	100.00	3400.00
100.00	10000.00	110.00	11000.00	100.00	10000.00	100.00	10000.00

63600.00	VINAYAK TECHNICO
18000.00	BAKHTAWA R AHMAD RATHER
7800.00	M/S KUCHAY CONSTRUCTION CORPORATION
3400.00	M/S LUCKY BUILDERS
10000.00	BAKHTAWA R AHMAD RATHER, VINAYAK TECHNICO, M/S LUCKY BUILDERS

Total in Figures

3804100.00

4234923.00

4143375.00

4231500.00

Lowest Amount Quoted BY: VINAYAK TECHNICO(3804100.00)

BOQ Summary Details

Tender Title: Special Repair Work of Apron at Srinagar International Airport
Tender ID: 2023_AAI_169306_1

Sheet Name	Sl.No	Bidder Name	Amount	Bid Rank
BoQ1	1	VINAYAK TECHNICO	3804100.00	L1
	2	BAKHTAWAR AHMAD RATHER	4143375.00	L2
	3	M/S LUCKY BUILDERS	4231500.00	L3
	4	M/S KUCHAY CONSTRUCTION CORPORATION	4234923.00	L4

Signature Not Verified

Digitally signed by **SMERDEEP SINGH**
Date: 2023.11.06 13:06:24 IST
Location: eProcurement System for Central
PSUs