



भारतीय विमानपत्तन प्राधिकरण,
Airports Authority of India
सिविल एन्क्लेव, बरेली
Civil Enclave, Bareilly.

संख्या:-भाविप्रा/बीएलवाई/एजीएम (ई-ई)/एसआईटीसी-बी एच एस / का0आ0-08/2023-24/1029-1035 दिनांक :-07.12.2023

Ref:- AAI/BLY/AGM(E-E)/SITC-BHS/W.O-08/2023-24/1029-1035

Date :- 07.12.2023

(Through Speed Post/Email)

सेवा में /To ,

मेसर्स गैनन डनकली एंड कंपनी लि.

16ए/1, एरले स्टेट

फ्लैट सं० एन-1 (1st फ्लोर), कोलकाता,

वेस्ट बंगाल- 700026

M/s. Ganon Dunkerley & Co. Ltd.

16A/1, Earle State,

Flat No. N-1, (1st Floor), Kolkata,

West Bengal-700026

कार्य का नाम :- प्रोविजन ऑफ स्टैंडबायी अराइवल कन्वेयर एट बरेली एयरपोर्ट।

Name of Work: - Provision of Standby Arrival Conveyor at Bareilly Airport.

संदर्भ :- 1) आपका टेंडर आईडी0 (2023_AAI_170817_1) खोला गया दिनांक - 17.11.2023

Your tender ID. - (2023_AAI_170817_1) opened on dated - 17.11.2023

महोदय / Sir,

- उपरोक्त कार्य हेतु आपका आफर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताये गये मद मूल्यों पर आपका ऑफर कुल रुपये **34,90,000/-** (रुपये चौतीस लाख नब्बे हजार केवल) (जी0एस0टी0 अतिरिक्त) है। जोकि टैण्डर की अनुमानित/न्यायसंगत राशि **रु0 35,54,000/-** से **01.80** प्रतिशत कम है।

Your offer for the work mentioned above work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs **34,90,000/-** (Rupees. Thirty-Four lakh Ninety Thousand Only) (GST Extra). Which is 01.80% below the justified cost put to tender of Rs. **35,54,000/-**

- सहा0 महा0 प्रबन्धक (इंजी-विद्युत) भाविप्रा, सिविल एन्क्लेव, बरेली कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामों पर हस्ताक्षर करने के लिए दिनांक 25.12.2023 तक अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित हो तथा करारनामों को पूरा करें। ठेके का करारनामा 100/-रुपये के नोनज्यूडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा, तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asstt. General Manager Engg. (Elect.), AAI, Civil Enclave, Bareilly - 243122, shall be the Engineer in charge of the work. You are requested to attend the office of undersigned by 25-12-2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.

- आपके इ-टेंडर के साथ प्राप्त धरोहर राशि रुपये 71,080/- ठेके के सामान्य भातों पर दी गयी भात 1(A) के अनुसार जमानत राशि में परिवर्तित कर दी जायेगी। कृपया इस पत्र के जारी होने के 15 दिनों के

जारी/Contd...

07.12.2023
AGM (EE)

(1/5)

भीतर सिक्यूरिटी डिपोजिट के लिए रुपये 3,55,400/- (रु. तीन लाख पचपन हजार चार सौ मात्र) जमा कर दे, अन्यथा ठेके के करारनामे में दी भार्त के अनुसार इतनी राशि आपके रनिंग बिलों से काट ली जाएगी।

The earnest money amount of Rs. 71,080/- received along with your e-tender will be treated and converted as part of Security Deposit as per GCC Clause 1(A) of the contract document. Please deposit Rs 3,49,000/- (Rupees Three-Lakh Fourty-Nine Thousand Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per condition of the contract.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (रेगुलेशन एवं अबोलिशन) एवं न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अब तक के संशोधन के साथ अनुपालन करें) ।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments with upto date amendments.

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एन्क्लेव, बरेली से मिलें वह आपको साईट सौपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का समय 90 दिन है जोकि दिनांक 12.12.2023 से गिना जाएगा।

You are also directed to contact Manager Engg. (E), AAI, Civil Enclave, Bareilly immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be 90 days which shall be reckoned from dated 12.12.2023.

6. इस ठेके के संबध में आगे का कोई भी पत्राचार सहा0 महाप्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एन्क्लेव, बरेली, . 243122 उत्तर प्रदेश के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Asstt. Gen.Manager Engg. (E), AAI, Civil Enclave, Bareilly, - 243122,U.P.

7. उक्त कार्य का त्रुटि दायित्व अवधि 12 (बारह) महीने होगी ।

The defects liability period of the contract is 12 (Twelve) months.


8. कृपया पावती भेजे।

Please acknowledge the receipts

नोट : हिंदी या अंग्रेजी संस्करण में अंतर या अस्पष्टता के मामले में अंग्रेजी संस्करण मान्य होगा

Note : In case of difference or amguity in Hindi or English Version, the English version will prevail.

भवदीय / Your's Faithfully,


07.12.2023

सहायक महा प्रबन्धक (अभि.-विधुत),
Asstt. General Manager Engg.(Elect.),

कृते तथा और से अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India.

सिविल एन्क्लेव बरेली-243122

Civil Enclave, Bareilly -24312

संलग्न / Enclosed – शेडयूल ऑफ क्वान्टटी (3 पेज) / SOQ (3 Pages) Schedule "A"

जारी / Contd...

SCHEDULE OF QUANTITY

Name Of Work:- Provision of Standby Arrival Conveyor at Bareilly Airport.


Sr. No.	Descriptions of Items	No. of Qty	Units	Rate(Without GST)	Amount
	SH:- SITC of Arrival Conveyor System				
1	Endless Slat Conveyor Design, supply, installation, testing and commissioning of heavy duty endless slat type Arrival Baggage conveyor system having nominal useful width of 950 mm having rubber slats back in colour with smooth top of PVC/PU/Rubber, Antistatic, flame-retardant, height 450 mm from finished floor level and speed of 24-30 MPM. The Carousel shall have die cast aluminium chain block friction type suitable capacity drive unit complete with overlapping slats finished chain track unit frame work tension adjustment device stainless steel side covering (inner & outer) in the passenger area as well as in non passenger area, toe kick plate at inner & outer sides, infill, rubber slat of suitable dimension with MS Slat support having live loading capacity of 35 Kg per linear, Metre, all accessories including cutting and drilling of holes, equipment grouting, earthing, necessary wiring, connection/interconnection etc. as required for successful commissioning of Baggage Conveyor System complete as required. Length 42 mtrs approx each.	1.00	Each	2016000.00	2016000.00
2	Control panel for arrival baggage handling system Design, supply installation, testing and commissioning of cubical type, indoor floor / frame mounting, compartmentlized, fabricated out of CRCA sheet steel of thickness 2 mm duly powder coated. The panel shall be front openable & accessible. All doors shall be provided with high quality neoprene rubber gasket. Door interlock feature with incoming power supply shall be provided as per manufacturer standard. The type of protection for enclosure of the panel shall be minimum IP42 & suitable for operation on 415 volts, 3 Phase, 50 Hz AC supply i/c earthing, connections and comprising of the following component as required for arrival baggage handling system: Incoming Control Unit : 415 Volts TPN MCCBs of breaking capacity of 25KA (Ics=100Icu) with over load & short circuit protection. The rating of the MCCB shall be so selected that only about 80% of its full current carrying capacity is utilized for meeting the requirement of the	1.00	Job	250000.00	250000.00

	specific application. Incoming Protection : i) Single Phase Protection ii) Phase reversal protection iii) Under voltage protection Status Indication / display : Indication lamps (LED type) in different colour for Three phases & power ON with protection MCB. Meters (Incoming) : a) Digital type Ammeter of Required range with selector switch & Current Transformers. (b) Digital type Voltmeter with selector switch and protection MCB. MOV & switch : Necessary Surge protection System (block 70KA minimum with Neutral protection) shall be provided at control panel of conveyor with incomer switch. Outgoing for Motors (s) : 1) MPCB of suitable current rating & breaking capacity of 10 KA for each motor. 2) Soft Starter for conveyor motor. Outgoing for rolling shutter : i) 2 Pole MPCB of 10 KA & suitable current rating for each shutter motor. ii) Interlocking with conveyor & limit switches / sensors. iii) Auto-manual switches, separate push button for UP /DOWN motion Emergency stop : Provision shall be made in panel & at three other locations for each				
3	Draught Curtain SITC of draught curtain cover for the opening of conveyer belt, of suitable size fabricated with 3mm thick Nylon Rubber flaps, to be fixed by SS flat strip as per size of shutter opening etc. the opening size shall be as per dimensions /drawings approved by engg.-in-charge, complete as required (For Arrival conveyors)	2.00	Job	12000.00	24000.00
4	Rolling Shutter SITC of electrically operated rolling shutter with arrangement for auto and manual operation to suit to the opening in wall fabricated MS provided with suitable rated tubular geared single phase motor directly coupled to the shaft of the shutter, limit switch or sensor interlock with conveyer starter, complete with guide channels , wiring, earthing, painting etc. as required for the successful operation of the shutter for minimum opening size 1.5mtr (L) x 1.35mtr (W) . (For Arrival conveyors)	2.00	Job	60000.00	120000.00
	SH:II- AICMC of Arrival Conveyor System				
5	All Inclusive Comprehensive Maintenance Contract (AICMC): AICMC after DLP of two years of complete Arrival Conveyor system as mentioned under SH:I along with all its Electrical and Mechanical accessories by providing requisite man-power, all required spares, tools, consumables, preventive & corrective maintenance and technical support as specified in SCC, Technical Specification and particular specifications of operation & AICMC with complete in all respect.				

(4/5)

[Signature]
07.12.23
A.L.M (EE)

5.1	For First Year (After DLP Period of Two Years)	1.00	Job	180000.00	180000.00
5.2	For Second Year	1.00	Job	195000.00	195000.00
5.3	For Third Year	1.00	Job	215000.00	215000.00
5.4	For Forth Year	1.00	Job	235000.00	235000.00
5.5	For Fifth Year	1.00	Job	255000.00	255000.00
Total					34,90,000.00
(Rs for Thirty-Four lakh Ninety Thousand Only)					


07.12.2023

Asst. General Manager (E-E)
AAI, Civil Enclave, Bareilly