



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

भा.भा.वि.प्रा./मदुरै/इ(वि)/MDU-406/23-24

Ref: AAI/MDU/E-E/MDU-406/23-24

दि:/Date: 04/01/2024

सेवा में /To,

M/s. Akshaya Associates,
198/5, Triveni Lands,
Nagaramalai Road, Alagapuram,
Salem - 636 016.
Email: akshayaaengg@gmail.com

विषय/Sub : Shifting of CCR including provision of New CCRs and diversion of AFL cables from existing CCR hall to New service block, ATC Tower at Madurai Airport. SH: SITC of CCRs at new service block, cable laying works and its associated works - Reg.

संदर्भ/Ref: Your e-tender (Financial bid-2023 AAI 172486 1) Opened on 15.12.2023

महोदय/Dear sir(s),

- 1) Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 1,57,31,901.38 (Rupees One Crore Fifty Seven Lakh Thirty One Thousand Nine Hundred and One and Paise Thirty Eight Only)** plus applicable GST which is 27.93% below the Justified cost put to tender of Rs.2,18,27,874.00 plus applicable GST.
- 2) Asst. General Manager (Engg-Elect.), Airports Authority of India, Madurai Airport, Madurai- 625 022, shall be the Engineer-in-charge of the work.
- 3) You are requested to attend the office of the Asst. General Manager (Engg-Elect.), AAI, Madurai Airport by **12.01.2024** to sign and complete the contract agreement. The contract Agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only). The tender document (GCC-2017) shall be downloaded and signed in each page which shall form part of the agreement. The entire cost towards stamp paper, downloading and printing tender document (GCC-2017) shall be borne by the contractor.
- 4) As per relevant clause of GCC-2017, which is a part of the contract agreement, security deposit @ 10% (Ten Percent) to be submitted, which shall be released after successful completion of Defects Liability Period, which shall be **Twelve Months** from the certified date of completion for SITC works and **Six Months** for AICMC of CCRs.

Contd....2

विमानपत्तन निदेशक का कार्यालय, मदुरै हवाई अड्डा, मदुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

-2-

- 5) You are requested to comply with the provisions of Contract Labour (Regulation and abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition and Regulation) and Act 1986, Construction workers (Regulation of employment and conditions of service) Act 1996, Building and other construction workers welfare cess Act 1996 as specified in Clause-19 on Page No.50 of GCC of tender and rules of Central and State Governments.
- 6) You are also directed to contact Manager (Engg-Elect)-I, AAI, Madurai Airport immediately who will arrange to hand over the site to you.
- 7) Please note that the time allowed for carrying out the work which shall be **03 (Three) Months** for SITC works and same shall be reckoned from **13.01.2024**. Five year AICMC of CCRs which shall be start after the completion of DLP period.
- 8) Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
- 9) Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith to the undersigned within (10) ten days from the date of issue of this award letter as a token of acceptance.
- 10) This work order is allotted the number **MDU-406** which shall be quoted by you future correspondence in connection with this work Contract.
- 11) All other terms & Condition shall be as per Tender Document.

Encl: Schedule of Work

Yours faithfully,

Asst. General Manager (E-E)
For and on behalf of the Chairman
Airports Authority of India

Item Rate BoQ

Tender Inviting Authority: AIRPORTS AUTHORITY OF INDIA

Name of Work: Shifting of CCR including provision of New CCRs and diversion of AFL cables from existing CCR hall to New service block, ATC Tower at Madurai Airport. SH: SITC of CCRs at new service block, cable laying works and its associated works.

Contract No: AAI/MDU/E-E/MDU-406/NIT-17/2023-24 **Tender ID -** 2023_AAI_172486_1

Name of the Bidder/ Bidding Firm / Company : M/s. Akshaya Associates, Salem – 636 016.

PRICE SCHEDULE

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Supply, Installation, Testing and commissioning of indoor type microprocessor based, air cooled constant current regulator of Thyristor control electronic type suitable for use on 240/415 VAC: 50/60 Hz, input AC supply with below mentioned output power at 20A/6.6 amps with 5 steps variation of current output suitable for local and remote control operation with 24/48 VDC control supply complete with output current indicated on multifunction digital display, over current, over voltage, earth fault protection and earth leakage meter, positive back indication equipments relay contactor, making connection with earthing strip by providing 16sq.mm flexible copper wire etc. as required.as per specification of following rating. 50KW MPCCR at 20 Amp, Supply voltage 415 VAC tapping at 40KW	3	Job	₹ 5,52,000.00	₹ 16,56,000.00	INR Sixteen Lakh Fifty Six Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
2	Supply, Installation, Testing and commissioning of indoor type microprocessor based, air cooled constant current regulator of Thyristor control electronic type suitable for use on 240/415 VAC: 50/60 Hz, input AC supply with below mentioned output power at 20A/6.6 amps with 5 steps variation of current output suitable for local and remote control operation with 24/48 VDC control supply complete with output current indicated on multifunction digital display, over current, over voltage, earth fault protection and earth leakage meter, positive back indication equipments relay contactor, making connection with earthing strip by providing 16sq.mm flexible copper wire etc. as required.as per specification of following rating. 20KW MPCCR at 20 Amp, Supply voltage 415 VAC tapping at 15KW	3	Job	₹ 3,84,000.00	₹ 11,52,000.00	INR Eleven Lakh Fifty Two Thousand Only
3	Supply, Installation, Testing and commissioning of indoor type microprocessor based, air cooled constant current regulator of Thyristor control electronic type suitable for use on 240/415 VAC: 50/60 Hz, input AC supply with below mentioned output power at 20A/6.6 amps with 5 steps variation of current output suitable for local and remote control operation with 24/48 VDC control supply complete with output current indicated on multifunction digital display, over current, over voltage, earth fault protection and earth leakage meter, positive back indication equipments relay contactor, making connection with earthing strip by providing 16sq.mm flexible copper wire etc. as required.as per specification of following rating. 7.5KW MPCCR at 20 Amp, Supply voltage 415 VAC tapping at 4KW	1	Job	₹ 2,46,000.00	₹ 2,46,000.00	INR Two Lakh Forty Six Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
4	Supply, Installation, Testing and commissioning of indoor type microprocessor based, air cooled constant current regulator of Thyristor control electronic type suitable for use on 240/415 VAC: 50/60 Hz, input AC supply with below mentioned output power at 20A/6.6 amps with 5 steps variation of current output suitable for local and remote control operation with 24/48 VDC control supply complete with output current indicated on multifunction digital display, over current, over voltage, earth fault protection and earth leakage meter, positive back indication equipments relay contactor, making connection with earthing strip by providing 16sq.mm flexible copper wire etc. as required.as per specification of following rating. 4KW MPCCR at 4 Amp, Supply voltage 415 VAC	3	Job	₹ 1,90,000.00	₹ 5,70,000.00	INR Five Lakh Seventy Thousand Only
5	Supply of 2C X 16 sq.mm, 5KV grade, stranded copper conductor, PVC insulated and PVC sheathed, unarmoured, underground unscreened, Anti-rodent & Anti-termite treated Airfield Lighting cable generally confirming to IS 1554 Part II with upto date amendments as required.	2583	Mtr	₹ 525.00	₹ 13,56,075.00	INR Thirteen Lakh Fifty Six Thousand & Seventy Five Only
6	Supply of 6 sq.mm, 5KV grade, single core, stranded copper conductor, PVC insulated and PVC sheathed, unarmoured, underground unscreened, Anti-rodent & Anti-termite treated Airfield Lighting cable generally confirming to IS 1554 Part II with upto date amendments as required.	15498	Mtr	₹ 105.00	₹ 16,27,290.00	INR Sixteen Lakh Twenty Seven Thousand Two Hundred & Ninety Only
7	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. OD-63 mm & ID-51mm nominal	15380	Mtr	₹ 89.00	₹ 13,68,820.00	INR Thirteen Lakh Sixty Eight Thousand Eight Hundred & Twenty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
8	Supply of 16 Sq mm, 5 KV grade dry type plug and receptacle of type I , class B primary connector kit with field attachment and suitable for 5KV grade single core copper conductor,PVC insulated PVC sheathed AFL cable complete as required .	7	Set	₹ 550.00	₹ 3,850.00	INR Three Thousand Eight Hundred & Fifty Only
9	Supply of 6 Sq mm, 5 KV grade dry type plug and receptacle of type I , class B primary connector kit with field attachment and suitable for 5KV grade single core copper conductor,PVC insulated PVC sheathed AFL cable complete as required.	21	Set	₹ 470.00	₹ 9,870.00	INR Nine Thousand Eight Hundred & Seventy Only
10	Supply of XLPE insulated PVC sheathed, Armoured Aluminium conductor power cable of 1.1 KV grade of following size etc as per IS 7098 part I 1988 with uptodate amendments etc complete as required. 3.5 C X 95Sq.mm	195	Mtr	₹ 560.00	₹ 1,09,200.00	INR One Lakh Nine Thousand Two Hundred Only
11	Supply of XLPE insulated PVC sheathed, Armoured Aluminium conductor power cable of 1.1 KV grade of following size etc as per IS 7098 part I 1988 with uptodate amendments etc complete as required. 3.5 C X 35Sq.mm	4560	Mtr	₹ 245.00	₹ 11,17,200.00	INR Eleven Lakh Seventeen Thousand Two Hundred Only
12	Supply of XLPE insulated PVC sheathed, Armoured Aluminium conductor power cable of 1.1 KV grade of following size etc as per IS 7098 part I 1988 with uptodate amendments etc complete as required. 2C X 25sq.mm	720	Mtr	₹ 145.00	₹ 1,04,400.00	INR One Lakh Four Thousand Four Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
13	Supply of XLPE insulated PVC sheathed, Armoured Aluminium conductor power cable of 1.1 KV grade of following size etc as per IS 7098 part I 1988 with uptodate amendments etc complete as required. 2C X 16sq.mm	1100	Mtr	₹ 123.00	₹ 1,35,300.00	INR One Lakh Thirty Five Thousand Three Hundred Only
14	Supply, Installation, Testing and Commissioning of cubical type, floor mounted, indoor LT panel suitable for 415 V, 3 phase, 4 wire 50 Hz AC supply system, fabricated in compartmentalized design from CRCA sheet steel of 2 mm thick for frame work, doors and covers, 3 mm thick for gland plates, 7 tank process for powder coating in approved shade, having extendable type 250 A capacity TPN Aluminium bus bars of high conductivity, DMC/SMC bus bar supports, IP 42 protection, bottom base channel of MS section not less than 100 mm x 50 mm x 5 mm thick, entire panel shall have a common earth bar of suitable size at the rear with 2 Nos. earth stud, connections from main bus bar to switch gears and control wiring with 2.5sq.mm. copper wire, cable chamber and cable gland plates in top, including providing and fixing following switch gears, accessories as per tender specification complete as required. Panel should be fabricated as per the line diagram enclosed Providing Class B Surge Protector Incomer: 1) 250 A, 4 pole, 50kA (ICu=ICs) Thermomagnetic MCCB with Overload & shortcircuit protection with Extended rotary handle - 2 Nos Metering: 1) Digital multifunction meter -02 Nos. 2) 3 Nos of CTs of suitable Amps ratio with class 1 accuracy - 2 sets	1	Job	₹ 2,95,000.00	₹ 2,95,000.00	INR Two Lakh Ninety Five Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
	3) R, Y, B phase Indication LED Lamps with 3 Nos of 2A Control MCBs - 02 Sets Outgoing: 1) 200A, - 4 pole 35kA (ICu=ICs) Thermomagnetic MCCB with Overload & shortcircuit protection with Extended rotary handle - 01 No 2) 100A, - 4 pole 35kA (ICu=ICs) Thermomagnetic MCCB with Overload & shortcircuit protection with Extended rotary handle - 02 Nos 3) 63A, - 4 Pole 35KA (ICu=ICs) Thermomagnetic MCCB with Overload & shortcircuit protection with Extended rotary handle - 03 Nos 4) 32A - 2 pole, 35KA (ICu=ICs) Thermomagnetic MCCB with Overload & shortcircuit protection with Extended rotary handle - 04 Nos					

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
15	SITC of following capacity Automatic Transfer Switch with Enclosure & UV/ OV phase sequence, single phasing protection. Provision of terminal shrouds, Phase Barriers & Source Separator. 200A, - 4 pole ATS Switch with Enclosure & ATS controller (with provision for priority setting of source, three mode operation: Auto,OFF,Manual) - 03 Nos	3	Job	₹ 68,400.00	₹ 2,05,200.00	INR Two Lakh Five Thousand Two Hundred Only
16	SITC of following capacity Automatic Transfer Switch with Enclosure & UV/ OV phase sequence, single phasing protection. Provision of terminal shrouds, Phase Barriers & Source Separator. 125A, - 4 pole ATS Switch with Enclosure & ATS controller (with provision for priority setting of source, three mode operation: Auto,OFF,Manual) - 09 Nos	9	Job	₹ 57,200.00	₹ 5,14,800.00	INR Five Lakh Fourteen Thousand Eight Hundred Only
17	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. (750 mm width X 62.5 mm depth X 2.0 mm thickness)	66	Mtr	₹ 2,900.00	₹ 1,91,400.00	INR One Lakh Ninety One Thousand Four Hundred Only
18	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. (450 mm width X 62.5 mm depth X 2.0 mm thickness)	102	Mtr	₹ 1,970.00	₹ 2,00,940.00	INR Two Lakh Nine Hundred & Forty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
19	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. (300 mm width X 62.5 mm depth X 2.0 mm thickness)	30	Mtr	₹ 1,600.00	₹ 48,000.00	INR Forty Eight Thousand Only
20	Making Field connections by crimping following sizes of plug & receptacle with the existing PVC copper conductor ,PVC insulated,PVC sheathed cable including filling the gap with water sealent material appplying HT insulation tape ,over which PVC tape etc as required 16 Sqmm	7	Set	₹ 200.00	₹ 1,400.00	INR One Thousand Four Hundred Only
21	Making Field connections by crimping following sizes of plug & receptacle with the existing PVC copper conductor ,PVC insulated,PVC sheathed cable including filling the gap with water sealent material appplying HT insulation tape ,over which PVC tape etc as required 6 Sqmm	21	Set	₹ 200.00	₹ 4,200.00	INR Four Thousand Two Hundred Only
22	Supplying and making end termination with brass compression gland aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required. 3.5C X 95Sq.mm	18	Set	₹ 1,200.00	₹ 21,600.00	INR Twenty One Thousand Six Hundred Only
23	Supplying and making end termination with brass compression gland aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required. 3.5C X 35Sq.mm	18	Set	₹ 650.00	₹ 11,700.00	INR Eleven Thousand Seven Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
24	Supplying and making end termination with brass compression gland aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required. 2C X 25Sq.mm	36	Set	₹ 400.00	₹ 14,400.00	INR Fourteen Thousand Four Hundred Only
25	Supplying and making end termination with brass compression gland aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required. 2C X 16Sq.mm	2	Set	₹ 320.00	₹ 640.00	INR Six Hundred & Forty Only
26	Laying of 63 mm dia (OD-63mm & ID-51 mm nominal) DWC HDPE pipe/ GI Pipe direct in ground with depth as specified in the Technical Specification below ground level in all type of soil/hard rock/gravel/bitumen road including excavation and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	15380	Mtr	₹ 123.00	₹ 18,91,740.00	INR Eighteen Lakh Ninety One Thousand Seven Hundred & Forty Only
27	Laying of one number PVC insulated and PVC sheathed XLPE power cable of 1.1 KV grade / 5KV grade single core/two core AFL cable of size not exceeding 35Sqmm in the existing RCC/ HUME/METAL/GI/HDPE/DWC pipe etc. complete as required.	22940	Mtr	₹ 25.00	₹ 5,73,500.00	INR Five Lakh Seventy Three Thousand Five Hundred Only
28	Laying of One number PVC insulated and PVC sheathed XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Upto 35 sq.mm	552	Mtr	₹ 25.00	₹ 13,800.00	INR Thirteen Thousand Eight Hundred Only
29	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1KV grade of following size on cable tray as required. Upto 35Sq.mm clamped with 1mm thick saddle.	1080	Mtr	₹ 45.00	₹ 48,600.00	INR Forty Eight Thousand Six Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
30	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1KV grade of following size on cable tray as required. Above 35Sq.mm and Upto 95 Sq.mm clamped with 25X3mm MS flat clamp.	195	Mtr	₹ 80.00	₹ 15,600.00	INR Fifteen Thousand Six Hundred Only
31	Earthing with copper earth plate 600mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. (but without charcoal/coke and Salt) as required.	4	Set	₹ 13,500.00	₹ 54,000.00	INR Fifty Four Thousand Only
32	Extra for using charcoal and salt for copper plate earth electrode as required.	4	Set	₹ 3,500.00	₹ 14,000.00	INR Fourteen Thousand Only
33	Providing and fixing 25 mm X 5 mm copper strip in 40mm dia G.I pipe from earth electrode as required.	48	Mtr	₹ 1,250.00	₹ 60,000.00	INR Sixty Thousand Only
34	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc.as required.	50	Mtr	₹ 1,100.00	₹ 55,000.00	INR Fifty Five Thousand Only
35	Providing and fixing 6SWG dia GI wire on surface or in recess for loop earthing along with existing surface/recessed conduit/submain wiring/cable as required.	24716	Mtr	₹ 27.00	₹ 6,67,332.00	INR Six Lakh Sixty Seven Thousand Three Hundred & Thirty Two Only
36	SITC of Fire siren 5Km vertical single mounting VST-500, 400/440 V complete as required including providing suitable Three phase contactor with enclosure for controlling the ON/OFF using ALCMS.	1	Job	₹ 74,200.00	₹ 74,200.00	INR Seventy Four Thousand Two Hundred Only
37	SITC of Gang Bell complete as required.	1	Job	₹ 2,500.00	₹ 2,500.00	INR Two Thousand Five Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
38	SITC of single phase contactor with suitable enclosure for operating Gang Bell including cable termination etc complete as required.	1	Job	₹ 2,500.00	₹ 2,500.00	INR Two Thousand Five Hundred Only
39	Supply of CI Transformer housing box water tight, round shape of outside dia 330mm height 450mm made of 10mm thick all round except on top surface which is 15mm thick having a clear opening of 220mm at the top surface and 6Nos. M10 tapped holes at the hole centre of 260mm to receive light fittings base plate and blots. The box shall have two clear holes opposite as per the site requirement at periphery centre at 75mm above bottom surface and suitable receive 50mm dia B class GI pipe and check nuts and also have a clear hole on the same side, centre at 100mm above between two hole centre and suitable to receive 15mm dia B class G.I pipes and check nuts. The box shall have two earth bolts of M 10 X 30mm inside near the hole (100mm above bottom surface) as per drawing as required. (Double hole).	12	Nos	₹ 8,500.00	₹ 1,02,000.00	INR One Lakh Two Thousand Only
40	Installation of 450mm CI transformer housing box by making suitable size pit and fixing the same with 1:2:4 concrete along the sides, plastering, finishing, etc. complete as required.	12	Nos	₹ 2,500.00	₹ 30,000.00	INR Thirty Thousand Only
41	Supply & Fixing of 6mm thick M.S. powder coated cover plate suitable for 330mm dia CI transformer housing box having 6nos of M10 tapped holes. Including Providing rubber gaskets suitable for 330mm dia CI transformer housing box.	12	NOs	₹ 1,500.00	₹ 18,000.00	INR Eighteen Thousand Only
42	Supply of series isolating transformer of rating 200W, 20A/6.6A of 5KV grade suitable for Runway light fittings etc as per particular specifications.	3	Nos	₹ 5,500.00	₹ 16,500.00	INR Sixteen Thousand Five Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
43	Supply of series isolating transformer of rating 200W, 6.6A/6.6A of 5KV grade suitable for Runway light fittings etc as per particular specifications.	6	Nos	₹ 5,750.00	₹ 34,500.00	INR Thirty Four Thousand Five Hundred Only
44	Supply of series isolating transformer of rating 15W, 6.6A/6.6A of 5KV grade suitable for Runway light fittings etc as per particular specifications.	3	Nos	₹ 3,200.00	₹ 9,600.00	INR Nine Thousand Six Hundred Only
45	Providing and fixing AFL lamps suitable for the each GLF circuit including providing metal box (for fixing lamp holder), Lamp, Lamp Holder, connector, 0.5 mtr Male secondary lead, 2C X 2.5 sq.mm flexible cable, 20mm dia GI Pipe along with accessories in recessed condition etc. complete as required. for indicating the status of the GLF circuit	12	Job	₹ 3,500.00	₹ 42,000.00	INR Forty Two Thousand Only
46	Shifting of CCRs from existing CCR hall to new CCR hall at service block including transportation, installation & commissioning of the same at the new location.	4	Job	₹ 10,000.00	₹ 40,000.00	INR Forty Thousand Only
47	All inclusive Comprehensive Maintenance Contract of 10 Nos Microprocessor based Constant Current Regulators (CCRs) which includes repair & replacement of all faulty parts of CCRs and shall have periodic Maintenance every quarterly (4 times in one year) 1 st Year (After Defects liability Period) 5 % of (item No.1 + item No.2 + item No.3 + item No.4)	1	Job	₹ 1,81,200.00	₹ 1,81,200.00	INR One Lakh Eighty One Thousand Two Hundred Only
48	All inclusive Comprehensive Maintenance Contract of 10 Nos Microprocessor based Constant Current Regulators (CCRs) which includes repair & replacement of all faulty parts of CCRs and shall have periodic Maintenance every quarterly (4 times in one year) 2nd Year (After Defects liability Period) (5% escalation on first year cost of item no.47)	1	Job	₹ 1,90,260.00	₹ 1,90,260.00	INR One Lakh Ninety Thousand Two Hundred & Sixty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
49	All inclusive Comprehensive Maintenance Contract of 10 Nos Microprocessor based Constant Current Regulators (CCRs) which includes repair & replacement of all faulty parts of CCRs and shall have periodic Maintenance every quarterly (4 times in one year) 3rd Year (After Defects liability Period) (5% escalation on 2nd year cost of item no.48)	1	Job	₹ 1,99,773.00	₹ 1,99,773.00	INR One Lakh Ninety Nine Thousand Seven Hundred & Seventy Three Only
50	All inclusive Comprehensive Maintenance Contract of 10 Nos Microprocessor based Constant Current Regulators (CCRs) which includes repair & replacement of all faulty parts of CCRs and shall have periodic Maintenance every quarterly (4 times in one year) 4th Year (After Defects liability Period) (5% escalation on 3rd year cost of item no.49)	1	Job	₹ 2,09,761.65	₹ 2,09,761.65	INR Two Lakh Nine Thousand Seven Hundred & Sixty One and Paise Sixty Five Only
51	All inclusive Comprehensive Maintenance Contract of 10 Nos Microprocessor based Constant Current Regulators (CCRs) which includes repair & replacement of all faulty parts of CCRs and shall have periodic Maintenance every quarterly (4 times in one year) 5th Year (After Defects liability Period) (5% escalation on 4th year cost of item no.50)	1	Job	₹ 2,20,249.73	₹ 2,20,249.73	INR Two Lakh Twenty Thousand Two Hundred & Forty Nine and Paise Seventy Three Only
Total					₹ 1,57,31,901.38	INR One Crore Fifty Seven Lakh Thirty One Thousand Nine Hundred & One and Paise Thirty Eight Only
Say Rs. 1,57,31,901.38 (One Crore Fifty Seven Lakh Thirty One Thousand Nine Hundred and One and Paise Thirty Eight Only) plus applicable GST as per government norms.						

Signature Not Verified

Digitally signed by Rajith V
Date: 2024.01.05 15:11:22 IST
Location: eProcurement System for Central PSUs



Assistant General Manager(E-E)
AAI, Madurai Airport