



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

सं.भा.वि.प्रा./डिब/अभि.-सिविल/मेन्ट/ W0-13/ टेन्साइल कैनोपी /२३-२४/
Ref.No.AAI/DIB/Engg-Civil/Maint/W0-13/Tensile Canopy/23-24

दिनांक:01.01.2024
Dated:01.01.2024

To,

M/s Pavee Construction,
Prop. Sh. Pardeep Kumar,
Regd. Office Main Street Gonder,
Gonder 35, Gonder,
Karnal Haryana -132024,
Email:-paveeconstruction@gmail.com

विषय: डिब्रूगढ़ हवाई अड्डे पर टर्मिनल भवन के आगमन की ओर टेन्साइल कैनोपी का प्रावधान।

Name of Work: Provision of Tensile Canopy at Arrival side of Terminal Building at Dibrugarh Airport.

संदर्भ: निविदा क्रमांक - 2023_AAI_175698_1 (कार्य की वित्तीय ई-बोली 21/12/2023 को खोली गई)
Ref.: Tender ID No. 2023_AAI_175698_1 (Financial E-Bid for the work opened on 21/12/2023).

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल **₹.2,26,03,240.00 (दो करोड़ छब्बीस लाख तीन हजार दो सौ चालीस मात्र)** गुड्स एंड सर्विस टैक्स के बिना, जो कि निविदा की प्राक्कलित मूल्य **₹.2,93,33,482.00** से **-22.94%** नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.2,26,03,240.00 (Two Crores Twenty-Six Lakhs Three Thousand Two Hundred Forty Only)** excluding GST which is **-22.94% (Twenty-Two Point Nine Four Percent)** below the estimate cost put to tender **₹.2,93,33,482.00**.

- वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल) एएआई, डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़, कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए **21/01/2024** तक वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल), एएआई, डिब्रूगढ़ हवाई अड्डे के कार्यालय में उपस्थित हों। अनुबंध अनुबंध 100/- रुपये (एक सौ रुपये मात्र) के गैर-न्यायिक स्टांप पेपर पर निष्पादित किया जाएगा और स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Senior Manager(Engg-Civil) AAI, Dibrugarh Airport, Dibrugarh, shall be the Engineer-In-Charge of the work. You are requested to attend the office of **Senior Manager (Engg-Civil)**, AAI, Dibrugarh Airport by **25/01/2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने के 10 दिनों के अन्दर प्रतिभूति जमा के रूप में **₹22,60,324.00 (बाईस लाख साठ हजार तीन सौ चौबीस मात्र)** की राशि इस कार्यालय में जमा करा दें अन्यथा संविदा की सामान्य शर्तों के खंड 1 A पृष्ठ संख्या जी.सी.सी 1 7 पर खंड 1A की शर्त के अनुसार घटाया जाएगा।

Please deposit **Rs.22,60,324.00. (Rupees Twenty-Two Lakhs Sixty Thousand Three Hundred Twenty-Four Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per GCC Clause 1A on page 17 of the contract document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्तों) के प्रावधान का पालन करें।) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड 19 पृष्ठ संख्या 50 पर में निर्दिष्ट है और संविदा की सामान्य शर्तों के पेज नं 89 और केंद्र और राज्य सरकार के नियम।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) central rules 1971, Child labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause 19 on page no. 50 and page no. 89 of GCC of tender and rules of Central and State Govt.

5. आपको यह भी निर्देश दिया जाता है कि आप **सहायक प्रबंधक (अभि.-सिविल)**, भा.वि.प्रा., डिब्रूगढ़ से अविलम्ब संपर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact **Asstt. Manager (Engg-Civil), AAI, Dibrugarh Airport, Dibrugarh** immediately who will arrange to hand over the work to you.

6. कृपया ध्यान दें कि कार्य करने के लिए नियत समय **04 (चार)** महीने होगा जिसकी गणना इस पत्र के जारी होने के 10 वें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be **04 (Four) months** and same shall be reckoned from the 10th day after issue of this letter.

7. अनुबंध के संबंध में कोई भी आगे का पत्राचार आम तौर पर **प्रभारी अभियंता यानी वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल)**, भारतीय विमानपत्तन प्राधिकरण, डिब्रूगढ़ हवाई अड्डा - 786012 को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the **Engineer-In-Charge i.e. Senior Manager (Engg-Civil)**, Airports Authority of India, Dibrugarh Airport - 786012.

8. कृपया इस पत्र के प्राप्ति की सूचना दें तथा इसके साथ संलग्न इस पत्र की प्रतिलिपि पर विधिवत हस्ताक्षर करने के उपरांत स्वीकृति के प्रमाण स्वरूप इसे अधोहस्ताक्षरी को वापस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancy is found then English version will be taken as correct.

धन्यवाद / Thanking you,

संलग्न: Item Rate SOQ. (Page-01 to 05)

भवदीय/Yours Sincerely,



पंकज कुमार मिश्रा (Pankaj Kumar Mishra)

वरिष्ठ प्रबंधक (इंजीनियरिंग.-सिविल)/ Senior Manager (Engg.- Civil)
कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI
भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन / AAI, Dibrugarh Airport

[Validate](#)[Print](#)[Help](#)**Item Rate BoQ**

Tender Inviting Authority: Pankaj Kumar Mishra, SM(Engg-Civil), AAI, Dibrugarh Airport

Name of Work: Provision of Tensile Canopy at Arrival side of Terminal Building at Dibrugarh Airport.

Contract No: 2023_AAI_175698_1

Name of the Bidder/
Bidding Firm
/ Company :

PAVEE CONSTRUCTION

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	1	3	4	5	6	7
1	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge	342.00	Cum	450.00	153900.00	INR One Lakh Fifty Three Thousand Nine Hundred Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	40.00	Cum	270.00	10800.00	INR Ten Thousand Eight Hundred Only
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	75.00	Cum	1800.00	135000.00	INR One Lakh Thirty Five Thousand Only
4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	5.00	Cum	1450.00	7250.00	INR Seven Thousand Two Hundred & Fifty Only
5	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: (a) Bituminous road.	39.00	Sqm	350.00	13650.00	INR Thirteen Thousand Six Hundred & Fifty Only
6	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles 10 mm to 25 mm	1,024.00	sqm	110.00	112640.00	INR One Lakh Twelve Thousand Six Hundred & Forty Only
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	10.00	cum	200.00	2000.00	INR Two Thousand Only

8	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	50.00	cum	850.00	42500.00	INR Forty Two Thousand Five Hundred Only
9	Extra for every additional lift of 1.5 m or part thereof in excavation /banking excavated or stacked materials. (a) All kinds of soil.	10.00	cum	100.00	1000.00	INR One Thousand Only
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. (a) 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	12	Cum	5800.00	69600.00	INR Sixty Nine Thousand Six Hundred Only
11	Centering and shuttering including strutting, propping etc. and removal of form for (a) Foundations, footings, bases of columns, etc. for mass concrete.	60.00	sqm	280.00	16800.00	INR Sixteen Thousand Eight Hundred Only
12	Centering and shuttering including strutting, propping etc. and removal of form for all heights :	50.00	sqm	400.00	20000.00	INR Twenty Thousand Only
13	Centering and shuttering including strutting, propping etc. and removal of form for all heights : (a) Columns, Piers, Abutments, Posts and Struts.	105.00	sqm	400.00	42000.00	INR Forty Two Thousand Only
14	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc.	50.00	sqm	400.00	20000.00	INR Twenty Thousand Only
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. (a) Thermo-Mechanically Treated bars (Fe-500).	23,550.00	kg	72.00	1695600.00	INR Sixteen Lakh Ninety Five Thousand Six Hundred Only
16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	500.00	kg	130.00	65000.00	INR Sixty Five Thousand Only
17	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	983.00	kg	120.00	117960.00	INR One Lakh Seventeen Thousand Nine Hundred & Sixty Only
18	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 450 mm dia RCC pipes.	30.00	metre	4000.00	120000.00	INR One Lakh Twenty Thousand Only
19	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all loads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg/cum	157.00	cum	7000.00	1099000.00	INR Ten Lakh Ninety Nine Thousand Only

20	Boring, providing and installation bored cast-in-situ reinforced cement concrete piles of grade M-25 of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by percussion drilling using Direct mud circulation (DMC) or Bailor and chisel technique by tripod and mechanical Winch Machine all complete, including removal of excavated earth with all its lifts and leads (length of pile for payment shall be measured up to bottom of pile cap). Note: Truck Mounted rotary/TMR/Tubewell boring machine shall not be used. 450 mm dia piles	414.00	metre	2500.00	1035000.00	INR Ten Lakh Thirty Five Thousand Only
21	Add for using extra cement in the items of design mix over and above the specified cement content therein.	10.00	Qlt.	700.00	7000.00	INR Seven Thousand Only
22	Providing and laying matt finished vitrified tile of size 300x300x15 mm having water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in out door floors such as footpath, court yard multi models etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as direction of Engineer-in-Charge.	1,024.00	sqm	950.00	972800.00	INR Nine Lakh Seventy Two Thousand Eight Hundred Only
23	Stone tile work for wall lining upto 10 m height with special adhesive over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement with an admixture of pigment to match the stone shade. 8mm thick (mirror polished and machine cut edge) Granite stone of any colour and shade	133.00	sqm	3500.00	465500.00	INR Four Lakh Sixty Five Thousand Five Hundred Only
24	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red Area of slab upto 0.50 sqm	133.00	sqm	3500.00	465500.00	INR Four Lakh Sixty Five Thousand Five Hundred Only
25	Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi models location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	280.00	sqm	1000.00	280000.00	INR Two Lakh Eighty Thousand Only
26	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand)	133.00	sqm	750.00	99750.00	INR Ninety Nine Thousand Seven Hundred & Fifty Only
27	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand).	23.00	cum	6500.00	149500.00	INR One Lakh Forty Nine Thousand Five Hundred Only
28	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	133.00	sqm	280.00	37240.00	INR Thirty Seven Thousand Two Hundred & Forty Only

29	Providing and fixing on unplasticised Rigid PVC withstanding 6 kgf pressure rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes a) 100 mm diameter	50.00	mt	400.00	20000.00	INR Twenty Thousand Only
30	Providing and fixing on unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 12.42.5 Bend 87.5° 12.42.5.2 100 mm bend	46.00	each	400.00	18400.00	INR Eighteen Thousand Four Hundred Only
31	Providing, Fabricating, Assembling, hoisting, erecting and placing in position MS Built-up section/Tubular Structure (MS built-up section :- Rolled section & plates conforming to IS 2062 Grade Yst 250 Tubular Structure:- made from Steel hollow sections, ISI marked conforming to IS 1161/4923, Grade Yst 310, thickness up to 10mm (from SAIL / RINL / TATA/JINDAL) in the profile shape as per conceptual drawings with special plate connector, pinion joints, Plates, hollow sections etc using water jet 3-D cutting system for obtaining smooth 3-dimensional curvature, SAW/MMAW/MIG welding process with special plate connectors, pinion joints, plates, hollow sections with cleaning the surface with sand blasting system and applying a coat of epoxy primer and including Preparation of detailed fabrication and erection drawings of Structural steel work from design drawings, transportation from fabrication yard, cutting, threading, machining, leads and lifts up to all heights, tools & plants and necessary scaffolding etc. required for all operations involved to make structure of Tensile Membrane canopy. The structure has to be provided as per conceptual drawings of Tensile fabric profile, including all arch beam, curved lateral beams and bracings, vertical support columns, nodal joints, bases of columns and high tensile bolts of grade not less than 10.9 having black phosphate coating. The complete structure to be sand blasted and coated with epoxy primer 2 coats and hard top two coats Polyurethane applications work at all locations in required DFT (dense film thickness) for each coat in total DFT of 280 microns as per technical specification and direction of Engineer-In-Charge.	85,694.00	kg	125.00	10711750.00	INR One Crore Seven Eleven Thousand Seven Hundred & Fifty Only
32	Providing, fabricating, assembling and erection of pre stressed Tensile Membrane Fabric structure in desired profile as per conceptual drawing, with SERGE FERRARI pre constraint TX-30 Type III or MEHLER FR 1000 Mehalop N-Type III having minimum Tensile strength (Warp/Weft) 5600/5500N/50 mm & minimum tear strength (Warp/Weft) of 800 / 650 N, high concentrated PVDF top coating and PVDF coated on bottom side, polyester fabric and should be weldable having a minimum weight of 1050 gm/sqm with a minimum 20 years warranty etc. over steel structure frames with all fittings and fixtures such as Galvanized MS End Plate ,Shackles, Rigging Screws , Turnbuckles, swedge, fork , keder rods & galvanized MS strands with stainless steel end terminals complete as per Drawing / Detail & as per Particular/ technical specifications and as per the directions of Engineer-in-charge. (Rate includes cost of fabric, patterns, forming, cutting, fabrication, hot weld stitch of fabric, Transport to the site ,assembling and installation with GI strands, hardware, EPDM gasket and required accessories wherever required complete including lifts up to all heights, tools & plants, and necessary affording etc. required for all operations in all respect as per direction of Engineer-In-Charge). (Note : (i) Actual plan area of canopy shall only be measured for payment. (ii) Galvanized strands, Galvanized MS end plate and powder coated aluminium flat bar only shall be paid separately under respective item.)	1,380.00	Sqm	2500.00	3450000.00	INR Thirty Four Lakh Fifty Thousand Only
33	Providing Engineering Consultancy services for steel structure for tensile fabric roofing structure, RCC foundation work, rain water drainage and testing for load bearing capacity with all relevant calculation sheet and design vetted by I.T./NIT, detailed construction drawing if required during execution etc. as specified in tender document and any other details related to consultancy work which are essential for successful execution of works etc completes as per direction and satisfaction of EIC.	1.00	Per Job	150000.00	1500000.00	INR One Lakh Fifty Thousand Only

34	Supplying of powder coated aluminium flat bar 75mm x 5 mm in same color code of fabric, of reputed brand to be used for peripheral locking for fabric all around the fabric in the gutter side and building side etc. complete as per drawing/detail and direction of Engineer-In-Charge.	260.00	Meter	300.00	78000.00	INR Seventy Eight Thousand Only
35	Supplying hot dipped galvanized Membrane Corner Plates of required thickness and design finished with a coat of Marine Primer and two coats of Polyurethane paint complete as per Drawing/Detail and fixing with high tensile bolts of grade not less than 10.9 having black phosphate coating complete as per Drawing/Detail and as per direction of Engineer-In-Charge.	25	Kg	140.50	3500.00	INR Three Thousand Five Hundred Only
36	Supplying of 25mm diameter, 1x19 Galvanized strands of required length of Grade 1570 (6000 mm length) with Stainless steel terminals and toggles at both ends as per approved shop drawings as Under fabric Cables complete in all respect as per direction of Engineer-In-Charge.	30	Each	4500.00	135000.00	INR One Lakh Thirty Five Thousand Only
37	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. internal work - Exposed on wall	80	metre	4500.00	360000.00	INR Three Lakh Sixty Thousand Only
38	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. internal work - Exposed on wall a) 165 mm dia (150 NB) a) 42 mm dia	138.00	metre	450.00	62100.00	INR Sixty Two Thousand One Hundred Only
39	Providing and placing self levelling/compacting cement grouting of all the column as per direction and satisfaction of E.I.C	23.00	each	2500.00	57500.00	INR Fifty Seven Thousand Five Hundred Only
40	Precasting and placing in position 125 mm dia Bollards 600 mm high of required shape including providing M.S. Pipe Sleeve 50 mm dia 300 mm long in the Bollard and M.S. Pipes 40 mm dia and 450mm long with 150x150x6mm M.S. plate welded at bottom and embedded 150mm in cement concrete 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources), including necessary excavation of size 250x250x450mm deep for the same in bitumen/concrete pavement at specified spacing.	24.00	each	12500.00	300000.00	INR Three Lakh Only
Total in Figures					22603240.00	INR Two Crore Twenty Six Lakh Three Thousand Two Hundred & Forty Only
Quoted Rate in Words		INR Two Crore Twenty Six Lakh Three Thousand Two Hundred & Forty Only				

85