



भाविप्रा /औ'बाद /अभि.-वि/कैप/23-24/डब्लू -04/ 437-47
AAI/AU/Engg-E/CAP/23-24/W-04/

दिनांक: 20.12.2023
Date: 20.12.2023

सेवा में,
मेसर्स ए के टेक्नोक्रेट्स
9, मधुबन, पाधर्डी पट्टा,
नाशिक - 422 010.

To,
M/s A.K. Technocrats,
9, Madhuban, Pathardi Phata,
Nashik - 422010

(PAN No. BBUPK9682C)
GST No. 27BBUPK9682C1Z0

कार्य का नाम : औरंगाबाद हवाई अड्डे पर मौजूदा टर्मिनल भवन का पुनर्निर्माण।
उपशीर्ष: आंतरिक विद्युत कार्य, अग्निशमन कार्य, बिल्डिंग साइनेज कार्य और फाउंटेन टाइप का वाटर कूलर।

Reconfiguration of Existing Terminal building at Aurangabad Airport. SH: Internal Electrical work, fire work, building signages work & Fountain type water cooler.

संदर्भ : 1) निविदा आई. डी संख्या : 2023_AAI_175870_1
2) आपकी ई -निविदा जो दिनांक 15.12.2023 को खोली.

महोदय,/ Dear Sir (S),

- उल्लिखित कार्य हेतु आपकी ई - निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा बताए गये मद मूल्यों पर रु. 74,44,445.00 (रु. चौराहतर लाख चोवालीस हजार चार सौ पैतालीस मात्र) (जी एस टी अतिरिक्त) के लिये स्वीकृत की जाती है जो कि अनुमानित लागत राशि रु. 1,16,29,944.00 से 35.99 % कम है.

Your e-tender for the work mentioned above is hereby accepted on behalf of the chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 74,44,445.00** (Rupees Seventy Four Lakh Forty Four Thousand Four Hundred & Forty Five Only) (Excluding GST) which is **35.99%** below the justification cost put to tender of **Rs.1,16,29,944.00**.

- वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, महाराष्ट्र कार्य के प्रभारी अभियंता होंगे, आपसे निवेदन है कि, आप दिनांक 30.12.2023 तक वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद, के कार्यालय में उपस्थित हों तथा करारनामे को पुरा करें. ठेके के करार नामा रुपये 100/- के नोनजुडिशियल स्टैम्प पर निष्पादित किया जायेगा तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा.

Senior Manager (E-E), AAI, Aurangabad Airport, Maharashtra, shall be the Engineer -In -Charge of the work. You are requested to attend the office of Senior Manager (E-E), AAI, Aurangabad Airport by 30.12.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one Hundred Only) and the cost of the stamp paper shall be borne by you.

विमानक्षेत्र नियंत्रक का कार्यालय, भा.वि.प्रा., औरंगाबाद, दूरभाष : (0240) 2477802,
O/O The Airport Director, AAI, Aurangabad. Phone No: (0240)2477802,

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (अभि.- विद्युत)
Sr. Manager (Engg.-Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

3. आपके निविदा के साथ प्राप्त बयाना राशि **2,29,382.00** रुपए को प्रतिभूति जमा के हिस्से के रूप में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर प्रतिभूति जमा राशि **5,15,063.00** रुपये ठेके के दस्तावेज के अनुसार जमा कर दें, अन्यथा निविदा में पृष्ठ जी सी सी 16 पर दी गई धारा 1(A) के अनुसार कटौती की जाएगी।

The earnest money amount of **Rs. 2,29,382.00** received along with your tender will be treated and converted as part of Security Deposit. Please deposit **Rs. 5,15,063.00** towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted as per condition of clause 1(A) at GCC Page 16 of the Contract Document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रवधानों के अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहा. प्रबंधक (अभियांत्रिकी - विद्युत), से मिलें वह आपको साईट सौंपने कि व्यवस्था करेंगे।

You are also directed to contact **Asstt. Manager (Engg-Elect.)**, AAI, Aurangabad Airport immediately who will arrange to hand over the site to you.


6. कृपया नोट करें कि कार्य करने का समय 06 (छह) माह रहेगा, जोकी कार्य आदेश जारी होने के दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** and same shall be reckoned from the 10th day of the date of placing of work order.

7. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।
If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

8. ई निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धी पत्र, प्रश्न, स्पष्टीकरण इत्यादि और उपर उल्लिखित पत्रों सहित उत्तरों के जवाब भी करारनामों के हिस्से होंगे।

All corrigendums, queries, clarifications etc, raised during e-tendering process and replies there of including the letters referred above shall also form part of the agreement.


श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (अभि. - विद्युत)
Sr. Manager (Engg.-Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

9. इस ठेके के संबंध में आगे को कोई भी पत्राचार वरि. प्रबंधक (अभि.- विद्युत), भाविप्रा. औरंगाबाद हवाईअड्डा, औरंगाबाद - 431007 के पते पर किया जाए।


Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Elect), AAI, Aurangabad Airport, Aurangabad - 431007.

10. कृपया इस पत्र को स्वीकार करे और हस्ताक्षर करने के बाद इसके साथ संलग्न पत्र की डुप्लिकेट प्रति स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को वापिस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न : मात्रा की अनुसूची
Encl : Schedule of Quantity

भवदीय/ Yours faithfully,


20/12/23

वरि. प्रबंधक [अभि - विद्युत]

Sr. Manager (E-E)

भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद
AAI, Aurangabad Airport, Aurangabad

श्री. सतीशकुमार कनौजिया

Sh. Sateesh Kumar Kanaujiya

वरि. प्रबंधक (अभि.- विद्युत)

Sr. Manager (Engg.-Electrical)

औरंगाबाद एअरपोर्ट

Aurangabad Airport

Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg.-Electrical), Airports Authority of India, Aurangabad Airport, Aurangabad- 431007.

Name of Work: Reconfiguration of Existing Terminal building at Aurangabad Airport. SH: Internal Electrical work ,fire work, building signages work & Fountain type water cooler.

Tender ID : 2023_AAI_175870_1

Name of the Bidder/ Bidding Firm / Company :	A K TECHNOCRATS
---	------------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
1.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	175	Point	1500.00	262500.00	INR Two Lakh Sixty Two Thousand Five Hundred Only
2.00	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	110	Point	925.00	101750.00	INR One Lakh One Thousand Seven Hundred & Fifty Only
3.00	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	2000	Meter	430.00	860000.00	INR Eight Lakh Sixty Thousand Only
4.01	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel conduit/raceway as required. 2 X 1.5 sq. mm +1 X 1.5 sq. mm earth wire	300	Meter	175.00	52500.00	INR Fifty Two Thousand Five Hundred Only

श्री. सतीश कुमार कनाजिया
Sh. Sateesh Kumar Kanaujiya
 वरिष्ठ प्रबंधक (अभि.- विद्युत)
Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
4.02	2 X 2.5 sq. mm +1 X 2.5 sq. mm earth wire	2570	Meter	140.00	359800.00	INR Three Lakh Fifty Nine Thousand Eight Hundred Only
4.03	2 X 4 sq. mm +1 X 4 sq. mm earth wire	4980	Meter	210.00	1045800.00	INR Ten Lakh Forty Five Thousand Eight Hundred Only
4.04	2 X 6 sq. mm +1 X 6 sq. mm earth wire	480	Meter	300.00	144000.00	INR One Lakh Forty Four Thousand Only
5.01	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. 20 mm	300	Meter	310.00	93000.00	INR Ninety Three Thousand Only
5.02	25 mm	2190	Meter	210.00	459900.00	INR Four Lakh Fifty Nine Thousand Nine Hundred Only
5.03	32 mm	200	Meter	510.00	102000.00	INR One Lakh Two Thousand Only
6.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).	20	Each	900.00	18000.00	INR Eighteen Thousand Only
7.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	50	Each	1500.00	75000.00	INR Seventy Five Thousand Only

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरिष्ठ प्रबंधक (अभि. - विद्युत)
Sr. Manager (Engg.-Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
8.01	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. 1 or 2 Module (75mm X 75mm)	20	Each	350.00	7000.00	INR Seven Thousand Only
8.02	6 Module (200mm X 75mm)	85	Each	510.00	43350.00	INR Forty Three Thousand Three Hundred & Fifty Only
8.03	8 Module (125mm X 125mm)	30	Each	650.00	19500.00	INR Nineteen Thousand Five Hundred Only
8.04	12 Module (200mm X 150mm)	30	Each	930.00	27900.00	INR Twenty Seven Thousand Nine Hundred Only
9.01	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 5/6 A switch	40	Each	175.00	7000.00	INR Seven Thousand Only
9.02	15/16 A switch	100	Each	275.00	27500.00	INR Twenty Seven Thousand Five Hundred Only
9.03	6 pin 15/16 A socket outlet	100	Each	375.00	37500.00	INR Thirty Seven Thousand Five Hundred Only
9.04	Telephone socket outlet	5	Each	275.00	1375.00	INR One Thousand Three Hundred & Seventy Five Only
10.01	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way (2+4), Double Door	6	Each	1800.00	10800.00	INR Ten Thousand Eight Hundred Only

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरिष्ठ प्रविण (अभि. - विद्युत)
Sr. Manag. Engg. - Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
10.02	8 way (2+6), Double Door	8	Each	1900.00	15200.00	INR Fifteen Thousand Two Hundred Only
10.03	12 way (2+10), Double Door	3	Each	2500.00	7500.00	INR Seven Thousand Five Hundred Only
11.00	Supplying and fixing of 6 way (8 +18), double door , metal, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing, blanking plates etc. as required. (But without MCB/RCCB/Isolator).(Make : L&T ; Model : 8537; 6 way (8 + 18) TPN DB Metal Door or Equivalent).	3	Each	4600.00	13800.00	INR Thirteen Thousand Eight Hundred Only
12.00	Supplying and fixing of 8 way (8 +24), double door , metal, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing, blanking plates etc. as required. (But without MCB/RCCB/Isolator).(Make : L&T ; Model : 8537; 8 way (8 + 24) TPN DB Metal Door or Equivalent).	3	Each	5400.00	16200.00	INR Sixteen Thousand Two Hundred Only
13.01	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 125 A,36KA,FPMCCB	2	Each	15000.00	30000.00	INR Thirty Thousand Only
14.01	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 A	6	Each	3020.00	18120.00	INR Eighteen Thousand One Hundred & Twenty Only
15.01	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 A	6	Each	3300.00	19800.00	INR Nineteen Thousand Eight Hundred Only

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (अभि.- विद्युत)
Sr. Manager (Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
16.00	Supplying and fixing 63A rating, 415 V, 10 kA, Four Pole MCB suitable for inductive load in the existing TPN MCB DB complete with connections, testing and commissioning etc. as required.	6	Each	1800.00	10800.00	INR Ten Thousand Eight Hundred Only
17.00	Supplying and fixing 63A rating, 240/415 V, 10 kA, "C" curve, DP miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	6	Each	1000.00	6000.00	INR Six Thousand Only
18.00	Supplying and fixing of 32 Amp rating, Two pole, (one phase and neutral), 415/240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	Each	3400.00	10200.00	INR Ten Thousand Two Hundred Only
19.00	Supplying and fixing of 32 Amp rating, Two pole, (one phase and neutral), 415/240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 100 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	Each	3330.00	9990.00	INR Nine Thousand Nine Hundred & Ninety Only
20.00	Supplying and fixing of 63 Amp rating, Four Pole, 415/240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	Each	4700.00	14100.00	INR Fourteen Thousand One Hundred Only
21.00	Supplying and fixing of 63 Amp rating, Four Pole, 415/240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 100 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	Each	4400.00	13200.00	INR Thirteen Thousand Two Hundred Only
22.01	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A, tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required. 4 way (4 + 12), Double door	1	Each	5000.00	5000.00	INR Five Thousand Only
22.02	8 way (4 + 24), Double door	1	Each	6000.00	6000.00	INR Six Thousand Only

श्री. सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujia
 वरि. प्रबंधक (आधि. - विद्युत)
 Sr. Manager (Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
23.01	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	250	Each	250.00	62500.00	INR Sixty Two Thousand Five Hundred Only
23.02	Double pole	20	Each	775.00	15500.00	INR Fifteen Thousand Five Hundred Only
23.03	Triple pole	10	Each	1200.00	12000.00	INR Twelve Thousand Only
23.04	Triple pole and Nutral	20	Each	1500.00	30000.00	INR Thirty Thousand Only
24.00	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	50	Each	40.00	2000.00	INR Two Thousand Only
25.00	Supply of recessed mounted LED downlighter 18W with pressure die-cast aluminium housing Lighting system comprising of LED of approved make ,having luminaire efficacy of not less than 100 lm/W. etc as per specifications and complete as required.	80	Each	1000.00	80000.00	INR Eighty Thousand Only
26.00	Supply of LED 36W luminaire suitable for recess mounting in modular false ceiling system powder coated CRCA housing with acrylic diffuser size 2 ft x 2 ft ,comprising of LED's of approved make with Constant current output driver, having luminaire efficacy of not less than 100 lm/W. etc as per specifications and complete as required.	80	Each	1100.00	88000.00	INR Eighty Eight Thousand Only
27.00	SITC of 3W LED Double sided Exit Signage (Green/Red) Light with inbuilt 2 hours battery back up etc as per specifications and complete as required .	10	Each	1400.00	14000.00	INR Fourteen Thousand Only

श्री सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 वरि. प्रमुख अभि.- विद्युत)
 Sr. Manager (Engrg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
28.00	Supply of flexible LED light strip 10W per running meter strip in transparent unit with approx. 120Nos of LEDs per meter (IP:65) complete with driver complete as required.	80	RM	540.00	43200.00	INR Forty Three Thousand Two Hundred Only
29.00	Installation, testing and commissioning of pre-wired, LED fitting with driver/ fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall/ surface, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	160	Each	140.00	22400.00	INR Twenty Two Thousand Four Hundred Only
30.01	Supply of following sizes of Power Cables , multi stranded copper conductor, XLPE Insulated, cores laid up, PVC tape / Extruded Inner sheathed , Armoured, FRLS at outer sheathed, 1100V grade as per IS 7098(Part 1) 1988 4CORE 10 sq.mm. CU Ar. XLPE cable	150	RM	700.00	105000.00	INR One Lakh Five Thousand Only
30.02	4CORE 16 sq.mm. CU Ar. XLPE cable	350	RM	900.00	315000.00	INR Three Lakh Fifteen Thousand Only
30.03	4CORE 25 sq.mm. CU Ar. XLPE cable	200	RM	1300.00	260000.00	INR Two Lakh Sixty Thousand Only
31.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size on surface / cable tray as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	700	Meter	60.00	42000.00	INR Forty Two Thousand Only
32.00	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	500	Meter	240.00	120000.00	INR One Lakh Twenty Thousand Only
33.01	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 4C X 10 sq. mm	10	Each	470.00	4700.00	INR Four Thousand Seven Hundred Only

श्री. सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 वरि. प्रबंधक (वि. विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
33.02	4C X 16 sq. mm	20	Each	500.00	10000.00	INR Ten Thousand Only
33.03	4C X 25 sq. mm	20	Each	550.00	11000.00	INR Eleven Thousand Only
34.00	Supply of 3.5CX 150 sq.mm size of XLPE insulated & PVC sheathed, armoured, aluminium conductor under ground cable of 1.1KV grade as per IS 7098:1988 Part-I with upto date amendments complete as required. (Make: As per AAI list of preferred makes)	300	Meter	970.00	291000.00	INR Two Lakh Ninety One Thousand Only
35.01	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 90 mm dia (OD-90 mm & ID-76 mm nominal)	300	Meter	455.00	136500.00	INR One Lakh Thirty Six Thousand Five Hundred Only
36.01	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC HDPE pipe as required Above 95 sq. mm and upto 185 sq. mm	300	Meter	150.00	45000.00	INR Forty Five Thousand Only
37.01	Supplying and making end termination with brass compression gland and aluminium/copper lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3½ X 150 sq. mm (50mm)	2	Each	1300.00	2600.00	INR Two Thousand Six Hundred Only
38.00	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4	Each	7500.00	30000.00	INR Thirty Thousand Only

श्री. सतीश कुमार कनौजिया
 Sh. Satesh Kumar Kanaujiya
 वरि. प्रबंधक (इंजि.- विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
39.01	Supply & Fixing of factory fabricated pre-galvanized G.I. sheet steel raceway in 1.6mm thickness for bottom & sides and 2mm thick top Cover including junction boxes with 2mm cover plate and as called for including necessary civil work such as chase cutting in screed, fixing/ jamming the raceway, aligning & levelling and finishing with sand cement plaster & chicken wire mesh. 150mm x 38mm (2mm top Cover)	550	Meter	610.00	335500.00	INR Three Lakh Thirty Five Thousand Five Hundred Only
40.00	Design, Supply, installation, testing & Commissioning of Outdoor Type, Floor Mounted compartmentalized cubical type Feeder Pillar of 415 Volt (Nominal), fabricated out of 2 mm thick CRCA Sheet, free standing and totally enclosed, IP65, Double Door Feeder pillar to cover incomers and outgoings confirming to IS: 61439, Weather proof / dust proof / vermin proof with bottom cable entries and cable alleys. The feeder pillar shall be suitable for operation on 3 Phase, 4 wire, 50 Hz AC supply and with suitable size busbar, earth bar and following switchgear instrumentation and protection devices etc. complete with connections, interconnection, earthing, painting and marking as per site conditions etc complete as required as per the specifications. Supplier must take Feeder Pillar Design Approval from EIC before the supply. I: - Incomer : a) 160 A, MCCB, 4P, 35-37 KA (Icu= 100% Ics) with extended rotary handle and spreaders - 01 Nos. b) Multi function meter (Shows Voltage, Current & Frequency) with 3 line LCD/LED Display of size 96 x 96 mm. - 01 Nos. c) Indication Lamp R, Y & B (LED Type) -01 set II - Outgoing : a) 100 A, MCCB, 4P, 30 KA (Icu= 100% Ics) with extended rotary handle - 02 Nos. b) 64A, MCCB, 4P, 30 KA (Icu= 100% Ics) with extended rotary handle - 04 Nos. c) Indication Lamp R & G (LED type) - 06 Set Other : a) 300A Copper busbar, 3 Phase and Neutral c) Necessary CT & Control wiring arrangement	1	Each	16000.00	16000.00	INR Sixteen Thousand Only

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (विद्युत) - विद्युत)
Sr. Manager (Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
41.00	Supply of Wall mounted SS Steel Hnad Drier with Air Purifier having suitable voltage range of 220-240 v , 50 Hz , Touch free infrared sensor activation , Brushless motor having 18000 RPM ,Noise level shoud not be more than 72 db (Make : Dolphy ; Model : DAHD0063 or Eququivalent)	6	Each	15000.00	90000.00	INR Ninety Thousand Only
42.00	Dismantling of existing conduit piping ,wiring , light fixture , switch borad , MCBDB etc as per the site requirement.	1	Job	5000.00	5000.00	INR Five Thousand Only
43.00	Supply of portable Airport mobile charging station compatible of 240 V, 50 Hz, having capacity of 7 Mobile chargers and 5 USB ports. (Design approval should be taken form EIC before the supply)	6	Each	5000.00	30000.00	INR Thirty Thousand Only


24.12.23
 20.12.23
 श्री.सतीशकुमार कनौजिया
 Sh.Sateesh Kumar Kanaujiya
 वरि. प्रबंधक (अभि.- विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
44.00	Supply installation, testing and commissioning of recessed bi level drinking water fountain with double chrome plated brass bubblers & one recess type sport bottle filling station with sensor and mechanical operation. Drinking water fountain having min. 8 GPH cooling capacity, stainless steel body , SS finish frame , suitable for operation min. range 50 to 90 PSI, chilling unit suitable for R134a refrigerant with suitable to operate on 220V +/- 5% Volt , 50 Hz. AC Single phase supply complete , adjustable thermo state,with all accessories etc as required . The system shall comply with ANSI 117.1 and ADA,UL listed , ANSI/NSF 61 complied . The recess type separete mechanical activation botter filler shall have silver ion antimicrobial protection with SS finish frame exterior . The unit shall be installed at standard height to meet the standard requirement as per direction and satisfaction of Engineer-Incharge.(Model- M8CRSBF Make:Oasis/Model:H1011.8 with 1900 Make:Haws/ equivalent approved make & model) NOTE: 1) Item to be executed by a specialized agency approved by Engineer-In-Charge. 2) Item to be executed as per shop drawing to be submitted by agency duly approved by Engineer-In-Charge.	5	Each	10000.00	50000.00	INR Fifty Thousand Only


 20.12.23
 श्री. सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 वरि. प्रबंधक (अभि.- विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
45.00	Supply, Installation, Testing & Commissioning of Reverse Osmosis System (RO) having min. capacity 50 LPH RO system along with five stage filtration along with media and carbon filter, RO membrane, UV filtration & TDS meter and pressure gauge with 60 ltrs. HTP pressure tank to generate the adequate pressure for meeting the operation for above "SOQ Item No. 16 drinking fountain". All the system will be enclosed in the powder coated M.S body with suitable mounting/fixing arrangement as per site requirement complete etc as required upto the satisfaction of Engg. In Charge. (Make: Danfrost Model RO 50L /Make: Oasis/equivalent approved make). NOTE:1) Item to be executed by a specialized agency approved by Engineer-In-Charge. 2) Item to be executed as per shop drawing submitted by agency duly approved by Engineer-In-Charge.	5	Each	10000.00	50000.00	INR Fifty Thousand Only
46.01	Design, supply, installation, testing & commissioning of wall/ ceiling mounted internally illuminated pictographs. The signage board shall be fabricated board by making "C" shaped 3 mm thick Aluminum profile sign board with inbuilt light proof ventilating system. The signage panel shall be fabricated from 2 mm aluminum sheet of approved make and shade having laser cut logo/ lettering in Marathi, Hindi & English. 3 mm poly carbonate sheet shall fixed at inner side of the panel sheet board so as the lettering will glow white as per the design approved by the Engineer-In-Charge. Boards shall be designed, fabricated and installed as per the detailed specification. The signage shall have system for easygraphic changes and easy access for maintenance. The illumination source shall be of LED's (2400 lumens/ SQMT) as light source with individual current regulator for every signage complete with all internal wiring, connectors etc. (Make of LED Modules and power supply driver module of make requivalent of OSRAM/ PHILIPS/ NICHIA) of minimum 5 years guarantee. The signboard can be either suspended from ceiling/ wall mounted with necessary Aluminum powdercoated pipe of 38 x 2 mm pipe on the top or side for fixing the same on the desired location as per conditions including wiring up to 5 meters in casing, capping, as required. The entire signage shall be powder coated in required shade as per direction of EIC. Single Side - 1700mm x 400mm X 75mm deep	13	No.	2000.00	26000.00	INR Twenty Six Thousand Only

श्री. सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 वरि. प्रबंधक (अभि.- विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
46.02	Double Side - 1700mm x 400mm X 75mm deep	2	No.	5000.00	10000.00	INR Ten Thousand Only
46.03	Single Side - 400mm x 400mm X 75mm deep	15	No.	5000.00	75000.00	INR Seventy Five Thousand Only
47.00	Dismantling and re-installation of existing signages board as per site condition including accessories like supporting piping etc as required.	1	Job	1000.00	1000.00	INR One Thousand Only
48.00	Supply, Installation, Testing & commissioning of UL / EN listed (latest version) Intelligent addressable smoke detector with inbuilt fault isolator / isolator base and with unique optical sensing chamber, visible LED, fully coated circuit board, superior RF / Transient protection suitable for 2 wires loop connection, complete with plug into common separate base & housing constructed of LEXAN (or polycarbonate) complete with connections etc. as required and to be installed below / above false ceiling roof and concealed space and as per enclosed specifications ,complete as required. (Cost of plug in common base shall deemed to be included in cost of detectors).	50	Each	3600.00	180000.00	INR One Lakh Eighty Thousand Only
49.00	Supplying, Installation, testing & commissioning of UL / EN listed (latest version) intelligent addressable manual call station (Resettable pull / push type) suitable for semi flush mounting, IP 54 for indoor use & IP 65 for outdoor use with inbuilt fault isolator / isolator module with double gang outlet box, equipment for key operated test reset lock, electronic or ratary switches for address setting. Manual pull station shall be connected with two wire to SLC loop of Fire control panel. Cover shall be made out of LEXAN (or poly carbonate equivalent) with clear operating instruction and the word fire appearing on the front complete with connections etc. as required and as per enclosed specifications.	10	Each	4500.00	45000.00	INR Forty Five Thousand Only
50.00	Supply, installation, testing and commissioning of UL / EN listed (latest version) loop powered addressable Hooter-cum- strobe with inbuilt fault isolator / isolator module with adjustable sound level in the range of min. 90 db to Max. 120 db at 1M distance complete with termination etc. as required and as per enclosed specification.	10	Each	4501.00	45010.00	INR Forty Five Thousand & Ten Only

श्री. सतीश कुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 बरि. प्रबंधक (अभि. विद्युत)
 Sr. Manager (Engg. Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
51.00	Supply and laying of 2 core , 1.5 sq. mm . Fire Survival cable, armoured copper conductor of 600/1000 V grade, insulated with specially formulated PVC , coated with special fire resistance materials and overall sheathed with special PVC, with special properties as Zero Halogen Low Smoke insulation Basic construction as per BS 7846 -2009 & cuircuit integrity as per BS 6387 C.W.Z/BS EN 50200.	400	Meter	240.00	96000.00	INR Ninety Six Thousand Only
52.00	Supply, Installation, Testing & Commissioning of UL/EN listed (latest version) Modular Microprocessor based expandable intellegent Addressable type Fire Alarm Control panel of 05 (Five) loops, with minimum 320 character graphics/ LCD display with tuch screen or other keypad and minimum 4000 events history long in the non volatile memory (EPROM), The panel should be equiped with loop capacity to take minimum 240 intellegent addressable detectors/ devices (In any combination with minimum 120 detector per loop) in one loop. Four access levels, capable of taking Protocol Devices, Graphical Display, sufficient numbers of programmable relay controls for controlling ventilation fan, fire pump room, monitoring of fire sprinkler and fire hydrant pump, 230 volts, 50 Hz AC power supply, inbuilt automatic battery charger, 24 volts sealed maintenance free lead acid batteries sufficient for 2 hourse normal working and then be capable of operating the system for 30 minutes during and emergency/ fault conditions along with battery stand as required. The panel shall have facility for seamless integration with PA system in case of fire) The panel shall be compatible for Building Management System with open protocol BACNET/MODBUS etc. as per specifiction, complete as required. The panel should be compatible with the existing fire alarm system inclung re-addressing, re-programming, re-commissioning of existing fire devices in fire alarm control panel etc. as required. (smoke detectors, multi criteria detectors , MCPs). EST3 fire panel shall be suitable for existing fire system. a) 5 Loop. Note: 1). Prior site inspection by OEM of the fire panel is mandatory before the delivery of panel. 2). All the re programmig of installed fire devices a	1	Job	20000.00	20000.00	INR Twenty Thousand Only

श्री.सतीशकुमार कनौजिया
 Sh.Sateesh Kumar Kanaujiya
 वरि. प्रबन्धक (विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport


NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
53.01	Supplying, fixing, testing and commissioning of butterfly valve of PN 1.6 rating with bronze/gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 of following sizes as required. 80 mm dia	2	Each	4500.00	9000.00	INR Nine Thousand Only
53.02	100 mm dia	4	Each	5500.00	22000.00	INR Twenty Two Thousand Only
53.03	150 mm dia	4	Each	8500.00	34000.00	INR Thirty Four Thousand Only
54.01	Providing, laying /erection, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling or with proper hanging arrangements (in case of sprinkler line with proper welding) with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required. 25 mm dia	150	Meter	450.00	67500.00	INR Sixty Seven Thousand Five Hundred Only
54.02	32 mm dia	80	Meter	550.00	44000.00	INR Forty Four Thousand Only
54.03	65 mm dia	50	Meter	850.00	42500.00	INR Forty Two Thousand Five Hundred Only
54.04	80 mm dia	80	Meter	975.00	78000.00	INR Seventy Eight Thousand Only
54.05	100 mm dia	100	Meter	1250.00	125000.00	INR One Lakh Twenty Five Thousand Only

श्री. सतीश कुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (आर्थिक - विद्युत)
Sr. Manager (Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
55	Supplying, installation, testing & commissioning of sprinkler flexible pipe (UL Listed) of stainless steel complete with 15 NPT on reducer thread with maximum working pressure of 175 PSI test pressure of 875 PSI (Burst) with branch line (Inlet) 25mm NPT male thread to sprinkler head (Outlet) 15mm NPT female thread with reducer, nipple, 2 side brackets, center bracket, stockbar of following sizes i/c quartzoid bulb complete as required after removing existing MS sprinkler drop (if it is required) or making arrangements for fixing of sprinkler flexible pipe in case of new sprinkler line. a) 1500 mm	25	Each	2000.00	50000.00	INR Fifty Thousand Only
56	Supply & fixing of 63 mm dia Stainless Steel (Grade 304) short branch pipe with 20 mm nominal internal diameter size nozzle conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling etc. as required.	10	Nos.	2500.00	25000.00	INR Twenty Five Thousand Only
57	Supply & fixing of 63 mm dia Stainless Steel (Grade 304) female coupling suitable for connection with existing fire hydrant to the 63 mm dia hose pipe conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling etc. as required.	20	Nos.	5500.00	110000.00	INR One Lakh Ten Thousand Only
58	Supplying and Fixing of M.S. Hose cabinet Wall mounted type fabricated out of S.S. sheet with glass fronted door and size of the cabinet shall be 600mm x 750 mm x 250 mm cabinet.	3	Nos.	8000.00	24000.00	INR Twenty Four Thousand Only
59	Supplying and Fixing of First Aid Hose Reel, wall mounting swinging type complete with drum & bracket of MS construction, spray painted in Post office Red, conforming to IS 884/1995 with upto date amendments, complete with the following as required. 30 Meter long 20 mm dia water hose Thermoplastic (Textile reinforced) Type - 2 as per IS : 12585 25 mm dia ball valve & nozzle. Drum and rackets for fixing the equipments on wall. Connection from riser with stop valve (gun metal) & M.S. Pipe	3	Nos.	7500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
60	Providing and fixing pre fabricated 4 mm thick glass door (with SS frame) of size 2.1 m x 0.9 m with centre opening for fire hose cabinet suitably marked on the outside with letters "Fire Hose" including locking arrangement suitable to accommodate 1 no Hydrant landing valves, 1 no fire hose reel, 2 nos. 15m long 63 mm dia hose pipe, 1 no branch pipe, 1 no fire man's axe and 2 nos fire extinguishers. All SS work to be in Red P.O Colour over appropriate primer.	3	Nos.	6500.00	19500.00	INR Nineteen Thousand Five Hundred Only

श्री. सतीशकुमार कनौजिया
Sh. Sateesh Kumar Kanaujiya
वरि. प्रबंधक (अग्नि-विद्युत)
Sr. Manager (Engg.-Electrical)
औरंगाबाद एअरपोर्ट
Aurangabad Airport

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
61	Dismantling and re-installation of existing fire fighting drop pipe as per site condition including accessories like socket, rozzar plate and cap etc as required.	10	Each	245.00	2450.00	INR Seventy Four Lakh Forty Four Thousand Four Hundred & Forty Five Only
Total in Figures					7444445.00	INR Seventy Four Lakh Forty Four Thousand Four Hundred & Forty Five Only
Quoted Rate in Words		INR Seventy Four Lakh Forty Four Thousand Four Hundred & Forty Five Only				


 20.12.23
 श्री. सतीशकुमार कनौजिया
 Sh. Sateesh Kumar Kanaujiya
 वरि. प्रबंधक (अभि.- विद्युत)
 Sr. Manager (Engg.-Electrical)
 औरंगाबाद एअरपोर्ट
 Aurangabad Airport

Signature Not Verified

Digitally signed by SATEESH KUMAR KANAUJIYA
 Date: 2024.04.29 16:19:12 IST
 Location: eProcurement System for Central PSUs

