



No: AAI/ENGG/ELECT/AGM/23-24/W.O-01/1799

Date: 29.01.2024

To

M/s BALAJI ENGINEERING

Flat No 18, 3rd Floor Queens castle

100 Feet Road Lakshmi Nagar

Nanganallur ,Chennai 600061.

Name of Work:- Additional Works for Internal & External Electrical Installations and Signages at New International Terminal (T2) at Chennai Airport.

Ref: - Tender ID. 2023_AAI_176374_1

Your E-Tender Opened on 05.01.2024

Dear Sir(s),

1. Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to **₹ 44,28,000/- (Rupees Forty-Four Lakhs Twenty-Eight Thousand Only) Excluding GST**. Which is **5.65%** below the Estimated Cost put to tender of ₹ 46,93,176 (Rupees Forty-Six Lakhs Ninety-Three Thousand One Hundred and Seventy-Six Only) Excluding GST.

उपर्युक्त कार्य के लिए आपकी निविदा को भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से आपके द्वारा उद्धृत मद दरों पर कुल **₹ 44,28,000/- (रुपये चौवालीस लाख अट्ठाईस हजार मात्र) जीएसटी को छोड़कर** पर स्वीकार किया जाता है, जो निविदा में लगाई गई अनुमानित लागत ₹ 46,93,176 (छियालीस लाख तिरानवे हजार एक सौ छिहत्तर रुपये मात्र जीएसटी को छोड़कर।) से **5.65%** कम है।

2. Joint General Manager Engineering (Elec)-I, Project Office, Airports Authority of India, Chennai Airport, Chennai – 600016 shall be the Engineer-in charge of the work. You are requested to attend the office of Joint General Manager Engineering (Elec)-I, Project Office, AAI, Chennai Airport on or before 05.02.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.

संयुक्त महाप्रबंधक इंजीनियरिंग (इलेक्ट्रिक)-I, परियोजना कार्यालय, भारतीय विमानपत्तन प्राधिकरण, चेन्नई हवाई अड्डा, चेन्नई - 600016 कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए 05.02.2024 को या उससे पहले संयुक्त महाप्रबंधक इंजीनियरिंग (इलेक्ट्रिक)-I, परियोजना कार्यालय, एएआई, चेन्नई हवाई अड्डे के कार्यालय में उपस्थित हों। अनुबंध, अनुबंध रु. 100/- (केवल एक सौ रुपये) के मूल्य के गैर-न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।



3. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules there of Central and State Governments.

आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 के प्रावधानों और केंद्र और राज्य सरकारों के न्यूनतम मजदूरी अधिनियम और नियमों का अनुपालन करें।

4. You are requested to furnish security deposit of ₹ 4,42,800 (Four Lakhs Forty Two Thousand Eight Hundred Only) within 10 days from the date of issue of this letter failing which the same will be deducted from your running bills as per relevant clauses of the contract document.

आपसे अनुरोध है कि इस पत्र के जारी होने के 10 दिनों के भीतर 4,42,800 रुपये (चार लाख बयालीस हजार आठ सौ रुपये मात्र) की सुरक्षा राशि जमा करें, ऐसा न करने पर अनुबंध दस्तावेज़ के प्रासंगिक खंडों के अनुसार आपके चल रहे बिलों से कटौती कर ली जाएगी।

5. You are also directed to contact Asst. General Manager Engineering (Electrical) Airport, Project Office, Airports Authority of India, Chennai Airport immediately who will arrange to hand over the site to you.

आपको महाप्रबंधक इंजीनियरिंग (इलेक्ट्रिकल) हवाई अड्डा, परियोजना कार्यालय, भारतीय विमानपत्तन प्राधिकरण, चेन्नई हवाई अड्डा से संपर्क करने का भी निर्देश दिया जाता है, जो आपको साइट सौंपने की व्यवस्था करेगा।

6. Please note that the time allowed for carrying out the work shall be **24 (Twenty-Four Months)** and same shall be reckoned from **01.02.2024**.

कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय होगा **24 (चाबीस महीने)** और वही से गिना जाएगा **01.02.2024**.

7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.

अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए।



कृपया रसीद स्वीकार करें और इसके साथ संलग्न इस पत्र की डुप्लिकेट प्रति हस्ताक्षर करने के बाद स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को लौटा दें।

Yours faithfully,

(B. PRADIP KUMAR)
Asst. General Manager (Engg.-Elect.)
AMED- (T2), AAI Chennai.

Encl: Schedule of Quantities (03 Pages)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
 चेन्नै ऐयरपोर्ट:: चेन्नै 600 016
CHENNAI AIRPORT:: CHENNAI 600 016
Schedule of Work

Name of Work: Additional Works for Internal & External Electrical Installations and Signages at New International Terminal (T2) at Chennai Airport

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1.00	Execution of works as per CPWD Delhi Schedule of rates (E&M)-2018 as and when required for two years.(Rate shall be quoted for 1st Year and 2nd year in the Indian rupees only), payment of DSR item will be released on the basis of percentage calculation of quoted amount and fixed amount of Rs.10,00,000.00 as clarified below. For example if desired to quote 5% above on DSR (E&M) 2018 rates,the rate column shall be filled as Rs.10,50,000. If desired to quote 5% below on DSR-2018 rates the rates coloumn shall be filled as Rs.9,50,000.00	1.00	Job	₹ 11,00,000.00	₹ 11,00,000.00
2.00	Supply of PVC insulated and PVC sheathed / XLPE unarmoured power cable of 1.1 KV grade of following size as & when required (Deviation Qty: -100% to +30 %)				
2.01	3X2.5 Sqmm	400.00	Mtr	₹ 100.00	₹ 40,000.00
2.02	3X 4 Sqmm	400.00	Mtr	₹ 125.00	₹ 50,000.00
2.03	3X 6 Sqmm	300.00	Mtr	₹ 150.00	₹ 45,000.00
2.04	4X4 Sqmm	200.00	Mtr	₹ 200.00	₹ 40,000.00
2.05	4X25 Sqmm	200.00	Mtr	₹ 300.00	₹ 60,000.00
3.00	Supply and fixing of PVC Casing Caping of following sizes with suitable Coupler, External ,Internal bend,Elbow , Tee and Junction box as required as per site condition. as & when required (Deviation Qty : -100% to +30 %)				
3.01	20X12mm	200.00	Mtr	₹ 100.00	₹ 20,000.00
3.02	25X16mm	200.00	Mtr	₹ 125.00	₹ 25,000.00
3.03	32x16mm	100.00	Mtr	₹ 200.00	₹ 20,000.00
4.00	Supply, assembly and laying of under floor trunking made out of 1.6mm(min) thick GI sheet complete with jointing sleeve, horizontal bends, vertical bends, level adjustment components and closer, vertical elbow, covers, access outlet. etc. complete with all other accessories under floor installation, making good the same, placing in position and cleaning from inside complete etc. as required (Deviation Qty :-100% to +30 %)				
4.01	150 mm wide x 38 mm deep raceway (1 compartment)	250.00	Mtr	₹ 500.00	₹ 1,25,000.00
4.02	50 mm wide x 38 mm deep raceway (1 compartment)	50.00	Mtr	₹ 300.00	₹ 15,000.00
5.00	Providing and fixing 300 x 300 x 50-70 mm deep GI (hot dip galvanized) cross over box made out of 1.6 mm thick sheet steel cross over box in under floor installation in complete as required as per specification.(Deviation Qty : -100% to +30 %)	10.00	Nos	₹ 700.00	₹ 7,000.00

Name of Work: Additional Works for Internal & External Electrical Installations and Signages at New International Terminal (T2) at Chennai Airport

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
6.00	Providing and fixing 225 x 225 x 50-70 mm deep GI (hot dip galvanized) cross over box made out of 1.6 mm thick sheet steel junction box in under floor installation in complete as required as per specification.(Deviation Qty : -100% to +30 %)	15.00	Nos	₹ 600.00	₹ 9,000.00
7.00	Providing and fixing 150 x 150 x 50-70 mm deep GI (hot dip galvanized) cross over box made out of 1.6 mm thick sheet steel junction box under floor installation in complete as required as per specification. (Deviation Qty : -100% to +30 %)	10.00	Nos	₹ 500.00	₹ 5,000.00
8.00	Supply and fixing of pop up type metal flush mounting box (floor mounted) on floor including Switch & sockets, connection & accessories etc. as required. (Deviation Qty : -100% to +30 %)				
8.01	3 Module (6 amps)	10.00	Nos	₹ 1,000.00	₹ 10,000.00
8.02	4 Module (6/16 amps)	6.00	Nos	₹ 1,000.00	₹ 6,000.00
9.00	Supply and fixing of pop up type metal flush mounting box (Furniture Mounted)including Switch & sockets, connection & accessories etc. as required.(Deviation Qty : -100% to +30 %)				
9.01	4 Module (6/16 amps)	5.00	Nos	₹ 1,200.00	₹ 6,000.00
10.00	Signages				
10.01	Providing and Fixing of computerised 3M vinyl cut text of approved matter in three language with directionional sign etc., in double colour on existing 5mm thick Polycarbonate sheet of different sizes as per site conditions including dismantling of existng polycarbonate sheet board from the existing signage board and remove the existing signage vinyl sticker over the polycarbonate sheet including cleaning of the complete polycarbonate surface without causing any damage and scratch over the surface and refixing the polycarbonate sheet on the existing sign board etc., as per direction of Engineer-in-Charge complete as required. (As per TATA Elxi standard) shall be got done	500.00	Sqft	₹ 3,000.00	₹ 15,00,000.00
11.00	Flour Mounted Sign Boards:Supply, Assembly, Installation, connecting ,testing commisioning of illuminated vinyl slim signage with 5mm thick polycarbonate sheet of following size(s) having the approved electrocut text matter (in three languagees) the signage frame shall be made 50mm wide powder coated colour RAL 9006 special aluminium extrusion with inbuilt frame and internal frame work shall be made of 25mm x 25mm x 1.3mm thick hollow squared sections shall be directly fixed to the sign frame. The sign board shall be fixed with 100mm x 100mm x 3mm thick mill finish Stainless steel square post (2Nos) including SS base plate and Gussets in 6mm thick with all hardware accessories. The SS plate with holes to fix it on holding down bolts anchored in concrete slab. The base plate shall be covered with a 3mm thick SS plate covering and approved by Engineerg-in-Charge. The pictographs boards with computerized automated self adhesive Translucent/coloured/blockout /white cast vinyl of 3M or coolybrite make having 2 or more layered facia as per requirement of approved art works including suitable ceiling mounting i/c gypsum board cutting and misc. ceiling works (if required) and make good the damage along with internal illumination acheived by using suitable 4Nos.12Volt 65watts LED strip (5mtrs.) 6500 K with 4Nos. 12 Volt driver complete with all internal wiring, connectors etc., as required as per the specification and approved drawings (Note: The item includes for providing 3x1.5sq.mm copper wiring i/c earthing in matalic flexible conduit from nearest source upto a distance of 5 mtrs.)				
11.01	Four Message board double side size: 1040mm (H) x 2100mm (B) X 50 mm (D)	3.00	Each	₹ 50,000.00	₹ 1,50,000.00
11.02	Five Message board double side size: 1300mm (H) x 2100mm (B) X 50mm (D)	2.00	Each	₹ 60,000.00	₹ 1,20,000.00


Name of Work: Additional Works for Internal & External Electrical Installations and Signages at New International Terminal (T2) at Chennai Airport

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
12.00	Flour Mounted Sign Boards:Supply, Assembly, Installation, connecting ,testing commisioning of illuminated vinyl slim signage with 5mm thick polycarbonate sheet of following size(s) having the approved electrocut text matter (in three languagees) the signage frame shall be made 50mm wide powder coated colour RAL 9006 special aluminium extrusion with inbuilt frame and internal frame work shall be made of 25mm x 25mm x 1.3mm thick hollow squared sections shall be directly fixed to the sign frame. The sign board shall be fixed with 100mm x 100mm x 3mm thick mill finish Stainless steel square post (2Nos) including SS base plate and Gussets in 6mm thick with all hardware accessories. The SS plate with holes to fix it on holding down bolts anchored in concrete slab. The base plate shall be covered with a 3mm thick SS plate covering and approved by Engineerg-in-Charge. The pictographs boards with computerized automated self adhesive Translucent/coloured/blockout /white cast vinyl of 3M or coolybrite make having 2 or more layered facia as per requirement of approved art works including suitable ceiling mounting i/c gypsum board cutting and misc. ceiling works (if required) and make good the damage along with internal illumination acheived by using suitable 4Nos.12Volt 65watts LED strip (5mtrs.) 6500 K with 4Nos. 12 Volt driver complete with all internal wiring, connectors etc., as required as per the specification and approved drawings (Note: The item includes for providing 3x1.5sq.mm copper wiring i/c earthing in matalic flexible conduit from nearest source upto a distance of 5 mtrs.)				
12.01	2100 X 285 X 50mm	10.00	Each	₹ 25,000.00	₹ 2,50,000.00
12.02	2100 X 575 X 50mm	10.00	Each	₹ 30,000.00	₹ 3,00,000.00
12.03	2100 X 865 X 50mm	15.00	Each	₹ 35,000.00	₹ 5,25,000.00

Total in Figures

₹ 44,28,000.00

Rupees Forty Four Lakhs Twenty Eight Thousand only


 (PRADIP KUMAR.B)
 Asst.Gen.Manager(E-E)

Signature Not Verified

Digitally signed by KANAPARTY RAMESH BABU
 Date: 2024.04.22 17:48:32 IST
 Location: eProcurement System for Central PSUs

