



भाविप्रा /औ'बाद/अभि.-वि/कैप/23-24/डब्लू -05/454-64
AAI/AU/Engg-E/CAP/23-24/W-05/

दिनांक: 03.01.2024

Date: 03.01.2024

सेवा में,
मेसर्स स्वाती एयरपोर्ट सपोर्ट सर्विसेस प्रा. लि
4-135, नेताजी कॉलोनी,
रोड नं 3, फते नगर,
हैदराबाद - 500018

To,
M/s Swati Airport Support Services Pvt. Ltd,
4 -135, Netaji Colony,
Road No 3, Fathe Nagar,
Hyderabad - 500018

(PAN No. AARCS2870G)
GST No. 36AARCS2870G1ZY

कार्य का नाम : औरंगाबाद हवाई अड्डे पर मौजूदा टर्मिनल भवन का पुनःनिर्माण। उपशीर्ष: औरंगाबाद हवाई अड्डे पर मौजूदा अंतरराष्ट्रीय अराइवल कन्वेयर बेल्ट और डिपार्च बैगेज हैंडलिंग सिस्टम (Make: Efacec) डिसमेंटलिंग और रिइन्स्टालेशन कार्य।

Reconfiguration of Existing Terminal Building at Aurangabad Airport. SH: Dismantling and Re-installation of existing international Arrival Conveyor Belt and Departure Baggage Handling System (Make: Efacec) at Aurangabad Airport.

संदर्भ : 1) निविदा आई. डी संख्या : 2023_AAI_176661_1

2) आपकी ई -निविदा जो दिनांक 22.12.2023 को खोली।

महोदय,/ Dear Sir (S),


- उल्लिखित कार्य हेतु आपकी ई - निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की और से आपके द्वारा बताए गये मद मूल्यों पर रु. **31,43,774.00** (रु. एकतीस लाख त्रीतालीस हजार सात सौ चौराहतर मात्र) (जी एस टी अतिरिक्त) के लिये स्वीकृत की जाती है जो कि अनुमानित लागत राशि रु. **33,51,400.00** से **6.20 %** कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 31,43,774.00** (Rupees Thirty One Lakh Forty Three Thousand Seven Hundred & Seventy Four Only) (Excluding GST) which is **6.20%** below the justification cost put to tender of **Rs.33,51,400.00**.

- वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, महाराष्ट्र कार्य के प्रभारी अभियंता होंगे, आपसे निवेदन है कि, आप दिनांक **13.01.2024** तक वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद, के कार्यालय में उपस्थित हों तथा करारनामे को पुरा करें. ठेके के करार नामा रुपये 100/- के नोनजुडिशियल स्टैम्प पर निष्पादित किया जायेगा तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा.

Senior Manager (E-E), AAI, Aurangabad Airport, Maharashtra, shall be the Engineer -In -Charge of the work. You are requested to attend the office of Senior Manager (E-E), AAI, Aurangabad Airport by **13.01.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one Hundred Only) and the cost of the stamp paper shall be borne by you.

विमानक्षेत्र नियंत्रक का कार्यालय, भा.वि.प्रा., औरंगाबाद, दूरभाष : (0240) 2477802,
O/O The Airport Director, AAI, Aurangabad. Phone No: (0240)2477802,


03/01/2024
व. प्रबं. अभि. वि.
वरि. प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा

3. आपके निविदा के साथ प्राप्त बयान राशि **67,028.00** रुपए को प्रतिभूति जमा के हिस्से के रूप में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर प्रतिभूति जमा राशि **2,47,349.00** रुपये ठेके के दस्तावेज के अनुसार जमा कर दें, अन्यथा निविदा में पृष्ठ जी सी सी 16 पर दी गई धारा 1(A) के अनुसार कटौती की जाएगी।

The earnest money amount of **Rs. 67,028.00** received along with your tender will be treated and converted as part of Security Deposit. Please deposit **Rs. 2,47,349.00** towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted as per condition of clause 1(A) at GCC Page 16 of the Contract Document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रवधानों के अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहा. प्रबंधक (अभियांत्रिकी - विद्युत), से मिलें वह आपको साईट सौंपने कि व्यवस्था करेंगे।

You are also directed to contact **Asstt. Manager (Engg-Elect.)**, AAI, Aurangabad Airport immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य करने का समय 06 (छह) माह रहेगा, जोकी कार्य आदेश जारी होने के दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** and same shall be reckoned from the 10th day of the date of placing of work order.

7. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।
If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

8. ई निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धी पत्र, प्रश्न, स्पष्टीकरण इत्यादि और उपर उल्लिखित पत्रों सहित उत्तरों के जवाब भी करारनाम के हिस्से होंगे।

All corrigendums, queries, clarifications etc, raised during e-tendering process and replies there of including the letters referred above shall also form part of the agreement.

9. इस ठेके के संबंध में आगे को कोई भी पत्राचार वरि. प्रबंधक (अभि.- विद्युत), भाविप्रा. औरंगाबाद हवाईअड्डा, औरंगाबाद - 431007 के पते पर किया जाए।


Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Elect), AAI, Aurangabad Airport, Aurangabad - 431007.

10. कृपया इस पत्र को स्वीकार करे और हस्ताक्षर करने के बाद इसके साथ संलग्न पत्र की डुप्लिकेट प्रति स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को वापिस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न : मात्रा की अनुसूची
Encl : Schedule of Quantity

भवदीय/ Yours faithfully,


08/01/2024

वरि. प्रबंधक [अभि - विद्युत]

Sr. Manager (E-E)

भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद
AAI, Aurangabad Airport, Aurangabad

वरि. प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा


Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg.-Electrical), Airports Authority of India, Aurangabad Airport, Aurangabad- 431007.

Name of Work: Reconfiguration of existing Terminal Building at Aurangabad Airport, Aurangabad SH: Dismantling and Re-installation of existing international Arrival Conveyor Belt and Departure Baggage Handling System (Make : Efacec) at Aurangabad Airport.


Tender ID: 2023_AAI_176661_1

Name of the Bidder/ Bidding Firm / Company :	M/s. Swati Airport Support Services Pvt Ltd					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
1	Design, Manufacturing and Supply of Transport Conveyor (Straight/declined/inclined/induction/T-Junction conveyor, etc.) along with drive unit for each section to match with x-ray machine level with minimum width of 1000mm between side walls suitable with existing BHS system make: Efacec complete in all respect and as per Technical Specifications.	20	Metre	89385.00	1787700.00	INR Seventeen Lakh Eighty Seven Thousand Seven Hundred Only
2	Design, Manufacturing and Supply of Draught Curtains in the openings wherever the conveyor pass through the walls, consisting of flexible overlapping slats of black belt strips as per site requirement. suitable with existing BHS system make: Efacec complete in all respect and as per Technical Specifications.	1	No.	32700.00	32700.00	INR Thirty Two Thousand Seven Hundred Only



 03/01/2024

व. प्र. अ. वि.
 वरि. प्रबंधक (अभि-विद्युत)
 नविका ओपन हवाई अड्डा

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
3	Design, Manufacturing and Supply of Motorized Fire Shutter of fire rating minimum 2 hours as per site requirement in the wall opening including limit switches, wiring & integration with control panel etc. suitable with existing BHS system make: Efacec complete in all respect and as per Technical Specifications.	1	No.	219000.00	219000.00	INR Two Lakh Nineteen Thousand Only
4.01	Installation, Testing and Commissioning (ITC) of following items for Departure & Arrival Conveyor System including minor civil works such as grouting of structures and making good the same including ITC of control panel along with necessary outgoing cables/wire, earthing for drive unit motor, limit switches, Emergency stop push buttons, indications, annunciation, IT network and control cables, power cabling etc. complete as required and as per Technical specifications. Transport Conveyor (Straight/declined/inclined/induction/T-Junction conveyor, etc.)	20	Metre	6654.00	133080.00	INR One Lakh Thirty Three Thousand & Eighty Only
4.02	Draught curtains	1	No.	8994.00	8994.00	INR Eight Thousand Nine Hundred & Ninety Four Only
4.03	Motorized Fire Shutter	1	No.	21800.00	21800.00	INR Twenty One Thousand Eight Hundred Only


 04/01/2024
 क. प्र. उ. अभि. वि.
 वरि. प्रबंधक (अभि-विद्युत)
 मसिमा औरंगाबाद हवाई अड्डा


NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
5	Dismantling & Re-installation of existing international arrival conveyor belt of Assembling, positioning, testing and commissioning of following with all accessories including minor Civil work such as Foundation etc. at the Airport site including installation, testing and commissioning of control panel along with necessary cables/wire, earthing for drive unit motor, rolling shutter motor & limit switches, Emergency stop push buttons, main and controls indications, annunciation, etc as required including power cabling complete as required. The following existing conveyor belt specification as per given point (i) & (ii). i) Heavy duty race track slat type inclined arrival baggage conveyor of loop length 54 m, measured along the centre line, useful width 1200 mm (minimum), having slope angle and speed of 24-30 metres/min (approx). Conveyor having die cast aluminium chain block, friction type suitable capacity drive unit compatible for soft starting mechanism, slat made of 2mm thick (minimum) stainless steel sloped plates with protective/ epoxy covering and dimensions with 3mm thick minimum M.S/ aluminium sheet painted slat support having loading capacity of 60 kg per meter linear, with stainless steel side covering, toe kick plate, trim/ fascia finish, emergency stop push buttons, chain track, drought curtains etc with all other accessories as required as per site conditions etc. ii) Heavy duty flat type arrival feeder baggage conveyor of 900 mm useful width with side covering, suitable for above feeding baggage conveyor having speed drive arrangement & complete with all required accessories. Feeder conveyor shall comprise of required horizontal sections, inclined sections & queuing section with necessary sensors for synchronized sequential feeding & energy efficient operations etc. as required. Feeder conveyor length : 23 metres. (Make: Efacec)	2	Job	305250.00	610500.00	INR Six Lakh Ten Thousand Five Hundred Only


 03/01/2024
 व. प्रबं. इ. अ. वि.
 वरि. प्रबंधक (अभि-विपुला)
 अविभा औरंगाबाद इकाई-अद्वय

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8
6	Dismantling & Re-installation of existing domestic departure baggage handling system of checking conveyor system in two sections comprising of weighing and despatch conveyors inclusive of drive unit for each conveyor section including topling devices of 20 Jobs & required section of take away/collector conveyors, tracking conveyors and horizontal transport conveyors inclusive of drive unit for each section of the above conveyors etc., as required totaling to length of 67 meters as per technical specification shape as per conveyor layout drawing. Power curves 2 Job inclusive of drive unit, Gravity roller conveyors of 3 mtrs. length. Control panel incorporating switch gears, protection devices, PLC microprocessor with all sensors including required numbers of ports and other components suitable for above conveyor system. (Make: Efacec)	1	Job	330000.00	330000.00	INR Three Lakh Thirty Thousand Only
Total in Figures					3143774.00	INR Thirty One Lakh Forty Three Thousand Seven Hundred & Seventy Four Only
Quoted Rate in Words		INR Thirty One Lakh Forty Three Thousand Seven Hundred & Seventy Four Only				

Signature Not Verified

Digitally signed by SATEESH KUMAR KANAOUJIYA
Date: 2024.07.05 11:50:41 IST
Location: eProcurement System for Central PSUs



मि. लोडा
03/07/2024
व. प्रब. शा. अ. अ.
वरि. प्रबंधक (अभि-विपुल)
महिला औरंगाबाद हवाईअड्डा