

भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

No. AAM/ENGG/ELEC/AMED-IX/ Signage /23-24/A-35

Date: 31.01.2024

M/s. Mirage Advertising World,
C-44, Phase - 1, Mangol Puri Industrial Area,
Behind Deep Hyundai,
Delhi - 110 083.


Name of Work: Provision of illuminated signage for Admin Block at Chennai Airport

Ref: Tender ID- 2023_AAI_177346_1

Dear Sir(s),

1. Your E-tender for the above-mentioned work has been accepted by the Competent Authority on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to ₹ 7,28,750.00 (Rupees Seven Lakhs Twenty-Eight Thousand Seven Hundred & Fifty Only) excluding GST which is 30.49% below the Estimated cost of ₹ 10,48,413.00 excluding GST put to tender.
2. Joint General Manager (Engg-Elect.), AAI, Chennai Airport, Chennai - 600 016 shall be the Engineer-in-Charge of the work. You are requested to attend to the Office of Joint General Manager (Engg-Elect.), AAI, Chennai Airport by 09.02.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value ₹ 100.00 (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
3. Please deposit an amount of ₹ 72,875.00 (Rupees Seventy-Two Thousand Eight Hundred Seventy-Five Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1A of Contract Document. Earnest Money Deposit amount will be returned back to your account after deducting equal amount of EMD against Security Deposit from your bill.
4. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act and Rules there of Central and State Governments.

फैक्स: 044 - 2256 0008 ई पी ए बी एक्स: 2256 0551, चेन्नई हवाई अड्डे, चेन्नई - 600 016
Fax: 044 - 2256 0008 EPABX: 2256 0551, Chennai Airport, Chennai - 600 016



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

5. Please note that the time allowed for carrying out the work shall be 03 (Three Months) and the same shall be reckoned with effect from 09.02.2024
6. You are also directed to contact Asst. Gen. Manager Engg. (Elect.), Airport Maintenance Electrical Division, Airports Authority of India, Operational Offices, Chennai Airport immediately for the execution of the above-mentioned work
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours faithfully,

(A. Mariappan)

Joint General Manager (Engg. -Elect.),
For and on behalf of the Chairman,
Airports Authority of India.


Encl: Schedule of Work (01 Page)

AIRPORTS AUTHORITY OF INDIA
CHENNAI AIRPORT::CHENNAI 600 016
SCHEDULE OF WORK

NAME OF WORK:- Provision of illuminated signage for Admin Block at Chennai Airport.

Sl. No	Description of Item	Unit	Qty	Basic Rate (Excluding GST)	Amount (Excluding GST)
1	Design, fabrication, supply and installation of illuminated signage board as per technical specifications, to the satisfaction of the Engineer-in-Charge. All exterior signs should be manufactured considering harsh outdoor conditions, weatherproofing techniques and materials shall be used. Sign Box The sign box shall be made in 4mm thick Aluminium composite panel in specified blue colour RAL 5013. Router cut, grooved and folded to achieve the desired shape and fixed with the internal frame structure. Sign Face The sign face shall be made in 4mm thick Aluminium composite panel in specified blue colour RAL 5013, provided with backlit LED lighting and shall have laser cut profiles to receive milky white 3mm thick poly carbonate sheet from back. All panels fixed using counter sunk screws. Internal Sign Structure Aluminum frame of 50mm x 25mm x 2mm shall be provided. Rectangular pipe to be provided inside the boxing & to screw the structure and make it rigid and to be fixed to the wall surface/ support structure to receive the sign face. Lighting Signboard shall be uniformly illuminated with adequate No. of LED strip/ Modules with LED life not less than 50,000 hrs with suitable rated weather proof driver (IP 67) to achieve required illumination level, suitable for 220 VAC operation input source to give constant brightness for all current variation, Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport Contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as required.	45	Sq.Mtr	₹ 11,750.00	₹ 5,28,750.00
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer with enamel painting all complete etc. as required.	1000	kg	₹ 180.00	₹ 1,80,000.00
3	Dismantling of the existing sign boards and transporting the same to AAI stores.	1	Job	₹ 20,000.00	₹ 20,000.00
Total (Excluding GST)					₹ 7,28,750.00

(Rupees Seven Lakhs Twenty Eight Thousand Seven Hundred and Fifty Only)


JGM (E-E)
AAI, Chennai Airport