



भारत 2023 INDIA
ONE EARTH - ONE FAMILY - ONE FUTURE



भारतीय विमानपत्तन प्राधिकरण / AIRPORTS AUTHORITY OF INDIA
विशाखपट्टणम हवाईअड्डा / VISAKHAPATNAM AIRPORT
ISO 9001:2015, ISO 14001:2015, ISO 45001:2018 & ISO 10002:2018 Certified

Ref: AAI/VZ/ENGG (E)/CW/WO-12/23-24/296-299

Date: 08/02/2024

To
M/s. Abhishek Integrations Ltd.,
801, Venus Benecia, Pakvan Dining Lane,
S. G. Highway, Bodakdev,
Ahmedabad - 380053.
Email : abhishekintegrationslimited@gmail.com

// SPEED POST //
email

Name of work : Supply and Laying of standby LT power cable from MSSR to EDVOR at Visakhapatnam Airport.

- Ref
1. Our tender ref. No. 2023_AAI_177416_1 at NIC CPP e-portal.
 2. Your price-bid opened on 25/01/2024.

प्रिय महोदय / Dear Sir(s),

1. ऊपर उल्लिखित कार्य के लिए आपका टेंडर जी.एस.टी छोड़कर उद्धृत दरों यानी - ₹ 16,74,871/- (केवल सोलह लाख चौहत्तर हजार आठ सौ इकहत्तर रुपए) पर भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से स्वीकार किया गया है, जो जी.एस.टी को छोड़कर अनुमानित लागत से 16.49% के नीचे है - ₹ 20,05,500/- (जी.एस.टी को छोड़कर)।

Your tender for the work mentioned above is here by accepted on behalf of the Chairman, Airports Authority of India at the quoted rates amounting to **Rs. 16,74,871/- (Rupees Sixteen lakhs seventy four thousand eight hundred and seventy one only)** excluding GST, which is **16.49% below** the estimated cost of **Rs. 20,05,500/- (Excluding GST)**.

2. वरिष्ठ प्रबंधक (अभि -वि)-II विशाखपट्टणम हवाईअड्डा कार्य के अभियंता प्रभारी होंगे। आपसे अनुरोध है कि अपने अधिकृत प्रतिनिधि को प्रतिनियुक्त करें जो वरिष्ठ प्रबंधक (अभि -वि)-II विशाखपट्टणम के कार्यालय में 19/02/2024 तक उपस्थित होकर अनुबंध समझौते पर हस्ताक्षर करके समझौते पूरा करने का अधिकार हैं। अनुबंध समझौते को १००/- मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टैप पेपर की लागत आपके द्वारा वहन की जाएगी।

Senior Manager Engg (Elect)-II, Visakhapatnam Airport shall be the Engineer-in-charge of the work. You are requested to depute your accredited representative, empowered to sign the Contract Agreement on your behalf to attend the office of the Senior Manager Engg (Elect)-II, Visakhapatnam by **19/02/2024** to sign and complete the Agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value of **Rs. 100/-** and the cost of the stamp paper shall be borne by you.

Anil Kumar Yadav
S.M.C.E.

वी.अनील कुमार यादव / V.Anil KumarYadav,
वरिष्ठ प्रबंधक (विद्युत) / Senior Manager (Elec),
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India,
विशाखपट्टणम हवाईअड्डा / Visakhapatnam Airport.

3. बयाना राशि आपके द्वारा यूटीआर नं. CH06376704 के द्वारा ₹ 40,110/- (चालीस हजार एक सौ दस) में जमा की जाती है, जिसका भुगतान सीपीपी पोर्टल के माध्यम से ऑनलाइन किया जाता है। कृपया इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में ₹ 1,67,487/- (एक लाख सड़सठ हजार चार सौ सत्तासी मात्र) जमा करें, ऐसा न करने पर आपके बिल से राशि काट ली जाएगी। अनुबंध दस्तावेज़ के जीसीसी पृष्ठ - 18 पर शर्त 1(A) के अनुसार।

Earnest money is deposited by you vide UTR No. CH06376704 for **Rs. 40,110/- (Rupees Forty thousand one hundred and ten only)** paid online through CPP portal. Please deposit **Rs. 1,67,487/- (Rupees One lakh sixty seven thousand four hundred and eighty seven only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your bill as per condition 1(A) on GCC page - 18 of the contract document.

4. आपसे अनुरोध है कि 1970 के ठेका श्रम (विनियमन और उन्मूलन) अधिनियम और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम, 1986 के प्रावधानों का पालन करने के लिए निर्माण श्रमिक (रोजगार और शर्तों का विनियमन) सेवा) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम, 1996 जैसा कि जीसीसी और न्यूनतम मजदूरी अधिनियम, 1948 और कर्मचारी भविष्य निधि और विविध में निर्दिष्ट है। प्रावधान अधिनियम, 1952 और ईएसआई अधिनियम, 1948 जैसा कि निविदा के जीसीसी और उसके नियमों में निर्दिष्ट है केंद्र और राज्य सरकारें।

You are requested to comply with the provisions of Contract Labour (regulation and Abolition) Act of 1970 and Contract Labour (regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act, 1986 Construction Workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other construction workers welfare cess Act, 1996 as specified in GCC and minimum wages act, 1948 and Employees Provident Fund & Misc. Provisions Act, 1952 and ESI Act, 1948 as specified in GCC of tender and rules thereof Central and State Governments.

5. आपको प्रबंधक (इंजी-विद्युत)-II, विशाखपट्टणम हवाईअड्डा से तुरंत संपर्क करने के लिए निर्देशित किया जाता है जो आपको साइट सौंपने की व्यवस्था करेगा।


You are also directed to contact Manager Engg. (Elect)-II / Visakhapatnam Airport immediately who will arrange to handover the site to you.

6. कृपया ध्यान दें कि कार्य पूरा करने के लिए अनुमत समय ०४ (चार) महीने का होगा जो इस पत्र जारी करने का १० वीं दिन से माना जाएगा।

Please note that time allowed for completion of the work shall be **04 (Four) months** which shall be reckoned from **10th day** of placing the letter.

7. इस संविदा के संबंध में आगे की कोई पत्राचार के लिए **वरिष्ठ प्रबंधक (अभि-वि)-II**, भा.वि.प्रा, विशाखपट्टणम - ५३०००९ को संबोधित किया जाना चाहिए।

Any further correspondence in connection with this contract should normally be addressed to **Senior Manager Engg (Elect)-II**, AAI, Visakhapatnam Airport, Visakhapatnam - 530 009.


SM(E-E)


8. कृपया प्राप्ति की पावती भेजें और स्वीकृति टोकन के रूप में अधोहस्ताक्षरी की हस्ताक्षर के बाद इस पत्र की डुप्लिकेट कॉपी को वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न: 02 पृष्ठ की अनुसूची

Encl : Schedule of quantities 02 page

भवदीय / Yours faithfully,


08/02/2024

[वि अनिल कुमार यादव / V. ANIL KUMAR YADAV]
वरिष्ठ प्रबंधक (अभि -वि)-II / Senior Manager Engg. (Elect) -II
आधायक्ष, भा वि प्रा, की ओर से / On behalf of Chairman, AAI
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
विशाखपट्टणम हवाई अड्डा / Visakhapatnam Airport
विशाखपट्टणम / Visakhapatnam - 530 009

ध्यान दें : व्याख्या के संबंध में किसी भी विवाद की स्थिति में अंग्रेजी पाठ को प्रामाणिक माना जाएगा।

Note : In the event of any dispute regarding interpretation the English text will be treated as authentic.

WORK ORDER SCHEDULE OF QUNTITIES - 'A'

Name of work: Supply and Laying of standby LT power cable from MSSR to EDVOR at Visakhapatnam Airport.

Sl. No.	Brief Description	Qty	Unit	Rate	Amount
1.00	Supply of 3.5 Core x 120 Sqmm size XLPE insulated PVC sheathed Aluminium conductor armoured power cable of 1.1 KV grade confirming to IS 7098 (part1)1988 with upto date amendments etc., complete as required.	2000	mtr	513.00	1026000.00
2.00	SITC of out door cable junction box of IP 65 enclosure, 200A TPN aluminum busbar with power coated standing on MS base frame with legs of suitable height as per site condition etc., complete as required.	4	Each	15660.00	62640.00
3.00	Supplying and fixing cable route marker with 10 cm x 10 cm x 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm x 6 mm angle iron, 60 cm long and fixing the same in ground as required.	60	Each	480.00	28800.00
4.00	Supplying and Making end termination with brass compression gland and aluminium lugs for 3.5 core 120 sq.mm XLPE insulated and PVC sheathed 1.1KV grade Aluminium cable etc., as required. 3½ x 120 sq. mm (45mm)	15	Set	1400.00	21000.00
5.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level)including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	1700	mtr	197.00	334900.00
6.00	Laying of one number XLPE insulated and PVC sheathed power cable of 1.1 KV grade of size Above 95 sq. mm and upto 185 sq. mm in the existing RCC/ HUME/ METAL pipe as required. Above 95 sq. mm and upto 185 sq. mm	1712	mtr	20.00	34240.00
7.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 95 sq. mm and upto 185 sq. mm	12	mtr	20.00	240.00
8.00	Providing, laying and fixing 50mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required	20	mtr	1355.00	27100.00
9.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	6	Cub	1500.00	9000.00
10.00	Earthing with G.I. earth pipe 4.5 mtr long, 40mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with Char coal/coke and Salt as required.	8	Set	7490.00	59920.00

Amr
SME-E

Sl. No.	Brief Description	Qty	Unit	Rate	Amount
11.00	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	80	mtr	130.00	10400.00
12.00	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	60	mtr	35.00	2100.00
13.00	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 3 ½ x 120 Sqmm size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	3	each	4368.00	13104.00
14.00	SITC of 200Amps Four Pole Onload Changeover Switch in Sheet Steel Enclosure including all necessary arrangements as per site condition etc., complete as required.	1	each	13648.00	13648.00
15.00	SITC of 3HP/2.2KW Monobloc Pump with Minimum Speed of 2810 RPM, Minimum Head of 14 mtr, Discharge of minimum 4.9 LPS Suitable to operate 415 Volts, 50Hz, AC Supply and including all necessary arrangements as per site condition etc., complete as required.	1	each	21699.00	21699.00
16.00	SITC of DOL Starter Panel for 3HP/2.2KW Monobloc pump with Single phase preventor and Relay range of 4-6.5 Amps, suitable to operate 415Volts, 50Hz, AC Supply and including all necessary arrangements as per site condition etc., complete as required.	1	each	10080.00	10080.00
	Total :				1674871.00
	Say				1674871.00

(Rupees Sixteen lakhs seventy four thousand eight hundred and seventy one only)

* Rates quoted are excluding GST

Amul
08/02/2024

Senior Manager Engg. (Elect.)
AAI / Visakhapatnam

Signature Not Verified

Digitally signed by Aditya Raghunandan Burra
Date: 2024.07.18 12:25:41 IST
Location: eProcurement System for Central PSUs