



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

सं.भा.वि.प्रा./डिब/अभि.-सिविल/मेन्त/ W0-15/विविध. काम(गैर-परिचालन)/२३-२४/ दिनांक: 14/02/2024
Ref.No.AAI/DIB/Engg-Civil/Maint/W0-15/Misc. Work(Non-ops)/23-24 Dated: 14/02/2024

To,

M/s Pavee Construction,
Prop. Sh. Pardeep Kumar,
Regd. Office Main Street Gonder,
Gonder 35, Gonder,
Karnal Haryana -132024,
Email:-paveeconstruction@gmail.com

विषय: डिब्रूगढ़ हवाई अड्डे पर गैर-परिचालन क्षेत्र में विविध कार्य।

Name of Work: Miscellaneous Works in Non-operational area at Dibrugarh Airport.

संदर्भ: निविदा क्रमांक - 2023_AAI_179359_1 (कार्य की वित्तीय ई-बोली 24/01/2024 को खोली गई)

Ref.: Tender ID No.2023_AAI_179359_1 (Financial E-Bid for the work opened on 24/01/2024).

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल **₹2,31,07,700.00** (दो करोड़ इकतीस लाख सात हजार सात सौ मात्र) गुड्स एंड सर्विस टैक्स के बिना, जो कि निविदा की प्राक्कलित मूल्य **₹2,87,54,050.00** से -19.64% नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.2,31,07,700.00 (Two crores Thirty One Lakhs Seven Thousand Seven Hundred Only) excluding GST** which is -19.64% (Nineteen Point Six Four Percent) below the estimate cost put to tender **₹.2,87,54,050.00.**

- वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल) एएआई, डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़, कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए 09/03/2024 तक वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल), एएआई, डिब्रूगढ़ हवाई अड्डे के कार्यालय में उपस्थित हों। अनुबंध अनुबंध 100/- रुपये (एक सौ रुपये मात्र) के गैर-न्यायिक स्टांप पेपर पर निष्पादित किया जाएगा और स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Senior Manager(Engg-Civil) AAI, Dibrugarh Airport, Dibrugarh, shall be the Engineer-In-Charge of the work. You are requested to attend the office of **Senior Manager (Engg-Civil)**, AAI, Dibrugarh Airport by **09/03/2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने के 10 दिनों के अन्दर प्रतिभूति जमा के रूप में **₹ 23,10,770.00 (तेईस लाख दस हजार सात सौ सत्तर मात्र)** की राशि इस कार्यालय में जमा करा दें अन्यथा संविदा की सामान्य शर्तों के खंड 1 A पृष्ठ संख्या जी.सी.सी 1 7 पर खंड 1A कि शर्त के अनुसार घटाया जाएगा।

Please deposit **Rs.23,10,770.00. (Rupees Twenty Three Lakhs Ten Thousand Seven Hundred Seventy Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per GCC Clause 1A on page 17 of the contract document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्तों) के प्रावधान का पालन करें।) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड 19 पृष्ठ संख्या 50 पर में निर्दिष्ट है और संविदा की सामान्य शर्तों के पेज नं 89 और केंद्र और राज्य सरकार के नियम।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) central rules 1971, Child labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause 19 on page no. 50 and page no. 89 of GCC of tender and rules of Central and State Govt.

5. आपको यह भी निर्देश दिया जाता है कि आप **सहायक प्रबंधक (अभि.-सिविल), भा.वि.प्रा., डिब्रूगढ़** से अविलम्ब संपर्क करें जो आपको कार्यस्थल सौपने की व्यवस्था करेंगे।

You are also directed to contact **Asstt. Manager (Engg-Civil), AAI, Dibrugarh Airport, Dibrugarh** immediately who will arrange to hand over the work to you.

6. कृपया ध्यान दें कि कार्य करने के लिए नियत समय **04 (चार) महीने जिसमें 01 (एक) माह वर्षा शामिल है** होगा जिसकी गणना इस पत्र के जारी होने के 10 वें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be **04 (Four) months including 01 (One) month rain** and same shall be reckoned from the 10th day after issue of this letter.

7. अनुबंध के संबंध में कोई भी आगे का पत्राचार आम तौर पर **प्रभारी अभियंता यानी वरिष्ठ प्रबंधक (इंजीनियरिंग-सिविल)**, भारतीय विमानपत्तन प्राधिकरण, डिब्रूगढ़ हवाईअड्डा - 786012 को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the **Engineer-In-Charge i.e. Senior Manager (Engg-Civil)**, Airports Authority of India, Dibrugarh Airport - 786012.

8. कृपया इस पत्र के प्राप्ति की सूचना दें तथा इसके साथ संलग्न इस पत्र की प्रतिलिपि पर विधिवत हस्ताक्षर करने के उपरांत स्वीकृति के प्रमाण स्वरूप इसे अधोहस्ताक्षरी को वापस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancy is found then English version will be taken as correct.

धन्यवाद / Thanking you,

संलग्न: Item Rate SOQ. (Page-01 to 06)

भवदीय/Yours Sincerely,



पंकज कुमार मिश्रा (Pankaj Kumar Mishra)

वरिष्ठ प्रबंधक (इंजीनियरिंग.-सिविल)/ Senior Manager (Engg.- Civil)
कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI
भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन / AAI, Dibrugarh Airport

Validate

Print

Help

Tender Inviting Authority: Pankaj Kumar Mishra, SME(Engg-Civil), AAI, Dibrugarh Airport

Name of Work/Miscellaneous works in Non-operational area at Dibrugarh Airport

Contract No: 2023_AAI_179359_1

Item Rate BoqName of the Bidder/
Bidding Firm
/ Company :

Pavee Construction

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge. All kinds of soil	1850.00	sqm	120.00	222000.00	INR Two Lakh Twenty Two Thousand Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	2677.00	cum	250.00	669250.00	INR Six Lakh Sixty Nine Thousand Two Hundred & Fifty Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	970.00	Cum	250.00	242500.00	INR Two Lakh Forty Thousand Five Hundred Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	25.00	Cum	5500.00	137500.00	INR One Lakh Thirty Seven Thousand Five Hundred Only
5	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	25.00	Sqm	400.00	10000.00	INR Ten Thousand Only
6	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	65.00	Sqm	400.00	26000.00	INR Twenty Six Thousand Only
7	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Suspended floors, roofs, landings, balconies and access platform	100.00	sqm	400.00	40000.00	INR Forty Thousand Only

8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars Grade of steel: Fe 500	7800.00	Kg	72.00	561600.00	INR Five Lakh Sixty One Thousand Six Hundred Only
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level 5.22A.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.	7800.00	Kg	72.00	561600.00	INR Five Lakh Sixty One Thousand Six Hundred Only
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	60.00	Cum	7500.00	450000.00	INR Four Lakh Fifty Thousand Only
11	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	105.00	cum	6200.00	651000.00	INR Six Lakh Fifty One Thousand Only
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) /AAC Block	49.00	cum	7500.00	367500.00	INR Three Lakh Sixty Seven Thousand Five Hundred Only
13	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	4430.00	Kg	120.00	531600.00	INR Five Lakh Thirty One Thousand Six Hundred Only
14	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	2000.00	kg	130.00	260000.00	INR Two Lakh Sixty Thousand Only
15	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	380.00	sqm	350.00	133000.00	INR One Lakh Thirty Three Thousand Only
16	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	250.00	sqm	350.00	87500.00	INR Eighty Seven Thousand Five Hundred Only
17	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	70.00	sqm	350.00	24500.00	INR Twenty Four Thousand Five Hundred Only
18	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	200.00	Sqm	150.00	30000.00	INR Thirty Thousand Only
19	Dispersing with 1st quality acrylic dispenser, having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour. Two coats.	1000.00	sqm	100.00	100000.00	INR One Lakh Only
20	Painting with synthetic enamel paint of approved brand and manufacturer to give an even shade : Two or more coats on new work.	210.00	sqm	100.00	21000.00	INR Twenty One Thousand Only
21	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	1050.00	sqm	850.00	892500.00	INR Eight Lakh Ninety Two Thousand Five Hundred Only

RS

22	Providing and applying 2.5 mm thick road making strips (retroreflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-Charge and accordance with applicable specifications.	550.00	Sqm	550.00	302500.00	INR Three Lakh Two Thousand Five Hundred Only
23	Providing and fixing precast galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (+0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	2500.00	Sqm	800.00	2000000.00	INR Twenty Lakh Only
24	Providing and fixing precast galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	300.00	metre	800.00	240000.00	INR Two Lakh Forty Thousand Only
25	Providing and fixing precast galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter (600 mm over all girth)	600.00	metre	850.00	510000.00	INR Five Lakh Ten Thousand Only
26	Providing and laying mat finished vitrified tile of size 300x300x16mm having water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in out door floors such as footpath, court yard multi models etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as direction of Engineer-in-Charge.	950.00	sqm	1200.00	1140000.00	INR Eleven Lakh Forty Thousand Only
27	Providing and inserting 12mm dia galvanised steel injection nipple in honey comb area and along crack line including drilling of holes of required diameter (20mm to 30mm) up to depth from 30mm to 80mm at required spacing and making the hole & crack dust free by blowing compressed air, sealing the distance between injection nipple with adhesive chemical of approved make and allow it to cure complete as per direction of Engineer-In-Charge	100.00	Each	180.00	18000.00	INR Eighteen Thousand Only
28	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/ masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.) a) Stirrer mixed SBR Polymer (of approved make) modified Cement slurry made with Shrinkage Compensating Cement in concrete/RCC work	350.00	Kg	100.00	35000.00	INR Thirty Five Thousand Only
29	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/ masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.) A) Epoxy injection grout in concrete/RCC work of approved make	350.00	Kg	90.00	31500.00	INR Thirty One Thousand Five Hundred Only

Signature

30	Providing and laying six courses water proofing treatment with bitumen felt over roof's consisting of first, third and fifth courses of blown or / and residual bitumen applied hot at 1.45, 1.20 and 1.70 kg per square metre of area respectively, second and fourth courses of roofing felt type 2 grade II (glass fibre base self finished bitumen felt) and sixth and final course of stone grit 6 mm and down size or pea sized gravel spread at 6 cubic decimetre per sqm including preparation of surface but excluding grading, complete.	590.00	sqm	650.00	383500.00	INR Three Lakh Eighty Three Thousand Five Hundred Only
31	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. 13.52.1 On steel work	600.00	Sqm	150.00	90000.00	INR Ninety Thousand Only
32	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level. Cement mortar 1:4 (1 cement :4 coarse sand)	100.00	Sqm	950.00	95000.00	INR Ninety Five Thousand Only
33	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	100.00	Kg	450.00	45000.00	INR Forty Five Thousand Only
34	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	740.00	cum	2600.00	1924000.00	INR Nineteen Lakh Twenty Four Thousand Only
35	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge	740.00	cum	2600.00	1924000.00	INR Nineteen Lakh Twenty Four Thousand Only
36	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	555.00	cum	6200.00	3441000.00	INR Thirty Four Lakh Forty One Thousand Only
37	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern	3700.00	sqm	900.00	3330000.00	INR Thirty Three Lakh Thirty Thousand Only
38	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand).	29.00	cum	7500.00	217500.00	INR Two Lakh Seventeen Thousand Five Hundred Only

PR

39	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	2.00	cum	3000.00	6000.00	INR Six Thousand Only
40	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	140.00	kg	10.00	1400.00	INR One Thousand Four Hundred Only
41	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	95.00	Sqm	400.00	38000.00	INR Thirty Eight Thousand Only
42	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand/zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	10.00	cum	7500.00	75000.00	INR Seventy Five Thousand Only
43	Providing and fixing M.S. angle 50x50x5 mm to act as nosing with lugs of M.S. flat 10x5 mm, 10 cm long, forked at end 60cm apart (minimum three lugs to be provided), including necessary welding and applying a priming coat of approved primer on exposed surface etc. complete.	705.00	Kg	150.00	105750.00	INR One Lakh Five Thousand Seven Hundred & Fifty Only
44	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	200.00	metre	280.00	56000.00	INR Fifty Six Thousand Only
45	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 lit/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	840.00	sqm	100.00	84000.00	INR Eighty Four Thousand Only
46	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chajjas, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done.	300.00	Sqm	250.00	75000.00	INR Seventy Five Thousand Only
47	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	16.00	Cum	250.00	4000.00	INR Four Thousand Only

48	Providing and filling. Boulders or river shingles of size ranging from 150 mm to 225 mm in layers not exceeding 25 cm in foundations upto plinth including filling voids/gaps with sand or graded river pebbles, watering and compacting with earth rammers or suitable compactors of sufficient capacity to achieve required density to the required thickness for improving the foundation soil all complete as per direction and satisfaction of Engineer-in-charge. (Note : Please read the Technical specifications of the item on before quoting).	30.00	Cum	2300.00	69000.00	INR Sixty Nine Thousand Only
49	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in : Cement mortar 1:6 (1 cement : 6 Coarse sand)	3.00	Each	7500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
50	Job contract for providing backhoe loader (JCB) i/c diesel, Driver and helper for clearing wild growth, levelling of ground etc. inside operational area including fuel, hydraulic oil, operator etc. complete. all complete as per satisfaction and Direction of Engineer-in-charge.	50.00	day	8500.00	425000.00	INR Four Lakh Two Thousand Five Hundred Only
51	Job contract for providing Tipper i/c diesel, Driver and helper inside operational area including fuel, hydraulic oil, operator etc. complete. all complete as per satisfaction and Direction of Engineer-in-charge.	50.00	day	8000.00	400000.00	INR Four Lakh Only
Total in Figures					23107700.00	INR Two Crore Thirty One Lakh Seven Thousand Seven Hundred Only
Quoted Rate in Words		INR Two Crore Thirty One Lakh Seven Thousand Seven Hundred Only				

Signature

Signature Not Verified
 Digitally signed by Bonny Bastian
 Date: 2024.07.15 19:04:25 IST
 Location: eProcurement System for Central PSUs