


	ORDNANCE FACTORY MEDAK HYDERABAD A UNIT OF ARMOUR VEHICLES NIGAM LIMITED GOVERNMENT OF INDIA ENTERPRISE MINISTRY OF DEFENCE YEDDUMAILARAM SANGAREDDY DISTRICT-502 205 PH:040-23283278, Fax:040-23292950, 08455-239074 Email: engg.ofmk@ord.gov.in	
---	---	---

No. 76025/OFMK/EO(CIVIL)/BLDG 151/23-24

DATE:24-08-2023

To

M/s Bantu Suresh Goud Civil Contractor
Shankarpally - 501 203.

Sir,

Sub: Repairs to Halls of Bldg. No. 151 at estate area of OFMK.

Ref: i) Tender No. 76025/**TE-19**/EOC/OFMK/BLDG 151/23-24, dtd: 22-07-2023
(Opened on: 22/07/23).

ii) Your CPPP Quotation.

* * * * *

For and on behalf of the President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 8,04,920/-** (Rupees Eight Lakh Four Thousand Nine Hundred Twenty Only) and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Annexure 'A'.

2. The contract is allotted with No. **CGM/OFMK/EO(C)/08 OF 2023-24 Dated 24/08/2023** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the **Security Deposit of Rs. 20,500/-** (Rupees Twenty Thousand Five Hundred Only) in favour of "**AVNL, Ordnance Factory Medak**" as mentioned in tender condition.


The maturity date of security Deposit shall be minimum **14 months** from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. SHRI G ELISHA JWM/IMS and SHRI PRAKASH MOHAPATRA JWM/IMS are nominated as Engineer-in-Charge and Site In-charge for the subject work respectively.

SIGN OF CONTRACTOR


JT.GM/EO
FOR CHIEF GENERAL MANAGER






ORDNANCE FACTORY MEDAK HYDERABAD

A UNIT OF ARMOUR VEHICLES NIGAM LIMITED
GOVERNMENT OF INDIA ENTERPRISE
MINISTRY OF DEFENCE
YEDDUMAILARAM

SANGAREDDY DISTRICT-502 205
PH:040-23283278, Fax:040-23292950, 08455-239074
Email: engg.ofmk@ord.gov.in



6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within sevendays from the date of receipt of this communication.


Copy to:

1. FINANCE/OFMK
2. SHRI G ELISHA JWM/IMS
3. SHRI PRAKASH MOHAPATRA JWM/IMS

SIGN OF CONTRACTOR

JT.GM/EO

FOR CHIEF GENERAL MANAGER

	ORDNANCE FACTORY MEDAK HYDERABAD A UNIT OF ARMOUR VEHICLES NIGAM LIMITED GOVERNMENT OF INDIA ENTERPRISE MINISTRY OF DEFENCE YEDDUMAILARAM SANGAREDDY DISTRICT-502 205 PH:040-23283278, Fax:040-23292950, 08455-239074 Email: engg.ofmk@ord.gov.in	

IN LIEU OF IAFW-1823(REVISED)

CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	08 OF 2023-24, dated 24/08/2023
Acceptance letter No.	76025/OFMK/EOC/BLDG. 151/23-24
Contractor's Name	BANTU SURESH GOUD
Name of the work	Repairs to Halls of Bldg. No. 151 at estate area of OFMK.
CA amount	Rs 8,04,920/-

PARTICULARS

1. Authority	CWC decision No. II
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm quotation for all Terms & Conditions therein & ratequoted in Annexure 'A'
3. Time effect	
a. Date of handing over of the site	25/08/2023
b. Date of commencement of work	26/08/2023
c. Date of Completion as per contract	26/12/2023
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs 8,04,920/-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	2079/111/809/01
6. Certified that no special rate is involved	
7. Technical Examiner	Shri P.R. Choudhary DGM/MP
8. Approved	Shri Ravi Singh JT.GM/EO
9. Accepted	M/s Bantu Suresh Goud Civil Contracor

Distribution to:

1. CONTRACTOR
2. FIANNCE/OFMK
3. SHRI G ELISHA JWM(SG)/IMS
4. SHRI PRAKASH MOHAPATRA JWM/IMS
5. SHRI P.R. CHOUDHARY, DGM/MP

SIGN OF CONTRACTOR


JT.GM/EO
FOR CHIEF GENERAL MANAGER

	ORDNANCE FACTORY MEDAK HYDERABAD A UNIT OF ARMOUR VEHICLES NIGAM LIMITED GOVERNMENT OF INDIA ENTERPRISE MINISTRY OF DEFENCE YEDDUMAILARAM SANGAREDDY DISTRICT-502 205 PH:040-23283278, Fax:040-23292950, 08455-239074 Email: engg.ofmk@ord.gov.in	
---	--	---

TERMS & CONDITIONS:

- 1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.
- 2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory and a record contractor has to maintain attendance and wages register has to pay their workmen in presence of Site-In-Charge of the work who is the authorised representative of principle employer. The Site-In-Charge shall endorse in the wages register that payment is made in his presence.
- 3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support in

 - (i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the work spot so that in case of accident fall, there might not be any fatality.
 - (ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.
 - (iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.
 - (iv) The contractor shall clear the site after completion of work.
 - (v) The contractor must employ the labour force duly insured against life risk.
 - (vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

DEVIATION CLAUSE:

- (i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.
- (ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.
- (iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)
- (iv) 10% of Work Order value (Contract value exceeding Rs.10 lakhs)

SIGN OF CONTRACTOR


RAVI SINGH
 JOINT GENERAL MANAGER
 FOR CHIEF GENERAL MANAGER
 FOR & ON BEHALF OF PRESIDENT OF INDIA

Name of the work : Repairs to Halls of Bldg. No. 151 at estate area of OFMK.

C.A. No. CGM/OFMK/EO(C)/08 OF 2023-24, dtd: 24-08-2023

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1	False Ceiling : S&F Exposed metal frame ceiling with calcium silicate board of siliceous and calcareous material 8 mm thk. reinforced with cellulose fibre for fixing in 600 mm x 600mm grid.	370.00	Sqm	450.00	166500.00
2	Snap Grid : S&F Anodised aluminium snap grid frame work Size of grid 605 x 605mm for false ceiling all as specified.	330.00	Sqm	480.00	158400.00
3	Dismantling False Ceiling : Dismantling Wall and ceiling boards (fibre, pulp, insulation, etc.) or insulation boards/slabs/ blankets, any thickness, including cover fillets.	370.00	Sqm	40.00	14800.00
4	Dismantling floor carpets : Dismantling Textile coverings including frames (if any) and cover fillets.	340.00	Sqm	38.00	12920.00
5	Carpet : Supply & Fixing of polypropylene floor carpet roll min. 4mm thickness for auditorium flooring including fixing to hard wood floors by means of staples, nails and/or approved adhesive.	340.00	Sqm	600.00	204000.00
6	OBD on walls : M&L :Distemping walls with distemper oil emulsion(1 coats), with colour matching with existing colour or as specified. Brand: Asian Paints Tractor Uno/ Nerolac Beauty/ Berger Bison	1000.00	Sqm	40.00	40000.00
7	Window Glass : S&F of Sheet glass, ordinary quality, 4 mm thk. and glazing with oil putty in square n exc 0.5 sq. m in each pane.	20.00	Sqm	690.00	13800.00
8	Repairs to Floor Boards : Repairs to existing floors in patches, including cutting out, piecing, heading joints etc for Boarding in Floors and Skirting, 25 mm thk 2nd class hardwood, Planed one side,	5.00	Sqm	1900.00	9500.00
9	Removing building materials etc. (other than spoil) to a distance of 100m or under, beyond the lead included in the rates, including loading, unloading and stacking at the destination.	5.00	Per Load	100.00	500.00
10	Point wiring: S&F /Drawing of cables in PVC conduit of 1"or 3/4" Dia ,one Light point or one fan point controlled by one switch with cables 1.5 sq.mm size of FR PVC copper conductor, Each point should have separte phase,neutral and earth wire. Make: Finolex/ Havells/Polycab/L&T in PVC conduit,includes all accessories like tees,screws,clips ,plugs, clamps, junction boxes, cutting holes in or through walls,fixing of boards and grouted into the wall,earth wire etc and testing as specified. All connections to be given by copper Pin/eye type lugs including for earth connections.	10.00	Each	950.00	9500.00
11	LED LIGHT FITTING : S&F of LED Light Fittings 2 feet x 2 feet recessed mounting, 45-50 watt, 220V, CCT cool white(5500K-6500K). Warranty - minimum 3 years. complete with all accessories. make: crompton/wipro/Philips. Complete all as specified and directed.	35.00	Each	5000.00	175000.00
Total					8,04,920.00

SIGN OF CONTRACTOR


 JT.GM/EO