

ACCEPTANCE LETTER No : MINUTES OF CWC - I HELD ON 13-10-2023

To

S. VINAYAGAMURTHY,
No. 1201, TNHB, KAKALUR SCHEME,
THIRUVALLUR – 602001

Dear Sirs,

Type of Work: ITEM RATE

Sub : **REPAIRS / REPLACEMENT OF DAMAGED MAIN SEWER LINE IN TYPE-V/7, TYPE-IV-10,11
AND TYPE-III-47, TYPE-II-69, TYPE-I-74 BLOCKS AT HVF ESTATE.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2023-24/27, Dt. 04-07-2023 with Tender ID: 2023_AVNL_159795_1
(ii) Your Bid No: 582404 in this tender & Price reduction offered vide email Dt. 10-10-2023.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 48,36,330 /- (Rupees Forty Eight Lakhs Thirty Six Thousand Three Hundred and Thirty Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/19/2023-24/Maint., dated 19-10-2023** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 1,21,000 /- (Rupees One Lakh and Twenty One Thousand Only) in favour of "Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.


The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. G. Ananda Kumar, WM / IMS is nominated as Engineer-in-Charge and Shri. C. Prem Kumar, JWM / IMS / CE (E) & Shri. S. Arunachalam, CM / IMS / CE (E), are nominated as Site In-charges for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :


1. GM / HR & F&A, HVF, Avadi, Chennai - 600054
2. Shri. G. Ananda Kumar, WM / IMS - Engineer -In- Charge
3. Shri. C. Prem Kumar, JWM / IMS / CE(E) - Site -In- Charge
4. Shri. S. Arunachalam, CM / IMS / CE (E) - Site -In- Charge
5. Shri. Prempal Singh, AWM / MM (GA) & CEO - Technical Examiner

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/19/2023-24/MAINT., dated 19-10-2023
Acceptance letter No.	MINUTES OF CWC - I HELD ON 13-10-2023
Contractor's Name	S. VINAYAGAMURTHY
Name of the work	REPAIRS / REPLACEMENT OF DAMAGED MAIN SEWER LINE IN TYPE-V/7, TYPE-IV-10,11 AND TYPE-III-47, TYPE-II-69, TYPE-I-74 BLOCKS AT HVF ESTATE. .
CA amount	Rs. 48,36,330 /-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 582404 in this tender & Price reduction offered vide email Dated 10-10-2023 in HVF/TE/13025/CEO/2023-24/27, Dt. 04-07-2023 with Tender ID: 2023_AVNL_159795_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	26/10/2023
b. Date of commencement of work	26/10/2023
c. Date of Completion as per contract	22/06/2024
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 48,36,330 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	809 / 02 (Revenue Grant)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. Prempal Singh, AWM / MM (GA) & CEO
8. Approved	Shri. K. Tulasi Rao, Jt. GM / IMS, EO & GS
9. Accepted	S. VINAYAGAMURTHY



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :--


1. S. VINAYAGAMURTHY
2. GM / HR & F&A, HVF, Avadi, Chennai - 600054
3. Sr. Security Officer
4. Shri. G. Ananda Kumar, WM / IMS - Engineer -In- Charge
5. Shri. C. Prem Kumar, JWM / IMS / CE (E) - Site-In- Charge
6. Shri. S. Arunachalam, CM / IMS / CE (E) - Site-In-Charge
7. Shri. Prempal Singh, AWM / MM (GA) & CEO - Technical Examiner
8. HOS/Safety, 9. HOS/Internal Audit cell, 10. HOS/Test Audit, 10. ALWC,
11. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai - 600034
12. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai - 600006.

SCHEDULE – “A”

Item Code	Item Description	Quantity	Unit	Rate/Unit (Rs.)	Total Cost (Rs.)
1	Demolition of brick work or stone / boulder masonry built in cement mortar or cement lime mortar	21.00	CUM	510.00	10710.00
2	M & L for cutting down the branches and Grubbing up tree trunk including cutting of trunk portion protruding over ground, digging out roots, filling holes and leveling off ground, stacking of serviceable material and removing of unserviceable material to a distance n exc. 50 m and clearing site (girth exc 30 cm and n.exc. 100cm)	20.00	Each	1850.00	37000.00
3	Material and labour for excavation of hard dense soil not exceeding 1.5m deep and getting out	1600.00	CUM	665.00	1064000.00
4	Material and labour for excavation of hard dense soil exceeding 1.5m deep and getting out	470.00	CUM	735.00	345450.00
5	Material and labour for use of timbering as planking and strutting for excavations in trenches exc. 1.5m not exc. 3.00m deep in soil, including wales, struts, open poling boards, etc., as may be necessary and fixing and removal to avoid the caving of the earth work.	750.00	SQM	177.00	132750.00
6	Road cutting work in soft/ disintegrated soil for foundation width and depth not exceeding 1.50m and getting out.	55.00	CUM	1300.00	71500.00
7	Demolition and breaking up drain pipes 200MM (Salt glazed ware, AC or Reinforced concrete) set in cement mortar.	100.00	RM	40.00	4000.00
8	Demolition and breaking up drain pipes 150MM (Salt glazed ware, AC or Reinforced concrete) set in cement mortar.	300.00	RM	40.00	12000.00
9	Material and labour for sand filling under floors or in foundations including watering and consolidation	80.00	CUM	2150.00	172000.00
10	Material and labour for PCC Type C2 1:3:6 40mm graded aggregate cement concretes in foundations, filling and mass concrete	115.00	CUM	6150.00	707250.00
11	M & L for Concrete bed to drain pipes (200mm).in PCC Type C2 1:3:6 Including acking under, and haunching against the sides of pipes after they are laid and tested; in	450.00	RM	700.00	315000.00
12	M & L for Concrete bed to drain pipes (150mm).in PCC Type C2 1:3:6 Including acking under, and haunching against the sides of pipes after they are laid and tested; in	325.00	RM	505.00	164125.00
13	Material and labour for cement concrete 1:2:4 Type B1 20mm graded aggregate in foundation filling and mass concrete.	23.00	CUM	6700.00	154100.00

Item Code	Item Description	Quantity	Unit	Rate/Unit (Rs.)	Total Cost (Rs.)
14	S & F of 200mm Salt-glazed stoneware drain pipes laid in trenches and jointed as specified.	450.00	RM	595.00	267750.00
15	S & F of 150mm Salt-glazed stoneware drain pipes laid in trenches and jointed as specified.	325.00	RM	485.00	157625.00
16	M & L for Brick work built in CM.1:6 using Sub-Class "B" Bricks, straight or curved on plan to any radius	70.00	CUM	6950.00	486500.00
17	M & L for providing plastering in CM 1:4, 15mm thick on brick /concrete surface.	470.00	SQM	250.00	117500.00
18	Material and labour for precast cement concret type B1 1:2:4 20 mm graded aggregate set in cemtn mortar 1:6 in landings , cover slabs, manholes, chullas hoods, chajjas water groughs, mangers, shelves and similar articles with plain faces	12.00	CUM	11000.00	132000.00
19	Material and labour for deformed or twisted mild steel bars 10 mm dia dn over cut to length bent to shape required including cranking, bending, spirally for hooping for columns, hooking ends and bnding with and including mild stee wire not less than 0.9 mm dia or securing with clips	1200.00	KG	82.00	98400.00
20	Taking up or down steel tubing of bore 50mm and connection including cleaning for refixing or removal to CE/E store.(Including all accessories).	50.00	RM	40.00	2000.00
21	S & F of steel tubing of bore 50mm bore medium grade galvanised with all fitting and fixed complete to concealed or walls and ceilings or laid in floors.	50.00	RM	410.00	20500.00
22	Taking up or down steel tubing of bore 20mm and connection including cleaning for refixing or removal to CE/E store.(Including all accessories).	60.00	RM	35.00	2100.00
23	S & F of steel tubing of bore 20mm bore medium grade galvanised with all fitting and fixed complete to concealed or walls and ceilings or laid in floors.	60.00	RM	180.00	10800.00
24	Demolition and breacking up drain pipes (Salt glazed ware, AC or Reinforced concrete) set in cement mortar.(100 mm)	90.00	RM	45.00	4050.00
25	S & F of PVC 110mm dia Pipes single socketed, in any length with rubber ring joints laid in trenches or in floors.	100.00	RM	205.00	20500.00
26	S & F of PVC (SWR) 110mm bends any radius	20.00	Each	125.00	2500.00

Item Code	Item Description	Quantity	Unit	Rate/Unit (Rs.)	Total Cost (Rs.)
27	S & F of PVC Bend with door 110mm dia any radius,	17.00	Each	185.00	3145.00
28	S & F of PVC (SWR) junction single,(Single T) equal or unequal 110mm dia any radius.	15.00	Each	450.00	6750.00
29	Returning / refilling of soil / loose including spreading, leveling, watering and well ramming in layers not exceeding 25cm.	1400.00	CUM	150.00	210000.00
30	Removal of excavated soils exceeding 250m but not exceeding 500mm and depositing where directed.	200.00	CUM	300.00	60000.00
31	M&L for 225 mm(inner dia) Cutting into existing manholes for connecting new drains, making good to pipe and rendering, cutting out existing benching for and forming branch channel (1/2 round or 3/4 section) in cement concrete 1:2:4 type B1 smooth finished, and reforming benching as required.	25.00	Each	1450.00	36250.00
32	M & L for white washing two coats to posts, pillars and walls using shell lime.	475.00	SQM	17.00	8075.00
Total of Items Rs.				48,36,330.00 /=	
Add Taxes as applicable Rs.				0.00	
Gross Total Rs.				48,36,330.00 /-	



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.


4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA