

ACCEPTANCE LETTER No : MINUTES OF CWC – I HELD ON 21-12-2023

To

SRI LAKSHMI INDUSTRIES
99, VENKATAPURAM
PATTABIRAM
CHENNAI – 600 072

Dear Sirs,

Type of Work: ITEM RATE

Sub : **SPECIAL REPAIRS TO THE DAMAGED PLINTH PROTECTION FOR TYPE-I, II, III, IV AND V QUARTERS AT HVF ESTATE.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2023-24/45, Dt. 27-09-2023 with Tender ID: 2023_AVNL_168961_1
(ii) Your Bid No: 619854 in this tender and Confirmations offered vide your letter Dt. 26-12-2023

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 2,21,62,900 /- (Rupees Two Crores Twenty One Lakhs Sixty Two Thousand and Nine Hundred Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/16/2023-24/CAP, Dated. 04-01-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 3,70,800 /- (Rupees Three Lakhs Seventy Thousand and Eight Hundred Only) in favour of "Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.

The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. G. Anandakumar, WM / IMS , is nominated as Engineer-in-Charge and Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) & Shri. S. Vijayakumar, JWM / IMS / CE (E) are nominated as Site In-charges for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | | |
|---|---|--------------------|
| 1. GM / HR & F&A, HVF, Avadi, Chennai – 600054 | - | |
| 2. Shri. G. Ananda Kumar, WM / IMS | - | Engineer-in-Charge |
| 3. Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) | - | Site-in-Charge |
| 4. Shri. S. Vijayakumar, JWM / IMS / CE (E) | - | Site-in-Charge |
| 5. Shri. Premal Singh, WM / MM(GA) & CEO | - | Technical Examiner |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/16/2023-24/CAP., dated 04-01-2024
Acceptance letter No.	MINUTES OF CWC - I HELD ON 21-12-2023
Contractor's Name	SRI LAKSHMI INDUSTRIES
Name of the work	SPECIAL REPAIRS TO THE DAMAGED PLINTH PROTECTION FOR TYPE - I, II, III, IV AND V QUARTERS AT HVF ESTATE.
CA amount	Rs. 2,21,62,900 /=-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 619854 in this tender and Confirmations offered vide your letter Dt. 26-12-2023 in T.E No. HVF/TE/13025/CEO/2023-24/45, Dt. 27-09-2023 with Tender ID: 2023_AVNL_168961_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect,	
a. Date of handing over of the site	18/01/2024
b. Date of commencement of work	18/01/2024
c. Date of Completion as per contract	17/01/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 2,21,62,900 /=-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	920 / 34 (CAPITAL GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. Prempal Singh, WM / MM(GA) & CEO
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS, EO & GS
9. Accepted	SRI LAKSHMI INDUSTRIES


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :-

1. SRI LAKSHMI INDUSTRIES
2. GM / HR & F&A, HVF, Avadi, Chennai - 600054
3. Sr. Security Officer
4. Shri. G. Ananda Kumar, WM / IMS - Engineer-in-Charge
5. Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) - Site-in-Charge
6. Shri. S. Vijayakumar, JWM / IMS / CE (E) - Site-in-Charge
7. Shri. Prempal Singh, WM / MM(GA) & CEO - Technical Examiner
8. HOS/Safety, 9. HOS/Internal Audit cell, 10. HOS/Test Audit, 11. ALWC,
11. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai - 600034
12. Dy. Chief Labour Commissioner(c), No. 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai - 600006.

SCHEDULE – "A"					
Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
1	Roughening surfaces of old concrete floor by picking , sweeping clean and washing down with water to remove dust etc complete all as directed by EIC.	SQM	14200.00	20.00	284000.00
2	Demolition of Cement Concrete structure of any description.	CUM	610.00	300.00	183000.00
3	Surface excavation in Hard/Dense soil n.exc (not exceeding) 30 cm deep and averaging 15cm deep and getting out	SQM	14200.00	30.00	426000.00
4	'M & L for P.C.C 1:4:8, D2 type using 40mm graded aggregated in foundation.	CUM	1520.00	4800.00	7296000.00
5	Material and labour for sand filling in foundation including watering and consolidation.	CUM	460.00	1100.00	506000.00
6	Material and labour for cement concrete 1:2:4 Type B1 20mm graded aggregate in foundation filling and mass concrete.	CUM	2080.00	6000.00	12480000.00
7	M&F Formwork to sides of concrete foundations, footings, bases of columns, raft and raft beams, sides and soffits (if any) of foundation and plinth beams; and similar work; vertical or to batter	SQM	2250.00	250.00	562500.00
8	Removal of excavated soils exceeding 250 m but not exceeding 500 m and depositing where directed.	CUM	2127.00	200.00	425400.00
Gross Total of Items (Rs.)					2,21,62,900 /-



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA