

ACCEPTANCE LETTER No : MINUTES OF CWC - II HELD ON 06-12-2023

To

LEELA CONSTRUCTIONS,
No. 7, MOSQUE ROAD,
DEFENCE ENCLAVE,
I.A.F, AVADI, CHENNAI – 600 055

Dear Sirs,

Type of Work: ITEM RATE

Sub : **REPAIRS / RENOVATION OF EXISTING BUS SHELTERS (2 Nos) AT HVF ESTATE.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2023-24/52, Dt. 17-10-2023 with Tender ID: 2023_AVNL_171098_1
(ii) Your Bid No: 629141 in this tender.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 18,91,550 /- (Rupees Eighteen Lakhs Ninety One Thousand Five Hundred and Fifty Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/22/2023-24/MAINT, Dated. 14-12-2023** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 47,300 /- (Rupees Forty Seven Thousand and Three Hundred Only) in favour of "Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.


The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) is nominated as Engineer-in-Charge and Shri. S. Arunachalam, Ch/M / IMS / CE (E) is nominated as Site In-charge for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS, EO & GS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | |
|---|------------------------|
| 1. GM / HR & F&A, HVF, Avadi, Chennai - 600054 | |
| 2. Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) | - Engineer -In- Charge |
| 3. Shri. S. Arunachalam, Ch/M / IMS / CE (E) | - Site -In- Charge |
| 4. Shri. P.G. Harish Kumar, JWM / CEO | - Technical Examiner |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/22/2023-24/MAINT., dated 14-12-2023
Acceptance letter No.	MINUTES OF CWC – II HELD ON 06-12-2023
Contractor's Name	LEELA CONSTRUCTIONS
Name of the work	REPAIRS / RENOVATION OF EXISTING BUS SHELTERS (2 Nos) AT HVF ESTATE.
CA amount	Rs. 18,91,550 /-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - II
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 629141 in this tender in HVF/TE/13025/CEO/2023-24/52, Dt. 17-10-2023 with Tender ID: 2023_AVNL_171098_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	27/12/2023
b. Date of commencement of work	27/12/2023
c. Date of Completion as per contract	24/06/2024
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 18,91,550 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	809 / 02 (REVENUE GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. P.G. Harish Kumar, JWM / CEO
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS, EO & GS
9. Accepted	LEELA CONSTRUCTIONS



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :-

1. LEELA CONSTRUCTIONS
2. GM / HR & F&A, HVF, Avadi, Chennai - 600054
3. Sr. Security Officer
4. Shri. K. Ravichandran, JWM (SG) / IMS / CE (E) - Engineer -In- Charge
5. Shri. S. Arunachalam, Ch/M / IMS / CE (E) - Site-In- Charge
6. Shri. P.G. Harish Kumar, JWM / CEO - Technical Examiner
7. HOS/Safety, 8. HOS/Internal Audit cell, 9. HOS/Test Audit, 10. ALWC,
11. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
12. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

SCHEDULE – "A"					
Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
1	Excavating in post holes in Hard/dense soils (or similar holes) each n exc 0.5 cu.m, getting out, returning, filling in and ramming earth or broken rubble mixed with eart around, in layers not exceeding 25cm.	EACH	10.00	380.00	3800.00
2	Earth work excavation in hard/ dense soil in trenches width and depth not exceeding 1.50m and getting out	CUM	6.00	675.00	4050.00
3	Material and labour for sand filling in foundation including watering and consolidation.	CUM	10.00	2200.00	22000.00
4	Material & Labour for PCC 1:3:6 type C2 using 40mm graded aggregate for foundation	CUM	10.00	5500.00	55000.00
5	M & L for providing reinforcement cement concrete in Footings, piles, Plinth beam with cement concrete A1 Type, 1:1.5:3 mix using 20mm graded aggregated.	CUM	6.00	7000.00	42000.00
6	M & L for form work to sides and soffits of floor or roof beam, beam, lintels, cantilevers, shelves, columns, slabs including supports, overhangs etc.,	SQM	35.00	400.00	14000.00
7	Supply and filling of moorum / red bajiri filling in floors in layers not exceeding 15 cm thick spread levelled and rammed including watering complete	CUM	11.00	1100.00	12100.00
8	Supply and fixing of mild steel reinforcement deformed or twisted bars 10mm dia and over including bending, cranking, hooking and tying with mild steel wire not less than 0.90mm dia	KG	360.00	80.00	28800.00
9	M & L for Brick work built in CM.1:6 using Sub-Class "B" Bricks.	CUM	3.00	6500.00	19500.00
10	M & L for plastering in CM 1:4, 15mm thick on fair faces of brick work and concrete surfaces.	SQM	40.00	300.00	12000.00
11	M&L for applying two coats of plastic emulsion on internal wall surfaces including preparation of old wall surfaces complete all as directed. Make: (Asian/Berger/Nerolac) (or) Suitably equivalent make	SQM	40.00	120.00	4800.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
12	Supplying and fixing of Bus shelter of size 6.00M x 3.0M with 5.0 Nos of vertical supports (2.70 m height) made out of stainless steel pipes of grade 316 and dia 219mm (OD) with suitable trusses, and stiffening plates with seating arrangements etc.,(6m x 3.0m) complete all as directed by EIC.	WJ	2.00	600000.00	1200000.00
13	Supply and Fixing of pre-printed galvalume aluminium zinc coating GI based corrugated steel sheet 0.50mm (TCT) thick of any clour having tensile strength of 550 Mpa as in roof covering /cladding to wall fixed with self tapping screws as specified.	SQM	55.00	700.00	38500.00
14	Supply and Fixing of Cement Concrete Tiles 20mm thick for open space machine pressed screed bed or bedding layer in CM1:3, 15mm thick and pointed in grey cement and pigment complete all as directed)	SQM	90.00	1200.00	108000.00
15	Supply and Fixing of Granite 20mm thick (of any type) work (table rubbed and polished) in steps, jambs, pillars, window-cills, cooking platforms and like in cement mortar (1:4) including pointing in white cement (1:2) using marble dust with admixture of pigment to match with shade of granite complete all as direced by EIC.	SQM	12.00	5000.00	60000.00
16	Supplying and fabricating of stainless steel pipe 50mm dia (14 gauge) 304 grade with base plate and clamp fixing , railing /Seating arrangements including polishing and generator charges etc.	RM	80.00	1500.00	120000.00
17	Providing illumination boards back light adversiting Banners with stainless steel frame panel and side board for displaying Bus Route Numbers and lighting arrangements to the Bus shelters .(SIZE of Board 3.00 m x 1.2 m)	EACH	4.00	35000.00	140000.00
18	Supplying and fixing Banners including stainless steel frame pane (6m x 0.6 m)	EACH	2.00	3500.00	7000.00
Gross Total of Items (Rs.)		18,91,550.00 /-			



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS, EO & GS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS, EO & GS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA