



दिल्ली मेट्रो रेल कॉर्पोरेशन लि०

DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का एक संयुक्त उपक्रम)
(A JOINT VENTURE OF GOVERNMENT OF INDIA AND GOVT. OF DELHI)

No. DMRC/Tender (O&M)/OEW-TR-07/2023

Dated: 11.04.2023

LETTER OF ACCEPTANCE

M/s Excellence Decor
F-6, Gautam Nagar,
South West Delhi,
Delhi-110049
Mob: 9811026852
Email Id:

Kind Attn: Suraj Prakash Gupta

Sub: Contract: OEW-TR-07 "Refurbishment work of CTMC and Miscellaneous Repair Work at DW & SN RSS in Traction L-3 of Delhi Metro Rail Corporation Ltd."

Ref : (i) Opening of Technical bids online on 15.02.2023
(ii) Opening of Financial bids online on 23.03.2023.
(iii) Contract No: 2023_DMRC_735992_1

Dear Sir,

1. With reference to above, Letter of Acceptance (LOA) is hereby issued to you for the above mentioned work at total cost of **INR 17,88,117.54 (Rs Seventeen Lakh Eighty Eight Thousand One Hundred seventeen and Paise Fifty Four Only)** including all taxes, duties, octroi, royalties etc.
2. This 'Letter of Acceptance' is sent herewith to you in duplicate. You are required to return one copy of it duly signed by you on all pages indicating "**Unconditional Acceptance**" thereof so as to reach the undersigned within seven days of the receipt of this letter.
3. This "Letter of Acceptance" shall be treated as "Notice to Proceed" as defined in clause 8.1 of GCC and the completion period for this work is **03 (Months)** from the stipulated date of commencement of work.
4. You shall ensure full compliance with Tax Laws of India with regard to this contract and shall be solely responsible for the same. You shall keep the employer fully indemnified against your liability of tax, interest, penalty etc. in respect thereof which may arise.
5. Sr. DGM/TR-3&AEL of this organization will be the Engineer In-charge for this contract.
6. You are requested to contact the Sr. DGM/TR-3&AEL immediately for further necessary action in this matter, and date of commencement of work shall be from 18.04.2023 or as per the instructions of Engineer In-charge.

Page 1 of 2 (OEW-TR-07)

7. All the works shall be executed in accordance with the specifications stipulated in Tender.
8. It may please be noted that until a formal agreement is executed, this letter will constitute a binding Contract between you and DMRC. Please take necessary action as required vide Clause Nos. F4 and F5 of Instructions to Tenderers (ITT) regarding signing of agreement within 45 days from the issue of Letter of Acceptance and submission of performance security within 30 days from the date of receipt of LOA. Further, it is pertinent to mention that delay in submission of performance security shall attract penal interest/lead to termination as per clause 4.2 of GCC.
9. Before commencing the work contractor is required to co-ordinate with Sh. Sachin Jain, MGR/TR-3 Mob No- 9560067213.
10. You are instructed to register yourself on vendor payment portal on receiving the LOA. The instructions to do the same are provided in Annexure-A.

Thanking you,

Yours sincerely,
For Delhi Metro Rail Corporation Limited


(JITENDER KUMAR)
Sr. DGM/TR-3 & AEL

Encl: -

- 1-One Copy of this letter in Duplicate
- 2-Annexure-A
- 3- Accepted BOQ

Copy to

1. **GM/Traction:** for kind information please.

Annexure A

In order to facilitate contract management and ensure timely processing of requests made by the vendor, DMRC has implemented the Vendor Payment Portal that will allow the vendor to register themselves, raise payment requests, modify vendor information and request variation in contract. The portal will provide updates to the vendor and DMRC of the current status of the process and help to ensure timely action.

To register on the portal follow these steps

1. Go to : <https://vpp.dmrc.org>
2. Click on vendor sign up button.
3. Enter the required contact information and contract details.
4. The information about nodal officer may be obtained from engineer-in-charge.
5. Click on submit button.
6. You will get the message "Your request has been sent to the nodal officer for verification. Once verified, you will receive notification via email and sms."

In case of any queries, click the help button on the landing page:

1. Queries can be sent on the following email id: vpp.support@dmrc.org
2. User manual is available by clicking the button: "Download vendor user manual" on the help page.



Accepted Bill of Quantity (BOQ)

Name of Work : OEW-TR-07 Re-Furbishment & Repair work of CTMC and Miscellaneous Repair Work at DW & SN RSS in Traction L-3 of Delhi Metro Rail Corporation Ltd"

PART-A: Re-Furbishment & Repair work of CTMC

S/N	Item description	Unit	Qty	Unit Rate (in Rs.)	Total Amount (in Rs.)
1	Supply and installation of LED headlights (100w,24V,20Amp.) frame dia. 19.50 cm	No's	4	20746.00	82984.00
2	Supply and Installation of LED red taillights (50 watts, 24V,12Amp, Lumen 6000) dia 10 cm	No's	4	10844.50	43378.00
3	Supply and installation of swiveling Search lights on roof (24V, 20amp, 60watts, frame dia.16.50 cm)	No's	4	3300.50	13202.00
4	Supply and installation of driver cabin fans along with its assembly(24V DC)size of blade housing - dia. =38cm	No's	4	1131.60	4526.40
5	Supply and installation of cabin LED lights 24V DC	No's	4	424.35	1697.40
6	Supply and installation of safety railing/handrail by welding GI sheet metal pipes of thickness 3mm or suitable with inner square cross-section area=25cm ² on Cabin roof having dimension L=3.60 mtr B = 3.20 mtr	No's	1	14616.50	14616.50
7	Water leakage proofing of driver cabin (L=3.60 mtr B=3.20 mtr) by supply and installation of suitable leakage proofing sealant.	No's	1	4715.00	4715.00
8	Supply and installation of Rear Windscreen glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 105 *43 cm	No's	2	2357.50	4715.00
9	Supply and installation of Front Windscreen glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 130 *50 cm	No's	2	2593.25	5186.50
10	Supply and installation of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 105 *80 cm.	No's	2	2168.90	4337.80
11	Supply and installation of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 97*35 CM	No's	2	1697.40	3394.80
12	Supply and installation of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 124 cm*94 cm	No's	2	1744.55	3489.10
13	Supply and installtion of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 83*68 CM	No's	2	1697.40	3394.80
14	Supply and installtion of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 92*59 CM	No's	2	1744.55	3489.10
15	Supply and installtion of windows glass rubber gasket (replacement of old worn out rubber gasket) having dimension 89*49 cm	No's	2	1697.40	3394.80



16	Supply and installtion of windows glass EPDM dense rubber gasket (replacement of old worn out rubber gasket) having dimension 105*52 cm	No's	2	2027.45	4054.90
17	Caliberation of Drivers Panel gauges : Emgine water Temperature needle gauge (Make-Cummines, Engine Lub. Oil pressure gauge (make Cummines) ,lub. Oil temp. gauge (make cummines),Fuel level gauge(make Cummines),transmission oil temperature gauge (make Cummines),transmission oil pressure gauge (make-VDO),ampere meter (make PRICOL),main reservoir/ Brake pressure duplex air pressure gauge (make midlands), Engine RPM cum Hour meter (Make Cummines),Speedometer (make Laxvan)	No's	10	11316.00	113160.00
18	Supply and installation of Overhead high voltage line indicator tested for 25 kv AC voltage (one for CTMC L3 and one for CMV L9)	No's	2	4243.50	8487.00
19	Supply and installation of wiper blades of reputed brands like for windshield cleaning with 24 v DC motor along with water tank suitable for windshield cleaning	No's	4	4243.50	16974.00
20	Supply and installtion of red indicator 24 V DC	No's	10	282.90	2829.00
21	Supply and installtion of green indicator 24 V DC	No's	10	282.90	2829.00
22	Supply and installation of Cradle wiring of size 18C* 4 sqmm Cu having length 20 mtr along wih suitable lug and thimbles	No's	1	35834.00	35834.00
23	Overhauling and repair of DG set 7.5 KVA make Kirloskar	No's	1	23575.00	23575.00
24	Painting of CTMC by applying two coat primer and reputed brand (Nerolac/Berger) enamel paint as per RDSO guidelines .Dimensions: CABIN (external) L=3.67 mtr;W=3.00 mtr;h=2.20 mt ; Rear floor and surface (external) L=8.20 mtr;W=3.00 mtr;h=0.80 mtr. DG set box external L=1.90 mtr. ,breadth=1.05 mtr, height=1.55 mtr ;hydraulic tank external L=65 cm B=81cm height=60 cm;Diesel tank- 2no. H=50cm . L=1.16 mtr B=50cm ; engine gaurd cover length=1.52 mtr width=1.20 mtr. height=1.0 mtr. ;vehicle Rear face L=75cm B=300cm ; cradle basket L=125 cm, B=140 cm, H=160cm; cradle boom L=510cm B=40cm. Supply of material (paint/primer/putty/emery paper/brushes and other necessary items) shall be in scope of contractor	No's	1	165025.00	165025.00
25	Supply and Installation of window door tower bolts	No's	6	377.20	2263.20
26	Supply and Installation of cabin door lock	No's	2	943.00	1886.00
27	Supply and installation of staff seat leather cover including backrest cover (seat: L= 135 cm , Width 60 cm, backrest: Length 135 cm , Width 65 cm)	No's	4	7072.50	28290.00
28	Supply and installation of Operator seat leather cover (backrest cover length=1.15 mtr Breadth=1.05 mtr ;seat= Length=71 cm, Breadth=71 cm)	No's	1	3772.00	3772.00

29	Supply and installation of furniture of material stainless steel of thickness 10 mm or suitable for keeping tools below staff seats with sliding door with lock having compartments. Dimension of compartment-1 (length 25 cm , width 43 cm, height = 34 cm)* dimension of compartment -2 (length 28 cm, width 43cm, height 34 cm)	No's	4	11316.00	45264.00
30	Repair of CTMC cabin floor by providing chequered plate of thickness 1.2-1.5 mm or suitable	No's	1	20746.00	20746.00
31	Securing and riveting and repair of CTMC cabin inner noise absorbing material wall size L=3.35 mtr B=2.85 mtr. H=2.08 mtr.	No's	1	3772.00	3772.00
32	Deep cleaning and disinfection of complete CTMC including oil stain removal	No's	1	42435.00	42435.00
33	Sub Total Amount (Part-A)				7,17,717.30
34	GST @ 18%				1,29,189.11
35	Total Amount (Part-A)				8,46,906.41

PART-B: Miscellaneous Repair Work at DW & SN RSS in Traction L-3

SN	Description	Unit	Qty	Unit Rate (in Rs.)	Total Amount (in Rs.)
1	Repair and painting of NGR as one job. The work shall comprise the following: i. Providing the MS sheet(16 guage) of size 11 ft X 7 ft for the roof of NGR by cutting and welding to protect any water leakage and reptile entry. ii. Supply of reputed brand enamel smoke grey paint and painting of two coat after primer of NGR roof. iii. Size of sheet=11 ftx7ft=77 sq ft	Sq ft	308	424.35	1,30,699.80
2	Repair and painting of NGR as one job. The work shall comprise the following: i. Providing the Perforated sheet of size 11 ft X 7 ft for the Bottom of NGR by cutting and welding to protect any water leakage and reptile entry. ii. Supply of reputed brand enamel smoke grey paint and painting of two coat after primer of NGR bottom. iii. Size of sheet=11 ftx7ft=77 sq ft	Sq ft	308	424.35	1,30,699.80
3	Repair of Filtration machine roof 6000Ltr. as one job. The work shall comprise the following: i. Providing the MS sheet (16gauge) on the roof of Filtration Machine by cutting and welding to protect water ingress and reptile entry ii. Supply of reputed brand enamel smoke grey paint and painting of two coat after primer of Roof. iii. Size of sheet =16 ft X 8 ft=128 sq ft	Sq ft	128	424.35	54,316.80
4	Supply and Fixing of PVC net in portals of Subhash Nagar Receiving Sub Station located in L-3 using Binding wireNote:- binding wire shall be	Sq ft	300	141.45	42,435.00

	supplied by DMRC & Work to be done only in Non revenue hours.				
5	Supply spreading/ leveling of gravels at yard (Subhash Nagar RSS, Dwarka RSS & Najafgarh FP) of size 20 mm	Cum	45	3017.60	1,35,792.00
6	Installation and commissioning of 25KV CB platform ladder. The work shall comprise the following: i. Structure should be made of 50X5 mm MS angel and 6 mm iron cheqward plate. ii. Supply of reputed brand enamel smoke grey paint and painting two coat after primer of complete stand iii. Total Angel used for 01 no Stand is approx. 42 Ft. iv. Total Round iron Pipe(1 inch) used for railing is approx.35 ft. v. Size of Cheqward Plate is 1.2 meter x 1.2 meter=01 nos and 0.3 meterX 0.5 meter=01 Nos vi. Sample photograph attached in Employer Requirement.	Job	2	33005.00	66,010.00
7	Installation and commissioning of fire extinguishers stand. The work shall comprise the following: i) Structure should be made of 50X5 mm MS angle , Total length- 10.2 mtr. ii) MS sheet 16 gauge , Total area 1.44 sq mter. iii)Supply of reputed brand paint and painting two coats after the primer of complete stand. iv) Welding, painting and installation of stand at site.	Job	3	8015.50	24,046.50
8	Supply and Installation of Signanebaord :- i) by using 35x3 MS angel ,18 guagems sheet and 2 Inch X 2 inch square Iron Pipe(Approx-17ft), size 8ftX4 ft With High Reflective letter for Display. ii) Supply of reputed brand paint and painting two coat after primer of complete frame of board. Sample photograph attached in Employer Requirement.	Job	1	17445.50	17,445.50
9	Supply and Installation of Signanebaord :- i) by using 35x3 MS angel ,18 guagems sheet and 2 Inch X 2 inch square Iron Pipe(Approx-17ft), size 6ftX3 ft With High Reflective letter for Display. ii) Supply of reputed brand paint and painting two coat after primer of complete frame of board. Sample photograph attached in Employer Requirement.	Job	3	16219.60	48,658.80
10	Supply and installation of PERFECT CONTROL make or suitable,i) WINDING TEMP. METERii) MODEL- 7214-07, SK-297iii) Aux. supply - 90-260 ac/dc, Input Signal- 4-20 mA, Temp. Range- 0-150 degree Centigrade, Size 90 x 90	Nos.	2	7826.90	15,653.80
11	Supply and installation of ACCORD ENTERPRISE make or suitable, i)TAP POSITION INDICATOR(TPI) ii)TYPE-TI-01	Nos.	2	8015.50	1,6031.00

	iii) AUX. SUPP. 85-250 V AC/DC					
12	Supply and installation of PRADEEP make or suitable, i) REMOTE TAP POSITION INDICATOR (TPI). ii) MODEL-TPC 2001 iii) TYPE-7214-07, AUX. SUPP. 240 V ac, 50Hz	Nos.	2	8109.80	16,219.60	
13	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC AMMETER ii) INPUT-0-1A, AC iii) RANGE- 0-200Amp, AC iv) ACCURACY: + -0.5% v) CTR-800-400-200/1A,Aux. Supply-240 V ac	Nos.	6	2121.75	1,2730.50	
14	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC AMMETER ii) INPUT-0-1A, AC iii) RANGE- 0-300Amp, AC iv) ACCURACY: + -0.5% v) CTR-300-600-1200-2400/1A,Aux. Supply-240 V ac, 50Hz	Nos.	6	2216.05	13,296.30	
15	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC AMMETER ii) INPUT-0-1A, AC iii) RANGE- 0-1200Amp, AC iv) ACCURACY: + -0.5% v) CTR-2500-1200/1A,Aux. Supply-240 V ac, 50Hz	Nos.	1	2168.90	2,168.90	
16	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC AMMETER ii) INPUT-0-1A, AC iii) RANGE- 0-800Amp, AC iv) ACCURACY: + -0.5% v) CTR-1600-800/1A,Aux. Supply-240 V ac, 50Hz	Nos.	1	2216.05	2,216.05	
17	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC VOLTMETER ii) INPUT- 0-133.3A, AC iii) RANGE- 0-80KV, AC iv) ACCURACY: + -0.5% v) PTR-66KV/110V, AC,Aux. Supply-240 V ac, 50Hz	Nos.	8	2121.75	16,974.00	
18	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC AMMETER ii) INPUT-0-1A, AC iii) RANGE- 0-1250Amp, AC iv) ACCURACY: + -0.5%v) CTR-2500-1250/1A,Aux. Supply-230 V ac, 50Hz	Nos.	4	2216.05	8,864.20	
19	Supply and installation of AE make or suitable (66KV) i) TYPE- DIGITAL AC VOLTMETER ii) INPUT-0-154A, AC iii) RANGE- 0-35KV, AC	Nos.	4	2121.75	8,487.00	

*	iv) ACCURACY: + -0.5% v) PTR-25KV/110V, AC,Aux. Supply-240 V ac, 50Hz					
20	Supply and installation of Automatic Regulating relay Type EE301-M,Aux 110/230V AC,50 hz,15 VA	Voltage Supply-	Nos.	1	34891.00	34,891.00
21		Sub Total Amount (Part-B)				7,97,636.55
22		GST @ 18%				1,43,574.58
23		Total Amount (Part-B)				9,41,211.13
		Grand Total Amount (Part A + Part-B)				17,88,117.54

Signature Not Verified

Digitally signed by Om Tiwari
Date: 2023.05.17 10:54:38 IST
Location: eProcure-EPROC

