



इरकॉन इंटरनेशनल लिमिटेड

(भारत सरकार का उपक्रम)

IRCON INTERNATIONAL LIMITED

(A Govt. of India Undertaking)

An Integrated Engineering and Construction Company



IRCON/2056/AANRLP/Tender/Patrolling track/265/LOA/1084

Dated: 16.01.2024

M/s Tutan Ghosh,
Add. Jamjuri, Udaipur, Gomati,
Tripura-799105,
Phone No- +91- 9862331309
Email: ghoshtutan@gmail.com

(Letter Of Acceptance)

Sub: Construction of Foot path to connect passenger and cargo platform and patrolling track both side along the railway track in no men's land up to zero line of Bangladesh boarder for patrolling of BSF in connection with Agartala- Akhaura New Rail Link Project- **Letter of Acceptance.**

Ref: 1. IRCON/2056/AANRLP/Tender/Patrolling track/265 Date: 26.12.2023
2. Financial bid opened on 12.01.2024.

Dear Sir,

With reference to above, please be informed that your offer for the subject work has been accepted at total cost of **INR 49,99,806 (Rupees Forty-Nine Lakh Ninety-Nine Thousand & Eight Hundred Six only)** inclusive of all taxes and Duties (GST etc.) as per BOQ attached at Annexure-A with a completion period of **01 (One) Months** from the date of issue of this letter of acceptance and terms & condition as stipulated in tender documents.

- 1. Scope of work:** The Scope of work covered under this work shall be as per clause 4.0 of SCC.
- 2.** In terms of Clause 8.0 of SCC, you are requested to submit a Performance Guarantee (P.G.) in the form of irrevocable bank guarantee as per the Performa given as Annexure-IX of SCC from any Scheduled Bank for an amount of 5 % (Five Percent) of the contract value i.e., **Rs. 2,50,000.00 (Rupees Two Lakh Fifty Thousand only) within 21 days from the date of issue of LOA.** Alternatively, the performance security can be furnished by the Contractor in the form of Fixed Deposit Receipt (FDR) from a scheduled bank endorsed in favour of IRCON INTERNATIONAL LIMITED.



[Signature]
16/01/2024

Pg. 1



3. Your kind attention is invited to the provision of clause 17.0 of SCC. You are required to submit/ comply the following:
- i. **In terms of clause 17 (I) of SCC:** The Contractor shall submit the programme for completion of work to the Engineer for his approval within 7 days from the date of receipt of letter of acceptance considering completion period as indicated in Key Information Table (KIT) in Para 1.1 of e-Procurement Notice. Unless otherwise directed, the programme shall be in the form of Bar-Chart showing proposed execution of quantities of principal items of work. The programme shall be related to the capability of equipment proposed to be deployed and site conditions. Programme so submitted and agreed by IRCON will become part of the contract agreement. The Contractor shall also provide in writing methodology for execution of major items of work as desired by the Engineer. The submission and approval of such programme shall not relieve the Contractor of any of his duties or responsibilities or obligations under the contract. The Engineer shall have full power and authority during the progress of work, to issue such instructions as may be necessary for the proper and adequate execution of the work.
 - ii. **In terms of clause 17 (II) of SCC:** Within 7 days of award of contract, the Contractor shall submit to IRCON for approval a Detailed Supply/Completion Programme with Milestones/Key dates based on completion period as indicated in Key Information Table (KIT) in Para 1.1 of e-Procurement Notice of the Tender. These shall be incorporated in the Contract Agreement after approval by Engineer in charge.
 - iii. **In terms of clause 17 (III) of SCC:** Within 7 days of award of contract, the contractor shall also submit resource deployment program i.e. key personnel, manpower, Plant & Machinery and Other resources deployment program. These shall be to be incorporated in the Contract Agreement after approval by Engineer in charge.
 - iv. **In terms of clause 17 (IV) of SCC:** Within 7 days of award of contract, the contractor shall also submit Cash flow statement and cumulative monthly progress plan (in the form of S curve). These shall be to be incorporated in the Contract Agreement after approval by Engineer in charge.
 - v. **In terms of clause 17 (V) of SCC:** Within 7 days of award of contract, the Contractor shall submit to IRCON Method statement for various activities and Quality Assurance Plan (QAP) and start the work after their approval.
 - vi. **In terms of clause 17 (VI) of SCC:** Within 7 days of the award of the contract, the contractor shall submit to IRCON, Organization chart of the project with the CV of the key personnel's to be deployed at the project site. The scrutiny of the same will be done by the IRCON and will be approved by the Engineer.



4. Quantity Variation:

Quantity variation shall be dealt as per the SCC cl. no. 35 and clause no 42 of Indian Railway General Condition of Contract April' 2022.

5. Taxes and duties:

The quoted rates shall include all the taxes, duties etc. Income tax on works contract shall be deducted from the payments to the contractors as per the prevailing tariff for which necessary TDS Certificates shall be issued. The taxes and duties shall be dealt under clause no. 42.2 of SCC.

6. Completion Period:

The work is required to be completed within a continuous period of **One months** from the date of issue of letter of acceptance as per clause no 10 of SCC. The work has to be executed in co-ordination with other agencies working on or near the project.

7. Liquidated Damages:

Liquidated Damages shall be dealt as per the clause no.46.8 of SCC.

8. Defect Liability period:

Defect liability period shall be dealt as per the clause no 45 of SCC.


9. Insurance:

As per, the clause no. 11 of SCC, you have to obtain contractor's All Risk Policy for the works In the Joint name of IRCON and Yourself.

10. Contract agreement:

The contractor shall enter into and execute the Contract Agreement within 28 days after the date of issue of Letter of Acceptance as per clause 14 (V) of SCC.

11. This letter of acceptance, along with your submitted offer shall constitute a binding contract between you and IRCON International Limited, till a formal agreement is drawn and executed.




12. This letter of acceptance is being issued in duplicate and you are requested to return one copy of this letter of Acceptance duly accepted, signed and stamped of each page by your authorized representative.
13. You are requested to mobilize the resources to commence the work. You are requested to contact Addl. General Manager/ Civil/ IRCON/ Agartala for further instructions.

Thanking You,
Yours Sincerely,

For & on behalf of,
Northeast Frontier Railways


16/01/2024
Addl. General Manager/Civil
Ircon International Limited



D/A: BOQ at Annexure -A

CC: 1. General Manager/ PH for Kind information.
2. Manager/ F&A

IRCON INTERNATIONAL LIMITED

Agartala-Akhaura New Rail Link Project

Name of the Work: - "Construction of Foot path to connect passenger and cargo platform and patrolling track both side along the railway track in no men's land up to zero line of Bangladesh boarder for patrolling of BSF in connection with Agartala- Akhaura New Rail Link Project."

NIT No. IRCON/2056/AANRLP/Tender/ Patrolling track / 265 Date 26.12.2023

Bill Of Quantity

Item No.	Ref. S.No.	Ref. to MoRTH Spec	Description	Unit	Quantity	Base Rate	Amount
Schedule 1: Road Works TSR- 2023 Items							
1	2.3	201	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per MoRT&H Technical Specification clause 201.				
		A	In area of light jungle	Hactare	0.21	73,126.44	15,356.55
2	3.16	300	Construction of Embankment with Material obtained from Borrowpits Construction of embankment with approved material obtained from borrow pits with all lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per MoRT&H Technical Specification clauses of section 300	cum	600.00	191.60	1,14,960.00
CARRIAGE OF MATERIALS							
3	1.2		Loading and unloading of Stone Boulder, stone aggregate, Brick Aggregate, Kankar, earth, Crushed slag, Stone for masonry Work by Manual Means including a lead upto 30m.	cum	600.00	127.03	76,218.00
4	1.10		Haulage of materials by tipper / truck excluding cost of loading, unloading and stacking.(i) Surfaced Road	t-km	17,685.00	3.56	62,958.60
5	3.22	300	Turfing with Sods Furnishing and laying of the live sods of perennial turf forming grass on embankment slope , verges or other locations shown on the drawing or as directed by the Engineer including preparation of ground, fetching of sods and watering as per MoRT&H Technical Specification clauses of section 300.	Sqm	400.00	43.31	17,324.00
6	4.17	401	Granular Sub-Base with Well Graded Material(using jhama brick aggregate) (Table:- 400.1) A. By Mix in Place Method Construction of granular sub-base by providing well graded material (Jhama Brick Aggregate, as per Table:- 400.1, Grading-I), spreading in uniform layers with tractor with attachments or motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, applying and brooming sand to fill up the interstices of coarse aggregate, watering and compacting with smooth wheel roller to achieve the desired density, complete as per MoRT&H Technical Specification Clause 401.	Cum	282.00	4,030.93	11,36,722.26



Bill Of Quantity

Item No.	Ref. S.No.	Ref. to MoRTH Spec	Description	Unit	Quantity	Base Rate	Amount
7	M-1.24	1500	Providing and laying factory made chamfered edge Cement Concrete paver blocks of required strength, thickness & size/ shape, made by table vibratory method to attain superior smooth finish using PU or equivalent moulds, laid in required grey colour & pattern over 50 mm thick compacted bed of sand, compacting and proper embedding/ laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with fine sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. all complete as per specifications & approval/ direction of the Engineer -in-Charge: (a) 80 mm thick c.c. paver block of M-35 grade with approved colour, design and pattern.	Sqm	900.00	1,315.25	11,83,725.00
8	11.4		Wrought iron and mild steel welded work (using angles, square bars, tees and channel in grills, grating frames, gates and tree guards of any size and design etc. including cost of screens and welding rods or bolts and nuts complete fixed in position but without the cost of excavation and concrete for fixing which will be paid separately as per MoRT&H technical specifications Clauses and as directed.	Kg	670.00	101.10	67,737.00
Total for Schedule-1							26,75,001.41
Schedule 2: Buil. Works TSR- 2023 Items							
	4.1		Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - -All work upto plinth level:				
9	4.1.1		1:1:2 (1 Cement: 1 fine sand : 2 graded stone aggregate 20 mm nominal size)	Cum	79.00	11,807.02	9,32,754.58
10	4.1.6		1:3:6 (1 Cement: 3 fine sand : 6 graded stone aggregate 20 mm nominal size)	Cum	11.00	8,958.14	98,539.54
	5.8		Centering shuttering including struttings, propping etc. and removal of form work for:			-	
11	5.8.1.1		Foundations, footings, bases for columns etc. for mass concrete with timber plank	Sqm	101.00	282.97	28,579.97
	5.20A		Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level.			-	
12	5.20A-1		Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	3,300.00	83.39	2,75,187.00
Total for Schedule-2							13,35,061.09
Schedule 3: Non-SoR Item							
13	NS-1	Based on LAR	Construction of excavated blanketing Materials and spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per MoRT&H Technical Specification Clause 401.	Cum	140.00	282.6	39,564.00
Total for Schedule-3							39,564.00
Sub-Total for Schedule-(1+2+3)							40,49,626.50
Agency Quoted above 4.63%							1,87,497.71
Sub-Total Amount							42,37,124.21
Add GST @ 18 %							7,62,682.36
Grand Total inclusive of GST							49,99,806.57
Say							49,99,807

