



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

INLAND WATERWAYS AUTHORITY OF INDIA

पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार

क्षेत्रीय कार्यालय:

गायघाट, पोस्ट - गुलजारबाग, पटना - 800007

फोन : 0612.2310026

फैक्स : 0612.2310029

(Ministry of Ports, Shipping and Waterways, Govt. of India)



Regional Office:

Gaighat, P. O. - Gulzarbagh,

Patna - 800007

Phone/Tele fax : 0612-2310026/2

E-mail: iwaipn@rediffmail.co

NO. -12/IWAI/ ENGG/P(94)/2023-24/ 815

Date: 18.09.2023

To,

✓ M/s Sabita Udyog,
10/7, Kasundia 2nd Bye Lane,
Howrah, Pin-711104.
Email Id: arunkumardutta2020@gmail.com.

Sub: Work order for Annual repair of **CSD MAHANANDA** for the FY.2023-24-reg.

Ref: 1. IWAI e-tender dated 12.08.2023

2. Your financial e-bid dated 15.09.2023

Sir,

Reference to the above subject, this office is pleased to place the work order for Annual repair of **CSD Mahananda** for the FY.2023-24 at the total cost of **Rs. 3,93,750.00** (Rupees three lakhs ninty three thousand seven hundred fifty rupees only) (Labour charges Rs. 2,84,681.00 and tentative cost of spares (Actual+ 10% basis) of Rs. 1,09,069.00) excluding GST . The detail BOQ enclosed herewith at annexure-I.

Terms and conditions:-

1. The work shall be completed within **30 (Thirty days)** from the date of receipt of vessel at Gaighat(NW-I). In case of delay in completion of the repair work of the vessel and delivery, liquidated damages as per clause no. 35 of contract will be applicable.
2. The payment of the final bill/running account bill shall be made as per the clause no. 40 and 43 of the General Terms & Conditions of the contract.
3. You are requested to submit performance gurantee of **Rs. 19,688** (Rupees nineteen thousand six hundred eighty eight only) being 5% of the contract value by **RTGS/NEFT** in account of **"IWAI FUND"** in the **A/c no. 0352105000002** IFSC Code: **CNRB0000352, CANARA BANK, Main Branch-South Gandhi Maidan Patna-800001**. The performance gurantee shall be refunded as per clause 4 of the General Terms & Conditions of the contract.
4. In case of any additional work, the delivery period shall be extended proportionally as per clause 34 of the General Terms & Conditions of the contract.
5. In case of any additional work/items to be required necessary, contractor shall take prior permission in writing from EIC or his representative as per clause no. 11 of technical specification & special conditions.

Contd. P/2



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण
INLAND WATERWAYS AUTHORITY OF INDIA



क्षेत्रीय कार्यालय:

गायघाट, पोस्ट – गुलजारबाग, पटना – 800007

फोन : 0612.2310026

फैक्स : 0612.2310029

(Ministry of Ports, Shipping and Waterways, Govt. of India)

Regional Office:

Gaighat, P. O. – Gulzarbagh,

Patna – 800007

Phone/Tele fax : 0612-2310026/23

E-mail: iwaipn@rediffmail.co

-2-

6. The payment shall be made as per the BOQ (enclosed at annexure-I) for actual work executed and as per the payment terms of the agreement.
7. The cost of spare will be paid on actual plus 10% basis submission of proper GST bills in support of the purchase of spares is mandatory along with challan. The old spares replaced shall also be returned.
8. The contractor shall guarantee all the items, which are attended/supplied by them against all defects, defective materials and/or workmanship for a period of **6(SIX) Months** from the date of delivery of the vessel after its satisfactory repair. In case of any defects notice during the guarantee period shall have to attend at anywhere in NW-I.
9. Director, IWAI, RO, Patna shall be Engineer-in-Charge (EIC) for the said work.
10. You are requested to attend this office to enter into an agreement within 10 days from the date of issue of this work order alongwith all documents with two non-judicial stamp paper of Rs.1000/- each.
11. You are requested to acknowledge the receipt of the Letter of Award and send your acceptance immediately.

Yours faithfully


(L.K. Rajak)
Director

Enc: As Stated.

Copy to:

1. Account section, IWAI, Patna.

BOQ for Annual repair of CSD Mahananda for the year 2023-24.

Dimen. (40.30x7.0x2.46) M , G.T. - 194.0, Draft - 1.5M

Sl. No	Description of work	Unit	Qty.	Rate	Amount
1	The entire ship from LWL to main deck, deck plate, superstructure, bathroom, anchor, anchor rake, engine room, store rooms, hydraulic cooling pump room, spud, spud bracket, carriage, vent, cutter ladder, bollard, deck crane, railing, jet nozzle, railing-chain and outside alongwith other fitment etc, are to be proper cleaned, scrapped, wire brushed, chipped and painted by 3 coats of existing colour marine paint. (1 coat zinc chromate primer, followed by two coat of existing colour of marine paints). All pipe lines should be colored as per marine color code. After it name of vessel, depts. and logo to be made by fluorescent sticker as required as per direction of EIC.	Sq-m	1150	190.00	218500.00
2.0	Both side anchor winch swing pulley is not working smoothly. Same is to be serviced/renewed(capacity - 1tons) along with renewal of pin, sleeve, bush as per direction of EIC.				
2.1	Labour charges	Comp. Job	1.00	15000.00	15000.00
2.2	Cost of spares (on Actual + 10 % basis)				
3.0	Replacement of worn out/damaged anchor wire of the swing pulleys(dia-18 mm, length-120 m). The wire rope of ladder pulleys (dia-22mm) to be checked and if required to replaced with same length and steel grade wire rope as required as per direction of EIC.				
3.1	Labour charges	Comp. Job	1.00	15000.00	15000.00
3.2	Cost of spares (on Actual + 10 % basis)				
4.0	Auxiliary spud of the dredger was reported not holding and falling automatically, same is to be serviced/repared and make fully operational as required as per direction of EIC.				
4.1	Labour charges	Comp. Job	1	25000.00	25000.00
4.2	Cost of spares (on Actual + 10 % basis)				
5	Top overhauling of both the generator engine model no. S3.8G4, make - Cummins , Capacity: 52 BHP, Speed :1500 RPM , is to be done, cooler to be cleaned, radiator to be serviced & cleaned, silencer, safety system to be checked & serviced, checking of exhaust line, repairing of exhaust lagging etc; 2 set of filters etc to be given as required as per direction of EIC.				
5.1	Labour charges	No.	2	15000.00	30000.00


 T.A/M
 18/09/23

6.2	Cost of spares (actual + 10%)				
6.0	Installation of 500 litres capacity water tank on roof of toilet with pump of suitable capacity (for filling the same) with pipelines and other accessories such as valves etc. upto toilet/washroom in the vessel as per direction of EIC.				
6.1	Labour charges	Comp. Job	1	5000.00	5000.00
6.2	Cost of spares (on Actual + 10 % basis)				
7.0	Fabrication and installation of removable shed on deck over the engine room area including steel structure, FRP sheet of good quality and other required material, labour charges all complete as per direction of EIC.				
7.1	Labour charges	Comp. Job	1	15000.00	15000.00
7.2	Cost of spares (on Actual + 10 % basis)				
8.0	Repairing of the toilet of the vessel with necessary repairing of the structures, tiles and other structural parts all complete as per direction of EIC.				
8.1	Labour charges	Comp. Job	1	10000.00	10000.00
8.2	Cost of spares (on Actual + 10 % basis)				
9	Falls cealing in the operating room of the dredger are reported damage, same to be renewed with good quality water proof ply with sunmica alongwith its frame as required as per direction of EIC.				
9.10	Labour charges	No.	1	3000.00	3000.00
9.20	Cost of spare/material actual + 10% basis				
10.00	Fixed Operator Chair in the wheel house was reported damage, same to be repaired with good quality cushion and to be covered with seat cover of good quality as required as per direction of EIC.	Comp. Job	1	5000.00	5000.00
11.00	Truck tyre alongwith bull dog clamp and wire rope to be supplied and fitted including labour and material as required as per direction of EIC.	No.	8	2500.00	20000.00
12.00	Provision of spare for completing the repair work for BOQ sl. No. 01 to 11				138500.00
	TOTAL (Rs.)	Labour charge and cost of spares			500000.00
Quoted Labour Charge @ 21.25% below of (Rs.3,61,500) in Rs.					284681.25
Tentative Cost of spares on actual +10% basis (Rs.)					109068.75
GRAND TOTAL (Labour charge & cost of spares) Rs.					393750.00

In words:- Three lakhs ninty three thousand seven hundred fifty rupees only

*GST as applicable

Chelvan
TA/M
18/09/23