



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

फाइल सं. एएआई/एसएपी/इंजी (सि)/मंदिर/2023-24/552-561
F.No. AAI/SAP/Engg(C)/Mandir/2023-24

दिनांक: 06.03.2024

Date: 06.03.2024

सेवा में

To

मेसर्स खैराती लाल
M/s Khairati Lal
आरजेड-246/पी, राज नगर-II
RZ-246/P, Raj Nagar-II
पालम कॉलोनी, नई दिल्ली- 110045
Palam Colony, New Delhi-110045
Email id: lal_khairati@yahoo.com

विषय : आईएनए कॉलोनी, नई दिल्ली में मंदिर का संशोधन और नवीनीकरण।

Subject : Modification and Renovation of Mandir at INA Colony, New Delhi

संदर्भ : आपकी वित्तीय बोली दिनांक 29.02.2024 को खोली गई (निविदा आईडी: 2024_AAI_182872_1)

Ref : Your Financial Bid opened on dated 29.02.2024 (Tender ID: 2024_AAI_182872_1)

महोदय,

Sir,

- उपर्युक्त कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत मद दरो पर कुल रु. 1,22,35,416/- (रुपये एक करोड़ बाईस लाख पैंतीस हजार चार सौ सोलह मात्र) (जीएसटी को छोड़कर) की धनराशि, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद द्वारा स्वीकार की जाती है, जो कि अनुमानित लागत रु 1,92,86,000/- (रुपये एक करोड़ बानबे लाख छियासी हजार मात्र) (जीएसटी को छोड़कर), से 36.56% कम है, जैसा कि शैड्यूल 'ए' में संलग्न है।

Your e- tender for work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 1,22,35,416/- (Rs. One Crore Twenty Two Lakh Thirty Five Thousand Four Hundred Sixteen Only) (Excluding GST) which is 36.56% below the estimated cost put to tender of Rs. 1,92,86,000/- (Rupees One Crore Ninety-Two Lakh Eighty-Six Thousand Only) (Excluding GST) as per Schedule 'A' attached.

- 1/16 -

Signature
06.03.2024
AGMLB-4

2. सहायक महाप्रबंधक, (अभियांत्रिकी सिविल), सफदरजंग हवाई अड्डा, नई दिल्ली- 110003 कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि सहायक महाप्रबंधक, (अभियांत्रिकी सिविल), सफदरजंग एयरपोर्ट, नई दिल्ली-110003 के कार्यालय में इस पत्र के जारी होने में 15 दिनों के भीतर या उससे पहले उपस्थित होकर अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने का कष्ट करें। अनुबंध 100/- रुपये के मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

Asstt. Gen. Manager, (Engg.-Civil), Safdarjung Airport, New Delhi- 110003 shall be Engineer-in-charge of the work. You are requested to attend the office of Asstt. Gen. Manager, (Engg.-Civil), Safdarjung Airport, New Delhi- 110003, within 15 days from issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of the stamp paper shall be borne by you.

3. बयाना राशि रु 3,85,720/- (रुपये तीन लाख पचासी हजार सात सौ बीस मात्र), आपकी निविदा के साथ प्राप्त अनुबंध दस्तावेज की शर्त के अनुसार सुरक्षा जमा के हिस्से के रूप में माना जाएगा। कृपया रु. 8,37,822/- (रुपये आठ लाख सैंतीस हजार आठ सौ बाईस मात्र) इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में जमा करें। ऐसा न करने पर, उसकी कटौती अनुबंध दस्तावेज भाग के पृष्ठ जीसीसी- 16 पर खंड 1 (ए) की शर्त के अनुसार की जाएगी।

The earnest money amount of Rs. 3,85,720/- (Rupees Three Lakh Eighty-Five Thousand Seven Hundred Twenty Only) received along with your tender will be treated as part of security deposit as per condition of contract document. Please deposit Rs. 8,37,822/- (Rupees Eight Lakh Thirty-Seven Thousand Eight Hundred Twenty-Two Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause 1 (A) on page GCC - 16 of the contract document.

4. आप से अनुरोध किया जाता है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियमों 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार नियमन और सेवा की स्थिति) अधिनियम 1996, खंड में विनिर्दिष्ट के अनुसार भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 केन्द्रीय और राज्य सरकार के निविदा और नियमों के जीसीसी के धारा 19 पृष्ठ संख्या 49 से 55 व तदसम्बन्धी नियमों का अनुपालन करें।

You are requested to comply with the provision of contract labour (Regulation & Abolition) Act of 1970 and contract labour (Regulation & Abolition) central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on Page no. 49 to 55 of GCC of tender and rules of Central and State Government.

5. आपको सहायक प्रबंधक अभियांत्रिकी (सिविल), सफदरजंग हवाई अड्डा से तुरंत संपर्क करने का भी निर्देश दिया जाता है जो आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asstt. Manager Engg. (Civil), SAP immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने की समयावधि 10 (दस) महीने होगी और ये समय इस पत्र के जारी होने के पश्चात 10 वें दिन से प्रारम्भ माना जायेगा।

Please note that the time allowed for carrying out the work is 10 (Ten) Months and same shall be reckoned from the 10th day after issue of this letter.

7. इस अनुबंध के संबंध में किसी अन्य पत्राचार को सामान्य रूप से अभियंता प्रभारी को संबोधित किया जाना चाहिए।

Any further correspondence in connection with this contract should normally be addressed to the Engineer-in-charge.

8. कृपया रसीद स्वीकार करें और स्वीकृति के टोकन के रूप में अधोहस्ताक्षरी को हस्ताक्षर करने के बाद इस पत्र की डुप्लिकेट प्रति संलग्न करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. यदि हिंदी और अंग्रेजी संस्करण में कोई विसंगति है, तो अंग्रेजी संस्करण मान्य होगा।

If there is any discrepancies in Hindi and English version, then the English version shall prevail.

संलग्न: अनुसूची - 'A'
Encl: SCHEDULE- 'A'

भवदीय,
Yours Faithfully,

Shabir
06.03.2024

सहायक महाप्रबंधक (इंजीनियरिंग सिविल)
Asst. Gen. Manager (Engg. Civil)
सफदरजंग हवाई अड्डा, नई दिल्ली-03
Safdarjung Airport, New Delhi-03
अध्यक्ष की ओर से,
For & on Behalf of The Chairman,
Airports Authority of India
भारतीय विमानपत्तन प्राधिकरण

Tender Inviting Authority: Airports Authority of India

Name of Work: Modification and Renovation of Mandir at INA Colony, New Delhi

Contract No: 2024_AAI_182872_1

Name of the
Bidder/ Bidding
Firm / Company :

M/s KHAIRATI LAL

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Value only.)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P.	TOTAL AMOUNT Without Taxes in Rs. P.	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Civil Works Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer in-charge. - All kinds of soil	100.00	cum	200.00	20000.00	INR Twenty Thousand Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. - All kinds of soil	552.00	cum	250.00	138000.00	INR One Lakh Thirty Eight Thousand Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	326.00	cum	100.00	32600.00	INR Thirty Two Thousand Six Hundred Only
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	73.00	cum	800.00	58400.00	INR Fifty Eight Thousand Four Hundred Only
5	Supplying chemical emulsion in sealed containers including delivery as specified. - Chlorpyrifos/ Lindane emulsifiable concentrate of 20%	116.00	litres	338.00	39208.00	INR Thirty Nine Thousand Two Hundred & Eight Only
6	Diluting and injecting chemical emulsion for POST CONSTRUCTIONAL antitermite treatment (excluding the cost of chemical emulsion) : - Treatment of soil under existing floors using chemical emulsion @ one litre per hole, 300 mm apart including drilling 12 mm diameter holes and plugging with cement mortar 1 : 2 (1 cement : 2 Coarse sand) to match the existing floor. With Chlorpyrifos/Lindane E.C. 20% with 1% concentration	209.00	sqm	20.00	4180.00	INR Four Thousand One Hundred & Eighty Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	19.00	cum	5800.00	110200.00	INR One Lakh Ten Thousand Two Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder	TOTAL AMOUNT Without Taxes in	TOTAL AMOUNT in Words
1	2	4	5	13	53	55
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. - 1:4:8 (1 Cement : 4 coarse sand (zone III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	107.00	cum	4000.00	428000.00	INR Four Lakh Twenty Eight Thousand Only
9	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	94.00	sqm	400.00	37600.00	INR Thirty Seven Thousand Six Hundred Only
10	Centering and shuttering including strutting, propping etc. and removal of form work for : - Foundations, footings, bases of columns, etc. for mass concrete	200.00	sqm	300.00	60000.00	INR Sixty Thousand Only
11	Centering and shuttering including strutting, propping etc. and removal of form work for : - Suspended floors, roofs, landings, balconies and access platform	389.00	sqm	300.00	116700.00	INR One Lakh Sixteen Thousand Seven Hundred Only
12	Centering and shuttering including strutting, propping etc. and removal of form work for : - Lintels, beams, plinth beams, girders, bressumers and cantilevers	398.00	sqm	300.00	119400.00	INR One Lakh Nineteen Thousand Four Hundred Only
13	Centering and shuttering including strutting, propping etc. and removal of form work for : - Columns, Pillars, Piers, Abutments, Posts and Struts	142.00	sqm	300.00	42600.00	INR Forty Two Thousand Six Hundred Only
14	Centering and shuttering including strutting, propping etc. and removal of form work for : - Arches, domes, vaults up to 6 m span	137.00	sqm	450.00	61650.00	INR Sixty One Thousand Six Hundred & Fifty Only
15	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentering at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured). Suspended floors, roofs, landing, beams and balconies (Plan area to be measured)	352.00	sqm	100.00	35200.00	INR Thirty Five Thousand Two Hundred Only
16	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. - Thermo-Mechanically Treated bars of grade Fe 500D or more.	13188.00	kg	70.00	923160.00	NR Nine Lakh Twenty Three Thousand One Hundred & Sixty Only
17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe 500D or more.	19311.00	kg	73.00	1409703.00	INR Fourteen Lakh Nine Thousand Seven Hundred & Three Only

- 5/16 -

(Signature)
06.03.2024
AGM (E-1)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rupees To be entered by the Bidder	TOTAL AMOUNT Without Taxes in Rupees	TOTAL AMOUNT in Words
1	2	4	5	13	53	55
18	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. - All works upto plinth level - Concrete of M25 grade with minimum cement content of 330 kg /cum	84.00	cum	6500.00	546000.00	NR Five Lakh Forty Six Thousand Only
19	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. - All works above plinth level upto floor V level - Concrete of M25 grade with minimum cement content of 330 kg /cum	123.00	cum	6550.00	805650.00	NR Eight Lakh Five Thousand Six Hundred & Fifty Only
20	Add for using extra cement in the items of design mix over and above the specified cement content therein.	68.00	quintal	700.00	47600.00	NR Forty Seven Thousand Six Hundred Only
21	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	49.00	cum	5500.00	269500.00	NR Two Lakh Sixty Nine Thousand Five Hundred Only
22	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : - Cement mortar 1:6 (1 cement : 6 coarse sand)	90.00	cum	6000.00	540000.00	NR Five Lakh Forty Thousand Only
23	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level - Cement mortar 1:4 (1 cement : 4 coarse sand)	24.00	sqm	500.00	12000.00	NR Twelve Thousand Only
24	Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the marble shade (to be secured to the backing by means of cramps, which shall be paid for separately). Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble. Area of slab over 0.50 sqm	91.00	sqm	1250.00	113750.00	NR One Lakh Thirteen Thousand Seven Hundred & Fifty Only

- 6/16 -

Shakul
06.13.2024
ACM LE-1

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rs. To be entered by the Bidder	TOTAL AMOUNT Without Taxes in Rs.	TOTAL AMOUNT In Words
		4	5	13	53	55
25	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red Area of slab over 0.50 sqm	115.00	sqm	2280.00	262200.00	INR Two Lakh Sixty Two Thousand Two Hundred Only
26	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	30.00	sqm	800.00	24000.00	INR Twenty Four Thousand Only
27	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.50	cum	115000.00	57500.00	INR Fifty Seven Thousand Five Hundred Only
28	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class teak wood 35 mm thick	10.00	sqm	3000.00	30000.00	INR Thirty Thousand Only
29	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part 1) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	15.00	sqm	3000.00	45000.00	INR Forty Five Thousand Only
30	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	15.00	sqm	150.00	2250.00	INR Two Thousand Two Hundred & Fifty Only
31	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws: 35 mm thick shutters With ISI marked stainless steel butt hinges of required size Second class teak wood	10.00	sqm	4500.00	45000.00	INR Forty Five Thousand Only
32	Providing 40x5 mm flat iron hold fast 400 mm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 300x100x150mm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).	12.00	each	250.00	3000.00	INR Three Thousand Only
33	Providing and fixing IS : 12817 marked stainless steel butt hinges (heavy weight) with stainless steel screws etc. complete: 100x60x2 50 mm	8.00	each	200.00	1600.00	INR One Thousand Six Hundred Only
34	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	2.00	each	800.00	1600.00	INR One Thousand Six Hundred Only

- 7/16 -

Chakul
06.03.2024
AQM (E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Rs. To be entered by the	TOTAL AMOUNT Without Taxes in Rs.	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
35	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS - 2045 Type S, including cost of adhesive of approved quality. 1.0 mm thick	30.00	SQM	600.00	18000.00	INR Eighteen Thousand Only
36	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	5000.00	kg	85.00	425000.00	INR Four Lakh Twenty Five Thousand Only
37	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	3500.00	kg	95.00	332500.00	INR Three Lakh Thirty Two Thousand Five Hundred Only
38	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	1500.00	kg	82.00	123000.00	INR One Lakh Twenty Three Thousand Only
39	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	1000.00	kg	430.00	430000.00	INR Four Lakh Thirty Thousand Only
40	Marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with Makrana white second quality	352.00	SQM	2100.00	739200.00	INR Seven Lakh Thirty Nine Thousand Two Hundred Only
41	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	602.00	SQM	950.00	571900.00	INR Five Lakh Seventy One Thousand Nine Hundred Only
42	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	10.00	SQM	1000.00	10000.00	INR Ten Thousand Only
43	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1 : 4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	35.00	SQM	950.00	33250.00	INR Thirty Three Thousand Two Hundred & Fifty Only

- 8/16 -

800.5

Shabir
06.03.2024
AEM/EC

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rupee To be entered by the bidder	TOTAL AMOUNT Without Taxes in Rupee	TOTAL AMOUNT in Words
1	2	4	5	13	53	55
44	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to IS : 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600 x 600 mm	8.00	sqm	1000.00	8000.00	INR Eight Thousand Only
45	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. - 110 mm diameter	50.00	metre	350.00	17500.00	INR Seventeen Thousand Five Hundred Only
46	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channel 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : - 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2099 (Part I) 2011 (Board with BIS certification mark)	180.00	sqm	705.00	126900.00	INR One Lakh Twenty Six Thousand Nine Hundred Only
47	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	802.00	sqm	600.00	481200.00	INR Four Lakh Eighty One Thousand Two Hundred Only
48	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	639.00	sqm	220.00	140580.00	INR One Lakh Forty Thousand Five Hundred & Eighty Only
49	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	1091.00	sqm	250.00	272750.00	INR Two Lakh Seventy Two Thousand Seven Hundred & Fifty Only

-9/16-

Shakun
06.03.2024
AGM (E-1)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In ₹ (To be entered by the Bidder)	TOTAL AMOUNT Without Taxes in ₹	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
50	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	1091.00	sqm	40.00	43640.00	INR Forty Three Thousand Six Hundred & Forty Only
51	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	1000.00	sqm	40.00	40000.00	INR Forty Thousand Only
52	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	1000.00	sqm	80.00	80000.00	INR Eighty Thousand Only
53	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1730.00	sqm	80.00	138400.00	INR One Lakh Thirty Eight Thousand Four Hundred Only
54	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	639.00	sqm	100.00	63900.00	INR Sixty Three Thousand Nine Hundred Only
55	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in -charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	602.00	sqm	70.00	42140.00	INR Forty Two Thousand One Hundred & Forty Only
56	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in -charge.	34.00	cum	450.00	14850.00	INR Fourteen Thousand Eight Hundred & Fifty Only
57	Extra for scrapping, cleaning and straightening reinforcement from R.C.C. or R.B. work.	389.00	kg	100.00	38900.00	INR Thirty Eight Thousand Nine Hundred Only
58	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in-charge. In cement mortar	35.00	cum	350.00	12250.00	INR Twelve Thousand Two Hundred & Fifty Only
59	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50 m (stacks of cleaned bricks shall be measured): From brick work in cement mortar	2.59	1000 Nos.	1500.00	3885.00	INR Three Thousand Eight Hundred & Eighty Five Only
60	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area 3 sq. metres and below	19.00	each	200.00	3800.00	INR Three Thousand Eight Hundred Only
61	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	500.00	kg	3.00	1500.00	INR One Thousand Five Hundred Only
62	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	262.00	sqm	50.00	13100.00	INR Thirteen Thousand One Hundred Only
63	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	67.00	sqm	50.00	3350.00	INR Three Thousand Three Hundred & Fifty Only

- 10/16 -

Shakur
06.03.2024
AQM (E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rs. To be entered by the bidder	TOTAL AMOUNT Without Taxes in Rs.	TOTAL AMOUNT In Words
1	2	4	5	13	51	55
64	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	500.00	sqm	50.00	25000.00	INR Twenty Five Thousand Only
65	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	1.00	each	6000.00	6000.00	INR Six Thousand Only
66	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work Exposed on wall 25 mm nominal dia Pipes	200.00	metre	140.00	28000.00	INR Twenty Eight Thousand Only
67	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia Pipes	100.00	metre	100.00	10000.00	INR Ten Thousand Only
68	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 25 mm nominal bore	2.00	each	600.00	1200.00	INR One Thousand Two Hundred Only
69	Providing and fixing unplasticised PVC connection pipe with brass unions - 45 cm length 20 mm nominal bore	10.00	each	100.00	1000.00	INR One Thousand Only
70	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C.I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design : - With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	5.00	each	5800.00	29000.00	INR Twenty Nine Thousand Only
71	Constructing masonry Chamber 120x120x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100 mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:1.5:3 mix (1 cement : 5 coarse sand : 3 graded stone aggregate 20 mm nominal size), including necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	5.00	each	9000.00	45000.00	INR Forty Five Thousand Only
72	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	2000.00	litres	6.30	12600.00	INR Twelve Thousand Six Hundred Only

- 11/16 -

Shabir
06.03.2024
AGN/LE-1

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Rupees To be entered by the Bids.	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
73	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe	100.00	RM	400.00	40000.00	INR Forty Thousand Only
74	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	50.00	kg	400.00	20000.00	INR Twenty Thousand Only
75	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	100.00	kg	430.00	43000.00	INR Forty Three Thousand Only
76	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. - Pre-laminated particle board with decorative lamination on both sides	20.00	sqm	700.00	14000.00	INR Fourteen Thousand Only
77	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	20.00	sqm	550.00	11000.00	INR Eleven Thousand Only
78	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg. for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. - With brass cover plate minimum 1.25 mm thickness	4.00	each	3500.00	14000.00	INR Fourteen Thousand Only

- 12/16 -

Signature
06.03.2024
AGM

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rupees To be entered by the bidder	TOTAL AMOUNT Without Taxes in Rupees	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
79	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	2.00	each	1800.00	3600.00	INR Three Thousand Six Hundred Only
80	Brick work with old bricks in substructure/ superstructure in all shapes and sizes in : (a) Cement mortar 1:6 (1 cement : 6 coarse sand) [Note: Bricks shall be supplied by Deptt at free of cost]	5.00	cum	1500.00	7500.00	INR Seven Thousand Five Hundred Only
81	Providing & fixing GRC (Glass Fiber reinforced Concrete) ITEMS made out of White cement having 25 mm thickness in required shape and size as per approved Architectural/ Structural design & drawings. The items shall be made by using high power spray machine, using Cem-fill manufactured AR Glass fiber with minimum ZrO2 17%. Individual/ Composite GRC items shall be fixed with proper jointing/sealing with approved adhesives & sealants and drilling holes in RCC/ Steel/ Brick work and fixing on to external façade with Stainless steel 316 grade clamps/ fastener of suitable dia & lengths, grouting with sealants as per manufacturer's specifications etc. complete as per drawing and as directed by Engineer-in-Charge. Contractor shall arrange sample as per intent design for approval. Mock-up shall be carried out for minimum one panel of approved sample with suggested fixing arrangement. Work shall be carried out as per approved sample, Mock-up, and shop drawing. Note: 1. The rate for the items shall include approval of design, fabrication/ manufacturing, carriage at site, fixing the GRC items as per manufacturer's specification at all heights and levels.	90.00	sqm	4500.00	405000.00	INR Four Lakh Five Thousand Only
82	Deduct for taking away of aluminium scrap i/c butt hinges, sliding door bolts, tower bolts, pull boly lock, handle, door stopper, casement stay, tee chanals, plates etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	50.00	kg	68.00	-3400.00	INR Minus Three Thousand Four Hundred Only
83	Deduct for taking away of steel scraps i/c frames, shutters, trusses, channels, beams, Tee, angles, bolts, washers etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer in-Charge or his authorised representative all complete.	889.00	kg	30.00	-26670.00	INR Minus Twenty Six Thousand Six Hundred & Seventy Only
84	Providing Engineering Consultancy Services for structural designing and vetting of single storied RCC Framed Mandir with domes/Shikhars based on architectural/conceptual drawings supplied by AAI including submission of detailed soil investigation report, detailed structural design with calculations, detailed GFC/Construction drawings with all relevant calculation sheets duly vetted by IIT/NIT/Govt. Engineering College and revision of drawing/designs, if required during execution etc. as specified in tender document and any other details related to consultancy work which are essential for successful execution of works etc. complete as per direction and satisfaction of Engineer in Charge.	1.00	Job	350000.00	350000.00	INR Three Lakh Fifty Thousand Only
85	Horticulture Works Providing of Ficus Panda Plant, well developed, height 3 feet and above fresh, healthy, bushy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	100.00	each	300.00	30000.00	INR Thirty Thousand Only
86	Providing of Juniperus golden Plant, well developed, height 3 feet and above fresh, healthy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	50.00	each	300.00	15000.00	INR Fifteen Thousand Only
87	Providing of ficus benjamina Plant, well developed, height 3 feet and above fresh, healthy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	100.00	each	150.00	15000.00	INR Fifteen Thousand Only

- 13/16 -

Shabeer
06.03.2024
AGM/LEU

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Rs. To be entered by the Bidder	TOTAL AMOUNT Without Taxes in Rs.	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
88	Providing of Areca Palm Plant, well developed, height 3 feet and above fresh, healthy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	50.00	each	250.00	12500.00	NR Twelve Thousand Five Hundred Only
89	Providing of Morpankhi Thuja Compacta Plant, well developed, height 3 feet and above fresh, healthy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	50.00	each	200.00	10000.00	NR Ten Thousand Only
90	Providing of Dieffenbachia plant well developed, height 1.50 to 2.00 feet and above fresh, healthy leaves in pots/ Earthen /Plastic pot as per direction of officer-in-charge.	50.00	each	250.00	12500.00	NR Twelve Thousand Five Hundred Only
91	Providing and Stacking of Tulsi of ht. 30cm with multi branches in Poly bag of size 20 cm. as per direction of the officer-in-charge.	20.00	each	40.00	800.00	NR Eight Hundred Only
92	Supply of round cement pots size 16 X 16 inch having 4 no. wire vertical and 3 no. wire horizontal of good quality as per direction of officer-in-charge.	150.00	each	500.00	75000.00	NR Seventy Five Thousand Only
93	Electrical Works Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.					
93.1	Group A	20.00	Point	1500.00	30000.00	NR Thirty Thousand Only
93.2	Group C	73.00	Point	1800.00	131400.00	NR One Lakh Thirty One Thousand Four Hundred Only
94	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	92.00	Meter	90.00	8280.00	NR Eight Thousand Two Hundred & Eighty Only
95	Wiring for light/ power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 2 Nos. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	138.00	Meter	175.00	24150.00	NR Twenty Four Thousand One Hundred & Fifty Only
96	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.					
96.1	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	200.00	Meter	80.00	16000.00	NR Sixteen Thousand Only
96.2	2 X 6 sq. mm + 1 X 6 sq. mm earth wire	25.00	Meter	160.00	4000.00	NR Four Thousand Only
97	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	13.00	Each	800.00	10400.00	NR Ten Thousand Four Hundred Only
98	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	25.00	Each	38.00	950.00	NR Nine Hundred & Fifty Only
99	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connections etc. as required.	17.00	Each	100.00	1700.00	NR One Thousand Seven Hundred Only

- 14/16 -

Shakul
06.03.2024
Agmle-1

Sr. No.	Item Description	Quantity	Units	BASIC RATE IN Rs. To be entered by the Bidder	TOTAL AMOUNT Without Taxes in Rs.	TOTAL AMOUNT In Words
		4	5	13	53	55
100	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connect on etc. as required.	26.00	Each	100.00	2600.00	INR Two Thousand Six Hundred Only
101	Supplying and fixing 3 pin, 5A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	20.00	Each	35.00	700.00	INR Seven Hundred Only
102	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	2.00	Each	500.00	1000.00	INR One Thousand Only
103	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required.					
103.1	Group C	41.00	Point	1250.00	51250.00	INR Fifty One Thousand Two Hundred & Fifty Only
104	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 2 nos. 3 pin 5/6 A modular socket outlet and 2 nos. 5/6 A modular switch, connections etc. as required.	3.00	Each	100.00	300.00	INR Three Hundred Only
105	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connections, painting etc. as required.	6.00	Each	100.00	600.00	INR Six Hundred Only
106	Supplying and fixing PVC batten/ angle holder including connection etc. as required.	5.00	Each	50.00	250.00	INR Two Hundred & Fifty Only
107	MCD & DB: Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)					
107.1	12 way, Double door	1.00	Each	7000.00	7000.00	INR Seven Thousand Only

- 15/16 -

Kotaku
06.03.2024
AGM (E-L)

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Rupees To be entered by the Bidder R P	TOTAL AMOUNT Without Taxes in R P	TOTAL AMOUNT In Words
		4	5	13	53	55
1	2					
108	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required (But without MCB/RCCB/Isolator)					
108.1	8 way (4 + 24), Double door	1.00	Each	6000.00	6000.00	INR Six Thousand Only
109	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
109.1	Single pole	34.00	Each	200.00	6800.00	INR Six Thousand Eight Hundred Only
110	Supplying and fixing following rating, double pole, 240 V, MCB in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
110.1	40 A	1.00	Each	600.00	600.00	INR Six Hundred Only
111	Supplying and fixing following rating, four pole, 415 V, MCB in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
111.1	100 A	1.00	Each	6500.00	6500.00	INR Six Thousand Five Hundred Only
112	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 Volts, on surface/ recess, complete with testing and commissioning etc. as required.					
112.1	For 12 way, Double door SPN MCBDB	1.00	Each	7500.00	7500.00	INR Seven Thousand Five Hundred Only
113	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following triple pole and neutral, sheet steel, MCB distribution board, 415 Volts, on surface/ recess, complete with testing and commissioning etc. as required.					
113.1	For 8 way, Double door TPN MCBDB	1.00	Each	6000.00	6000.00	INR Six Thousand Only
114	Earthing Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	3.00	Each	8000.00	24000.00	INR Twenty Four Thousand Only
115	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	10.00	Meter	28.00	280.00	INR Two Hundred & Eighty Only
116	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	50.00	Meter	150.00	7500.00	INR Seven Thousand Five Hundred Only
117	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required	10.00	Meter	28.00	280.00	INR Two Hundred & Eighty Only
Total in Figures					12235416.00	INR One Crore Twenty Two Lakh Thirty Five Thousand Four Hundred & Sixteen Only
Quoted Rate in Words				INR One Crore Twenty Two Lakh Thirty Five Thousand Four Hundred & Sixteen Only		

- 16/16 -

Ghakar
06.03.2017
A/C

वितरण सूची:

Distribution List:

- | | | | |
|---|---|---|------------------------|
| 1 | कार्यपालक निदेशक (अभि.), एमआईएस एवं एस टी डी, भाविप्रा, राजीव गांधी भवन, सी एच क्यू नई दिल्ली | : | जानकारी के लिए |
| | E.D.(Engg), MIS & STD, AAI, Rajiv Gandhi Bhawan, CHQ, New Delhi | : | For information please |
| 2 | महाप्रबंधक (अभि.), भाविप्रा, एमआईएस एवं एस टी डी राजीव गांधी भवन, सी एच क्यू नई दिल्ली | : | जानकारी के लिए |
| | G.M.(Engg), AAI, MIS & STD, Rajiv Gandhi Bhawan, CHQ, New Delhi | : | For information please |
| 3 | निदेशक, भा.वि प्रा., सफदरजंग हवाई अड्डा, नई दिल्ली | : | जानकारी के लिए |
| | Airport Director, AAI, Safdarjung Airport, New Delhi | : | For information please |
| 4 | उप महाप्रबंधक (अभि. सिविल), आई एम् यू, एएआई, राजीव गांधी भवन, सी एच क्यू नई दिल्ली | : | जानकारी के लिए |
| | D.G.M.(Engg-C), IMU, AAI,, Rajiv Gandhi Bhawan, CHQ, New Delhi | : | For information please |
| 5 | सहायक महाप्रबंधक (वित्त), एएआई, एएआई, सफदरजंग हवाई अड्डा | : | जानकारी के लिए |
| | AGM (Fin.), AAI, SAP | : | For information please |
| 6 | सहायक महाप्रबंधक (ई-ई), एएआई, सफदरजंग हवाई अड्डा | : | जानकारी के लिए |
| | AGM (E-E), AAI, SAP | : | For information please |
| 7 | सहायक महाप्रबंधक (अभि. सिविल), आई एम् यू, एएआई, राजीव गांधी भवन, सी एच क्यू नई दिल्ली | : | जानकारी के लिए |
| | A.G.M.(Engg-C), IMU, AAI,, Rajiv Gandhi Bhawan, CHQ, New Delhi | : | For information please |
| 8 | सहा. प्रबंधक(अभि. सिविल), एएआई, सफदरजंग हवाई अड्डा, नई दिल्ली | : | आवश्यक कार्रवाई हेतु |
| | AM. (E-C), AAI, Safdarjung Airport, New Delhi | : | For Necessary Action |
| 9 | अनुबंध समझौते प्रति
Contract Agreement copy | | |

Shakur
06.03.2024

सहायक महाप्रबंधक (ईजी-सिविल) / A.G.M. (Engg-Civil),
सफदरजंग एयरपोर्ट, नई दिल्ली / Safdarjung Airport, New Delhi