



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

औरंगाबाद हवाईअड्डा AURANGABAD AIRPORTS

संदर्भ सं: भाविप्रा/औबाद/अभि-सिविल/W-141/2024/ 1039

दिनांक : 22.03.2024

सेवा में,
मेसर्स पारीख कश्यप इंदुलाल
801 रामेश्वर अपार्टमेंट, जलाराम-1
स्ट्रीट नं, 2/3 युनीवरसीटी रोड
राजकोट - 360 007 मो. 9909003837

To,
M/s Parikh Kashap Indulal
801, Rameshwar Apartment, Jalaram-1
Street 2/3, University Road
Rajkot - 360 007 Mob. 909003837

कार्य का नाम : औरंगाबाद हवाई अड्डे पर टर्मिनल भवन के मौजूदा शौचालय ब्लॉकों का नवीनीकरण ।

Name of work : Renovation of existing Toilet blocks of Terminal Building at Aurangabad Airport.

संदर्भ : दिनांक 20.03.2024 को खोली गयी आपकी ई-निविदा सं. 2024_AAI_183043_1

Ref. : (i) Your e-tender no. 2024_AAI_183043_1 opened on Dt. 20.03.2024


महोदय / Dear Sir,

1. उपर उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण कि ओर से आपके द्वारा बताए गये मद मुल्यों पर रू 99,76,195/- (रू. निन्यानवे लाख छिहतर हजार एक सौ पचानवे रुपये मात्र मात्र) को सभी करों को शामिल करके परंतु जी. एस. टी विरहित स्वीकृत की जाती है जोकी कार्य की अनुमानित लागत रुपये 1,07,89,952/- से 7.54% कम है।
1. Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the Item Rates quoted by you totaling to **Rs. 99,76,195/-** (Rupees Ninety Nine Lakhs Seventy Six Thousand One Hundred Ninety Five Only) inclusive of all taxes but excluding of GST which is 7.54% below the estimate cost put to tender Rs. 1,07,89,952/-.
2. सहा. महाप्रबंधक अभियांत्रिकी (सिविल), औरंगाबाद हवाईअड्डा कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामे पर हस्ताक्षर करने के लिये दिनांक 01.04.2024 को या पहले तक सहा. महाप्रबंधक अभियांत्रिकी (सिविल), भाविप्रा., औरंगाबाद हवाईअड्डा के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करें। ठेके का करारनामा रुपये 100/- के नोनजुडिशियल स्टेम्प पर निष्पादित किया जायेगा तथा स्टेम्प पेपर का खर्चा आपके द्वारा उठाया जायेगा।
2. **Asstt. General Manager Engg (Civil), AAI, Aurangabad Airport** shall be **Engineer-in-charge** of the work. You are requested to attend the office of sign the contract agreement at the office of the Asstt. General Manager Engg (Civil), AAI, Aurangabad Airport **on or before 01.04.2024** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of the stamp paper shall be borne by you.

22/03/2024

सहा. महा प्रबंधक (अभि. सिविल)
ASSTT. GENERAL MANAGER (ENGG-CIVIL)
भा.वि.प्रा.औरंगाबाद विमानक्षेत्र
AAI AURANGABAD AIRPORT

3. आपकी निविदा के साथ प्राप्त धरोहर राशि ऑन लाईन रु. 2,15,800/- (रु. दो लाख पंद्रह हजार आठ सौ मात्र) ठेके के दस्तावेज से पृष्ठ 16 पर दि गई खण्ड 1 ए के अनुसार जमानत राशि में परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर जमानत राशि की बकाया रु. 7,81,820/- (रु. सात लाख इक्कासी हजार आठ सौ बीस मात्र) जमा कराना है। असफल होने पर आपके चालु बिल से काट लिया जायेगा।
3. The earnest money amount of Rs. 2,15,800/- (Rupees Two Lakhs Fifteen Thousand Eight Hundred Only) received online along with your tender has been converted as part of security deposit as per clause-1 (A) on page 16 of tender document. Please deposit **Rs. 7,81,820/- (Rupees Seven Lakhs Eighty One Thousand Eight Hundred Twenty Only) towards Security deposit within 15 days from the date of issue of this letter**, failing which the same will be deducted from your running bill as per clause-1 (A) on page 16 of the tender document.
4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम नियमन तथा उन्मूलन एवं केंद्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रावधानों का अनुपालन करें।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and Minimum Wages Act & rules thereof Central and State Governments.
5. आप वस्तु एवं सेवा कर (जी.एस.टी.) के तहत पंजीकृत हैं। आपके निविदा मद दर में किसी भी कर, टैक्स, फिस और शुल्क शामिल है, जिसके तहत कोई भी नियम जीएसटी विरहित बोली प्रस्तुत करने की अंतिम तिथि के अनुसार लागू और आप जीएसटी प्रावधान के अनुरूप हैं। जी.एस.टी प्रावधानों का अनुपालन और किसी भी इनपुट क्रेडिट की रूकावट के मामले में, आप भाविप्रा को क्षतिपूर्ति करने के लिए जिम्मेदार होंगे।
5. You are registered under Goods & Service Tax (GST). Your tendered item rate is inclusive of any taxes duties, cess, fee and charges levied under any statute but excluding GST as applicable on the last date of bid submission and has given undertaking that you are compliant of GST provision. In case of non-compliance of GST provisions and blockage of any input credit, you shall be responsible to indemnify AAI.
6. आपको निर्देश दिया जाता है कि आप तुरंत सहा. प्रबंधक (अभि-सिविल), भा.वि.प्रा., औरंगाबाद हवाईअड्डा, औरंगाबाद से मिलें वह आपको साईट सौंपने की व्यवस्था करेंगे।
6. You are also directed to contact **Asstt. Manager (Engg-Civil), AAI, Aurangabad Airport, Aurangabad** immediately who will arrange to hand over the site to you.
7. कृपया नोट करें कि काम करने का अनुमत समय **09 (नौ) माह** है जो इस पत्र के जारी होने के दसवें दिन **01.04.2024** से शुरू होगा।
7. Please note that the time allowed for carrying out the work is **09 (Nine) months** and shall be reckoned from the tenth day i.e. **01.04.2024** after issue of this letter.


22/03/2024

8. हिंदी और अंग्रेजी के बीच विसंगति के मामले में अंग्रेजी संस्करण का पालन किया जाएगा।
8. In case of discrepancy between hindi and english, english version will be followed.
9. इस ठेके के सम्बंध में आगे कोई भी पत्राचार सहा. महाप्रबंधक अभियांत्रिकी (सिविल), भाविप्रा., औरंगाबाद हवाईअड्डा, औरंगाबाद — 431 007 के पते पर किया जाए।
9. Any further correspondence in connection with the contract should normally be addressed to the **Asstt. General Manager Engg. (Civil), AAI, Aurangabad Airport, Aurangabad – 431 007.**
10. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
10. All letters referred above shall form part of contract.
11. अनुरक्षण अवधि के दौरान क्षति, दोषों के लिए ठेकेदार ठेके के दस्तावेज से खण्ड 17 पृष्ठ 47 व 48 पर दी गई अवधि के लिए जिम्मेदार होगा।
11. Contractor shall be liable for damages, defects during maintenance period as mentioned in clause 17 on page 47 and 48 of the contract document.
12. कृपया पावती भेजे।
12. Please acknowledge the receipt.

सलग्न : (11) ग्यारह शेड्यूल की प्रती

भवदीय,
सहा. महा प्रबंधक (अभि. सिविल)
ASSTT. GENERAL MANAGER (ENGG-CIVIL)
भा.वि.प्रा.औरंगाबाद विमानक्षेत्र 22/09/2024
AAI AURANGABAD AIRPORT (राजेश वाणी)
सहा. महाप्रबंधक (अभियांत्रिकी-सिविल)
भाविप्रा, औरंगाबाद हवाईअड्डा

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. General Manager (Engg-Civil) Airports Authority of India, Aurangabad Airport

Name of Work: Renovation of existing Toilet blocks of Terminal Building at Aurangabad Airport

Contract No: 2024_AAI_183043_1

Name of the Bidder/ Bidding Firm / Company : Parikh Kashyap Indulal

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)	TEXT #
1	2	4	5	13	53	55	
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground upto 1000 m lead within Airport premises.	960.00	sqm	90.00	86400.00	INR Eighty Six Thousand Four Hundred Only	
2	Demolishing cement concrete manually/ by mechanical means including disposal of material upto 1000 m lead within Airport premises as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	21.00	cum	700.00	14700.00	INR Fourteen Thousand Seven Hundred Only	
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material upto 1000 m lead within Airport premises as per direction of Engineer-in-charge. - In cement mortar	115.00	cum	700.00	80500.00	INR Eighty Thousand Five Hundred Only	
4	Dismantling and taking away doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. including disposal of unserviceable surplus material as directed by Engineer-in-charge - Of area 3 sq. metres and below	77.00	each	250.00	19250.00	INR Nineteen Thousand Two Hundred & Fifty Only	

22/08/2024

सहा. महा प्रबंधक (अभि. सिविल)
ASSTT. GENERAL MANAGER (ENGG-CIVIL)
भा.वि.प्रा.औरंगाबाद विमानक्षेत्र
AAI AURANGABAD AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
5	Dismantling stone slab flooring /granite/marble laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 1000 metres lead of Airport premises.	116.00	sqm	150.00	17400.00	INR Seventeen Thousand Four Hundred Only
6	Dismantling tile work in floors and walls laid in cement mortar including stacking material upto 1000 m lead within Airport premises. (For thickness of tiles 10 mm to 25 mm)	1688.00	sqm	80.00	135040.00	INR One Lakh Thirty Five Thousand & Forty Only
7	Disposal of building rubbish / maba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond initial lead, for all leads including all lifts involved.	230.00	cum	400.00	92000.00	INR Ninety Two Thousand Only
8	Dismantling W.C. Pan, Urinals, Wash basins of all sizes including disposal of dismantled materials within Airport premises i/c maba all complete as per directions of Engineer-in-Charge.	169.00	each	97.00	16393.00	INR Sixteen Thousand Three Hundred & Ninety Three Only
9	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make Kajaria/Soman/Grancier/Donato or equivalent, in all colours & shade, in walls, skirting, dado, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of tile ranging from 500x500 mm - 1200x1200 mm	907.00	sqm	1600.00	1451200.00	INR Fourteen Lakh Fifty One Thousand Two Hundred Only
10	Cement Plaster in fine sand. 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	500.00	sqm	450.00	225000.00	INR Two Lakh Twenty Five Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
11	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/ making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. a) GI Metal Ceiling Lay in plain Tegal edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	488.00	sqm	1829.00	892552.00	INR Eight Lakh Ninety Two Thousand Five Hundred & Fifty Two Only
12	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	375.00	sqm	55.00	20625.00	INR Twenty Thousand Six Hundred & Twenty Five Only
13	Wall painting with acrylic emulsion paint of approved brand Nerolac/Asian Paints or equivalent, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. - Two coats	375.00	sqm	170.00	63750.00	INR Sixty Three Thousand Seven Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
14	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour Italian Biege, black, Cherry/Ruby red - Area of slab over 0.50 sqm	138.00	sqm	3300.00	455400.00	INR Four Lakh Fifty Five Thousand Four Hundred Only
15	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	101.00	metre	200.00	20200.00	INR Twenty Thousand Two Hundred Only
16	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. - Granite work	101.00	metre	120.00	12120.00	INR Twelve Thousand One Hundred & Twenty Only
17	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	47.00	each	2500.00	117500.00	INR One Lakh Seventeen Thousand Five Hundred Only
18	Providing and fixing uplasticised PVC connection pipe with brass unions : 45 cm length - 15 mm nominal bore	50.00	each	100.00	5000.00	INR Five Thousand Only
19	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1.0 mm thick.	53.00	sqm	750.00	39750.00	INR Thirty Nine Thousand Seven Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
20	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete : For pipes 100 to 250 mm diameter	15.00	each	4000.00	60000.00	INR Sixty Thousand Only
21	Constructing brick masonry road gully chamber 50x45x60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design : With common burnt clay F.P.S. (non modular) bricks of class designation 5.	15.00	each	6000.00	90000.00	INR Ninety Thousand Only
22	Providing & fixing commercial waterproof plywood of ISI approved brand and make to be fixed at any location with fevicol, nail & screw etc. complete as per the directions of Engineer-in-charge. a) 18 mm thick plywood	53.00	sqm	1200.00	63600.00	INR Sixty Three Thousand Six Hundred Only
23	Providing and laying matt finished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) conforming to IS: 15622 with water absorption less than 0.08% of approved make Kajaria/Somani/Grancier/Donato or equivalent in all colours and shades, with cement based high polymer modified quick-set tile adhesive conforming to IS: 15477, in average 3mm thickness. etc., complete. Size of Tile ranging from 500x500 mm -1200x1200 mm	488.00	sqm	1500.00	732000.00	INR Seven Lakh Thirty Two Thousand Only
24	Providing and fixing Unplasticized Polyvinyl Chloride (UPVC) pipe including all UPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with UPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. - 15 mm nominal dia Pipes	120.00	metre	300.00	36000.00	INR Thirty Six Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
25	Providing and fixing Unplasticized Polyvinyl Chloride (UPVC) pipe including all UPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with UPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. - 25 mm nominal dia Pipes	350.00	metre	500.00	175000.00	INR One Lakh Seventy Five Thousand Only
26	Providing and fixing Unplasticized Polyvinyl Chloride (UPVC) pipe including all UPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with UPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 32 mm nominal dia Pipes	350.00	metre	600.00	210000.00	INR Two Lakh Ten Thousand Only
27	Providing and fixing Unplasticized Polyvinyl Chloride (UPVC) pipe including all UPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with UPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. - 50 mm nominal dia Pipes	120.00	metre	950.00	114000.00	INR One Lakh Fourteen Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
28	Providing and fixing toilet cubicles of Merino Besco (Titan series), Greenlam Sturdo (Classique's Evergreen series) or equivalent, made of heat, bacteria, water, chemical, scratch, impact, anti-bacterial resistant 12 mm thick solid compact laminate panel board which includes doors, pilasters and intermediate panels finished with approved texture/shade as per the detailed drawings and as per IS 2046 (Indian Standards) and fire retardant BS-476/97 standards. This also includes providing and fixing in position necessary hardware made out of SS (grade 304) as per manufacturer's specification and Engineer-in-Charge instructions like - (i) Door Knobs, (ii) Gravity Hinges, (iii) Thumb turn lockset with Occupancy indicators, (iv) Coat hooks with door stopper (v) U/F- channel, (vi) Adjustaple foot/pedestal, (vii) Top rail with corner connector, (viii) Rubber noise deafening tape, (ix) Screws and wall plugs etc. The top fitting should consist of SS rectangular top rail which will get fixed with pilasters with SS panel tube holder, SS corner bend (connected with top rail) will be used on the corner of cubicle in absence of brick wall. SS wall fixing is used only on the wall which will hold the SS top rail. All screws shall be of 304 grade in Stainless steel with satin finish. All pilasters are supported by stainless steel bottom cladding. The base of the stainless steel bottom cladding will be anchored to the door with a clearance height upto 150 mm. Size of each Cubical - (a) Plan area of cubicle varies from 1.50 to 2.00 Sqm (b) Height of cubicle is 1980 mm including bottom leg of 150 mm (c) Width of door is 600 mm. (The rates shall include providing and fixing of compact laminate panel board, fittings and fixtures, wastage, scaffolding, tools, plants, all cost of toilet cubicle and labour involved in all the operations described above including cartage lifts and all taxes excluding GST)	65.00	each	32000.00	2080000.00	INR Twenty Lakh Eighty Thousand Only
29	Providing and fixing Urinal Partition system using 12 mm thick panel of Besco Merino (Urinal Modesty SS Series) or equivalent with each panel size 500 mm X 1200 mm, overall height of 1850 mm including bottom gap of 650 mm, including fixing the panel at wall with fixtures, fitting and accessories such as SS Right angle brackets, screws, wall plugs, and of approved colour and shade as per site requirement as per specification and directions of Engineer-in-Charge	49.00	each	4750.00	232750.00	INR Two Lakh Thirty Two Thousand Seven Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
30	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 5 in foundations and plinth in : Cement mortar 1:3 (1 cement : 3 coarse sand)	55.00	sqm	1012.00	55660.00	INR Fifty Five Thousand Six Hundred & Sixty Only
31	Providing and fixing white vitreous china flat back urinal of size 385x325x635 mm of make JAQUAR URS-WHT-13253N or Equivalent with fittings and standard accessories, standard size C.P. brass flush pipe, spreaders, waste coupling with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, waste trap with outlet grating and other couplings in C.P. brass, painting, fitting, cutting and making good the walls and floors wherever required as per satisfaction of Engineer-in-Charge.	44.00	each	5000.00	220000.00	INR Two Lakh Twenty Thousand Only
32	Providing and fixing Under counter wash basin of size 605 x 430 x 200 mm and oval shape of Jaquar CNS-WHT-705 or Equivalent including waste coupling 32 mm size full threaded of Jaquar ALD-CHR-705 make or equivalent fixing, painting of fittings, cutting and making good the walls wherever required as per the directions of Engineer-in-Charge.	47.00	each	2200.00	103400.00	INR One Lakh Three Thousand Four Hundred Only
33	Providing and fixing white rimless Wall hung type water closet pan of size 570 x 390 x 365 mm of JAQUAR VGS-WHT-81953UF make or Equivalent including UF seat cover with hinges, accessories, etc. all complete as per direction of Engineer-in-Charge.	44.00	each	13500.00	594000.00	INR Five Lakh Niney Four Thousand Only
34	Providing and fixing white Orissa pattern W.C. pan of size 440x575x250 mm of Essco Jaquar make ECS-WHT- 451 or Equivalent including all fixing accessories complete as per direction of Engineer-in-Charge	11.00	each	1500.00	16500.00	INR Sixteen Thousand Five Hundred Only
35	Providing and fixing Push Pillar cock with Auto-closing system and 65 mm extension body of Jaquar PRS-CHR-031L65 make or Equivalent including making connection, etc as per direction of Engineer-in-Charge.	47.00	each	2200.00	103400.00	INR One Lakh Three Thousand Four Hundred Only
36	Providing and fixing Angular Stop Cock with wall flange of Jaquar CON-CHR-059KN make or equivalent as per direction of Engineer-in-Charge.	47.00	each	750.00	35250.00	INR Thirty Five Thousand Two Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
37	Providing and fixing bottle trap of 32 mm size of Jaquar ALD-CHR-769L300x190 make or Equivalent including 300 mm and 190 mm long wall connection pipes with wall flanges and making connection, etc. all complete as per direction of Engineer-in-charge	47.00	each	1450.00	68150.00	INR Sixty Eight Thousand One Hundred & Fifty Only
38	Providing and fixing dual flow 32 mm concealed body metropole flush valve with exposed shut off provision & round flange (3 / 6 litres per flushing) for WC of Jaquar FLV-CHR-1085N make or Equivalent including making connection etc complete. as per direction of Engineer-in-charge	55.00	each	2700.00	148500.00	INR One Lakh Forty Eight Thousand Five Hundred Only
39	Providing and fixing auto closing concealed urinal flush valve with built in control cock and wall flange of Jaquar (PRS-CHR-073) make or Equivalent including making connection etc complete as per direction of Engineer-in-charge.	44.00	each	2100.00	92400.00	INR Ninety Two Thousand Four Hundred Only
40	Providing and fixing health faucet 8mm size of minimum length 1 metre of JAQUAR(ALD-CHR-573) make or Equivalent with 1 m long flexible connecting in chrome finish, wall hooks, etc. tube including making connection all complete as per direction of Engineer-in-charge	55.00	each	1200.00	66000.00	INR Sixty Six Thousand Only
41	Providing and Fixing tissue paper roll holder for toilets of Jaquar AKP-CHR-35751P make or equivalent and as per direction of Engineer-in-charge.	55.00	each	1225.00	67375.00	INR Sixty Seven Thousand Three Hundred & Seventy Five Only
42	Providing & Fixing soap dispenser with metallic bottle of Jaquar ACN-CHR-1137N or make or equivalent etc. complete as per directions of Engineer in charge.	47.00	each	2200.00	103400.00	INR One Lakh Three Thousand Four Hundred Only
43	Providing and fixing wall hung wash basin of Jaquar OPS-WHT-15305 or Equivalent of size 575 x 475 x 195 mm including waste coupling of Jaquar make or equivalent fixing accessories, painting of fittings, cutting and making good the walls wherever require as per direction of Engineer-in-charge	5.00	each	3800.00	19000.00	INR Nineteen Thousand Only
44	Providing and fixing 2 way bib cock with wall flange of Jaquar VGP-CHR-81041 make or Equivalent including making connection, etc as per direction of Engineer-in-charge.	55.00	each	1800.00	99000.00	INR Ninety Nine Thousand Only
45	Providing and fixing 6 mm thick mirror of superior glass (of approved quality) and of required size. Mirror to be fixed on wall with the help of CP brass screws and cap, including brackets, etc, complete as per direction of Engineer-in-charge.	23.00	sqm	1600.00	36800.00	INR Thirty Six Thousand Eight Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
46	Providing & Fixing PVC ball valve with lever of size 32 mm nominal dia of make Astral/Supreme/Prince or equivalent all complete as per directions of Engineer in charge.	40.00	each	400.00	16000.00	INR Sixteen Thousand Only
47	Providing & Fixing PVC ball valve with lever of size 50 mm nominal dia of make Astral/Supreme/Prince or equivalent all complete as per directions of Engineer in charge.	40.00	each	1100.00	44000.00	INR Forty Four Thousand Only
48	Providing & Fixing PVC ball valve with lever of size 75 mm nominal dia of make Astral/Supreme/Prince or equivalent all complete as per directions of Engineer in charge.	40.00	each	2100.00	84000.00	INR Eighty Four Thousand Only
49	Providing and fixing bronze gate valve Zoloto or equivalent make 40 mm nominal bore of approved quality to existing pipeline as per the direction of Engineer-Incharge.	25.00	each	3500.00	87500.00	INR Eighty Seven Thousand Five Hundred Only
50	Providing and fixing SWR PVC pipes conforming to IS Code 13592 having minimum working pressure 4kgf/sqcm of approved make such as Astral/Supreme/Prince/Kisan or equivalent including cost for bends, unions, traps, junctions, tees, elbows, etc. complete as per direction of Engineer In Charge - 110 mm Dia.	291.00	metre	400.00	116400.00	INR One Lakh Sixteen Thousand Four Hundred Only
51	Providing and fixing SWR PVC pipes conforming to IS Code 13592 having minimum working pressure 4kgf/sqcm of approved make such as Astral/Supreme/Prince/Kisan or equivalent including cost for bends, unions, traps, junctions, tees, elbows, etc. complete as per direction of Engineer In Charge - 75 mm Dia.	100.00	metre	315.00	31500.00	INR Thirty One Thousand Five Hundred Only
52	Providing and fixing SWR PVC pipes conforming to IS Code 13592 having minimum working pressure 4kgf/sqcm of approved make such as Astral/Supreme/Prince/Kisan or equivalent including cost for bends, unions, traps, junctions, tees, elbows, etc. complete as per direction of Engineer In Charge - 50 mm Dia.	100.00	metre	175.00	17500.00	INR Seventeen Thousand Five Hundred Only
53	Providing and fixing in position 30 mm thick machine cut Cuddapah stone for kitchen platform, shelves, venly counters, stand etc. complete at all levels as per the direction of Engineer-In-charge.	23.00	sqm	960.00	22080.00	INR Twenty Two Thousand & Eighty Only
54	Providing and fixing self closing sliding door system for flush doors of LAMP LM80-WOOD or equivalent etc complete as per direction of Engineer - in - Charge. (Flush door items will be paid separately)	5.00	each	15000.00	75000.00	INR Seventy Five Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
55	Providing and fixing stainless steel jali (grating) with or without hole for waste pipe for floor / Nahani trap 100 mm diameter including sealing with white cement as per the direction of Engineer-in-charge	135.00	each	150.00	20250.00	INR Twenty Thousand Two Hundred & Fifty Only
56	Providing and fixing Baby Diaper changing Station of Euronics EDC1 or equivalent. Size of changing station shall be minimum 800-900 mm in length & 500-600 mm in width having min weight capacity of 25 kgs. Rate shall be including installation, transportation, taxes etc, complete as per direction of Engineer - in - charge.	5.00	each	15000.00	75000.00	INR Seventy Five Thousand Only
Total in Figures					9976195.00	INR Ninety Nine Lakh Seventy Six Thousand One Hundred & Ninety Five Only
Quoted Rate in Words	INR Ninety Nine Lakh Seventy Six Thousand One Hundred & Ninety Five Only					


 22/03/2024
 सहा. महा प्रबंधक (अभि. सिविल)
 ASSTT. GENERAL MANAGER (ENGG-CIVIL)
 भा.वि.प्रा.औरंगाबाद विमानक्षेत्र
 AAIAURANGABAD AIRPORT