



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

देवी अहिल्याबाई होलकर विमानपत्तन, इंदौर-452 005

(आई.एस.ओ.9001:2015 आई.एस.ओ.14001: 2015 एवं आई.एस.ओ. 45001:2018 प्रमाणित विमानतल)

DEVI AHILYA BAI HOLKAR AIRPORT, INDORE-452 005

(ISO 9001:2015, ISO 14001: 2015 & ISO 45001: 2018 Certified Airport)

संदर्भ संख्या : भाविप्रा/इंदौर/अभि.-वि)/कार्य आदेश-02/2024-25

Ref. No.: AAI/ID/ENGG(E)/WO-02/2024-25

सेवा में,

To,

मेसर्स गैन्न डंकर्ले एंड कंपनी लिमिटेड,
16ए/1, अर्ल स्ट्रीट, फ्लैट नं. एन-1, पहली मंजिल,
कोलकाता - 700 026

M/s Gannon Dunkerley & Co. Ltd.,
16A/1, Earle Street, Flat No. N-1, 1st Floor,
Kolkata - 700 026

कार्य का नाम:- रिकन्फिगरेशन ऑफ इन्टीग्रेटेड टर्मिनल बिल्डिंग एण्ड रिनोवेशन ऑफ ओल्ड टर्मिनल बिल्डिंग एट डी.ए.बी.एच. एयरपोर्ट, इन्दौर।

सबहेड : एसआईटीसी ऑफ नॉन-इनलाईन बैगेज हैंडलिंग सिस्टम एट ओटीबी ऑफ डीएबीएच एयरपोर्ट, इन्दौर।

Name of Work: - Reconfiguration of Integrated Terminal Building & Renovation of Old Terminal Building at D.A.B.H. Airport, Indore.

Subhead :- SITC of Non-Inline Baggage Handling System at OTB of DABH Airport, Indore.

संदर्भ :- आपकी ई-निविदा दिनांक 19.02.2024, वित्तीय बिड खोलने का दिनांक 12.03.2024 और रिवर्स नीलामी दिनांक 14.03.2024.

Ref: Your E-Tender dated 19.02.2024, Financial Bid opened on 12.03.2024 & Reverse Auction dtd. 14.03.2024.

महोदय / Dear Sir,

- उपरोक्त कार्य के लिए आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार की जाती है। आपके द्वारा (उद्धृत रिवर्स नीलामी) के साथ कुल रु. 4,79,82,529/- (रुपये चार करोड़ उनअस्सी लाख बयासी हजार पांच सौ उनतीस मात्र) (जीएसटी छोड़कर) (एसआईटीसी कार्य के लिए रु. 85,12,539.48 और संचालन और एसआईसीएमसी कार्य के लिए रु. 3,94,69,989.60) जो कि निविदा की अनुमानित लागत रु. 6,77,92,687/- (छः करोड़ सतत्तर लाख बयान्ने हजार छः सौ सत्यासी मात्र) (जीएसटी को छोड़कर) से 29.22% कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted (along with reverse auction) by you totaling to Rs. 4,79,82,529/- (Rupees Four Crore Seventy Nine Lakh Eighty Two Thousand Five Hundred Twenty Nine only) (excluding GST) (Rs. 85,12,539.48 for SITC work and Rs. 3,94,69,989.60 for Operation and AICMC work) which is 29.22% below the Estimated cost of Rs. 6,77,92,687/- (Rs. Six Crore Seventy Seven Lakh Ninety Two Thousand Six Hundred Eighty Seven Only) (excluding GST).

Continued on page No. ...02

देवी अहिल्याबाई होलकर विमानतल इन्दौर दूरभाष - 0731-2626609

DEVI AHILYA BAI HOLKAR AIRPORT INDORE PHONE 0731-2626609



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

देवी अहिल्याबाई होलकर विमानपत्तन, इंदौर-452 005

(आई.एस.ओ.9001:2015 आई.एस.ओ.14001: 2015 एवं आई.एस.ओ. 45001:2018 प्रमाणित विमानतल)

DEVI AHILYA BAI HOLKAR AIRPORT, INDORE-452 005

(ISO 9001:2015, ISO 14001: 2015 & ISO 45001: 2018 Certified Airport)

-02-

2. सहायक महाप्रबंधक (अभि.-विद्युत)-I, भाविप्रा., दे.अ.बा.हो. विमानतल, इन्दौर कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि दिनांक 29.05.2024 तक सहायक महाप्रबंधक (अभि.-विद्युत)-I, भाविप्रा., दे. अ.बा.हो. विमानतल, इन्दौर के कार्यालय में आपकी ओर से अनुबंध समझौते पर हस्ताक्षर करने के लिए अधिकृत मान्यता प्राप्त प्रतिनिधि को नियुक्त करें। अनुबंध समझौता रुपये 100/- (एक सौ रुपये मात्र) के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The Assistant General Manager (Engg.-Elect.)-I, AAI DABH Airport, Indore shall be The Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract Agreement on your behalf, to attend the office of the Assistant General Manager (Engg.-Elect.)-I, AAI, DABH Airport, Indore by 29.05.2024 to sign and complete the Agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. एस.सी.सी. खंड संख्या 42.1 (i) निविदा दस्तावेज के पृष्ठ सं. SCC-29 के अनुसार, कृपया रुपये 4,25,627/- (रुपये चार लाख पच्चीस हजार छः सौ सत्ताईस मात्र) एस.आई.टी.सी. कार्य की सुरक्षा जमा के प्रति बी.जी. के रूप में इस पत्र के जारी होने की तारीख से 01 सप्ताह के भीतर जमा करें। ऐसा न करने पर उपरोक्त राशि को आर ए बिलों से काटी जायेगी। एस.सी.सी. खंड संख्या 42.1 (ii), निविदा दस्तावेज के पृष्ठ सं. SCC-29 के अनुसार, कृपया रुपये 1,32,702/- (रुपये एक लाख बत्तीस हजार सात सौ दो केवल) ऑपरेशन और ए.आई.सी.एम.सी. कार्य के सुरक्षा जमा के प्रति बीजी के रूप में ओ एण्ड एम अनुबंध के प्रारंभ होने की तिथि के 30 दिनों के भीतर जमा करें।

As per SCC clause No. 42.1 (i), page no. SCC- 29 of Tender Document, Please deposit Rs. 4,25,627/- (Rupees Four Lakh Twenty Five Thousand Six Hundred Twenty Seven only) for SITC Work toward Security Deposit in the form of Bank Guarantee within a week from the date of issue of this letter, failing which, same shall be deducted from RA Bills. Further as per clause 42.1 (ii) page no. SCC-29 of tender document you are required to deposit Rs. 1,32,702/- (Rs. One Lakh Thirty Two Thousand Seven Hundred Two Only) for Operation & AICMC work toward Security Deposit in form of Bank within 30 days after the date of commencement of O&M contract.

4. एस.सी.सी. खंड संख्या 42.2 (i), निविदा दस्तावेज के पृष्ठ सं. SCC-29 के अनुसार, कृपया रुपये 4,25,627/- (रुपये चार लाख पच्चीस हजार छः सौ सत्ताईस केवल) एस.आई.टी.सी. कार्य की निष्पादन गारंटी के प्रति बी.जी. के रूप में इस पत्र के जारी होने की तारीख से 60 दिनों के भीतर निविदा दस्तावेज की पृष्ठ संख्या GCC-103/104 पर उपलब्ध प्रोफार्मा के अनुसार जमा करें।

Continued on page No. ...03

देवी अहिल्याबाई होलकर विमानतल इन्दौर दूरभाष - 0731-2626609

DEVI AHILYA BAI HOLKAR AIRPORT INDORE PHONE 0731-2626609



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

देवी अहिल्याबाई होलकर विमानपत्तन, इंदौर-452 005

(आई.एस.ओ.9001:2015 आई.एस.ओ.14001: 2015 एवं आई.एस.ओ. 45001:2018 प्रमाणित विमानतल)

DEVI AHILYA BAI HOLKAR AIRPORT, INDORE-452 005

(ISO 9001:2015, ISO 14001: 2015 & ISO 45001: 2018 Certified Airport)

-03-

एस.सी.सी खंड संख्या 42.2 (i), निविदा दस्तावेज के पृष्ठ सं. SCC-30 के अनुसार, कृपया रुपये 5,26,952.00 (रुपये पांच लाख छब्बीस हजार नौ सौ बावन केवल) ऑपरेशन और ए.आई.सी.एम.सी. कार्य की निष्पादन गारंटी के प्रति बी.जी. के रूप में ओ एंड एम अनुबंध के प्रारंभ होने की तिथि के 60 दिनों के भीतर जमा करें ।

As per SCC Clause No. 42.2 (i), page no. SCC-29 of Tender Document, you shall submit for SITC work Performance Bank Guarantee for an amount of Rs. 4,25,627/- (Rupees Four Lakh Twenty Five Thousand Six Hundred Twenty Seven Only) within 60 days of issue of this letter and as per the Proforma available at page no. GCC-103/104 of the Tender Document. Further, as per Clause 42.2 (ii), page no. SCC-30 of tender document you are required to deposit Rs. 5,26,952/- (Rupees Five Lakh Twenty Six Thousand Nine Hundred Fifty Two Only) against O&M Work Performance Bank Guarantee within 60 days from the date of commencement of O&M contract.

5. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम (नियमन तथा उन्मुलन) तथा 1971 के केन्द्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मुलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों का अनुपालन करें।

You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Government.

6. आपको प्रबंधक (अभि.-विद्युत), भाविप्रा., दे.अ.बा.हो. विमानतल, इन्दौर से तुरंत संपर्क करने का भी निर्देश दिया जाता है जो आपको साइट सौंपने की व्यवस्था करेंगे ।

You are also directed to contact Manager (Engg.-Elect.), AAI, DABH Airport, Indore, immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि एस आई टी सी कार्य करने के लिए समय 04 (चार) महीना होगा और इसकी गणना इस पत्र के जारी होने की बाद की तिथि के बाद दसवें दिन से की जाएगी ।

Please note that the time allowed for carrying out the SITC work shall be 04 (Four) months and same shall be reckoned from the tenth day after the date of issue of this letter.

8. इस ठेके के संबंध में आगे कोई भी पत्राचार सहायक महाप्रबंधक (अभि.-विद्युत)-I, भा.वि.प्रा., दे.अ.बा. हो. विमानतल, इन्दौर म.प्र.-452005 के पते पर या ई-मेल rrbagre@aai.aero पर किया जाए ।

Any further correspondence in connection with this contract should normally be addressed to Assistant General Manager (Engg. -E)-I, AAI, D.A.B.H. Airport, Indore, M.P.- 452005 Or email-id rrbagre@aai.aero.

9. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे ।

All letters referred above shall form part of contract.

Handwritten signature
M. P. 452005

Continued on page No. ...04

देवी अहिल्याबाई होलकर विमानतल इन्दौर दूरभाष - 0731-2626609

DEVI AHILYA BAI HOLKAR AIRPORT INDORE PHONE 0731-2626609



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

देवी अहिल्याबाई होलकर विमानपत्तन, इंदौर-452 005

(आई.एस.ओ.9001:2015 आई.एस.ओ.14001: 2015 एवं आई.एस.ओ. 45001:2018 प्रमाणित विमानतल)

DEVI AHILYA BAI HOLKAR AIRPORT, INDORE-452 005

(ISO 9001:2015, ISO 14001: 2015 & ISO 45001: 2018 Certified Airport)

-04-

10. ठेका दस्तावेज की शर्तों के अनुसार त्रुटि दायित्व अवधि एसआईटीसी कार्य के लिये 24 (चौबीस) माह एवं ऑपरेशन और एआईसीएमसी कार्य के लिये 01 (एक) माह होगी।

The Defects Liability Period will be 24 (Twelve) Months for SITC work & 01 (One) Month for Operation & AICMC Work as per terms of Contract.


11. कृपया पावती भेजें एवं आपकी स्वीकृति के प्रतीक के रूप में इस कार्य आदेश की डुप्लीकेट प्रति पर हस्ताक्षर कर अधोहस्ताक्षरी को पुनः भेजने का कष्ट करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

12. यदि अंग्रजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रजी विवरण सही माना जायेगा।
If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

Encl: Schedule of Quantities (06 Pages)

भवदीय /Yours Faithfully,


14/05/2024

सहायक महाप्रबंधक (अभि.विद्युत)-I,
Assistant General Manager (Engg-Elect)-I

भा.वि.प्रा. इन्दौर विमानतल, इन्दौर


AAI, DABH AIRPORT, INDORE

कृते तथा ओर से, अध्यक्ष

For and on behalf of Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India



14/05/24

SCHEDULE OF QUANTITIES

Name of Work :- Reconfiguration of Integrated Terminal Building and Renovation of Old Terminal Building at D.A.B.H. Airport Indore.

SH : SITC of Non Inline Baggage Handling System at OTB of DABH Airport Indore.

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
A	SH:I SITC OF PASSENGER BAGGAGE HANDLING SYSTEM				
1.01	Design, supply, installation, testing and commissioning of heavy duty endless, race track type horizontal flexible overlapping slat type, flat arrival baggage carousel, having 950 mm long (min), 300 mm wide and 5 mm (min) thickness and black in colour with smooth top. The material of slat shall be of PVC/ABS /PU/Rubber of high quality. The black colour slat shall be flexible, antistatic and flame retardant. The slat carrier support shall be minimum 3.0 mm thick fabricated from MS sheet duly painted/ powder coated having capacity normal live load rating of 35 Kg. (approx.) per linear meter. The height of conveyor system shall be 450mm from finished floor level and speed of 24-30 mtr./min. The carousel shall have curve radius, chain block, friction type suitable capacity drive unit, finished chain, frame work, supports, chain track, Take up section, side covering (inner & outer), Trim / Fascia, toe kick plate (inner & outer) in the passenger area as well as in the non-passenger area, Infill materials and all other accessories as per technical specifications for baggage handling system including cutting & drilling of holes, equipment Grouting, Earthing, necessary capacity cabling for drive from control panel, connection and interconnection, etc. as required for successful commissioning of baggage conveyor system in the baggage break up area. (a) (42+42) Mtrs.	84.00	Mtr.	40266.72	3382404.48


mgp(66)



Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.02	Electrical Control panel for Arrival baggage handling system: Design, Supply Installation, Testing and Commissioning of cubical type, Indoor floor / frame mounting, compartmentalized, fabricated out of CRCA sheet steel of thickness 2 mm duly powder coated with propoer ventilated with air louvers/ fans. The panel shall be front openable & accessible with doors having high quality neoprene rubber gasket & Door interlock feature with incoming power supply as per manufacturer standerd. The degree of protection for enclosure of the panel shall be minimum IP42 & suitable for operation on 415 volts +/- 10, 3 Phase, 50 Hz AC supply i/c Earthing, connections and comprising of the following component as required for arrival baggage handling system: 1) Incoming Control Unit : 415 Volts TPN MCCBS of breaking capacity of 25KA (Ics=100Icu) with over load & short circuit protection. The rating of the MCCB shall be so selected that only about 80% of its full load current carrying capacity is utilized for meeting the requirement of the specific application with Incoming Protection for Single Phase Protection, Phase reversal protection, Under voltage protection. 2) Metering and Status Indication / display : (a) Digital type Ammeter of Required range with selector switch & Current Transformers. (b) Digital type Voltmeter with selector switch and protection MCB. (c) LED Indication lamps in different colour for Three phases & power ON with protection MCB as per requirement. 3) MOV & switch : Necessary Surge protection System (block 70KA minimum with Neutral protection) with incomer switch. 4) Outgoing for Motors (s) : a) MPCB of suitable current rating & breaking capacity of 10 KA for each motor b) Soft Starter of suitable rating for conveyor motor(s). 5) Outgoing for rolling shutter : i) 2 Pole MPCB of 10 KA & suitable current rating for each shutter motor. ii) Interlocking with conveyor & limit switches / sensors. iii) Auto-manual switches, separate push button for UP /DOWN mode 6) Emergency stop : Provision shall be made in panel & at minimum three or more locations for each carousel in the passenger baggage claim area. 7) Alarm / Time delay : Provision for time delay start, duly interconnected with buzzer and start the sequence of carousel. 8) Interlock & Logic : A programmable logic to meet the operational requirement shall be worked out and got approved from Engineer-in-charge. 9) Number of sensors and other control devices - to meet the functional logical operation of conveyor along with sequential operation of feeder conveyors as required shall be provided. 10) End Terminations: For control panel all incoming & out going cable end termination shall be carried out as per site requirement.	2.00	Job	251667.00	503334.00

Handwritten signature

Handwritten signature

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.03	Integrated Weighing Scale Conveyor: Design, supply, installation, testing & commissioning of following size heavy duty slider bed belt weighing scale conveyor equipped with illuminated push button for introduction of baggage into dispatch conveyor (after baggage had been weighed & tagged) complete with LCD dual display type weighing scale with 4 nos. high resolutions load cells each of suitable capacity, Accuracy class C3 to C6 with 2 ply, 3mm minimum thickness polyster black colour carcass PVC smooth / rough top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt having useful width 650mm (minimum) and overall frame size 800mm (maximum), height as per system design of OEM and functional requirment at passenger end and the other end suitably sloped for easy flow of baggage with speed as per system design of OEM and functional requirment. The bed shall be made of 3 mm thick (minimum) galvanized or epoxy coated mild steel sheet, weighing scale, drive pulley, Tension adjustment, frame and supports, Trim / fascia covering / finishing, head and tail pulley, return / snub rollers, side wall / Guard with control logic and protection as per technical specifications for baggage handling system including all Electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment Grouting, Earthing, etc., complete as required for successful continuous operation of the system. (a) Length - 1200 mm (Minimum)	14.00	Job	85179.60	1192514.40
1.04	Dispatch Conveyor: Design, supply, installation, testing & commissioning of following size heavy duty slider bed belt dispatch conveyor complete with 2 ply, 3mm minimum thickness polyster black colour carcass PVC smooth top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt (Diamond cut Belt of 7.5 mm thickness ia also acceptable), normal live load 35 kg per linear meter having useful belt width such that it fits within the frame, without much side play and shall match with that of integrated weighing conveyor and overall frame size matching with integrated weighing conveyor, height as per system design of OEM and functional requirment suitably sloped for easy transfer of baggage from one section to adjoining section with speed as per system design of OEM and functional requirment. The bed shall be made of 3 mm thick (minimum) galvanized or epoxy coated mild steel, drive pulley, tension adjustment, frame and supports, Trim / fascia covering / finishing, head and tail pulley, return rollers, side wall / Guard, Vertical baggage guide / tipping device with control logic as per technical specifications for baggage handling system including all electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment Grouting, Earthing, etc., complete as required for successful continuous operation of the system. (a) Length – 1200 mm (Minimum)	14.00	Job	77436.00	1084104.00
1.05	Collector / Take away Conveyor: Design, supply installation, testing and commissioning of heavy duty slider bed belt type Collector / Take away Conveyor system having useful belt width of 950mm and frame size 1050 mm and height 400 mm from finished floor level, Normal live load 35 Kg. per linear mtr, speed of 21-25 mtr. per min. / as per system functional requirment complete with 2 ply, 3mm minimum thickness polyster black colour carcass PVC smooth top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt. The bed shall be made of 3 mm thick (minimum) galvanized or epoxy coated mild steel sheet, drive unit, tension adjustment, frame and supports and cross members, support spacing, Trim / fascia covering / finishing, drive pulley, head and tail pulley, take up pulley and snub rollers, return rollers, vertical baggage guide / tipping device side wall / Guard with control logic and protection as per technical specifications for baggage handling system including provision of all electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment Grouting, Earthing, etc., complete as required for successful continuous operation of the system for the Departure check-in area. (a) (25+18.5) Mtrs.	43.50	Mtr.	30974.40	1347386.40

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.06	Control Panel for Departure Conveyor: Design, supply installation, testing and commissioning of cubical type indoor floor mounting compartmentlised, fabricated out of CRCA sheet steel of thickness 2mm duly powder coated indoor type floor mounted with locking arrangement & proper ventilated with air louvers/ fans. The panel (IP42 protection) shall be front open able & accessible. All doors shall be provided with high quality neoprene rubber gasket, door interlock feature with incoming power supply & suitable for operation on 415 volts +/-10, 3 Phase, 50 Hz AC supply i/c. Earthing, connections and comprising of the following component as required for departure conveyor system. 1) Incoming Control Unit : 415 Volts, 4 Pole MCCB (micro processor type) of breaking capacity of 35KA (Ics = 100 Icu) with over load, short circuit protection & earth fault protection. The rating of the MCCB shall be so selected that only about 80% of its full current carrying capacity is utilized for meeting the requirement of the specific application including future load of expansion of four more check in counters. Incoming Protection : (i) Single Phase Protection (ii) Phase reversal protection (iii) Under voltage protection Status Indication / display : Indication lamps (LED type) in different colour for Three phases & power ON with protection MCB. Meters (Incoming) : (a) Digital type Ammeter of Required range with selector switch & Current Transformers. (b) Digital type Voltmeter with selector switch and protection MCB. MOV & switch : Necessary Surge protection System (block 70KA minimum with Neutral protection) shall be provided at control panel of conveyor with incomer switch. Outgoing for each section : MPCB of suitable current rating & breaking capacity of 10 KA for each motor. Outgoing for rolling shutter : i) 2 Pole MPCB of 10 KA & suitable current rating for each shutter motor. ii) Interlocking with conveyor & limit switches / sensors. iii) Auto-manual switches, separate push button for UP /DOWN movement	1.00	Job	580770.00	580770.00
	Outgoing for each weighing scale conveyor & dispatch conveyor : MPCB of suitable current rating for each weighing scale conveyor & each of dispatch conveyor. Emergency stop : i) Provision shall be made in panel & at minimum two or more locations of take away conveyor. ii) Provision shall be made at one location close to each of weighing conveyors. iii) The emergency stop button shall be "press to stop" and release type. Alarm / Time delay : Provision for time delay start, duly interconnected with buzzer and start the sequence of carousel. Interlock & Logic : A PLC based programmable logic to meet the operational requirement shall be worked out and got approved from Engineer-in-charge. Required number of sensors and other control devices shall be provided to meet the functional logical operation of conveyor along with sequential operation of feeder conveyors as required. Provision for Incomer : The incomer switch rating & control panel should have provision toward addition of switch gear, controls, cabling, wirings, etc. to accommodate the weigh-scale, dispatch & take away conveyor suitable for FOUR nos. additional check-in counters in future.				
1.07	Gravity Rollers: Supply and installation of Gravity Rollers of suitable section length as site requirement, having roller length 950mm (approx.), roller capacity 35 Kg per linear meter, 60/50mm pitch / dia or as per manufacturer's recommendation, width section 1000mm and height suitably matched and sloped, complete in all respects i/c conveyor frame section, rollers, supports as per technical specifications for baggage handling system including cutting & drilling of holes, equipment grouting, etc. as required.	3.00	Job	54205.20	162615.60

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.08	Rolling Shutter: Supply, installation, testing and commissioning of electrically operated Rolling Shutter fabricated from MS of deep convex corrugations with side channel guides plate brackets. All MS shall be suitably painted / epoxy coated matching with side wall /frame colour and as approved by Engineer-In-charge. Rolling Shutter of nominal suitable size 1.5 mtr. (L) x 1.4 mtr. (W) are required to be provided wherever the conveyors are entering the space within the terminal building. The rolling shutters shall be provided with suitable rated geared motor directly coupled to the shaft of the shutter. Up & down movement of the rolling shutter shall be controlled by either limit switch or sensor. Interlocking with conveyor motor starter so that the conveyor would start only when the shutter is in full open condition. Down movement of the shutter could be done only with OFF switch of Conveyor System including manual operation and manual locking as specified in the specifications with wiring, earth connections, as required for the successful operation of the shutter and conveyor, cutting & drilling of holes, equipment fixing, etc. as required.	5.00	Job	42589.80	212949.00
1.09	Drought Curtain (Flaps): Supply, installation, testing and commissioning of min. 2 mm thick PVC flaps with reinforcement and overlapping inside Drought Curtain of nominal size 1.5mtr.(L) x 1.4 mtr. (W)/ suitable for the opening to be fixed with SS strip, as per site requirement including cutting & drilling of holes, etc. as required.	5.00	Job	9292.32	46461.60
	Total SITC Amount (A)				8512539.48
B	SH:II Annual Operation & All Inclusive Comprehensive Maintenance Contract				
2	Operation of the Departure & Arrival Baggage Handling System with Electrical Control Panels as provided in this scope including all Electrical / mechanical, safety, control as per special conditions, technical specifications after the commissioning & handing over of the system.				
2.01	Operation Charges for 1st Year	1.00	Year	1828350.00	1828350.00
2.02	Operation Charges for 2nd Year	1.00	Year	1905786.00	1905786.00
2.03	Operation Charges for 3rd Year	1.00	Year	2000430.00	2000430.00
2.04	Operation Charges for 4th Year	1.00	Year	2107980.00	2107980.00
2.05	Operation Charges for 5th Year	1.00	Year	2185416.00	2185416.00
2.06	Operation Charges for 6th Year	1.00	Year	2271456.00	2271456.00
2.07	Operation Charges for 7th Year	1.00	Year	2366100.00	2366100.00
2.08	Operation Charges for 8th Year	1.00	Year	2452140.00	2452140.00
2.09	Operation Charges for 9th Year	1.00	Year	2559690.00	2559690.00
2.1	Operation Charges for 10th Year	1.00	Year	2658636.00	2658636.00
2.11	Operation Charges for 11th Year	1.00	Year	2753280.00	2753280.00
2.12	Operation Charges for 12th Year	1.00	Year	2839320.00	2839320.00
2.13	Operation Charges for 13th Year	1.00	Year	2989890.00	2989890.00
2.14	Operation Charges for 14th Year	1.00	Year	3110346.00	3110346.00
2.15	Operation Charges for 15th Year	1.00	Year	3226500.00	3226500.00

[Signature]
mg/16-21

[Signature]

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
3	All inclusive comprehensive maintenance contract (AICMC) of Complete Baggage Handling System (Departure conveyor system -01 no and Arrival Conveyor System-02 nos.) including all electrical / mechanical Equipments, safety control, rolling shutters, gravity rollers, flaps installed under this contract as per special condition of contract and technical specification immediately after the commissioning & handing over of the system. (AICMC during DLP is covered in the SITC of conveyors installed in this scope. Bidder shall quote accordingly). AICMC will start after completion of DLP of 2 years.				
3.01	AICMC Charges for 1st Year	1.00	Year	170359.20	170359.20
3.02	AICMC Charges for 2nd Year	1.00	Year	170359.20	170359.20
3.03	AICMC Charges for 3rd Year	1.00	Year	170359.20	170359.20
3.04	AICMC Charges for 4th Year	1.00	Year	170359.20	170359.20
3.05	AICMC Charges for 5th Year	1.00	Year	170359.20	170359.20
3.06	AICMC Charges for 6th Year	1.00	Year	170359.20	170359.20
3.07	AICMC Charges for 7th Year	1.00	Year	170359.20	170359.20
3.08	AICMC Chargesfor 8th Year	1.00	Year	170359.20	170359.20
3.09	AICMC Charges for 9th Year	1.00	Year	170359.20	170359.20
3.10	AICMC Charges for 10th Year	1.00	Year	170359.20	170359.20
3.11	AICMC Charges for 11th Year	1.00	Year	170359.20	170359.20
3.12	AICMC Charges for 12th Year	1.00	Year	170359.20	170359.20
3.13	AICMC Charges for 13th Year	1.00	Year	170359.20	170359.20
	Total Operation and AICMC Amount (B)				39469989.60
	TOTAL VALUE OF WORK (IN RUPEES) (A+B)				47982529.08
				Say Rupees	47982529.00

(Rupees Four Crore Seventy Nine Lakh Eighty Two Thousand Five Hundred Twenty Nine Only)

Note : GST Extra, as applicable.

[Signature]
m/8/16/27

[Signature]
14/05/2024
Assistant General Manager (E-E)-I
AAI,DABH, Airport, Indore.