



संदर्भ सं.: भाविप्रा/प.क्षे./व.प्र (इंजी-विद्युत)/कांडला/सीडब्लू-04/2023-24/970
Ref. No: AAI/WR/AGM (E-E)/Kandla/CW-04/2023-24/

दिनांक: 12.03.2024
Date: 12.03.2024

सेवा में/ To,

मेसर्स सुरभि एशोसिएशन / M/s Surbhi Association

ई-17-बी, सुरेन्द्र विहार, बागमुगलिया / E-17-B, Surendra Vihar, Bagmugaliya,
होशंगाबाद रोड, भोपाल-462 043/Hoshangabad Road, Bhopal-462 043

विषय/ Sub: कांडला हवाई अड्डे पर सी.डब्ल्यू.आई.एस और मौसम विज्ञान उपकरणों की स्थापना के लिए मेट पार्क का निर्माण SH: विद्युत् कार्य / Construction of MET PARK for installation of C.W.I.S and Meteorological Instruments at Kandla Airport. SH: Electrical Works.

संदर्भ: आपकी ई निविदा नं. 2024_AAI_184910_1 दिनांक 07.03.2024 को खोला गया।
Your E-Tender No.: 2024_AAI_184910_1 opened on Dated 07.03.2024.

महोदय,/ Dear Sir(s),

- उल्लेखित कार्य हेतु आपके द्वारा बताए गये मद मूल्यों पर आपकी ई निविदा की कुल राशि **रु. 11,33,800 (रुपये ग्यारह लाख तैंतीस हजार आठ सौ मात्र) जीएसटी के साथ** है जेम बीड अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है, जो कि ई-निविदा की उचित लागत राशि **रु. 16,03,007/- से 29.27% नीचे** है। एजन्सी द्वारा वैध टैक्स इन्वॉइस प्रस्तुत करने पर जीएसटी अदा किया जाएगा। गुजरात राज्य के लिए जीएसटी क्र. GSTIN:-24AAACA6412D1ZE है।
Your E-tender for the work mentioned above is hereby accepted on behalf of The Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs.11,33,800 (Rupees Eleven lakh Thirty Three Thousand Eight Hundred only) + GST** which is **29.27% Below** the Justified cost of **Rs.16,03,007 /-**. GST will be paid against valid Tax invoice from the agency. For Gujarat state AAI GST no. is GSTIN:24AAACA6412D1ZE
- सहा महाप्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, विलेपार्ले (पुर्व), मुंबई-400099, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आपकी ओर से एक विश्वसनीय प्रतिनिधी प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक **21.03.2024** तक सहा महाप्रबंधक (इंजी-विद्युत), भाविप्रा, परिचालन कार्यालय भवन, न्यु एअरपोर्ट कालोनी, विलेपार्ले (पुर्व), मुंबई-400099 के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करें। ठेके का करारनामा रु. 300/- के नॉनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।
AGM (ENGG. - ELECT.), RHQ (WR), Vile Parle (E), Mumbai - 400 099 shall be the Engineer-In-Charge of this work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office to the AGM (ENGG- ELECT.), RHQ (WR), Operational office building, New Airport Colony, Vile Parle (E), Mumbai-400 099 by **21.03.2024** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.300/-** and the cost of the stamp paper shall be borne by you.
- कृपया **रु.1,13,380.00 (रुपये एक लाख तेरह हजार तीन सौ अस्सी)** प्रतिभूति जमा के रूप में यह पत्र जारी करने के तारीख के 10 दिन के अंदर जमा किजीये। जमा करने की असफलता में वह राशि बिल से ठेके की शर्तों के अनुसार काट दी जायेगी।
Please deposit **Rs. 1,13,380.00/- (Rupees One Lakh Thirteen Thousand Three Hundred Eighty only)** towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your bill as per contract conditions.

P.T.O



4. निविदा के संविदा की सामान्य शर्त के पृष्ठ 52 पर दी गई क्लोज 19 के अनुसार आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम (नियम तथा उन्मुलन) 1971 के केन्द्रीय नियम श्रम नियम (नियमन तथा उन्मुलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।
You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation & Abolition) Central Rule 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 52 of GCC of tender and rules of Central and State Government.
5. आपको यह निर्देश दिया जाता है कि आप सहायक प्रबंधक (इंजी-विद्युत), कांडला हवाईअड्डा से संपर्क करें जो आपको साइट सौंपने की व्यवस्था करेंगे।
You are directed to contact Asstt.Mgr (E-E), Kandla Airport immediately who will arrange to handover the site.
6. कृपया नोट कर लें कि काम करने का अनुमानित समय 03 (तीन) माह है जोकि दिनांक **21.03.2024** से गिना जाएगा।
Please note that the time allowed for carrying out the complete work is **03 (Three) month**, which shall be reckoned from **21.03.2024**.
7. एएआई ने टीआरडीएस के तहत एक खरीददार के रूप में पंजीकरण है और विक्रेता भारत सरकार की पहल टीआरडीएस का लाभ उठा सकते हैं और एमएसएमई विक्रेताओं को चालान/दावा जमा करने/ प्रक्रिया शुरू करने के 45 दिनों के के अंदर में बाद भुगतान किया जाएगा।
AAI has registered as a buyer under TREDS and vendors may avail the benefits of TREDS, a Govt. of India initiative and the payment would be released within 45 days to MSME vendors after submission/processing of invoices/claims.
8. इस ठेके के संबंध में आगे का कोई भी पत्राचार सहायक महाप्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, एकीकृत प्रचालन कार्यालय भवन, विलेपार्ले (पुर्व), मुंबई-400099 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to AGM (E-E), RHQ (WR), Integrated Operational office building, Vile Parle (E), Mumbai - 400099.
9. कृपया पावती भेजें तथा इस आदेश की दोहरी प्रति आपके हस्ताक्षर के पश्चात इस कार्यालय में भेजें जो कि स्वीकृती टोकन समझा जाएगा।
Please acknowledge the receipt and return the duplicate copy of this order enclosed herewith after signing to the undersigned as a token of acceptance.

यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जायेगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

धन्यवाद/ Thanking You,

Encl: 1. SOQ

भवदीय / Yours faithfully,

मो. सदरुल हुदा

12.03.2024

(मो. सदरुल हुदा) / (Md. Sadrul Huda)

सहायक महाप्रबंधक (इंजी-विद्युत),

Asstt. General Manager (Engg.-Elect.)

कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,

For and on behalf of Chairman, Airports Authority of India

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst.General Manager (E-E)

Name of Work: "Construction of MET PARK for installation of CWIS and Meteorological Instruments at Kandla Airport. SH: Electrical works"

Tender ID: 2024_AAI_184910_1

Name of the Bidder/
Bidding Firm /
Company :

Sunil Dubey / Surbhi Association

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of 3.5 core x 35 Sqmm XLPE insulated , PVC sheathed , armoured FRLSH aluminium conductor power cable of 1.1 KV grade confirming to IS 7098 standards.	1870.00	Mtrs	220.00	411400.00	INR Four Lakh Eleven Thousand Four Hundred Only
2	Supply and Laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 16205 (Part 24) : 2018 complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	1840.00	Mtrs	175.00	322000.00	INR Three Lakh Twenty Two Thousand Only
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of 3.5 core x 35 sq. mm in the existing RCC/ HUME/ PVC /METAL pipe as required.	1870.00	Mtrs	20.00	37400.00	INR Thirty Seven Thousand Four Hundred Only
4	Providing, laying and fixing 100 mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re filling etc as required.	30.00	Mtrs	1400.00	42000.00	INR Forty Two Thousand Only
5	SITC of single phase 2.0 KVA UPS (in the existing feeder pillar) with input voltage range 150-280 V AC, and output voltage 230 VAC, having minimum backup time-15 min on full load and Total harmonic Distortion should be less than 3%, suitable for operating atmospheric temperature between 0 Dg to 45° C, along with the protection like short circuit protection overload protection, battery deep discharge & over charge protection.	1.00	Each	45000.00	45000.00	INR Forty Five Thousand Only
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	6.00	Each	450.00	2700.00	INR Two Thousand Seven Hundred Only
7	Supply of UTP CAT 6 LAN cable.	50.00	Mtrs	50.00	2500.00	INR Two Thousand Five Hundred Only
8	SITC of cubical, outdoor type , self standing , dust and vermin proof and having IP 54 protection Feeder Pillar made out of 2 mm thick CRCA sheet steel suitable for 415V, 3 phase, 4 wire 50 Hz AC supply system having 100 Amps. capacity TPN Aluminium Alloy bus bars of high conductivity, DMC/ SMC bus bar supports, interconnections etc. as required with rain canopy and suitable coupling to provide frangibility to the panel , having sufficient space to accommodate 2 KVA UPS & heat dissipation provision i/c providing following switch gears & accessories confirming to technical specifications : Incomer MCCB 40 A 4P - 3 Nos. (2+1 spare) Automatic Changeover switch 40 A - 1 no. DIN mounted Basic MF meter (1P, V, A, kW, kWh) Outgoing MCB 20 A DP C series - 2 Nos., MCB 6 A SP C series-3 Nos.,MCB 10 A DP C series-1 no.,Contactor - Timer assembly (for obstruction light)- 1 set,power Distribution Board 5 A socket outlets - 5 nos. Accessories RYB indication lamps for each incomer - 2 Set. and suitable CTs as required.	1.00	Each	112000.00	112000.00	INR One Lakh Twelve Thousand Only
9	SITC of loop in - loop out box of appropriate height made out of 2 mm thick CRCA sheet steel confirming to IP 54 suitable for termination of 5 no.(1 no. I/C and 4 no. O/G) 3.5 x 35 sqmm. AL. cable i/c civil masonry works with following provisions. 100 A TPN AL Bus Bar - 1 Set. 20 A 4 P MCB - 1 no. Industrial Plug and connector - 1 set.	3.00	Each	20000.00	60000.00	INR Sixty Thousand Only
10	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5 core x 35 sq. mm (32mm) of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.(01 Set equals 2 nos.)	11.00	set	300.00	3300.00	INR Three Thousand Three Hundred Only
11	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 40 cm X 40 cm at the bottom and 30 cm X 30 cm at the top with a thickness of 10cm including inscription duly engraved as required.	50	Each	800.00	40000.00	INR Forty Thousand Only
12	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	2	Each	7000.00	14000.00	INR Fourteen Thousand Only
13	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	10	Mtrs	650.00	6500.00	INR Six Thousand Five Hundred Only
14	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required (Note: Vertical type MCB TPDB is normally used where 3 phase outlets are required.) 4 way (4 + 12), Double door	2	Each	7000.00	14000.00	INR Fourteen Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
15	Supplying and fixing 63A rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 100 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2	Each	4000.00	8000.00	INR Eight Thousand Only
16	Supplying and fixing 63A rating, four pole, 415 V, Miniature circuit Breaker(MCB) in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2	Each	2000.00	4000.00	INR Four Thousand Only
17	Supplying and fixing 40A rating, 415 V, "C" curve, TPN miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	4	Each	1800.00	7200.00	INR Seven Thousand Two Hundred Only
18	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	12	Each	150.00	1800.00	INR One Thousand Eight Hundred Only
Total in Figures					1133800.00	INR Eleven Lakh Thirty Three Thousand Eight Hundred Only
Quoted Rate in Words					INR Eleven Lakh Thirty Three Thousand Eight Hundred Only	

मो. सदरुल हुदा
12.03.2024

मो. सदरुल हुदा / Md. Sadrul Huda
सहायक महाप्रबंधक (अभि.-विद्युत) / Asst. General Manager (Engg-Elect.)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
प. क्षेत्र. मुख्यालय, मुंबई / WR, Mumbai - 400 099.

Signature Not Verified

Digitally signed by MD SADRUL HUDA
Date: 2024.07.16 16:13:49 IST
Location: eProcurement System for Central PSUs

