

भारतीय विमानपत्तन प्राधिकरण

जय. प्र. ना. अंतरा. विमानपत्तन, पटना- 800014

AIRPORTS AUTHORITY OF INDIA

J.P.N.I. AIRPORT, PATNA-800014

द्रुतगामी डाक/Speed Post

संदर्भ सं. भाविप्रा/पट/स.महा.प्र.(अगि0-सि0)/का.आ-01/2024-25/

दिनांक : 01/04/2024

Ref. No:- AAI/PAT/AGM(Engg.-C)/W.O.-01/2024-25/672-77

Date : 01/04/2024

सेवा में/To,

मेसर्स अनिल कुमार,

M/s Anil Kumar,

कानौली कोठी, लालेश्वर मार्केट लेन,

Kanauli Kothi, Laleshwar Market Lane,

आर.एम.एस. कॉलोनी, कंकड़बाग, पटना - 800020

R.M.S. Colony, Kankarbagh, Patna - 800020

(Email Id/ Mobile No. - anilkumar7932@gmail.com/ 7564009999)

विषय:- जय प्रकाश नारायण अंतर्राष्ट्रीय हवाई अड्डा, पटना में एम.टी. अनुभाग, नई कार्गो बिल्डिंग, डी.जी. सेट और संबद्ध सिविल कार्यों के लिए शेड का निर्माण।

Subject:- Construction of Shed for MT Section, New Cargo Building, DG Set and allied Civil Works at JPNI Airport, Patna.

संदर्भ : ई-टेंडरिंग द्वारा आपकी निविदा दिनांक 22.03.2024

Ref : Your e-tender dated 22.03.2024 through e-tendering

महोदय,/Sir,


1. उल्लेखित कार्य हेतु आपकी निविदा संलग्न अनुसूची के अनुसार आपके द्वारा उद्धृत कुल ₹ 77,20,420.00 (रुपये सतहत्तर लाख बीस हजार चार सौ बीस मात्र) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है। जो निविदा हेतु तय अनुमानित लागत ₹ 95,83,961 (रुपये पन्चान्वे लाख तेरासी हजार नौ सौ एकसठ मात्र) से 19.44% (उन्नीस दशमलव चार चार प्रतिशत) नीचे है। कोटेड दर में जीएसटी शामिल नहीं है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 77,20,420.00 (INR Seventy Seven Lakhs Twenty Thousand Four Hundred Twenty only) which is 19.44% (Nineteen Point Four Four Percent) below estimated cost put to tender of Rs. 95,83,961.00 (INR Ninety Five Lakhs Eighty Three Thousand Nine Hundred Sixty One only). Quoted rate is excluding GST.

2. उप महाप्रबंधक, (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, ज०प्र०ना०अ० हवाई अड्डा, पटना इस कार्य के प्रभारी अभियंता होंगे।
Dy. General Manager (Engg-C), Airports Authority of India, J.P.N.I. Airport, Patna shall be the Engineer-in-charge of the work.
3. आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु इस पत्र के जारी किए जाने के दस दिनों के भीतर उप महाप्रबंधक, (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, ज०प्र०ना०अ० हवाई अड्डा, पटना के कार्यालय में उपस्थित हों। संविदा करार ₹ 1,000/- (रुपये एक हजार मात्र) के न्यायिकेतर (नॉन-जुडिशियल) स्टॉप पेपर पर बनाया जाएगा तथा स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Signature
20/04/24
Ame (E-5)





भारतीय विमानपत्तन प्राधिकरण ;

जय. प्र. ना. अंतरा. विमानपत्तन, पटना- 800014
AIRPORTS AUTHORITY OF INDIA
J.P.N.I. AIRPORT, PATNA-800014

You are requested to attend the office of the Dy. General Manager (Engg.-Civil), Airports Authority of India, J.P.N.I. Airport, Patna within Ten days from the date of issue of this letter to sign and complete the Contract Agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 1,000/- (INR One Thousand only) and the cost of the stamp paper shall be borne by you.

4. आपकी निविदा के साथ प्राप्त रू० 1,91,679/- (रुपये एक लाख एकान्चे हजार छः सौ उन्नासी मात्र) की अग्रिम धन राशि प्रतिभूति जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर शेष प्रतिभूति जमा के रूप में रू० 5,80,363/- (रुपये पाँच लाख अस्सी हजार तीन सौ तिरसठ मात्र) जमा करे अन्यथा इस राशि की कटौती संविदा कागजात के पृष्ठ 17 के अनुबंध के खंड की धारा 1 (ए) के अनुसार आपके चालू बिलों से कर ली जाएगी।

The Earnest Money amount of Rs. 1,91,679/- (Rupees One Lakhs Ninety One Thousand Six Hundred Seventy Nine only) received along with your tender will be treated and converted a part of Security Deposit. Please deposit Rs. 5,80,363/- (Rupees Five Lakhs Eighty Thousand Three Hundred Sixty Three only) towards balance Security Deposit within 10 (Ten) days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1 (A) of Clause of Contract on page 17 of the contract document.

5. आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970 तथा संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971 एवं न्यूनतम मजदूरी अधिनियम के प्रावधानों और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।

You are requested to comply with the provision of contract labour (Regulation & abolition) Act of 1970 and contract labour (Regulation & abolition) Central Rules 1971 and minimum wages Act and Rules thereof central and State Govt.

6. आपको प्रबंधक (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, पटना हवाई अड्डा, से तत्काल संपर्क करने का भी निर्देश दिया जाता है जो आपको कार्यस्थल (साइट) सौंपने का व्यवस्था करेंगे।

You are requested to contact Manager (Engg.-C), Airports Authority of India, Patna Airport immediately, who will arrange to hand over the site to you.

7. कृपया नोट करें कि कार्य पूरा करने के लिए आपको 04 (चार) महीने का समय प्रदान किया जाता है। यह समय कार्य आदेश जारी होने की तारीख से 10वें दिन या साईट हैंड ओवर करने के दिन, जो भी पहले हो, से माना जाएगा।


Please note that the time allowed for carrying out the work shall be 04 (Four) Months and same shall be reckoned from 10th day of issue of this work order or handing over of site whichever is earlier.

8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः प्रभारी-अभियंता के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.


02/04/21
Engg.-C






भारतीय विमानपत्तन प्राधिकरण
जय. प्र. ना. अंतरा. विमानपत्तन, पटना- 800014
AIRPORTS AUTHORITY OF INDIA
J.P.N.I. AIRPORT, PATNA-800014

10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In Case any discrepancy is found, then English version will be taken as correct.

भवदीय/Yours faithfully


(एलबीओ सिंह/L.B. Singh)

सहायक महाप्रबंधक (इंजीनियरिंग – सिविल)

Asstt. General Manager (Engg.-C)
भाविप्रा, ज०प्र०ना०अ०हवाई अड्डा, पटना

AAI, J.P.N.I. Airport, Patna
के लिए एवं तरफ से अध्यक्ष

For and on behalf of Chairman
भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India


संलग्नक:- अनुसूची – 'अ'

Enclosure: Schedule 'A'

मूल प्रति पर नहीं/N.O.O.

प्रतिलिपि/Copy to:-

1. The Regional Executive Director (E/R), AAI, Operational Offices, NSCBI Airport, Kolkata - 52
2. The General Manager (Engg.-Proj.), AAI, JPNI Airport, Patna - 14
3. The General Manager (Fin), (E/R), AAI, Operational Offices, NSCBI Airport, Kolkata - 52
4. The Airport Director, AAI, JPNI Airport, Patna - 14
5. The DGM (Engg.-C), AAI, JPNI Airport, Patna - 14
6. The DGM (Finance), AAI, JPNI Airport, Patna - 14
7. The AGM (Vig.), (E/R), AAI, Operational Offices, NSCBI Airport, Kolkata - 52
8. The Manager (Engg.-C), AAI, JPNI Airport, Patna - 14
9. The Regional Labour Commissioner (Central), Mauryalok Complex, A Block, 2nd Floor, Room No. 6 & 16, Patna - 01
10. The Regional Provident Fund Commissioner, Bhavishat Nidhi Bhawan, Road No. - 6, R - Block, Patna - 01
11. Work File.
12. Office Copy


(एलबीओ सिंह/L.B. Singh)

सहायक महाप्रबंधक (इंजीनियरिंग – सिविल)

Asstt. General Manager (Engg.-C)
भाविप्रा, ज०प्र०ना०अ०हवाई अड्डा, पटना

AAI, J.P.N.I. Airport, Patna
के लिए एवं तरफ से अध्यक्ष

For and on behalf of Chairman
भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India



Government eProcurement System

Created By: Lal Babu Singh
Created Date/Time: 22-Mar-2024 02:26 PM
Tender Title: Construction of Shed for MT Section, New Cargo Building, DG Set and allied Civil Works at JPN Airport, Patna.
Tender ID: 2024_AAI_185824_1

Tender Inviting Authority: <AGM (Engg.-Civil), JPN Airport, Patna>

Name of Work: <Construction of Shed for MT Section, New Cargo Building, DG Set and allied Civil Works at JPN Airport, Patna>

Contract No: <2024_AAI_185824>

SCHEDULE OF WORK / ITEM(S)

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTN-NA)-681859	
				Rate	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge.	259.00	sqm	100.00	25,900.00
2	All kinds of soil Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	229.00	cum	200.00	45,800.00
3	All kinds of soil Filling available excavated earth (excluding rock) in trenches, plinth sides of foundations etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, lead upto 50 m and for all lift.	74.00	cum	150.00	11,100.00
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	16.00	cum	1500.00	24,000.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	54.00	cum	6000.00	3,24,000.00
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	77.00	cum	8000.00	6,16,000.00
7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillies, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	7.00	cum	8000.00	56,000.00
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, linkhs bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	6.00	cum	9000.00	54,000.00
9	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	309.00	sqm	300.00	92,700.00

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTY-NA)-681859	
				Rate	Amount
10	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	64.00	sqm	700.00	44,800.00
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	5449.00	kg	90.00	4,90,410.00
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	890.00	kg	90.00	80,100.00
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	9.00	cum	8000.00	72,000.00
14	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand)	18.00	sqm	800.00	14,400.00
15	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.00	sqm	1500.00	3,000.00
16	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	500.00	kg	150.00	75,000.00
17	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	7.00	each	600.00	4,200.00
18	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	6650.00	kg	110.00	7,31,500.00
19	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	13580.00	kg	150.00	20,37,000.00
20	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete	196.00	kg	90.00	17,640.00
21	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	330.00	kg	130.00	42,900.00

Handwritten signature

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTN-NA)-681859	
				Rate	Amount
22	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	66.00	mt	250.00	16,500.00
23	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Shoe (Plain) 110 mm shoe	16.00	each	100.00	1,600.00
24	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	1071.00	sqm	600.00	6,42,600.00
25	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	40.00	metre	450.00	18,000.00
26	Providing & fixing false ceiling at all height including providing & fixing of framework made of special section, power pressed from M.S. sheets and galvanised with zinc coating of 120 gms/ sqm (both side inclusive) as per IS : 277 and consisting of angle cleat of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm, at 1200mm c/c, one flange fixed to the ceiling with dash fastener 12.5mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25 x10 x0.50mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I channels 45 x15 x 0.90mm running at the spacing of 1200 mm c/c, to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26 mm each having lips of 10.5mm, at 450mm c/c, shall be fixed in a direction perpendicular to G.I intermediate channel with connecting clip made out of 2.64mm dia x 230mm long G.I wire at every junction, including fixing perimeter channels 0.50mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/ partitions with the help of Rawl plugs at 450mm centre, with 25mm long dry wall screws @ 230mm interval, including fixing of Calcium Silicate Board to ceiling section and perimeter channels with the help of dry wall screws of size 3.5 x25mm at 230mm c/c, including jointing & finishing to a flush finish of tapered and square edges of the board with recommended jointing compounds, jointing tapes, finishing, with jointing compounds in three layers covering up to 150mm on both sides of joints and two coats of primer suitable for boards, all as per manufacture's specification and also including the cost of making opening for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in charge but excluding the cost of painting with: 8 mm thick Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process.	17.00	sqm	1300.00	22,100.00

Handwritten signature and date: 25/11/2020

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTN-NA)-681859	
				Rate	Amount
27	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	116.00	sqm	250.00	29,000.00
28	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	20.00	sqm	300.00	6,000.00
29	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coats applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 kg/10 sqm)	129.00	sqm	110.00	14,190.00
30	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	3600.00	sqm	175.00	6,30,000.00
31	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	50.00	sqm	400.00	20,000.00
32	With cement mortar 1:4 (1 cement : 4 fine sand) Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	236.00	cum	1250.00	2,95,000.00
33	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	2.00	cum	1500.00	3,000.00
34	In cement mortar Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	120.00	kg	4.00	480.00
35	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	150.00	kg	3.00	450.00
36	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of G.S. Sheet	69.00	sqm	100.00	6,900.00
37	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	220.00	cum	200.00	44,000.00
38	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	113.00	cum	700.00	79,100.00
39	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge.	78.00	sqm	900.00	70,200.00
40	Made of G.I. wire of dia 4 mm Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	255.00	sqm	100.00	25,500.00

Handwritten signature and date
24/11/2024

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTN:NA)-681859	
				Rate	Amount
41	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer?in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	255.00	sqm	300.00	76,500.00
42	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	600.00	kg	450.00	2,70,000.00
43	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	105.00	kg	550.00	57,750.00
44	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer?in-charge Pre-laminated particle board with decorative lamination on both sides	143.00	sqm	900.00	1,28,700.00
45	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	34.00	sqm	950.00	32,300.00
46	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	250.00	kg	550.00	1,37,500.00

Signature
20/11/24

Sl. No.	Description of Work / Item(s)	No. of Qty	Units	ANIL KUMAR (GSTN-NA)--681859	
				Rate	Amount
47	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws complete : Gutter (approx. 600 mm over all girth)	67.00	sqm	1800.00	1,20,600.00
48	Supplying & fixing at site : Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately).	200.00	kg	50.00	10,000.00
49	Designing of Shed Structure (for the subject work) including foundation, Pedestals, MS Sections (posts, truss, purlins, side members etc.) as per site conditions especially in view of proximity of Aircraft Operations and other loadings as per relevant design codes & Airport manuals and preparation & providing of structural drawings and good for fabrication, erection and construction drawings, and getting the drawing vetted by IIT/NIT or equivalent Engineering institutions all complete as per direction and satisfaction of Engineer-In-Charge. (This item shall be executed with the prior approval of Engineer In-charge after verification of the the experience of the designer/ structural consultant.) (The Submission of the vetted drawing has to be done within 20 days of the award of the work or as per direction & satisfaction of Engineer-In-Charge)	1.00	job	100000.00	1,00,000.00
Total in Figures				77,20,420.00	

(Signature)
Asstt. G.M. (Engg.-C)
AAI, JPNI Airport, Patna

Signature Not Verified

Digitally signed by LAL BABU SINGH
Date: 2024.04.08 18:56:38 IST
Location: eProcurement System for
Central PSUs



Scanned with OKEN Scanner