



संख्या / No: AAI/COB/AGM(E-E)/CW-01/2024-25/200

दिनांक / Date: 25-04-2024

सेवा मे / To,

M/s. Aquatics Engineers,
G-4/106-107, 1st Floor, Sector-11,
Rohini, New Delhi-110085

E-Mail: mukesh.mangla001@gmail.com

विषय/Subject: Replacement of different type of Unit ACs of Terminal / Admin Building at Cooch Behar Airport.

संदर्भ / Ref : 1) E-Tender ID No.: 2024_AAI_186662_1

प्रिय महोदय / Dear Sir(s),

- उपर्युक्त कार्य हेतु आपका निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गए मद मूल्यों पर आपकी उद्धृत राशि कुल रु. 25,25,250/- (जी.एस.टी. छोड़कर), जो कि टेंडर की न्यायोचित राशि रु. 26,89,303.00 से 6.10% नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 25,25,250.00** (Rupees Twenty Five Lakhs Twenty Five Thousand Two Hundred and Fifty only) excluding GST, which is 6.10% (Six point One zero percent) below the Justified Cost of Rs. 26,89,303.00 (excluding GST).

- सहायक महाप्रबंधक (अभि.-विद्युत), भा.वि.प्रा., बागडोगरा हवाईअड्डा, बागडोगरा-734421, इस कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे निवेदन है कि आपकी ओर से आप अथवा आपके द्वारा अधीकृत प्रतिनिधि नियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 10.05.2024 तक सहायक महाप्रबंधक (अभि.-विद्युत) के कार्यालय में करार पर हस्ताक्षर करने एवं उसको पूरा करने हेतु उपस्थित हो। ठेके का करारनामा रु. 100/- (रुपया एक सौ मात्र) के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assistant General Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra-734421 shall be the Engineer-in-Charge of the work. You are requested to attend the office of Assistant General Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra - 734421 by **10.05.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- कृपया इस पत्र के 10 दिन में सुरक्षा जमा के लिए रु. 2,52,525/- जमा करवा दें, ऐसा नहीं करने पर संविदा दस्तावेज के पृष्ठ 17 | GCC पर दी गई क्लॉज जी.सी.सी. 1(ए) के अनुसार आपके रनिंग बिल से काट ली जाएगी।

Please deposit Rs. 2,52,525/- (Rupees Two Lacs Fifty Two Thousand Five Hundred and Twenty Five only) towards Security Deposit within 10 days from issue of this letter, failing which, the same will be deducted from your running bills as per GCC clause 1(A) on page 17 | GCC of the contract document.

- आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम श्रम अनुबंध नियम तथा 1971 के केंद्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन अवश्य करें।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971 and minimum wages act and rules thereof Central and State Governments.

- कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमानित समय 03(तीन) महीने होगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन के बाद से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be 03 (Three) months and same shall be reckoned from the 10th day after issue of this letter.

Cont'd Page No. 2

25/04/2024
A. M. (E-E)

6. आपको निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभि.-विद्युत), भा.वि.प्रा., बागडोगरा हवाईअड्डा, बागडोगरा-734421 से मिले वह आपको साईट सौंपने की व्यवस्था करेंगे।

You are directed to contact with the Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra-734421 who will arrange to hand over the site to you.

7. इस ठेके के संबंध में आगे का कोई भी पत्राचार इंजीनियर-इन-चार्ज को किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineering-in-Charge.

8. कृपया पावती भेजे और स्वीकृति प्रतिलिपि के तौर पर संलग्नित पत्र की हस्ताक्षरित प्रति इस कार्यालय को अवश्य भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. यदि अंग्रेजी और हिन्दी पाठ में कोई असंगति पाया जाता है तो अंग्रेजी पाठ को सही माना जाएगा।

If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

संलग्न/Encl : i) Schedule of work.

निष्ठा पूर्वक/Yours faithfully,



(देबदीप दत्त /Debdeep Dutta)

सहायक महा प्रबंधक (अभि.-विद्युत),

Assistant General Manager (Engg. -Elect.),

ए.ए.आई./बागडोगरा विमानतल

AAI, Bagdogra Airport.

सिलिगुड़ी-734421/Siliguri-73421

AIRPORTS AUTHORITY OF INDIA
ENGINEERING ELECTRICAL WING
BAGDOGRA AIRPORT

SCHEDULE OF QUANTITY

Name of Work: Replacement of Different type of Unit ACs of terminal/ Admin building at Cooch Behar Airport.


Sl.No	Description of Item	Quantity	Units	Rate (Rs.)	Amount (Rs.)
1	SITC of minimum 4 TR capacity Floor Standing AC units comprising of fixed speed technology based twin rotary compressor compatible with R-410A/R 32 gas (pre Charged) suitable for operation on 415V(±,10%), 3phase, 50Hz AC supply ,with air cooled condenser, LCD display unit with control panel mounted on Indoor Unit , wireless remote control ready to be installed as per site conditions.	10	Job	90,000.00	9,00,000.00
2	SITC of 2 TR capacity Inverter Type wall mounted Split A.C of 5 star BEE rating suitable for operation on 230V(±,10%), 1 phase, 50Hz AC supply complete as required as per site condition.	25	Job	43,800.00	10,95,000.00
3	Supply & fixing of following sizes of Copper refrigerant piping for connecting IDU & ODU including thermal insulation and insulation taping suitable for 2 Tr. Hi-Wall Split ACs. Refrigerant piping work shall be including of all types of bends, elbows etc. and connection/termination as required at site.				
3.1	(1/4") dia with min 13mm thick nitrile rubber insulation	200	Metre	180.00	36,000.00
3.2	(5/8") dia with min 13mm thick nitrile rubber insulation	200	Metre	600.00	1,20,000.00
4	Supply of 3c x 2.5 Sqmm XLPE insulated and PVC sheathed copper conductor unarmoured Power Cable of 1.1KV grade, confirming to IS 7098, Part-I 1988 with up to date amendments and confirming to technical specifications.	200	Metre	150.00	30,000.00
5	Supply & fixing of following sizes of Copper refrigerant piping for connecting IDU & ODU including thermal insulation and insulation taping suitable for 4 Tr. Tower ACs. Refrigerant piping work shall be including of all types of bends, elbows etc. and connection/termination as required at site.				
5.1	(3/4") dia with min 19mm thick nitrile rubber insulation	50	Metre	750.00	37,500.00
5.2	(3/8") dia with min 13mm thick nitrile rubber insulation	50	Metre	500.00	25,000.00

AKB
25/04/2024
AGM(E-E)

Sl.No	Description of Item	Quantity	Units	Rate (Rs.)	Amount (Rs.)
6	Supply of 6c x 2.5 Sqmm XLPE insulated and PVC sheathed copper conductor unarmoured Power Cable of 1.1KV grade, confirming to IS 7098, Part-I 1988 with up to date amendments and confirming to technical specifications.	50	Metre	400.00	20,000.00
7	Supply of 100 watt capacity (minimum) wall fan of 400mm sweep suitable to operate on 220V - 240V, 1Ø, 50 Hz power supply complete as required with all kinds of accessories ready to install at site.	30	each	1,900.00	57,000.00
8	Supply and Fixing of CPVC hard pipe of 25 mm dia (ISI marked) class on surface/recessed for draining out the water including interconnection of drain pipe etc. complete as required.	200	Metre	100.00	20,000.00
9	Laying of unarmoured copper cables upto 6c x 2.5 Sqmm for interconnection of Indoor and Outdoor unit on wall surface / along refrigerant Piping with appropriate saddling / pvc fastener etc. as applicable as per site condition.	250	Metre	20.00	5,000.00
10	Dismantling of the existing Hi-wall, Casatte & Tower type split AC units (upto 4Tr capacity - both IDU & ODU) with all types of accessories and keeping the same in AAI store (within 100 mtr.) as per the direction of EIC.	31	Job	600.00	18,600.00
11	Installation of Outdoor unit with provision of Iron angle support/Iron frame/Masonry base as per the site requirement including all kind of materials along-with civil works.	35	Job	2,490.00	87,150.00
12	SITC of full stainless steel body water cooler cum purifier (RO + UV) of storage capacity 150 Ltr. (minimum) & cooling capacity 60 Ltr. (minimum) including making foundation and required plumbing work as per site condition ready to use at site.	1	Job	74,000.00	74,000.00
Total Amount Rs.				₹	25,25,250.00

(Total Amount: Rupees Twenty Five Lakh Twenty Five Thousand Two Hundred Fifty Only)

* Note: GST will be paid on production of actual tax invoice as per prevailing rates Govt. Of India


 Asstt. Gen. Manager (Engg-Elect)-I
 AAI, Bagdogra Airport
 Bagdogra-734421

Signature Not Verified

Digitally signed by SUBHRA SANTA GHOSH
 Date: 2025.09.26 15:25:42 IST
 Location: eProcurement System for Central PSUs