



भारतीय विमानपत्तन प्राधिकरण /
AIRPORTS AUTHORITY OF INDIA
वीएसएस हवाईअड्डा / VSS AIRPORT
झारसुगुड़ा / JHARSUGUDA



Ref. No. AAI/JH/ Engg. (c)/W-61/Lane /2024-25/ 1151-1160

Date: 01.07.2024

To,

श्री प्रशांत कुमार बेउरिया,

M/s Prasanta Kumar Beuria,

प्लॉट नंबर -169, हाउस नंबर -1680, नुआपटना,

Plot No.-169, House No-1680, Nuapatana,

पीओ/ बांगुराई, वाया- फुलानाखरा,

P.O- Bangurai, Via- Phulanakhara,

जिला- खुर्दा, ओडिशा - 754001

Dist- Khurda, Odisha - 754001

विषय:- वीएसएस हवाई अड्डे, झारसुगुड़ा में यात्रियों की सुविधा के लिए सिटी साइड में नई लेन का निर्माण।

Name of work:- Construction of new lanes in city side for facilitation of passengers at VSS Airport, Jharsuguda.

संदर्भ : आपकी निविदा दिनांक ०९.०४.२०२४ खोली गई।

Ref : Your tender opened on date- 09.04.2024

महोदय/ Sir (s),

- उपरोक्त कार्य के लिए आपकी निविदा एतद्वारा अध्यक्ष की ओर से भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर कुल रु. 1,11,70,757.04 /- (मात्र एक करोड़ ग्यारह लाख सत्तर हजार सात सौ सत्तावन रुपये और चार पैसे) जो कि अनुमानित लागत से 8.22 % (आठ दशमलव दो दो प्रतिशत) कम है जो निविदा में रु. 1,21,69,918.00 /- (मात्र एक करोड़ इक्कीस लाख उनसठ हजार नौ सौ अठारह रुपये)। Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling to Rs. 1,11,70,757.04 (Rupees One crore eleven lakhs seventy thousand seven hundred fifty seven and paise four only) which is 8.22% (Eight point two two percent) below estimated cost put to tender of Rs. 1,21,69,918.00 (Rupees One crore twenty one lakhs sixty nine thousand nine hundred and eighteen only).
- सहायक उपप्रबंधक इंजीनियरिंग (सी), एएआई, वी.एस.एस. हवाई अड्डा, झारसुगुड़ा, कार्य के लिए प्रभारी अभियंता होंगे। आपसे अनुबंध अनुबंध पर हस्ताक्षर करने और उसे पूरा करने के लिए इस कार्यालय में उपस्थित होने का अनुरोध किया जाता है। अनुबंध अनुबंध १००.०० रुपये (केवल एक सौ रुपये) के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

0/c



भारतीय विमानपत्तन प्राधिकरण /
AIRPORTS AUTHORITY OF INDIA
वीएसएस हवाईअड्डा / VSS AIRPORT
झारसुगुड़ा / JHARSUGUDA



The Deputy. General Manager Engg.(C), AAI, V.S.S. Airport, Jharsuguda, shall be the Engineer-In-Charge for the work. You are requested to attend this Office to sign and complete the Contract Agreement. The Contract Agreement shall be executed on non-judicial stamp paper of value of Rs.100.00 (Rupees One Hundred only) and cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तारीख से १० दिनों के भीतर सुरक्षा जमा के रूप में रु. 11,17,075.70/- जमा करें, ऐसा न करने पर पृष्ठ पर खंड १ए, जीसीसी के अनुसार काट लिया जाएगा। अनुबंध दस्तावेज़ के 13।

Please deposit Rs. 11,17,075.70 (Rupees Eleven lakhs seventeen thousand seventy five and paise seventy only) towards Security Deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per clause 1A, GCC on page 13 of the contract document.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम-1971 और न्यूनतम मजदूरी अधिनियम और केंद्र और राज्य सरकार के नियमों के प्रावधानों का पालन करें।

You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) central Rules-1971 and minimum wages Act and Rules thereof of Central and State Government.

5. आपको उप महाप्रबंधक इंजी. (सी), एएआई, वी.एस.एस. एयरपोर्ट, झारसुगुड़ा, तुरंत, जो आपको साइट सौंपने की व्यवस्था करेगा।

You are directed to contact Deputy General Manager (Engg.-C), AAI, V.S.S. Airport, Jharsuguda, immediately, who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि निविदा दस्तावेज़ में दर्ज किए गए कार्य को करने के लिए अनुमत समय 06 महीने हैं, जिसे इस पत्र के जारी होने की तारीख से 10 वें दिन से गिना जाएगा।

Please note that the time allowed for carrying out the work as entered in the Tender document is 06 Months, which shall be reckoned from 10th day from the date of issue of this letter.

7. अनुबंध के संबंध में कोई भी अन्य पत्राचार सामान्य रूप से उप प्रबंधक इंजी. (सी), एएआई, वी.एस.एस. एयरपोर्ट, झारसुगुड़ा को संबोधित किया जाना चाहिए।

Any further correspondences in connection with the contract should normally be addressed to The Deputy General Manager Engg. (C), AAI, V.S.S Airport, Jharsuguda.

8. कृपया रसीद की पावती दें और इसके साथ संलग्न इस पत्र की डुप्लीकेट प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरी को स्वीकृति के प्रतीक के रूप में लौटा दें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.



भारतीय विमानपत्तन प्राधिकरण /
AIRPORTS AUTHORITY OF INDIA
वीएसएस हवाईअड्डा / VSS AIRPORT
झारसुगुड़ा / JHARSUGUDA



9. यदि कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण को सही माना जाएगा।
In case any discrepancy is found, then English version will be taken as correct.

धन्यवाद/ Thanking you,

Encl: Bill of Quantity

01.07.24

(P. Sethy)

Deputy General Manager, (Engg.-C)
AAI, V.S.S. Airport, Jharsuguda
FOR AND ON BEHALF OF THE CHAIRMAN,
AAI, NEW DELHI

N.O.O.

Copy to:

1. The Regional Labour Commissioner, Rourkela (C), Old Chief Engineers Banglow, Sector-5, Rourkela-769002.
2. The Regional Provident Fund Commissioner-II, Vabisyanidhi Bhawan, Panposh Road, Rourkela-769004.
3. The Manager, ESI Corporation, Jharsuguda, Hospital chowk, Jharsuguda-768201.
4. The Income Tax Officer, Sarbahal Road, Jharsuguda-768201.

Internal

1. The Regional Executive Director (ER), AAI, Operational Offices, NSCBI Airport, Kolkata-52. [Kind attn.: The General Manager, Engg. ER].
2. The Airport Director, AAI, VSS Airport, Jharsuguda.
3. The AGM (Finance), ER, AAI, BPI Airport, Bhubaneswar.
4. Works file.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AIRPORTS AUTHORITY OF INDIA

Name of Work: Construction of new lanes in city side for facilitation of passengers at VSS Airport, Jharsuguda

Contract No:

Name of the
Bidder/
Bidding Firm
/ Company :

PRASANTA KUMAR BEURIA

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	13	54	55
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	Item1	1664.00	cum	190.00	316160.00	INR Three Lakh Sixteen Thousand One Hundred & Sixty Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Item2	832.00	cum	207.00	172224.00	INR One Lakh Seventy Two Thousand Two Hundred & Twenty Four Only
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Item3	100.00	cum	1700.00	170000.00	INR One Lakh Seventy Thousand Only
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Item4	30.00	cum	1961.00	58830.00	INR Fifty Eight Thousand Eight Hundred & Thirty Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	13	54	55
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	Item5	35.12	cum	5907.00	207453.84	INR Two Lakh Seven Thousand Four Hundred & Fifty Three and Paise Eighty Four Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Item6	33.00	cum	6900.00	227700.00	INR Two Lakh Twenty Seven Thousand Seven Hundred Only
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Item7	10.00	cum	7300.00	73000.00	INR Seventy Three Thousand Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo Mechanically Treated bars of grade Fe-500D or more.	Item8	31000.00	kg	87.00	2697000.00	INR Twenty Six Lakh Ninety Seven Thousand Only
9	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc.	Item9	1000.32	sqm	207.00	207066.24	INR Two Lakh Seven Thousand & Sixty Six and Paise Twenty Four Only
10	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. Old work (One or more coats).	Item10	500.00	sqm	137.00	68500.00	INR Sixty Eight Thousand Five Hundred Only
11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Item11	624.00	sqm	127.00	79248.00	INR Seventy Nine Thousand Two Hundred & Forty Eight Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE Figures (Excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	13	54	55
12	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Item12	300.00	cum	7000.00	2100000.00	INR Twenty One Lakh Only
13	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm)	Item13	250.00	cum	2700.00	675000.00	INR Six Lakh Seventy Five Thousand Only
14	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	Item14	250.00	cum	1700.00	425000.00	INR Four Lakh Twenty Five Thousand Only
15	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	Item15	416.00	cum	6000.00	2496000.00	INR Twenty Four Lakh Ninety Six Thousand Only
16	Providing and fixing pre-moulded joint filler in expansion joints of RCC roads / CC pavements after making the joints dust free with high pressure air jet cleaners, all complete as per direction of the Engineer-in-Charge. (Pre-moulded joint fillers shall be made of bitumen hot sealing compound impregnated fibre board having impregnation more than 35%, conforming to IS:1838 for fibre board and IS: 1834 for hot sealing bitumen compound grade A.)	Item16	4000.00	per cm depth per cm width per metre length	3.70	14800.00	INR Fourteen Thousand Eight Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	13	54	55
17	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834.	Item17	3528.00	per cm depth per cm width per metre length	6.07	21414.96	INR Twenty One Thousand Four Hundred & Fourteen and Paise Ninety Six Only
18	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes.	Item18	20.00	Mtr	2320.00	46400.00	INR Forty Six Thousand Four Hundred Only
19	Supplying and filling good earth in layers of 20 cm finished depth, breaking clouds / over size material, removal of stumps / roots and the like & watering, grading / levelling each layer with dozers / grader and rolling every layer with vibratory roller / earth compactor of minimum 8-12 tonnes capacity and dressing to the required grade, camber and slope complete as per specification and directed by the Engineer-in-charge. (The item includes cost of work, payment of necessary royalty , carriage of good earth upto work site for all lead and lifts involved. The work to be carried out as per MORTH specifications. Payment to be made for compacted quantity only).	Item19	3120.00	Cum	287.00	895440.00	INR Eight Lakh Ninety Five Thousand Four Hundred & Forty Only
20	Providing and laying polythene sheet of 200 microns on the base course with overlaps of not less than 100mm longitudinally and 150 mm transversely as per specifications and as directed by Engineer-in-charge.	Item20	1664.00	Sqm	80.00	133120.00	INR One Lakh Thirty Three Thousand One Hundred & Twenty Only
21	Providing and fixing dual directional speed breaker of size 350mm X 250 mm X 50mm, made of sturdy plastic (ABS) Acrylonitrile Butadiene Styrene, extremely resistant to harsh weather conditions, having pre-colored materials (black and yellow) with the UV stabilized process resulting in permanent color which does not fade easily, studded with non-breakable Prismatic reflector panels fixed on front and back for night time visibility with angle set on 32 degrees on either side, which are clearly visible for motorists in night hours, etc. all complete as per the direction of Engineer-in-charge.	Item21	96.00	metre	900.00	86400.00	INR Eighty Six Thousand Four Hundred Only
Total in Figures		Signature Not Verified				11170757.04	INR One Crore Eleven Lakh Seventy Thousand Seven Hundred & Fifty Seven and Paise Four Only
Quoted Rate in Words		Digitally signed by PREMANANDA SETHY Date: 2024.09.04 13:02:22 IST Location: eProcurement System for Central PSUs					INR One Crore Eleven Lakh Seventy Thousand Seven Hundred & Fifty Seven and Paise Four Only


 01.07.24
 NLM B/S