



75
आज़ादी का
अमृत महोत्सव

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ सं.: एएआई/सीबीई/एसएम(इंजी-सिविल) डब्ल्यू-37/2023-24/106
AAI/CBE/SM(ENGG-CIVIL)/W-37/2023-24

दि: 18.04.2024
Date: 18.04.2024

// BY SPEED POST //

सेवामें / To

मैसर्स. एसपी एंटरप्राइजेज / 'M/s. SP Enterprises, H. No: 1084,
मकान नंबर 1084/ House No. 1084
दतला एसपी हाउस/ Datla SP House,
ग्राम सचिवालय के बगल में/ Beside Grama Sachivalayam,
पेदागुम्मलुरु गांव और पोस्ट/ Peddagummuluru Village and Post,
एस रायवरम, मंडल/ S Rayavaram, Mandal,
विशाखापत्तनम जिला/ Visakhapatnam District,
आंध्र प्रदेश - 531 083/ Andhra Pradesh - 531 083.

Name of Work: कार्य का नाम: कोयंबतूर अंतरराष्ट्रीय हवाई अड्डे के सिटी साइड के संबंध में
विविध सिविल कार्य // Misc. Civil Works in connection with City Side
of Coimbatore International Airport.

Reference: Your Tender for the above work opened on Dated 05.04.2024.

संदर्भ: निविदा आईडी- 2024_ एएआई_188248_1/ (Tender ID No: 2024_AAI_188248_1).

महोदय / Dear Sir,

1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उपर्युक्त कार्य के ई-निविदा के लिए उद्धृत मद दर राशि रु. 71,81,555/- (रूपया ब्यानबे लाख ग्यारह हजार आठ सौ पच्चीस मात्र) को स्वीकृत किया जाता है। जो कि निविदा की अनुमानित लागत रु. 98.27 लाख से 26.92% कम है। /Your E-tender for the work mentioned above is accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs.71,81,555/- (Rupees Seventy-One Lakhs Eighty-One Thousand Five Hundred and Fifty-Five Only) which is 26.92% below the estimated cost put to tender of Rs.98.27 Lakhs.
2. संयुक्त महा प्रबंधक (इंजी-सिविल), एएआई, कोयंबटूर इंटरनेशनल एयरपोर्ट कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप जेटी के कार्यालय में उपस्थित हों। समझौते पर हस्ताक्षर करने और उसे पूरा करने के लिए संयुक्त महा प्रबंधक (इंजी-सिविल), एएआई, कोयंबटूर एयरपोर्ट 29.04.2024 तक। अनुबंध समझौते को रुपये के मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा। 100.00 (रुपए केवल सौ) और स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी। Joint General Manager (Engg-Civil), AAI, Coimbatore International Airport, shall be the Engineer-in-charge of the work. You are requested to attend the office of the Joint General Manager (Engg-Civil), AAI, Coimbatore International Airport, Coimbatore Before 29.04.2024 to sign and complete the Agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value of Rs.100/- (Hundred) and the cost of the stamp paper shall be borne by you.



75
आज़ादी का
अमृत महोत्सव

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

3. कृपया इस पत्र जारी होने के 10 दिन के अंदर सुरक्षा जमा राशि के रूप में ₹. 718155/- को जमा करें, अगर ऐसा नहीं किया तो पृष्ठ सं. 42 के खंड 1A के अनुसार राशि की कटौती की जाएगी। /Please deposit Rs.718155/- (Rupees Seven Lakhs Eighteen Thousand One Hundred & Fifty-Five Only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no 1A on page 42 of the contract document.
4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 और न्यूनतम मजदूरी अधिनियम और केंद्र और राज्य सरकार के नियमों के प्रावधानों का पालन करें। You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act & Rules there of Central and State Governments.
5. आपको निर्देश दिया जाता है कि साईट सौंपने की व्यवस्था के लिए तत्काल अधोहस्ताक्षरी से संपर्क करें। कृपया ध्यान दें कि कार्य समाप्ती के लिए 04 (चार) महीने का समय दिया जाएगा और इसकी गणना इस पत्र जारी के 10 वें दिन से की जाएगी। /You are also directed to contact the undersigned immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be 04 (Four) Months and the same shall be reckoned from the 10th day after issue of this letter.
6. अनुबंध के संबंध में अन्य पत्राचार के लिए संयुक्त महा प्रबंधक (इंजी-सिविल), भा.वि.प्राकोयंबतूर अंतरराष्ट्रीय हवाई अड्डा का संबोधन करें। / Any further correspondence in connection with this contract should normally be addressed to the Joint General Manager (Engg- Civil), AAI, Coimbatore International Airport.
7. कृपया पावती भेजें और यहां संलग्नित पत्र को हस्ताक्षर के बाद उसके प्रतिलिपि को अधोहस्ताक्षरी को प्राप्ती के तौर पर भेजें। / Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

भवदीय / Yours faithfully,
शिवु जोस / SHIBU JOSE

संयुक्त महाप्रबंधक (अंजी-सि) / Joint General Manager (E-C)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport

कोयंबतूर / Coimbatore

शिवु जोस / Shibu Jose

संयुक्त महा प्रबंधक (इंजी-सिविल) / Jt.GM (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport

कोयंबतूर / Coimbatore- 641 014



75
आज़ादी का
अमृत महोत्सव

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

एएआई/सीबीई/एसएम(इंजी-सिविल) डब्ल्यू-37/2023-24
AAI/CBE/SM(ENGG-CIVIL)/W-37/2023-24

दि: 18.04.2024
Date: 18.04.2024

FORM - III

Under rule of 21(2) of the Contract Labour (Regulation & Abolition) Central Rules,

1971 & rule 7(3) of the Inter - State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules 1980.

FORM OF CERTIFICATE BY PRINCIPAL EMPLOYER

Certified that:

- 1). I have engaged the applicant **M/s. SP Enterprises**, H. No. 1084, Datla SP House, Beside Grama Sachivalayam, Peddagummuluru Village and Post, S Rayavaram, Mandal, Visakhapatnam District, Andra Pradesh - 531 083 as a contractor in my establishment for the work of **"Misc. Civil Works in connection with City Side of Coimbatore International Airport."**
- 2). I undertake to be bound by all the provisions of the Contract Labour (Regulation & Abolition) Act 1970 (37 of 1970) and the Contract Labour (Regulation & Abolition) Central Rules 1971 / the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules 1980 in so far as the provisions are applicable to me in respect of the employment of Contract Labour / Inter State- Migrant Workmen by the applicant in my establishment.
- 3). The engagement of contract labour in the said work is not prohibited under sub-section of section 10 of the Contract Labour (Regulation & Abolition) Act 1970 (37 of 1970) or an award or a settlement.

Signature of Principal Employer

शिवु जोस / SHIBU JOSE

संयुक्त महाप्रबंधक (अभि-सि) / Joint General Manager (E-C)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport

कोयंबतूर / Coimbatore - 641 014

(ENGINEER-IN-CHARGE) - CIVIL

संयुक्त महा प्रबंधक (इंजी-सिविल)/ Jt.GM (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport

कोयंबतूर / Coimbatore- 641 014

Principal Employer Regn No: R.02/2013-A/M Dt 18.02.2013.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Sr. Manager (E-C)

Name of Work: Misc. Civil Works in connection with City Side of Coimbatore International Airport

Contract No: W-37/2023-24/SM(E-C)

Name of the Bidder/ Bidding

SP ENTERPRISES

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	250.00	Cum	190.00	47500.00	INR Forty Seven Thousand Five Hundred Only
2	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1 kilometre, as per direction of Engineer-in-charge.	35.00	Cum	700.00	24500.00	INR Twenty Four Thousand Five Hundred Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	45.00	Cum	6850.00	308250.00	INR Three Lakh Eight Thousand Two Hundred & Fifty Only

शिवु जोस / SHIRU JOSE

संयुक्त महाप्रबंधक (अभि-सि) / Joint General Manager (E-C)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

कोयंबटूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport

कोयंबटूर / Coimbatore - 041 014.

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	90.00	Cum	6450.00	580500.00	INR Five Lakh Eighty Thousand Five Hundred Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	95.00	Cum	5449.00	517655.00	INR Five Lakh Seventeen Thousand Six Hundred & Fifty Five Only
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	Cum	7800.00	7800.00	INR Seven Thousand Eight Hundred Only
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	1.00	Cum	7800.00	7800.00	INR Seven Thousand Eight Hundred Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	100.00	Kg	105.00	10500.00	INR Ten Thousand Five Hundred Only
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	100.00	Kg	105.00	10500.00	INR Ten Thousand Five Hundred Only
10	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	2.00	Sqm	500.00	1000.00	INR One Thousand Only

शिबु जोसे / SHIBU JOSE
 संयुक्त महाप्रबंधक (अभि-सि) / Joint General Manager (E-C)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 कोयंबटूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
 कोयंबटूर / Coimbatore - 641 014,

11	Centering and shuttering including strutting, propping etc. and removal of form for Weather shade, Chajjas, corbels etc., including edges	1.00	Sqm	600.00	600.00	INR Six Hundred Only
12	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in : Cement mortar 1:6 (1 cement : 6 Coarse sand)	4.00	Cum	6500.00	26000.00	INR Twenty Six Thousand Only
13	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	3.00	Cum	6250.00	18750.00	INR Eighteen Thousand Seven Hundred & Fifty Only
14	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	6.00	Sqm	1800.00	10800.00	INR Ten Thousand Eight Hundred Only
15	Providing and fixing to existing door frames 30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.	2.00	Sqm	2000.00	4000.00	INR Four Thousand Only
16	Providing and fixing ISI marked oxidised M.S. door latches conforming to IS:5930 with screws etc. complete : (copper oxidized as per IS: 1378) 250x20x6 mm	1.00	Each	450.00	450.00	INR Four Hundred & Fifty Only

शिवु जोस / SHIBU JOSE

संयुक्त महासंचालक (अभिनवि) / Joint General Manager (E.C)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 कोयंबटूर अंतराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
 कोयंबटूर / Coimbatore - 414 014.



17	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : (copper oxidized as per IS: 1378) 250x16 mm	1.00	Each	300.00	300.00	INR Three Hundred Only
18	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 250x10 mm	1.00	Each	300.00	300.00	INR Three Hundred Only
19	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : (copper oxidized as per IS: 1378) 125 mm	2.00	Each	200.00	400.00	INR Four Hundred Only
20	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	25500.00	Kg	130.00	3315000.00	INR Thirty Three Lakh Fifteen Thousand Only
21	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	760.00	Sqm	740.00	562400.00	INR Five Lakh Sixty Two Thousand Four Hundred Only


शिवु जोसे / SHIBU JOSE
 संयुक्त महाप्रबंधक (अधि-सि) / Joint General Manager (E-C)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 कोयंबटूर अंतराष्ट्रीय विमानतळ / Coimbatore Intl. Airport
 कोयंबटूर / Coimbatore - 441 014.

22	Providing and fixing precoated galvanised steel sheet roofing accessories of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with Zinc coating 120 gram per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter (600 mm over all girth)	70.00	meter	425.00	29750.00	INR Twenty Nine Thousand Seven Hundred & Fifty Only
23	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	30.00	Sqm	300.00	9000.00	INR Nine Thousand Only
24	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	30.00	Sqm	280.00	8400.00	INR Eight Thousand Four Hundred Only
25	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	30.00	Sqm	160.00	4800.00	INR Four Thousand Eight Hundred Only
26	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, and of required shade and colour all complete, to achieve even shade and colour New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gms/litre	30.00	Sqm	80.00	2400.00	INR Two Thousand Four Hundred Only
27	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	30.00	Cum	600.00	18000.00	INR Eighteen Thousand Only
28	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	500.00	Kg	20.00	10000.00	INR Ten Thousand Only
29	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	8500.00	sqm	15.00	127500.00	INR One Lakh Twenty Seven Thousand Five Hundred Only

शिवु जोसे / SHIBU JOSE

संयुक्त महाप्रबंधक (अभि-नि) / Joint General Manager (E-C)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबटूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
कोयंबटूर / Coimbatore - 441 014.

30	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. New work (Two or more coats)	50.00	Sqm	120.00	6000.00	INR Six Thousand Only
31	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1.00	Each	4500.00	4500.00	INR Four Thousand Five Hundred Only
32	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore	1.00	Each	1500.00	1500.00	INR One Thousand Five Hundred Only
33	Providing and laying factory made Precast concrete solid blocks of 200 mm thickness of grade M10 made of C&D waste from approved manufacturer in foundation and plinth Cement mortar 1:6 (1 cement : 6 coarse sand)	1.50	cum	6000.00	9000.00	INR Nine Thousand Only
34	Providing and fixing UPVC. pipes (SHD 80) complete with all fittings including UPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step UPVC solvent & testing of joints complete as per direction of Engineer in Charge. 32 mm dia nominal bore	340.00	meter	380.00	129200.00	INR One Lakh Twenty Nine Thousand Two Hundred Only

शिवु जोषे / SHIVU JOSE

संयुक्त महाप्रबन्धक (अभियन्ता) / Joint General Manager (E-C)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबटूर अंतरराष्ट्रीय हवाई जंक्शन / Coimbatore Intl. Airport
कोयंबटूर / Coimbatore - 641 014.

35	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	15.00	Sqm	1100.00	16500.00	INR Sixteen Thousand Five Hundred Only
36	Construction of Subgrade embankment with the Available earth of the airport .The complete operation will include spreading the Moorum with dozer, dressing, levelling, providing camber, grading with motor grader and consolidating with vibratory roller 8-1	3600.00	Cum	250.00	900000.00	INR Nine Lakh Only
37	Carriage of material By Mechanical Transport and stacking: -earth upto 1km	3600.00	cum	125.00	450000.00	INR Four Lakh Fifty Thousand Only
Total in Figures					7181555.00	INR Seventy One Lakh Eighty One Thousand Five Hundred & Fifty Five
Quoted Rate in Words					INR Seventy One Lakh Eighty One Thousand Five Hundred & Fifty Five Only	

शिवु जोसे / SHIBU JOSE
 संयुक्त महाप्रबंधक (अभियंता) / Joint General Manager (E-C)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
 कोयंबटूर / Coimbatore - 411 014



Signature Not Verified

Digitally signed by PARAPPIL GOPAL GOPALAKRISHNAN
 Date: 2025.01.08 16:43:49 IST
 Location: eProcurement System for Central PSUs

