



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

सं.: भा.वि.प्रा./मंडल-III/ई.एम.डी. -III/ एसवीडीजीएस /2024-25/ 78
No. AAI/CIRCLE-III/EMD-III/SVDGS/2024-25/ 78

दिनांक: 28.05.2024
Date: 28.05.2024

To,
M/s. Youngmen Traders,
P-27/1, Rastraguru Avenue,
Dumdum, Kolkata - 700 028,
West Bengal;
E-mail: boseranjan@hotmail.com

कार्य का नाम : कोलकाता हवाई अड्डे पर स्मार्ट विजुअल डॉकिंग गाइडेंस सिस्टम की एसआईटीसी।
एसएच: ने.सु.चं.बो.आ. हवाई अड्डे, कोलकाता में एसवीडीजीएस की स्थापना के लिए आवश्यक बिजली आपूर्ति, पाइप और संबंधित अन्य कार्यों का प्रावधान।

Name of Work: SITC of Smart Visual Docking Guidance System at Kolkata Airport.
SH: Provision of power supply, pipes and related other works required for installation of SVDGS at NSCBI Airport, Kolkata.

संदर्भ/Ref: Your e-bid (Financial) opened on 05.04.2024 (Tender ID No: 2024_AAI_189229_1)

महोदय/Dear Sir (s),

- 1) ऊपर उल्लिखित कार्य हेतु आपका ई-टेंडर (निविदा क्रमांक 2024_AAI_189229_1) के लिए अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है, आपके द्वारा बताए गए मद मूल्यों पर आपकी ई-टेंडर राशि रु. 97,43,190.00 (जीएसटी को छोड़कर) (केवल सत्तानवे लाख तैंतालीस हजार एक सौ नब्बे रुपये) के लिए स्वीकृत किया जाता है, जो टेंडर कि अनुमानित लागत राशि रु. 1,52,93,891.00 (जीएसटी को छोड़कर) से 36.29% कम है।

Your e-tender (Tender ID No: 2024_AAI_189229_1) for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 97,43,190.00 (Rupees Ninety-Seven Lakhs Forty-Three Thousand One Hundred and Ninety) only (excluding GST) which is 36.29% below the Justified Cost of Rs. 1,52,93,891.00 (excluding GST) put to tender.

- 2) संयुक्त महाप्रबंधक (अभि.-वि.), भा.वि.प्रा., ने.सु.चं.बो.अं. कोलकाता हवाई अड्डा, इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी और से एक विसवासनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह पत्र के 15 दिन के अंदर तक संयुक्त महाप्रबंधक (अभि.-वि.), भा.वि.प्रा., ने.सु.चं.बो.अं. कोलकाता हवाई अड्डा के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100.00 (केवल एक सौ रुपये) के गैर न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Jt. General Manager (Engg. - Elect.), AAI, NSCBI Airport, Kolkata shall be Engineer-In-Charge of the work. You are requested to attend the office of Jt. General Manager (Engg. - Elect.), AAI, NSCBI Airport, Kolkata within 15 days from the date of issue of this award letter to sign and complete the contract agreement. The contract agreement shall be executed on non-judicial stamp paper of Rs.100.00 (Rupees One hundred only) and cost of the stamp paper shall be borne to you.

(Signature)
28/5/2024
26m(EE)



- 3) आपसे अनुरोध किया जाता है कि आप रु 9,74,319.00 (नौ लाख चौहत्तर हजार तीन सौ उन्नीस रुपये) मात्र राशि की सुरक्षा के रूप में जमा करें इस पत्र के जारी होने की तारीख से 10 दिनों के अंदर ऐसा न करने पर अनुबंध दस्तावेज़ के जीसीसी पृष्ठ संख्या 79 पर खंड संख्या 1A की शर्त के अनुसार कटौती की जाएगी। Please deposit Rs. 9,74,319.00 (Rupees Nine Lakhs Seventy-Four Thousand Three Hundred and Nineteen) only towards security deposit within 10 days from the date of issue of this letter failing which the same will be deducted as per condition of Clause No. 1A of GCC Page No. 79 of contract agreement.

- 4) आपसे निवेदन है कि अनुबंध श्रम नियम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियमों 1971, बाल श्रम (निषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार और सेवा की स्थिति का विनियमन) के प्रावधान का पालन करें। अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 जैसा कि केंद्र तथा राज्य सरकार के नियम जो की निबिदा के दस्तबेज़ पर दी गई शर्त 19 में है का अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 of GCC of tender and rules of Central and State Government.

- 5) आपको निर्देश दिया जाता है कि आप तुरंत सहायक महाप्रबंधक (अभि. - वि.) भा.वि.प्रा., ने.सु.चं.बो.अं. कोलकाता हवाई अड्डा से मिलें, वह आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. General Manager (Engg.-Elect.) AAI, NSCBI Airport, Kolkata immediately, who will arrange to hand over the site to you.

- 6) कृपया ध्यान दें की कार्य करने के लिए अनुमत समय 06 (छह) माह है, जो कार्य आदेश के जारी करने के 06.06.2024 से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be 6 (Six) months which shall be reckoned from 06.06.2024.

- 7) अनुबंध के नियमों और शर्तों के अनुसार और अभियंता प्रभारी के निर्देशानुसार कार्य किया जाएगा।

The work shall be carried out as per contract terms and conditions and as per directive of the Engineer-In-Charge.

- 8) इस ठेके के संबंध में आगे का कोई भी पत्राचार प्रभारी अभियंता, भा.वि.प्रा., ने.सु.चं.बो.अं. कोलकाता विमानक्षेत्र के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

Handwritten signature and date:
28/5/2024
JGM/EE



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

- 9) कृपया पावती भेजे तथा इस पत्र की डुप्लिकेट प्रतिलिपि स्वीकृति के एक टोकन के रूप में अधिसूचना में हस्ताक्षर करने के बाद इस के साथ संलग्न करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

- 10) अन्य सभी नियम और शर्त एनआईटी के अनुसार होगी।

All other terms and conditions shall be as per NIT.

- 11) यदि अंग्रेजी और हिंदी के बीच कोई विसंगति है तो अंग्रेजी में व्युत्पन्न अर्थ को वरीयता दी जाएगी।

If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

धन्यवाद/Thanking you,

भवदीय/Yours faithfully,

संलग्न/Encl.: Schedule of work.


28/05/2024

(संदीप पिंपलापुरे/Sandeep Pimplapure)
संयुक्त महाप्रबंधक (अभि-विद्युत)/Jt.. Gen. Manager (Engg-E),
कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,
For and on behalf of Chairman,
Airports Authority of India.



प्रतिलिपि / Copy to:

- i) आयकर अधिकारी, आयकर भवन, पी-7 चौरंगी स्कोयर, कोलकाता – 700 069
Income Tax Officer, Aayakar Bhavan, P-7 Chowringhee Square, Kolkata- 700 069
- ii) क्षेत्रीय श्रम आयुक्त (केंद्रीय), 2 एम.एस. बिल्डिंग, 5 फ्लोर, निज़ाम पैलेस, 234/4 ए.जे.सी. बोसे रोड, कोलकाता – 700 020
Regional Labour Commissioner (Central), 2nd MS Building, 5th floor, Nizam Place, 234/4 A.J.C Bose Road, Kolkata 700 020
- iii) आयुक्त, कार्य अनुबंध सेल, 14, बेलियाघाता मैन रोड, कोलकाता – 700015
The Commissioner, Work Contract Cell, 14, Beliaghata Main Road, Kolkata-700 015

N.O.O.:

- i) विमानपत्तन निदेशक, भा.वि.प्रा., ने.सु.चं.बो.अं. हवाईअड्डा – 700052
PA to Airport Director, AAI NSCBI Airport, Kolkata – 700 052
- ii) म.प्र. (अभि- विद्युत), भा.वि.प्रा., ने.सु.चं.बो.अं. हवाईअड्डा – 700052
G. M. (Engg.-Elect.), AAI, NSCBI Airport, Kolkata – 700 052
- iii) म.प्र. (अभि-वित्त), भा.वि.प्रा., ने.सु.चं.बो.अं. हवाईअड्डा – 700052
G. M. (F & A), AAI, NSCBI Airport, Kolkata – 700 052
- iv) सहायक महाप्रबंधक (अभि- विद्युत), भा.वि.प्रा., ने.सु.चं.बो.अं. हवाईअड्डा – 700052
AGM (Engg-Elect.), AAI, NSCBI Airport, Kolkata – 700 052
- v) प्रबंधक (अभि- विद्युत), भा.वि.प्रा., ने.सु.चं.बो.अं. हवाईअड्डा – 700052
Manager (Engg-Elect.), AAI, NSCBI Airport, Kolkata – 700 052
- ✓ vi) समझौता
Agreement


28/5/2024

(संदीप पिंपलापुरे/Sandeep Pimlapure)

संयुक्त महाप्रबंधक (अभि-विद्युत)/Jt. Gen. Manager (Engg-E),
कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,

For and on behalf of Chairman,
Airports Authority of India.



Schedule of Work

Name of Work: SITC of Smart Visual Docking Guidance System at Kolkata Airport.

SH: Provision of power supply, pipes and related other works required for installation of SVDGS at NSCBI Airport, Kolkata.

Sl. No.	Description of item	Qty.	Unit	Rate (in Rs.)	Amount (in Rs.)
SH: I	Electrical Related Works				
1	Supply of nominal 63 mm outer dia, PE 100 grade, PN 12.5 rated, SDR - 11 HDPE pipe conforming to IS: 4984:2016 (along with latest amendments) and as directed by Engineer-in-Charge.	6000	Mtr.	165.00	9,90,000.00
2	Supply of nominal 125 mm outer dia, PE 100 grade, PN 12.5 rated, SDR - 11 HDPE pipe conforming to IS: 4984:2016 (along with latest amendments) and as directed by Engineer-in-Charge.	1500	Mtr.	645.00	9,67,500.00
3	Supply and fixing of 25 mm steel conduit along with accessories in surface / recess including cutting the wall and making good the same in case of recessed conduit as required.	200	Mtr.	95.00	19,000.00
4	Supply and fixing of 25 mm medium class PVC conduit along with accessories in surface / recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.	200	Mtr.	30.00	6,000.00
5	Supply and fixing of PVC cable junction box (IP65) suitable for termination upto 4 sq. mm copper cable including fixing of suitable terminal connector along with end termination kits (IP65) for cable and fixing the same on wall / surface / existing poles etc. complete as per site requirement. Size: 300 mm x 450 mm x 170 mm.	20	Nos.	4,200.00	84,000.00
6	Supply and fixing of PVC cable junction box (IP65) suitable for termination upto 4 sq. mm copper cable including fixing of suitable terminal connector along with end termination kits (IP65) for cable and fixing the same on wall / surface / existing poles etc. complete as per site requirement. Size: 600 mm x 400 mm x 250 mm.	10	Nos.	5,500.00	55,000.00
7	Supply & fixing of 240 V/415 V, 50 Hz, 10 Ka "C" Series 25 amps DP MCB (in accordance with IS/IEC 60898-1 & IS/IEC 60947-2)	25	Nos.	350.00	8,750.00
8	Supply of 3 core 4 sq. mm XLPE insulated, PVC inner sheathed, Armoured Cu. conductor cable, extruded PVC type ST2 outer sheathed, 650 /1100 Volt grade as per IS 7098 (Part 1) 1988 with upto date ammendments.	3000	Mtr.	140.00	4,20,000.00

28/5/2024
JG/11/EE



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

9	Supply of 3.5 core 70 sq. mm XLPE insulated, PVC inner sheathed, armoured AL conductor cable, extruded PVC type ST2 outer sheathed, 650 /1100 Volt grade as per IS 7098 (Part 1) 1988 with upto date ammendments.	3000	Mtr.	300.00	9,00,000.00
10	Laying of following size permanently lubricated HDPE (high density polyethylene) pipe along with its necessary accessories like coupler, end plugs etc. below the ground (i/c road crossing, cement concrete apron area) at a depth of 3 m to 5 m through horizontal directional derilling etc. complete as required after doing ground penetrating radar survey and submitting its report of the underground utilities as per technical specifications.				
10.01	63 mm outer dia	1000	Mtr.	350.00	3,50,000.00
10.02	125 mm outer dia	1000	Mtr.	400.00	4,00,000.00
11	Laying of high density polyethylene (HDPE) pipe of outer dia 63 mm complete with all accessories like couplers, bends, tees, etc. in the apron including machine cutting of apron surface of width 110 mm and upto 200 mm deep and taking the excavated material out of the area within a lead of 2 kms and refilling & making good the same by concreting as per site requirement.	2000	Mtr.	500.00	10,00,000.00
12	Kerf cutting with machine in apron of PQC / bituminous surface of depth 50 mm and width upto 15 mm for laying of cables including wrapping cotton tape on cables and refilling the same by suitable sealing material (Pidilite) etc. complete as required and as per instruction of EIC.	2500	Mtr.	300.00	7,50,000.00
13	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
13.01	Upto 35 sq. mm.	50	Mtr.	300.00	15,000.00
13.02	Above 35 sq. mm and upto 95 sq. mm	50	Mtr.	325.00	16,250.00
14	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/HDPE/METAL pipe/concrete groove as required.				
14.01	Upto 35 sq. mm.	2800	Mtr.	45.00	1,26,000.00
14.02	Above 35 sq. mm and upto 95 sq. mm	2100	Mtr.	50.00	1,05,000.00

Signature
28/5/2024
JGMEC



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

15	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
15.01	Upto 35 sq. mm.	10	Mtr.	20.00	200.00
15.02	Above 35 sq. mm and upto 95 sq. mm	200	Mtr.	25.00	5,000.00
16	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.				
16.01	Upto 35 sq. mm. (clamped with 1mm thick saddle)	20	Mtr.	50.00	1,000.00
16.02	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	600	Mtr.	55.00	33,000.00
17	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.				
17.01	Upto 35 sq. mm. (clamped with 1mm thick saddle)	120	Mtr.	40.00	4,800.00
17.02	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	50	Mtr.	55.00	2,750.00
18	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required				
18.01	3 x 4 sq. mm.	48	Nos.	350.00	16,800.00
18.02	3.5 x 70 sq. mm.	16	Nos.	650.00	10,400.00
19	Design, fabrication, supply, installation, testing and commissioning of Floor Mounted outdoor type, suitable size control panel cum feeder pillar made of CRCA sheet steel of 2 mm thick for frame work and covers complete with powder coating in approved shade, having 250 amps capacity TPN aluminium busbars, Incomer of 4 pole 200 amps Thermal Release based MCCB - 2 Nos., 4 Pole Automatic Transfer Switch of 200 amps - 1 No., Outgoing 25 amps DP MCB - 8 Nos. along with voltmeter and ammeter with necessary CTs, selector switches, LED indication lamps - Red, Yellow, Blue, ON, OFF, Trip, bottom base of MS channel and Legs, having bottom cable entry and a common GI earth bar with 2 nos. earth stud, internal connection by suitable aluminium strip/bar or aluminium cable as per specification and control wiring with 2.5 Sq.mm PVC insulated copper conductor cable for 3-phase, 4 wire 50 Hz system and same should be fixed 2 ft. height (from ground level) on brick foundation complete etc as required.	4	Nos.	2,50,000.00	10,00,000.00
20	SH-II: Earthing Works				
20.01	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	32	Nos.	5,500.00	1,76,000.00

Handwritten signature and date:
28/5/2024
JGM/EE



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

20.02	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	6	Nos.	7,500.00	45,000.00
20.03	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	30	Mtr.	525.00	15,750.00
20.04	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	30	Mtr.	125.00	3,750.00
20.05	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	30	Mtr.	190.00	5,700.00
20.06	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	100	Mtr.	22.00	2,200.00
21	SH-III: Miscellaneous Works				
21.01	Excavation for foundation in soft soil including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 metres.	10	Cum	250.00	2,500.00
21.02	Filling available excavated earth (excluding rock) in trenches, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 metres.	10	Cum	150.00	1,500.00
21.03	Demolishing cement concrete manually / by mechanical means including disposal of materials within 50 metres lead as per direction of Engineer-in-Charge.	10	Cum	1,200.00	12,000.00
21.04	Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	10	Cum	2,200.00	22,000.00
21.05	Demolishing brick work manually/ by mechanical means in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	8	Cum	1,000.00	8,000.00

Handwritten signature and date:
28/5/2024
JGM(EE)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

21.06	Providing and laying in position cement concrete of 1:1.5:3 (1 Cement : 1.5 Coarse sand : 3 graded stone aggregate 20 mm nominal size) derived from natural resources excluding the cost of centering and shuttering - all work upto plinth level.	10	Cum	7,000.00	70,000.00
21.07	Providing and laying in position cement concrete of 1:2:4 (1 Cement : 2 Coarse sand : 4 graded stone aggregate 20 mm nominal size) derived from natural resources excluding the cost of centering and shuttering - all work upto plinth level.	10	Cum	6,000.00	60,000.00
21.08	Providing brick work (in width 225 mm or more) with F.P.S. bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels.	10	Cum	8,000.00	80,000.00
21.09	Providing 15 mm thick cement plaster with a floating coat of neat cement of mix 1:4 (1 cement : 4 fine sand) at all levels.	30	Sq. Mtrs	300.00	9,000.00
21.10	Providing, laying and fixing 100 mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required	50	Mtrs.	1,500.00	75,000.00
21.11	Providing and making masonry inspection chamber of size not less than 1000 x 1000 x 750 mm deep (inside) including excavation of soil, 75 mm flat brick soling at the bottom, 50 mm base PCC concrete over brick soling, 250 mm brick work with cement mortar, cement plaster on brick work and bottom (only inside surface) providing RCC slabs of suitable size on top of the chamber with suitable lifting arrangement complete as required.	6	Nos.	12,000.00	72,000.00
21.12	Fabrication works in M.S. C channel / angle / flat / plates including cutting to required length, welding including sparay / manual painting the same with two coats of ISI marked synthetic enamel paint of approved colour over one coat of red oxide metal primer as per direction of Engineer-in-Charge.	2000	Kg.	95.00	1,90,000.00
22	SH-IV: (IT Related Works)				
22.01	Supply of CAT6 UTP Outdoor Armoured Ethernet Cable.	9000	Mtr.	45.00	4,05,000.00
22.02	Supply of 6 core Single Mode Outdoor Armoured Multi-Tube Optical Fiber Cable.	6000	Mtr.	35.00	2,10,000.00
22.03	Supply, installation, testing & commissioning of Fiber Optical Patch Cord	48	Nos.	105.00	5,040.00

Handwritten signature and date:
28/5/2024
JG M (EE)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

22.04	Supply, installation, testing & commissioning of steel frame powder coated Floor Standing Rack 36U with front door lockable double toughened glass door or perforated along with 19 inch mounting angles made of formed steel conforming to DIN 41494 or equivalent standard.	1	No.	26,000.00	26,000.00
22.05	Supply, installation, testing & commissioning of powder coated IP 55 Outdoor Pole Rack made of 1.2/1.5 mm thick CRCA sheet of 6U x 550 mm width x 500 mm depth.	24	Nos.	7,000.00	1,68,000.00
22.06	Supply, installation, testing & commissioning of 6 port fixed LIU - Rack Mount fully loaded.	6	Nos.	1,500.00	9,000.00
22.07	Supply, installation, testing & commissioning of 12 port fixed LIU - Rack Mount fully loaded.	24	Nos.	2,000.00	48,000.00
22.08	Supply, installation, testing & commissioning of 24 port fixed LIU - Rack Mount fully loaded.	2	Nos.	3,000.00	6,000.00
22.09	Supply, installation, testing & commissioning of Industrial grade (outdoor) Managed 8 port Gigabit Ethernet Switch with 2-SFP port.	24	Nos.	7,000.00	1,68,000.00
22.10	Supply, installation, testing & commissioning of Industrial grade (outdoor) Managed 24 port Gigabit Ethernet Switch with 4 SFP port.	8	Nos.	15,000.00	1,20,000.00
22.11	Supply, installation, testing & commissioning of Single mode Optical Fiber converter module.	24	Nos.	1,200.00	28,800.00
22.12	Supply, installation, testing & commissioning of Managed 4 x Gigabit SFP Fiber port & 8 x 10/100/1000 Base T port Ethernet switch along with 10 nos. of single mode SPF module.	2	Nos.	15,000.00	30,000.00
22.13	Crimping, splicing, testing and commissioning of existing CAT6 UTP / OFC cable along with all accessories etc. complete as required.	300	Job	175.00	52,500.00
22.14	Laying of Fiber optic cable in existing / recessed steel conduit / PVC conduit / HDPE pipe / open surface / cable tray as required.	6000	Mtr.	22.00	1,32,000.00
22.15	Laying of CAT6 Ethernet cable in existing / recessed steel conduit / PVC conduit / HDPE pipe / open surface / cable tray as required.	9000	Mtr.	22.00	1,98,000.00
Total excluding GST (Rs.)					97,43,190.00

(Rupees Ninety-Seven Lakhs Forty-Three Thousand One Hundred and Ninety Only including all taxes etc. but excluding GST)


28/5/2024

(संदीप पिंपलापुरे/Sandeep Pimplapure)
संयुक्त महाप्रबंधक (अभि-विद्युत)/Jt. Gen. Manager (Engg-E),
कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,
For and on behalf of Chairman, Airports Authority of India

Form-III


(Under rule 21(2) of the contract labour (Regulation and abolition) central rules, 1971; and rule 7(3) of the inter-state migrant workmen (regulation of employment and conditions of service) central rules, 1980)

Form of certificate by principal employer

Certified that:

1. I have engaged the applicant M/s. Youngmen Traders, P- 27/1, Rastraguru Avenue, Dum Dum, Kolkata – 700 028, West Bengal, India as a contractor in my establishment for the work of *"SITC of Smart Visual Docking Guidance System at Kolkata Airport. SH: Provision of power supply, pipes and related other works required for installation of SVDGS at NSCBI Airport, Kolkata"* to be carried out from 06.06.2024 to 05.12.2024.
2. I undertake to be bound by all the provisions of the contract labour (regulation and abolition) Act, 1970 (37 of 1970) and the contract labour (regulation and abolition) central rules, 1971 / the inter- state migrant workmen (regulation of employment and conditions of service) Act, 1979 (30 and 1979) and the inter- state migrant workmen (regulation of employment and conditions of service) central rules, 1980 in so far as the provisions are applicable to me in respect of the employment of contract labour/ inter - state migrant workmen by the applicant in my establishment.
3. The engagement of contract labour in the said work is not prohibited under sub section (1) of section 10 of the contract labour (regulation and abolition) Act, 1970 (37 of 1970) or an award or a settlement.

**Signature of the principle
Employer:**


28/5/2024

Printed Name: Shri. Sandeep Pimlapure
संदीप पिपलापुरे/Sandeep Pimlapure
सं. महाप्रबंधक (अभि.-वि.)/Jt. Gen.Mgr.(Engg.-Elect.)
भा.वि.प्र., ने.सु.व.वो.अ. हवाई अड्डा, NSCBI Airport
कोलकाता/Kolkata 700 052

Place: Kolkata

Date: 28.05.2024

**Registration Number of the Principal
Employer's establishment** : **LIN:** 46/R/(11)/2011-E-3
Dated: 20/03/2023

Principal Employer Site
Name of PE:
Airports Authority of India
Netaji Subhash Chandra Bose International Airport
Jessore Road, Dum Dum, Kolkata, West Bengal – 700 052
Email:- sandeep@aaai.aero
Mobile No: - 9423188568
Reg. No: - 46/R/(11)/2011-E-3
Dated: 20/03/2023


28/05/2024
संदीप पिंपलापुरे/Sandeep Pimlapure
सं. महाप्रबंधक (अधि.-वि.)/Jt. Gen.Mgr.(Engg.-Elect.)
भा.वि.प्रा., ने.सु.च.बो.अ. हवाई अड्डा/AAI, NSCB Airport
कोलकाता/Kolkata 700 052

Name: - M/s. Youngmen Traders,
P- 27/1, Rastraguru Avenue,
Dum Dum, Kolkata – 700 028,
West Bengal,
India.
e-mail: boieranjan@hotmail.com
Mobile No.: - 9831086452