



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संख्या: AAI/KSG/AGM(C)/ AMC/WO-1/2021-22/ 580

SPEED POST/Email
Dated 01/05/2024

सेवा में,

मैसर्स प्रधान एन्टरप्राइजेज,
18, सरस्वती एन्क्लेव, एसएफएस,
मानसरोवर, जयपुर -302015

M/s Pradhan Enterprises,
18, Saraswati Enclave, SFS,
Mansarovar, Jaipur-302015

Name of work:- "Annual Maintenance Contract of Civil work for Operational and Non Operational Areas at Kishangarh Airport (2024-25)."

संदर्भ :- दिनांक 12.04.2024 को खोली गई आपकी ई-निविदा। (वित्तीय निविदा)

Reference :- Your e-tender opened on 12.04.2024 (financial bid)

E-bid No. :- 2024_AAI_191508_1

महोदय/ Sir,

- उल्लेखित कार्य हेतु आपकी निविदा, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत प्रतिशत दर जो कि अनुसूची-ए (DSR 2023 & Additional Misc. Items) पर 50.51 % कम है, पर एतद् द्वारा स्वीकृत की जाती है। इस कार्य के लिए आवंटित कुल राशि 24.75 लाख (जीएसटी के अतिरिक्त) है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the percentage rate quoted by you which is 50.51% below at Schedule-A (DSR 2023 and additional miscellaneous items). The total amount allotted to this work is **Rs. 24.75 Lacs (without GST)**.

- सहायक महाप्रबंधक अभियांत्रिकी (सिविल), भारतीय विमानपत्तन प्राधिकरण, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजीनियरिंग प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **26.05.2024** तक सहायक महाप्रबंधक अभियांत्रिकी (सिविल), भारतीय विमानपत्तन प्राधिकरण, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हों। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन- ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा तथा स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

Asst. Gen. Manager Engg (C), AAI, Kishangarh Airport, Ajmer shall be the Engineer-in-charge of the work. You are requested to attend the office of the Asst. Gen. Manager Engg (C), AAI, Kishangarh Airport, Ajmer by **26.05.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees one hundred only) and the cost of the stamp paper shall be borne by you.

- आपकी निविदा के साथ प्राप्त रु. 100000/- की अग्रिम धन राशि को संविदा दस्तावेज के पृष्ठ जीसीसी-23 पर शर्त 1 A के अनुसार प्रतिभूति जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर शेष प्रतिभूति जमा के रूप में रु 147450/- (मात्र एक लाख सेत्तालीस हजार चार सो पच्चास रुपये) जमा करें अन्यथा इस राशि की कटौती आपके चालू बिलों से कर ली जाएगी।

The earnest money amount **Rs. 100000/-** received along with your tender will be treated and converted as part of security deposit as per Condition no. 1A on page no. GCC-23 of contract document. Please deposit **Rs. 147450/- (Rupees One Lakhs Forty Seven Thousand Four Hundred Fifty Only)** towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your RAR bill.

किशनगढ़ हवाई अड्डा, अजमेर, राजस्थान- 305801 Kishangarh Airport, Ajmer, Rajasthan - 305801
फोन-01463-297107, ईमेल : apdkishangarh@aai.aero Tel: 01463-297107 E-mail: apdkishangarh@aai.aero



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

4. आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970 तथा संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971 एवं न्यूनतम मजदूरी अधिनियम के प्रावधानों और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।

You are requested to comply with the provision of contract labour (Regulation & abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules 1971 and minimum wages Act and Rules there of Central and state Govt.

5. आपको प्रबन्धक (अभि. सि.), किशनगढ़ से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा ही किया जाएगा।

You are also directed to contact Manager (Engg - Civil), Kishangarh immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको 12 माह का समय प्रदान किया जाता है। यह समय इस पत्र के जारी होने के दसवें दिन से या साइट अधिग्रहण की तारीख, जो भी पहले हो से प्रारम्भ माना जाएगा।

Please note that the time allowed for carrying out the work shall be **12 Months**. It shall be reckoned from the 10th day after the date of issue of this letter or the date of site takeover, whichever is earlier.

7. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-प्रभारी के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer In-Charge.

8. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In case any discrepancy is found, then English version will be taken as correct.

संलग्न/Encl: 1. % rate BOQ
2. SOQ (08 pages.)
3. Form-V

भवदीय,
Yours faithfully,


01/05/24
(खेम राज मीना)

(Khem Raj Meena)

सहा. महाप्रबन्धक (अभि.-सि.)

Asst. Gen. Manager (Engg C)

के लिए एवं तरफ से अध्यक्ष

For and on behalf of Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

Percentage Rate BOQ

Annual Maintenance Contract of Civil work for Operational and Non Operational Areas at Kishangarh Airport (2024-25)
Tender ID: 2024_AAI_191508_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Item Description	Estimated Rate	Quoted Percentage	Quoted Rate in Figures and Words	
				Rate	Amount
1	Schedule -A (DSR-2023 and Additional Miscellaneous works Items) Note: The Payment of item shall be regulated as below i) DSR-2023 Items and Additional Miscellaneous works Items (except Item No. 27.30 to 27.33) Rate of item as per schedule =X Rate to be considered for payment = $(X / 1.2127) \times [(100 \pm \text{Quoted Percentage Rate}) / 100]$ ii) Schedule rate for AMW Item No. 27.30 to 27.33 Rate of item as per schedule = Y Rate to be considered for payment = Y	100.00	-50.51	49.49	Fourty Nine Point Fourty Nine


AGM (Engg.-C)
AAI, Kishangarh Airport, Ajmer

07/05/24

SCHEDULE 'A'**Schedule of Quantities**

Name of work:- Annual Maintenance Contract of Civil work for Operational and Non Operational Areas at Kishangarh Airport (2024-25).

S.I. No	Descriptions of Sub head	Subhead No.	Page No.		Reference
			From	To	
1	Carriage of Materials	1	79	88	DSR 2023
2	Earth Work	2	89	98	DSR 2023
3	Mortars	3	97	102	DSR 2023
4	Concrete Work	4	101	114	DSR 2023
5	Reinforcement cement concrete	5	111	134	DSR 2023
6	Masonry Work	6	125	144	DSR 2023
7	Stone Work	7	131	152	DSR 2023
8	Cladding work	8	137	164	DSR 2023
9	Wood and PVC Work	9	145	218	DSR 2023
10	Steel work	10	181	228	DSR 2023
11	Flooring	11	187	246	DSR 2023
12	Roofing	12	199	272	DSR 2023
13	Finishing	13	215	290	DSR 2023
14	Repairs to Buildings	14	227	306	DSR 2023
15	Dismantling & Demolishing	15	237	316	DSR 2023
16	Road work	16	245	344	DSR 2023
17	Sanitary installation	17	263	372	DSR 2023
18	Water Supply	18	277	430	DSR 2023
19	Drainage	19	307	446	DSR 2023
20	Pile work	20	317	454	DSR 2023
21	Aluminum work	21	323	464	DSR 2023
22	Water Proofing	22	329	476	DSR 2023
23	Rain water Harvesting & Tubewells	23	337	484	DSR 2023
24	Conservation of Heritage Building	24	343	490	DSR 2023
25	Structural Glazing and Aluminum Composite Panel	25	347	500	DSR 2023
26	New Technologies and Materials	26	353	546	DSR 2023
27	Additional Miscellaneous works-Part-I	27	SOQ-3	SOQ-6	At par DSR-2023
28	Additional Miscellaneous works- Part-II	28	SOQ-7	SOQ-8	At par DSR-2023

(Signature)
Aymur

Guidelines for quoting the % rate by the bidder=

- 1) Bid with NIL/BLANK/N.A./ZERO rate quoted in BOQ/ Schedule-A above will be rejected outrightly without giving any reason whatsoever. It will be considered as non-responsive bid.
- 2) The rate shall be quoted by the bidder in % age only on BOQ/ Schedule-A. The quoted percentage shall be consider up to two decimals points only.
- 3) For example- If bidder wants to quote 5% below on DSR-2023, then the bidder has to mention figure as 5 and select(-) less sign. If bidder wants to quote 5% above on DSR-2023, then the bidder has to mention figure as 5 and select (+) Excess sign.
- 4) The payment of items shall be regulated as below:

i) DSR-2023 items and Additional Miscellaneous works items (except item No. 27.30 to 27.33)

Rate of item as per schedule = X

Rate to be considered for payment = $(X / 1.2127) \times [(100 \pm \text{Quoted Percentage Rate}) / 100]$

ii) Schedule rate for AMW item No. 27.30 to 27.33

Rate of item as per schedule = Y

Rate to be considered for payment = Y


Agnes

27.0 ADDITIONAL MISCELLANEOUS WORKS-PART-I


Name of work - Annual Maintenance Contract of Civil work for Operational and Non Operational Areas at Kishangarh Airport (2024-25).

S. No.	Description of item	Unit	Rate
27.1	Repairing and refixing of door/windows shutter i/c removal of shutter from chaukhat, cutting where necessary removing and refixing but hinges on other side of frame of shutter wherever required (cost of hinges i/c fixing shall be paid extra)	Each	550.17
27.2	Making, Providing and placing the board made of letters "size and height of letters as per directed by Engineer-In-Charge" pasting over 3mm thick white/coloured acrylic sheet i/c printing cutting/pasting etc. complete as per direction of Engineer-in-charge (frame work to be paid separately if provided) a) with self adhesive vinyl sheet	Sqm	4190.77
27.3	Making, Providing and placing the Logo/sticker of specified matter made of computer cut letters "size and height of letters as per directed by Engineer-In-Charge" by self adhesive vinyl sheet i/c pasting at site etc. complete as per direction of Engineer-in-charge. The agency has to submit the sample for approval. (The item rate includes the visiting, measurement charges at site.)	Sqm	2565.78
27.4	P/F Vertical/Horizontal blinds 100mm wide of Dustguard range of Vista make or equivalent as per required design complete as per satisfaction of Engineer-in-charge.	Sqm	2799.03
27.5	Providing and fixing Roller Blinds of Dustguard range of Vista make or equivalent with aluminium pipe, bracket set chain and weight pipe complete in all respect as per Engineer-In-Charge.	Sqm	5442.55
27.6	Tightening of barbed wire or GI wire fencing i/c fixing of broken hooks complete as per satisfaction of Engineer-in-charge	Metre	6.08
27.7	Cleaning of choked / blocked rain water pipe, soil waste pipe vent pipe, manhole sewerage pipe, gully trap, EWC, wash basin, kitchen sink, bottle trap, house drain storm water chain i/c of any diameter and size i/c removal of malba as directed by Engineer-In-Charge.		
	a) Rain water pipe / soil waste & vent pipes	Metre	19.76
	b) Manhole i/c connected sewerage pipes upto the next manhole	Each	786.18
	c) Gully trap i/c connected soil waste pipe/ sewerage pipes upto the nearest manhole	Each	152.10
	d) EWC / IWC i.e. connected traps and soil waste pipe upto the nearest opening point in soil waste pipe	Each	36.88
	e) Storm Water Drain (Road Side)	Metre	33.10
	f) Storm water drain (Runway side)	Metre	189.35
	g) Septic Tank - surface area upto 7.5 sqm	Each	3942.04
	h) Septic Tank - surface area 7.5 sqm to 15 sqm	Each	6299.55
	i) Septic Tank - surface area above 15 sqm	Each	7671.02
27.8	Cleaning of under ground water tank / surface water tanks and removing of malba as directed by Engineer-In-Charge i/c disinfecting the tank with bleaching powder.		
	a) Upto 5000 litre capacity.	Each	1673.52
	b) For every additional 1000 liter capacity	Each	346.27
27.9	Cleaning of GI/MS/Masonry/Syntax over head water tank i/c removal of malba as directed by Engineer-in-charge and disinfecting the tank with bleaching powder		
	a) Upto 500 litre	Each	186.14
	b) For every additional 100 litre capacity upto 10000 ltr	Each	36.65
	c) Beyond 10,000 litre capacity	Each	217.60
27.10	Providing & fencing with G.I. barbed wire (9.38 kg/100 mtr min. weight) fixed with GI stapled or with GI binding wire complete (length of individual G.I. barbedwire will be measured) as per Engineer-in-charge	Metre	10.62
27.11	Replacement of neoprene beading in existing aluminium door and windows complete up to the satisfaction of Engineer-In-Charge.	Metre	97.55
27.12	Supplying and placing in position sand bags filled with fine sand in all respect as per direction of Engineer-In-Charge.	Each	95.73
27.13	Lettering with synthetic enamel paint of approved brand & manufacture per satisfaction of Engineer-In-Charge.	Per letter per cm height	4.50

S. No.	Description of item	Unit	Rate
27.14	Making, Providing and placing the Logo/sticker of specified matter made of computer cut letters "size, height and colour of letters as per directed by Engineer-In-Charge" by 3M reflective radium sheet i/c pasting at site etc. complete as per direction of Engineer-in-charge. The agency has to submit the sample for approval: (The item rate includes the visiting, measurement charges at site.)	Per letter per cm height	4.34
27.15	Providing and fixing mirror of superior glass 5mm (of approved quality) and of required shape and size of approved make and shade complete as per direction of Engineer-In-Charge.	Sqm	1957.10
27.16	Providing PVC Tank cover of approved make with necessary screw etc. as per direction of Engineer-in-charge.	Each	611.14
27.17	Clearing of grass bushes etc by grass cutting Talwar i/c sweeping and disposal of material so cleared at desired location in Airport premises complete as per direction and satisfaction of Engineer-in-charge.	Sqm	4.05
27.18	Providing and fixing drawer guide channel in wooden table complete as per direction of Engineer in charge.		
	a) 450 mm length	Per pair	1047.44
	b) 600mm length	Per pair	1293.12
27.19	Providing and fixing 8mm thick glass for table top (the glass edges should be smooth rounded properly) as per direction of Engineer-in-charge	Sqm	1818.82
27.20	Providing and fixing 3mm ACP (Aluminium Composite Panel) sheet of approved make/color on existing boards including necessary fittings & sealant as per direction of Engineer- In -Charge.	Sqm	3036.94
27.21	Providing services of Blacksmith (welder) with welding machine and other accessories/ equipments required for welding to MS frames, grills, iron gates etc complete as per direction of Engineer-in-charge.	Per day	1935.10
27.22	Supply of PVC ball valve in PVC cistern of approved quality make Commandar or equivalent as per directions of Engineer-in-charge.	Each	477.03
27.23	Attending various day to day complaints except Sunday and rectifying the defects cause of complaints by deploying manpower with necessary T&P i/c nails, screws, fevicol, tape, washers etc. The agency has to provide 01 no. supervisor/ enquiry clerck (skilled), 1 no. plumber (Skilled) & 1 no. carpenter (Skilled) daily for day to day works except Sunday. Item includes the payment of all above manpower nothing extra will be payable in this regards. (fitting & fixtures will be paid seperately if provided) Note: i) Minimum wages should be paid by agency to workers deployed against this job. ii) PF and ESI will be reimbursed only when the agency submits the PF and ESI challan, etc. to Engineer-In-Charge.	Per month	80065.94
27.24	Providing & Fixing brass handle valve Zoloto make or equivalent of approved quality complete as per satisfaction of Engineer-In-Charge.		
	a) 15 mm nominal bore.	Each	1032.08
	b) 20 mm nominal bore.	Each	629.02
	c) 25 mm nominal bore.	Each	1072.24
	d) 50 mm nominal bore.	Each	3987.72
27.25	Providing and fixing ply/ plywood board of approved make in partitions, panneling or any other works with necessary screws, nails etc. complete as per directions of Engineer-in-charge.		
	a) 12mm	Sqm	1495.05
	b) 19mm	Sqm	2148.16
27.26	Providing and operating tractor with trolly / horrow / levellor / rotoator in the operational /non operational area including transportation of the same to site, fuel, driver and any other incidental break down charges on this account etc as directed by Engineer-In-Charge. Nothing extra shall be paid on this account (Per Day = 8 Hrs. if tractor engaged for less time then payment proportionately)	Day	1911.97
27.27	Providing and fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of Size 595mmx595mm reinforced with fibre and natural filler of approved texture i/c removal/ dismental of existing false ceiling tiles. Tegular edge should be treated to be a durable edge, tile to be laid existing grid system complete as per manufacturer's specifications and satisfaction of Engineer-in-charge.	Sqm	2213.50

S. No.	Description of item	Unit	Rate
27.28	Providing and operating Hydraulic excavator of minimum 0.75 cum capacity at site for levelling cutting, filling etc. including fuel, driver and any other incidental break down charges on this account etc complete as per direction and satisfaction of Engineer-In-Charge. Nothing extra shall be paid on this account.	Per hour	1274.65
27.29	Supply of water tanker of 5000 litre capacity having arrangement to empty the water in underground sump / overhead tank in AAI premises, etc. all complete as per direction of Engineer-In-Charge.	Each	794.85
27.30	Providing services of Unskilled office boy/ labour for day to day maintenance jobs, shifting of office from one location to another location, for engagement to works/ duties for office etc. complete as per direction of Engineer-In-Charge. (Rate mentioned shall be fixed above/ below percentage as quoted by contractor shall not be applicable on this item) Note: i) The Contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future during the entire period of the contract by State/Central Govt. (whichever wage is higher). ii) The contractor will be responsible to supervise the work assigned to labours and has to supply T&P as per requirement. iii) PF and ESI will be reimbursed only when the agency submits the PF and ESI challan, etc. to Engineer-In-Charge.	Per day	728.37
27.31	Providing services of Skilled manpower for day to day works/ duties for office having graduation etc. complete as per direction of Engineer-In-Charge. (Rate mentioned shall be fixed above/ below percentage as quoted by contractor shall not be applicable on this item) Note: i) The Contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future during the entire period of the contract by State/Central Govt. (whichever wage is higher). ii) The contractor will be responsible to supervise the work assigned to labours and has to supply T&P as per requirement. iii) PF and ESI will be reimbursed only when the agency submits the PF and ESI challan, etc. to Engineer-In-Charge.	Per day	1024.63
27.32	Providing services of High Skilled computer operator for day to day works/ duties for office having graduation with minimum 02 years experience with sound computer skills (MS office, SAP, E-procurement & tendering etc.) etc. complete as per direction of Engineer-In-Charge. (Rate mentioned shall be fixed above/ below percentage as quoted by contractor shall not be applicable on this item) Note: i) The Contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future during the entire period of the contract by State/Central Govt. (whichever wage is higher). ii) The contractor will be responsible to supervise the work assigned to labours and has to supply T&P as per requirement. iii) PF and ESI will be reimbursed only when the agency submits the PF and ESI challan, etc. to Engineer-In-Charge.	Per day	1202.39
27.33	Providing services of High Skilled Technical Assistant for day to day works/ duties for office having diploma in civil engineering with 04 year experience or graduate civil engineer with minimum 02 years experience for overall supervision of the works etc. complete as per direction of Engineer-In-Charge. (Rate mentioned shall be fixed above/ below percentage as quoted by contractor shall not be applicable on this item) Note: i) The Contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future during the entire period of the contract by State/Central Govt. (whichever wage is higher). ii) The contractor will be responsible to supervise the work assigned to labours and has to supply T&P as per requirement. iii) PF and ESI will be reimbursed only when the agency submits the PF and ESI challan, etc. to Engineer-In-Charge.	Per day	1202.39
27.34	Deduct for taking away of C.P. brass/Brass bib cock, stop cock, long body bib cock, long nose bib cock, angle valve, ball valve, close hole basin mixer, C.P.-waste in basin/ sink and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg	199.88

S. No.	Description of item	Unit	Rate
27.35	Deduct for taking away of steel work in frames, shutters, trusses, channels, beams, Tee, angles, grill, round or square bars, bolts, washers, SCI pipe fitting, C.I. flushing cistern, G.I. pipes and fittings etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg	33.31
27.36	Deduct for taking away of PVC connections, PVC flushing cisten with fittings, PVC over head tank, PVC bib cock, stop cock, ball valve, loft tank etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg	13.33
27.37	Deduct for taking away of aluminium butt hinges, sliding door bolts, tower bolts, pull boly lock, handle, door stopper, casement stay, tee chanals, plates, frames, shutters, partition, tubular sections etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg	106.61
27.38	Deduct for taking away of Wooden/plywood frames and/or shutters for Doors/windows/ clerestory windows, trusses, battens, particle board, glazed, wired, panelled etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg	19.99


 07/05/24
 Asst. Gen. Manager (Engg.-C),
 Kishangarh Airport, Kishangarh

28.0 ADDITIONAL MISCELLANEOUS WORKS- PART-II

Name of work - Annual Maintenance contract of civil works for operational and non operational areas at Kishangarh Airport (2024-25).

S.No.	Description of Items	Unit	Rate
28.1	Supply of flexible tube 8mm dia 1.5 mtr. long for Health faucet (Cat no SHA-CHR-549D8) of Jaquar make or equivalent as approved by Engineer-In-Charge.	Each	1192.58
28.2	Supply of Soap Dispenser with metallic bottle(ACN-CHR-1137N) of Jaquar make or equivalent as per satisfaction of Engineer-in-charge.	Each	4644.79
28.3	Supply of Towel Ring Round (ACN-CHR-1121BN) of JAQUAR make or equivalent as per satisfaction of Engineer-in-charge.	Each	1318.12
28.4	Supply of Hand Shower (Health Faucet) with 8mm Dia, 1.2 Meter Long Flexible Tube & Wall Hook of Jaquar or equivalent make (Item Code No: ALD-CHR-573) at site as per direction and satisfaction of E-I-C	Each	1990.19
28.5	Supply of Metropole Flush Valve Regular 32mm Size (Concealed Body) With Exposed Shut Off Provision of Jaquar or equivalent make (FLV-CHR-1095N) as per direction and satisfaction of E-I-C.	Each	4715.21
28.6	Supply of 32mm size C.P. waste coupling, half thread of Jaquar or equivalent make (Item code :ALD-CHR-705) at site complete as per direction & satisfaction of Engineer-in-charge.	Each	673.60
28.7	Supply of Towel rail 300mm long (Item code: ACN-CHR-1101N) of Jaquar make or equivalent as approved by E.I.C.	Each	1867.71
28.8	Supply of soap dish holder (Item code: ACN-CHR-1131N) of Jaquar make or equivalent as approved by E.I.C.	Each	979.78
28.9	Supply of Toilet roll holder (Item code: ACN-CHR-1151N) of Jaquar make or equivalent as approved by E.I.C.	Each	949.17
28.10	Supply of Double coat hook (Item code: ACN-CHR-1161N) of Jaquar make or equivalent as approved by E.I.C.	Each	734.84
28.11	Supply of Pillar cock (Item code: CON-CHR-011KN) of Jaquar make or equivalent as approved by E.I.C.	Each	1684.00
28.12	Supply of Swan neck tap with left/right hand operating knob with 450 mm braided hose (Item code: CON-CHR-123BKN) of Jaquar make or equivalent as approved by E.I.C.	Each	3000.59
28.13	Supply of Bib cock with wall flange (Item code: CON-CHR-047KN) of Jaquar make or equivalent as approved by E.I.C.	Each	1469.68
28.14	Supply of Long body bib cock with wall flange (Item code: CON-CHR-107KN) of Jaquar make or equivalent as approved by E.I.C.	Each	1959.57
28.15	Supply of Angular stop cock with wall flange (Item code: CON-CHR-059KN) of Jaquar make or equivalent as approved by E.I.C.	Each	1224.73
28.16	Supply of PVC soap dispenser of Greenlime make 500W741022 or equivalent complete as per direction & satisfaction of E-I-C.	Each	1530.91
28.17	Supply of white WC seat cover for vitreous china European WC of approved make or equivalent make in approved shape & size as per direction and satisfaction of E-I-C.	Each	796.07
28.18	Supply of 520x360 mm size table top wash basin (Item code: FLS-WHT-5931) of Jaquar or equivalent make complete as per satisfaction of E-I-C.	Each	6674.78
28.19	Supply of CP brass hinge grating 100mm dia of openable type complete as per direction of Engineer-In-Charge	Each	55.11
28.20	Providing and fixing of Pressmatic Pillar cock of Jaquar make (PRS-CHR-031L65) as per direction and satisfaction of EIC.	Each	3980.37
28.21	Providing and fixing Imported paintable/customized wallpaper fixed with glue over a prepared surface of 1mm thick wall putty of approved make and pattern as directed by Engineer-In-charge.	Sqm	2890.36
28.22	P/F sun control film of Garware Polyester or equivalent on glass panes after thoroughly cleaning of existing surface (the rate i/c removal of existing suncontrol film where ever required) as per direction of Engineer-in-charge.		
	a) Non-reflective sun control films	Sqm	1732.19
	b) Sparkle frosted film	Sqm	1133.51

Agm

S.No.	Description of Items	Unit	Rate
28.23	Providing & filling of Silicone Sealant of approved make with necessary tools in joints/gaps of door/ windows etc. to arrest seepage as per direction of EIC. Silicone Sealant tube of capacity 300 ml.	Each	678.50
28.24	Providing and laying of packed elastomeric concrete compound (Flex o patch) of choksey chemicals or equivalent i/c proper demarcation, cutting, chipping concrete upto required depth & width, side locking on the vertical face, cleaning the prepared area by blower, masking and pouring the compound, finishing & texturing etc. including applying primer for elastomeric concrete compound (Flex o patch) of approved make all complete as per the direction of engineer in charge.	Cucm	1.19
28.25	Supplying of 'Shelmac PR or equivalent pavement repair material as per manufacturers specifications etc complete as per directions of Engineer-In-Charge.	Kg	133.32
28.26	Cleaning/sweeping of Runway/taxi track/apron area/Car parking area/approach road by manual/mechanical means complete as per direction and satisfaction of Engineer-in-charge.	Sqm	0.64
28.27	Repairing/ closing of small holes in operational boundary wall with hard stone in super structure and up to plinth level including all man power, material, machinery & finishing the surface etc. complete as per direction of E-I-C. Cement mortar 1:6 (1 Cement : 6 coarse sand) Note:- (Surface area should not more than 0.25 sqm. for this job)	Sqm	6037.79
28.28	Testing of potable water as per the standard of local (as per IS 10500) water supply authority i/c supplying of water sample to the laboratory and providing the sample test report to Engineer-in-charge.	Eact test	3612.95
28.29	Providing and fixing PVC pipes (ISI marked pressure 4 Kg./sq.cm) including fittings (coupler, elbow etc.) and joining the pipes and fittings with adhesive solution all complete as per the direction and satisfaction of Engineer-in-charge.		
	(a) 40 mm (outer dia)	Metre	159.42
	(b) 50 mm (outer dia)	Metre	181.82
	(c) 75 mm (outer dia)	Metre	225.14
	(d) 110 mm (outer dia)	Metre	394.88
28.30	Providing & fixing 75mm PVC speed retardes/breakers of approved make made of modified thermoplastic (polymer rubberised) in black & yellow colours, fixed with anchor fastner & two componant epoxy adhesive including fixing of end cap & other necessary fixing arrengments etc. as per direction of E.I.C.	Metre	2688.04
28.31	Deploying sewer suction machine of capacity 5 cum per trip for suction of sewage, mulba, sullage for opening of blocked manhole, sewer line etc. i/c its disposal at isolated/ desinated location as per direction of E.I.C.	Each trip	2919.27
28.32	Clearing grass /bushes using mechanical means (tractor attached with grass cutter attachment) or hand mechanical tools including removal of malba from Airport premises as directed by Engineer In Charge.	Sqm	0.78
28.33	Supply of multicolor flag of size 4' X 6' made of double layer shantoon/taffeta febric with printed AAI logo on both side including designing, printing, stiching etc. complete as per direction of Engineer-In-Charge.	Each	1083.89
28.34	Providing and fixing 12 mm thick Solid Acrylic Surface Boards of approved make for vanity counters and similar locations of required size, approved shade, colour and texture with matching polyfix acrylic adhesive etc. complete as per direction & satisfaction of Engineer in charge.	Sqm	12110.24
28.35	Providing 10 mm thick PVC synthetic dirt trap door mat with hevy quality (weight not less then 4 Kg/Sqm) of approved design, colour etc. complete as per direction of Enginner-in-charge.	Sqm	1054.25

Asst. Gen. Manager (Engg.-C),
Kishangarh Airport, Kishangarh

FORM V

FORM OF CERTIFICATE BY PRINCIPAL EMPLOYER

[Under Contract Labour (Regulation & Abolition) Act, 1970]

[Rule 21 (2)]

Certified that I have engaged the applicant "M/s Pradhan Enterprises, 18, Saraswati Enclave, SFS, Mansarovar, Jaipur-302015" as a contractor in my establishment. I undertake to be bound by all the provisions of contract labour (Regulation and Abolition) Act, 1970, and the Central Contract Labour (Regulation and Abolition) Rules, 1973, insofar as the provisions are applicable to me in respect of the employment of contract labour by the applicant in my establishment.

Place:- Kishangarh Airport, Ajmer

Date:-

 01/05/24

Signature & Seal of
The Principal Employer

Registration No.:- AJ(R)/21/2013-ALC Dated- 16/12/2013

Signature Not Verified

Digitally signed by KHEM RAJ MEENA
Date: 2024.10.26 15:41:39 IST
Location: eProcurement System for Central
PSUS