



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

स No. AAI/CL/AGM/ENGG[C]/B.WALL /2024-25/34

दिनांक DATE: 30.05.2024

सेवा में To

मैसर्स एच.एम.बी.एस. टेक्सटाइल्स प्राइवेट लिमिटेड M/s.H.M.B.S Textiles Pvt.Ltd

1105, 11वीं मंजिल, डी-मॉल 1105, 11th floor, D-Mall

नेताजी सुभाष प्लेस, पीतमपुरा, Netaji Subhash Place, Pitampura

दिल्ली-110034 Delhi-110034

BY Hand/Regd. Post with A/D

/By Speed Post/By E-mail

कार्य का नाम **Name of work : Development of additional RESA on either end on Runway 10-28 at Calicut Airport .SH: Construction of Compound wall for newly acquired land at either end of Runway /** कालीकट हवाई अड्डे पर रनवे 10-28 के दोनों छोर पर अतिरिक्त आरईएसए का विकास।

एसएच: रनवे के दोनों छोर पर नई अधिग्रहीत भूमि के लिए परिसर की दीवार का निर्माण

संदर्भ **Ref : 1) ई-निविदा आईडी: E-Tender ID No: 2024_AAI_192090**

2) Your e-tender dated: 08.04.2024 (वित्तीय बोली Financial Bid)

प्रिय महोदय **Dear Sir/s,**

- उपर्युक्त कार्य के लिए आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत कुल मद्दर ₹22287220 (जीएसटी को छोड़कर) (दो करोड़ बाईस लाख सत्तासी हजार दो सौ बीस रुपये) पर स्वीकार की जाती है संलग्न मात्रा की अनुसूची के अनुसार जो कि निविदा में लगाई गई अनुमानित लागत ₹29717755.00 से 25.00% कम है। Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to **₹22287220 (Excluding GST)** (Rupees Two crore Twenty Two lacs Eighty seven Thousand Two Hundred and Twenty only) as per the schedule of quantities attached which **25.00% Below** the estimated cost put to tender of **₹29717755.00**
- संयुक्त. महाप्रबंधक (इंजीनियरिंग-सिविल), इंजीनियरिंग विंग, भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाईअड्डा कार्य का प्रभारी इंजीनियर होगा। आपसे संयुक्त महाप्रबंधक(इंजीनियरिंग-सिविल), इंजीनियरिंग विंग, भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डे पर 29/06/2024 तक अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए कार्यालय में उपस्थित होने का अनुरोध किया जाता है। अनुबंध समझौता ₹200.00 (केवल दो सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी। Joint General Manager (Engineering-Civil), Engineering Wing, AAI, Calicut International Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Joint General Manager (Engineering-Civil), by **29.06.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **₹200.00** (Rupees Two Hundred only) and the cost of the stamp paper shall be borne by you.
- इस पत्र के जारी होने की तारीख के बाद 10 दिनों के भीतर सुरक्षा जमा के रूप में ₹2228722 (मात्र बाईस लाख अट्ठाईस हजार सात सौ बाईस रुपये), ऐसा न करने पर पृष्ठ पर शर्त खंड 1 ए के अनुसार कटौती की जाएगी। अनुबंध दस्तावेज़ का GCC-16। Please deposit **₹2228722** (Rupees Twenty Two lacs twenty Eight Thousand Seven Hundred and Twenty Two Only) towards Security Deposit within 10 days after the date of issue of this letter, failing which, the same will be deducted as per Clauses of contract, Clause 1 A on page -16 of GCC of the contract document.



4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवाओं की स्थिति) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 49-50 पर खंड 19 में निर्दिष्ट है और केंद्र और राज्य सरकार के नियम के प्रावधानों का अनुपालन करें। You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of Services) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no 49-50 of GCC of tender and rules thereof Central and State Governments.
5. सहायक आपको सहायक प्रबंधक - (इंजीनियरिंग-सिविल), एएआई, कालीकट इंटरनेशनल से संपर्क करने का भी निर्देश दिया जाता है। हवाई अड्डा तुरंत आपको साइट सौंपने की व्यवस्था करेगा। You are also directed to contact **Asst. Manager-(Engineering-Civil)**, AAI, Calicut Intl. Airport immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय 08 [आठ] महीने होगा [बारिश के लिए 2(माह) पर विचार सहित] और इसकी गणना इस पत्र के जारी होने के 15वें दिन से की जाएगी। Please note that the time allowed for carrying out the work shall be **08 [Eight] months [including 2(month) considered for rains]** and same shall be reckoned from the 15th day from issue of this letter.
7. अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए। Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. कृपया पावती स्वीकार करें और इसके साथ संलग्न इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को लौटा दें। Please acknowledge the receipt and return the duplicate copy of this letter, enclosed herewith, after signing it to the undersigned as a token of acceptance.

भवदीय Yours faithfully,

संलग्नक Encl: BOQ (06 pages)

स महाप्रबंधक (ई-सी) **Asst. Gen. Manager (Engineering-Civil)**
इंजीनियरिंग विंग **Engineering Wing**,
भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा **AAI, Calicut Intl. Airport**
कृते & अध्यक्ष की ओर से **For and on behalf of the Chairman**

प्रवीण.के./PRAVEEN.K
सहायक महाप्रबंधक (इंजी-सिविल)
Asst. Gen. Manager [Engg-C]
भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
AAI, Calicut International Airport

Note: In case of any discrepancy English version will be treated as valid

Validate

Print

Help

Item Rate SOQ

Tender Inviting Authority: <Bid Manager, O/o HOD [Civil], Engineering Wing, Calicut Airport, AAI, Calicut Intl. Airport-673647 >

Name of Work: <: Development of additional RESA on either end on Runway 10-28 at Calicut Airport

SH: Construction of Compound wall for newly acquired land at either end of Runway >

Contract No: <2024_AAI_192090>

Name of the Bidder/ Bidding	HMBS Textiles Private Limited								
PRICE SCHEDULE (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)									
NUMBER	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
Sl. No.	20	Item Code / Make	Quantity	Units	Estimate d Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)	
1	2	3	4	5	6	7	8	10	
1	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. 3km Earth		480.00	cum		175.00	84000.00	INR Eighty Four Thousand Only	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. All kinds of soil		100.00	cum		150.00	15000.00	INR Fifteen Thousand Only	
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. Ordinary rock		70.00	cum		300.00	21000.00	INR Twenty One Thousand Only	
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.		760.00	cum		220.00	167200.00	INR One Lakh Sixty Seven Thousand Two Hundred Only	
5	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock.		540.00	cum		500.00	270000.00	INR Two Lakh Seventy Thousand Only	

प्रवीण.के./PRAVEEN.K

सहायक महाप्रबंधक (इंजी-सिविल)

Asst. Gen. Manager [Engg-C]

भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा

AAI Calicut International Airport

30/05/2024

AUMC

1/6

Sl. No.	20	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)
1	2	3	4	5	6	7	8	10
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.		980.00	cum		250.00	245000.00	INR Two Lakh Forty Five Thousand Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size derived from natural sources)		90.00	cum		6000.00	540000.00	INR Five Lakh Forty Thousand Only
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)		20.00	cum		6000.00	120000.00	INR One Lakh Twenty Thousand Only
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete		930.00	sqm		450.00	418500.00	INR Four Lakh Eighteen Thousand Five Hundred Only
10	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Lintels, beams, plinth beams, girders, bressumers and cantilevers		1120.00	sqm		450.00	504000.00	INR Five Lakh Four Thousand Only
11	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Columns, Pillars, Piers, Abutments, Posts and Struts		1420.00	sqm		450.00	639000.00	INR Six Lakh Thirty Nine Thousand Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.		35300.00	kg		70.00	2471000.00	INR Twenty Four Lakh Seventy One Thousand Only
13	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum		350.00	cum		6500.00	2275000.00	INR Twenty Two Lakh Seventy Five Thousand Only


प्रवीण.के./PRAVEEN K.
 सहायक महाप्रबंधक (इंजीनियरिंग)
 Asst. Gen. Manager [Engineering]
 आर. सि. प्रा. वा. अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

2/6

Sl. No.	20	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)
1	2	3	4	5	6	7	8	10
14	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level Concrete of M25 grade with minimum cement content of 330 kg /cum		90.00	cum		6500.00	585000.00	INR Five Lakh Eighty Five Thousand Only
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.		21200.00	kg		70.00	1484000.00	INR Fourteen Lakh Eighty Four Thousand Only
16	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)		130.00	cum		4500.00	585000.00	INR Five Lakh Eighty Five Thousand Only
17	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.		4020.00	kg		80.00	321600.00	INR Three Lakh Twenty One Thousand Six Hundred Only
18	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works		8000.00	kg		80.00	640000.00	INR Six Lakh Forty Thousand Only
19	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)		2740.00	sqm		350.00	959000.00	INR Nine Lakh Fifty Nine Thousand Only
20	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)		2740.00	sqm		400.00	1096000.00	INR Ten Lakh Ninety Six Thousand Only
21	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)		1280.00	sqm		200.00	256000.00	INR Two Lakh Fifty Six Thousand Only
22	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm)		6200.00	sqm		250.00	1550000.00	INR Fifteen Lakh Fifty Thousand Only


 प्रवीण के. पार्वेणा
 सहायक महाप्रबंधक (आ-सिविल)
 Asst. Gen. Manager [Engg-C]
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Sl. No.	20	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)
1	2	3	4	5	6	7	8	10
23	Lettering with black Japan/Synthetic enamel paint of approved brand and manufacture		25000.00	per letter per cm height		21.00	525000.00	INR Five Lakh Twenty Five Thousand Only
24	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)		25.00	cum		1000.00	25000.00	INR Twenty Five Thousand Only
25	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.		20.00	cum		1200.00	24000.00	INR Twenty Four Thousand Only
26	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.		3560.00	kg		20.00	71200.00	INR Seventy One Thousand Two Hundred Only
27	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.		700.00	kg		10.00	7000.00	INR Seven Thousand Only
28	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : Water bound macadam road		32.00	sqm		200.00	6400.00	INR Six Thousand Four Hundred Only
29	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : bituminous road		32.00	sqm		380.00	12160.00	INR Twelve Thousand One Hundred & Sixty Only
30	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead up to a lead of 10 km. including all lifts involved.		100.00	cum		250.00	25000.00	INR Twenty Five Thousand Only
31	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 no's rounds per 6 metre length, up to 5 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)		1202.60	m		350.00	420910.00	INR Four Lakh Twenty Thousand Nine Hundred & Nine and Paise One Hundred Only
32	Dismantling laterite masonry work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. : In cement mortar.		10.00	cum		600.00	6000.00	INR Six Thousand Only



 Asst. Gen. Manager [Engg.]
 आ वि प्रा, कालीकट अंतराष्ट्रीय हवाई
 AAI, Calicut International

Sl. No.	20	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)
1	2	3	4	5	6	7	8	10
33	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material (rubble/ stone) within the operational area in location/s at any lead and/ or lift, as directed by the Engineer-in-charge; and disposal of Moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved stacking location for all leads including all lifts involved as per directions of Engineer-in-charge In cement mortar		10.00	cum		800.00	8000.00	INR Eight Thousand Only
34	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 with cement mortar 1 : 6 (1 cement : 6 coarse sand including dressing of sides etc. complete as per the direction of Engineer-in-charge All works up to plinth level. Note: All work up to 1.20m above plinth beam will be measured under this item.		430.00	cum		6000.00	2580000.00	INR Twenty Five Lakh Eighty Thousand Only
35	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 with cement mortar 1 : 6 (1 cement : 6 coarse sand including dressing of sides etc. complete as per the direction of Engineer-in-charge Above plinth level up to floor V level		300.00	cum		5000.00	1500000.00	INR Fifteen Lakh Only
36	Providing & fixing weep holes/ air holes in all kinds of masonry work at all levels using 110 mm (4") PVC pipe (4kgf) of approved quality as per the directions of Engineer-in-charge		560.00	m		400.00	224000.00	INR Two Lakh Twenty Four Thousand Only
37	Providing and fixing temporary sheet fencing, repeating the procedure till the material becomes unserviceable, with ISA 65 x 65 x 6mm as vertical members, ISA 50 x 50 x 6mm as horizontal members, connected with nut and bolt arrangement. Vertical members to be fixed at 3m centre to centre and embedded in concrete block of size 60 x 60 x 60 cm. 0.4mm thick colour coated sheet to be fixed with J hook to the horizontal member to form sheet fencing. The temporary fencing should be provided at locations where compound wall is broken for reconstruction as per the security standards and for prevention of animal entry. Once the work is completed, the sheet fencing should be dismantled, taken out and re-fixed at new locations. After completion of the whole work, the material will be returned to the agency. The rate shall include materials for the work, excavation of pit for embedding concrete block for fencing post, concreting, loading, unloading, transportation to new location, erection and repetition of process etc. complete as per the direction of Engineer-in-Charge		500.00	sqm		300.00	150000.00	INR One Lakh Fifty Thousand Only
38	Providing and operating the hydraulic excavator cum back hoe loader on pneumatic tyre like J.C.B 2DX max or equivalent for cutting, levelling etc. in the operational area including transportation to and from the site of operation, fuel and driver charges and other incidental expenses on this account etc. as directed by the Engineer-in-Charge. (The payment will be based on the number of hours worked at the site for items that are not quantified otherwise.)		100.00	hours		1450.00	145000.00	INR One Lakh Forty Five Thousand Only
39	Dry laterite stone pitching with laterite stone blocks in the operational area and preparing surface etc. complete.		1450.00	sqm		850.00	1232500.00	INR Twelve Lakh Thirty Two Thousand Five Hundred Only


 Asst. Gen. Manager (Engg-C)
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport


5/6

Sl. No.	20	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words (Excluding GST)
1	2	3	4	5	6	7	8	10
40	Deduct for using department material supplied free of cost in the item "Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works"		2850.00	kg		25.00	-71250.00	INR Minus Seventy One Thousand Two Hundred & Fifty Only
41	Job contract for executing the survey of an area by deploying highly skilled surveyors with surveying equipment like total station, dumpy level etc. and all related accessories. The rate is inclusive of the hire charges of the equipment and manpower, survey of designated area, preparation of drawings, submission of original data sheets, level sheet, drawings etc. and nothing extra shall be payable in this regard.		5.00	per job per day		30000.00	150000.00	INR One Lakh Fifty Thousand Only
Total in Figures							22287220.00	INR Two Crore Twenty Two Lakh Eighty Seven Thousand Two Hundred & Twenty Only
Quoted Rate in Words		INR Two Crore Twenty Two Lakh Eighty Seven Thousand Two Hundred & Twenty Only						


 प्रवीणक/PRAVEEN.K.
 सहायक महाप्रबन्धक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-C]
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Signature Not Verified

Digitally signed by Praveen K.
 Date: 2026.03.30 15:37:44 IST
 Location: eProcurement System for Central PSUs



6/6