



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

Ref No. AAI/CL/AGM/ENGG[C]/BARRACK /2024-'25/36

दिनांक DATE: 05.06.2024

सेवा में To

BY Hand/Regd. Post with A/D

मैसर्स यासीस एसोसिएट्स M/s. YASEES ASSOCIATES

/By Speed Post/By E-mail

पुन्नक्कड हाउस PUNNAKKAD HOUSE

चुंगम CHUNGAM, कोंडोटी KONDOTTY

मलप्पुरम MALAPPURAM, केरल KERALA-673638

कार्य का नाम Name of work : A/R & M/O Civil Works during 2024-'25, 2025-'26 at Calicut International Airport. SH: Annual Maintenance Contract for civil works in CISF Barrack / कालीकट अंतर्राष्ट्रीय हवाई अड्डे पर 2024-'25, 2025-'26 के दौरान ए/आर एवं एम/ओ सिविल कार्य।

एसएच: सीआईएसएफ बैरक में सिविल कार्यों के लिए वार्षिक रखरखाव अनुबंध

संदर्भ Ref: 1) ई-निविदा आईडी: E-Tender ID No: 2024_AAI_192682

2) Your e-tender dated: 13.05.2024 (वित्तीय बोली Financial Bid)

प्रिय महोदय Dear Sir/s,

- उपर्युक्त कार्य के लिए आपका ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत प्रतिशत दर पर ₹3000000 (जीएसटी को छोड़कर) (केवल तीस लाख रुपये) की राशि के लिए स्वीकार किया जाता है - आइटम नंबर 50 और 51 को छोड़कर सभी डीएसआर 2023 आइटम और अतिरिक्त आइटम 1 से 53 की दरों पर 3.12% (तीन दशमलव बारह प्रतिशत नीचे)। Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India for an amount of ₹3000000 (Excluding GST) (Rupees Thirty lakhs only) at the percentage rate quoted by you which is -3.12 % (Three point Twelve Percentage below) on the rates of all DSR 2023 items and additional items 1 to 53 except item No.50 & 51
- संयुक्त. महाप्रबंधक (इंजीनियरिंग-सिविल), इंजीनियरिंग विंग, भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा कार्य का प्रभारी इंजीनियर होगा। आपसे संयुक्त महाप्रबंधक (इंजीनियरिंग-सिविल), इंजीनियरिंग विंग, भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डे पर 25/06/2024 तक अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए कार्यालय में उपस्थित होने का अनुरोध किया जाता है। अनुबंध समझौता ₹200.00 (केवल दो सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी। Joint General Manager (Engineering-Civil), Engineering Wing, AAI, Calicut International Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Joint General Manager (Engineering-Civil), by 25.06.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value ₹200.00 (Rupees Two Hundred only) and the cost of the stamp paper shall be borne by you.
- इस पत्र के जारी होने की तारीख के बाद 10 दिनों के भीतर सुरक्षा जमा के रूप में ₹300000 (मात्र तीन लाख रुपये), ऐसा न करने पर पृष्ठ पर शर्त खंड 1 ए के अनुसार कटौती की जाएगी। अनुबंध दस्तावेज़ का GCC-16। Please deposit ₹300000 (Rupees Three Lakhs Only) towards Security Deposit within 10 days after the date of issue of this letter, failing which, the same will be deducted as per Clauses of contract, Clause 1 A on page -16 of GCC of the contract document.

1 | Page

कालीकट अंतर्राष्ट्रीय हवाई अड्डा
Calicut International Airport

कालीकट हवाई अड्डा (डा.घ.)
Calicut Airport (P.O.),



प्रवीण.के./PRAVEEN.K
सहायक महाप्रबंधक (इंजी-सिविल)
Asst. Gen. Manager (Engg-C)
भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
Kerala-673647

दूरभाष/Phone : 0483-2711 325
फैक्स/Fax : 0483-2711 406

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवाओं की स्थिति) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 49-50 पर खंड 19 में निर्दिष्ट है और केंद्र और राज्य सरकार के नियम के प्रावधानों का अनुपालन करें। You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of Services) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no 49-50 of GCC of tender and rules thereof Central and State Governments.
5. सहायक आपको सहायक प्रबंधक - (इंजीनियरिंग-सिविल), एएआई, कालीकट इंटरनेशनल से संपर्क करने का भी निर्देश दिया जाता है। हवाई अड्डा तुरंत आपको साइट सौंपने की व्यवस्था करेगा। You are also directed to contact **Asst. Manager-(Engineering-Civil)**, AAI, Calicut Intl. Airport immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय 18 [अठारह] महीने होगा और इसकी गणना 10.06.2024 से की जाएगी। Please note that the time allowed for carrying out the work shall be **18 [Eighteen] months** and same shall be reckoned from the 10.06.2024.
7. अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए। Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. कृपया पावती स्वीकार करें और इसके साथ संलग्न इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को लौटा दें। Please acknowledge the receipt and return the duplicate copy of this letter, enclosed herewith, after signing it to the undersigned as a token of acceptance.

भवदीय Yours faithfully,

संलग्नक Encl: BOQ (08 pages)

स महाप्रबंधक (ई-सी) **Asst. Gen. Manager (Engineering-Civil)**
 इंजीनियरिंग विंग **Engineering Wing,**
 भाविप्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा **AAI, Calicut Intl. Airport**
 कृते & अध्यक्ष की ओर से **For and on behalf of the Chairman**

प्रतीक के/PRAVEEN.K
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager (Engg-C)
 भावि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport
 05/06/2024
 Aum (1)

Note: In case of any discrepancy English version will be treated as valid

SCHEDULE OF QUANTITIES

Name of work : A/R & M/O Civil Works during 2024-'25, 2025-'26 at Calicut International Airport

SH: Annual Maintenance Contract for civil works in CISF Barrack

All DSR 2023 Items
and

Additional Items from Item No. 01 to Item No. 53

Item No.	Item Description	Unit	Rate Rs. Ps.
	Sub head I - Schedule DSR 2023 All DSR 2023 schedule items (with upto date correction slip)	DSR 2023 Units	DSR 2023 rates
	Sub head II - Schedule Items other than DSR 2023		
1	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 m with cement mortar 1 : 6 (1 cement : 6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer in charge Up to plinth level.	cum	6021.22
2	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 m with cement mortar 1 : 6 (1 cement : 6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer in charge. Above plinth level up to floor V level	cum	7197.71
3	Dry laterite stone pitching with laterite stone blocks and preparing surface etc. complete.	sqm	883.72
4	Dry laterite stone pitching with laterite stone blocks issued by department free of cost at various stacked locations in the operational area and preparing surface etc. complete.	sqm	233.73
5	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 m, issued by department free of cost at various stacked locations in operational area with cement mortar 1 : 6 (1 cement : 6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer in charge Up to plinth level.	cum	2611.41
6	Laterite masonry with laterite stone blocks of size 0.35 x 0.21 x 0.20 m, issued by department free of cost at various stacked locations in operational area with cement mortar 1 : 6 (1 cement : 6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer in charge Above plinth level up to floor V level	cum	3787.91

SOQ 1


05/06/2024
Ammk
प्रवीण के/PRAVEEN.K
सहायक महाप्रबंधक (इंजी-सिविल)
Asst. Gen. Manager [Engg-C]
भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
AAI, Calicut International Airport

Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
7	Random rubble masonry with available hard stone, issued by department free of cost at various stacked locations in operational area, in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	3824.50	
8	Random rubble masonry with available hard stone, (issued by department free of cost at various stacked locations in operational area), in superstructure above plinth level and up to floor five level, levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement: 6 coarse sand)	cum	5169.50	
9	Dismantling laterite work manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge. In Cement mortar	cum	1346.32	
10	Providing & fixing weep holes in the masonry wall of any width at an inclination of 25° or more (upward slope towards city side/ soil side of retaining wall) using 110 mm (4") un-plasticized Rigid PVC (4 kgf) pipes conforming to IS : 13592 Type A, including cutting masonry work and fixing in cement mortar 1:6 (1 cement : 6 coarse sand) and making good the wall etc. complete of approved quality .	metre	272.55	
11	Cleaning of choked/blocked rain water pipe, soil waste pipe, vent pipe, manhole, sewerage pipe, gully traps EWC, IWC, Wash basin kitchen sink, bottle traps, floor traps, house drain, storm water drain etc. of any diameter and sizes i/c removal of drain cover, cleaning of drain, removal of malba, grass and any other vegetation etc., replacing the drain covers in place etc. complete as directed by Engineer-in-charge. Building/ Runway/ Taxiway side drain (closed)	metre	37.64	
12	Cleaning of choked/blocked rain water pipe, soil waste pipe, vent pipe, manhole, sewerage pipe, gully traps EWC, IWC, Wash basin kitchen sink, bottle traps, floor traps, house drain, storm water drain etc. of any diameter and sizes i/c removal of malba as directed by Engineer-in-charge. Storm water drain.	metre	23.98	

SOQ 2


 प्रवीण.के./PRAVEEN.K
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-C]
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport


Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
13	Cleaning of choked/ blocked rain water pipe, soil waste pipe, vent pipe, manhole, sewerage pipe, floor traps, house drain, storm water drain etc. of any diameter and size including removal of malba as directed by Engineer-in-charge Roof terrace cleaning i/c cleaning of rain water pipe inlets.	sqm	2.10	
14	Cleaning of underground water tanks/surface water tanks and removal of malba and disinfecting the tank with bleaching powder as directed by the Engineer-in-Charge. For 50,000 litre capacity tank	each	5302.55	
15	Cleaning of underground water tanks/surface water tanks and removal of malba and disinfecting the tank with bleaching powder as directed by the Engineer-in-Charge. For 1,00,000 litre capacity tank	each	7720.72	
16	Cleaning of underground water tanks/surface water tanks and removal of malba and disinfecting the tank with bleaching powder as directed by the Engineer-in-Charge. For 3,00,000 litre capacity tank	each	10680.38	
17	Cleaning of GI/MS/Masonry/Sintex overhead water tanks including removal of malba and disinfecting the tank with bleaching powder as directed by the Engineer-in-Charge. Up to 1000 litre capacity tank	each	589.93	
18	Cleaning of GI/MS/Masonry/Sintex overhead water tanks including removal of malba and disinfecting the tank with bleaching powder as directed by the Engineer-in-Charge. Above 1000 litre, up to 5000 litre capacity tank	each	2002.93	
19	Providing and fixing CP brass basin waste coupling (full thread) of approved make for kitchen sink and wash basin waste tank line as per the direction of Engineer in charge.	each	332.70	
20	Providing and fixing 1/2" dia health faucet (Cera, prayag or equivalent) with wall hook and flexible tube up to 1 metre long of quality and make as approved by Engineer - in - charge.	each	911.53	
21	Providing and fixing CP brass pillar cock with aerator of approved make and quality conforming to IS standards for wash basin. 15mm nominal bore	each	1044.24	
22	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 20mm outer dia	metre	42.85	

SOQ 3

प्रवीण के. शर्मा
महायक महाप्रबंधक (इंजीनियरिंग)
Asst. Gen. Manager (Engg-C)
भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
AAI, Calicut International Airport
21/06/2024


Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
23	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 25mm outer dia	metre	62.55	
24	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 32mm outer dia	metre	86.51	
25	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 40mm outer dia	metre	122.30	
26	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 50.00 mm outer dia	metre	176.21	
27	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 63 mm inner dia	metre	279.57	
28	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 75 mm inner dia	metre	320.30	
29	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS : 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 100 mm nominal inner dia	metre	825.37	

SOQ 4


 प्रवीण.के./PRAVEEN.K
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-c]
 आ वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
30	Providing and fixing un-plasticized Rigid PVC (10 kgf) pipes conforming to IS: 13592 Type A complete with fittings in water line, sewer line, vent pipes etc. complete. The rate is inclusive of cutting, finishing etc., with required slope as per the direction of Engineer-in-charge. 150 mm nominal inner dia	metre	1412.25	
31	Providing and fixing UPVC pipes (Schedule 80), having thermal stability for water supply including all plain & brass threaded fittings. This includes jointing of pipes & fittings with one step solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 65 mm nominal inner dia pipes.	metre	657.19	
32	Providing and fixing UPVC pipes (Schedule 80), having thermal stability for water supply including all plain & brass threaded fittings. This includes jointing of pipes & fittings with one step solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 80 mm nominal inner dia pipes.	metre	822.50	
33	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 65 mm dia nominal bore	metre	984.66	
34	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 80 mm dia nominal bore	metre	1165.33	
35	Providing and fixing gun metal ball valve with lever of approved quality (screwed end) : 20 mm nominal bore	each	706.73	
36	Providing and fixing gun metal ball valve with lever of approved quality (screwed end) : 25 mm nominal bore	each	1106.21	
37	Providing and fixing gun metal ball valve with lever of approved quality (screwed end) : 50 mm nominal bore	each	3790.06	
38	Providing and fixing GI flange of approved quality including cutting and threading the pipe and making long screws etc. complete as per the direction of engineer in charge : 50 mm dia	each	470.39	
39	Providing and fixing GI flange of approved quality including cutting and threading the pipe and making long screws etc. complete as per the direction of engineer in charge: 100 mm dia	each	662.98	

SOQ 5


 सहसंचालक महानियंत्रक (स्वी-एंगो)
 Asst. Gen. Manager (Engg-C)
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
40	Providing and fixing brass valve of approved quality as per the direction of engineer in charge: 15 mm nominal bore	each	515.59	
41	Providing and fixing CPVC ball valve of approved quality as per the direction of engineer in charge : 4 inch nominal bore	each	7912.84	
42	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.40 mm (+0.05 %) total coated thickness with zinc coating 150 grams per sqm as per IS: 277, in 240 MPa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5 x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. JSW or equivalent	sqm	556.46	
43	Providing and fixing glazing in structural steel, window, ventilator shutters and partitions etc. with silicone complete as per the architectural drawings and the directions of Engineer-in-charge: With float glass panes of 4.0 mm thickness	sqm	947.60	
44	Fixing available concertina coil fencing with required dia 610 mm (having 50 no's round per 6 metre length) up to 3m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart all complete as per direction of Engineer-in-charge. The concertina coil will be provided by the department free of cost at various stacking yards within the operational area. The item is inclusive of carriage of the item from the stacking yard to the work site and nothing extra will be paid in this regard.	metre	43.04	


 05/06/2024
 ALM(C)
 प्रवीण.के./PRAVEEN.K
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-C]
 आ वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
45	Providing and fixing available concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 no's rounds per 6 metre length, up to 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with available 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately). The concertina coil and RBT wire will be provided by the department free of cost at various stacking yards within the operational area. The item is inclusive of carriage of the item from the stacking yard to the work site and nothing extra will be paid in this regard.	metre	78.32	
46	Providing and operating the backhoe loader for levelling, cutting etc. including transportation to and from the site of operation, fuel and driver charges and other incidental expenses on this account etc. as directed by the Engineer-in-Charge. (The payment will be based on the number of hours worked at the site.)	hour	1087.31	
47	Providing and operating the hydraulic excavator (3D) for levelling, cutting etc.including transportation to and from the site of operation, fuel and driver charges and other incidental expenses on this account etc. as directed by the Engineer-in-Charge. (The payment will be based on the number of hours worked at the site.)	hour	1304.77	
48	Providing and operating the hydraulic excavator (3D) with breaker attachment for levelling, cutting etc. of rocky terrain including transportation to and from the site of operation, fuel and driver charges and other incidental expenses on this account etc. as directed by the Engineer-in-Charge. (The payment will be based on the number of hours worked at the site.)	hour	2065.89	


 05/06/2024
 Aumc
 प्रवीण.के./PRAVEEN.K
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-C]
 भा वि प्रा, कालीकट अंतर्राष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport

Item No.	Item Description	Unit	Rate	
			Rs.	Ps.
49	Providing and operating tipper of capacity 5.50 cum for transporting soil and excavated rock from one location to another within the premises of the work site to level the site, including transportation to and from the site of operation, fuel and driver charges and other incidental charges on this account etc. as directed by the Engineer-in-charge. (The payment will be based on the no. of days worked at the site.) Note:-Minimum 4 working hours is required to be measured as a man day	day	4892.89	
50	Providing unskilled/semi skilled workers for temporary nature of works/works unsuceptible to measure as and when required including necessary T & P. (For e.g.. works like shifting of store/office, verification of annual stock, filling water in desert cooler, shifting of materials to prevent encroachment on AAI land, survey work and other misc. works as directed by the Engineer-in-charge). Unskilled labour/helper	day	893.42	
51	Providing unskilled/semi skilled workers for temporary nature of works/works unsuceptible to measure as and when required including necessary T&P. (For e.g.. works like shifting of store/office, verification of annual stock, filling water in desert cooler, shifting of materials to prevent encroachment on AAI land, survey work and other misc. works as directed by the Engineer-in-charge). Semi-skilled labour/helper	day	1008.65	
52	Clearing of sludge and other solid waste from the various elements of the biomethynation plant including clearing sludge, loading the same into vehicles designed for the same, transporting to uninhabited areas/ dumping yards and unloading the same. The cost is inclusive of all activities mentioned above and nothing extra will be paid in this regard.	job	25008.13	
53	Providing and placing on terrace (at all floor levels) cover for polyethylene water storage tank	each	101.36	
	Note: The above / below percentage quoted by contractor not applicable for the Item No.50,51. The rates shown here only shall be payable.			

The payment of items shall be regulated as below

Schedule of rate as per DSR 2023 and additional Miscellaneous item (except item no. 50&51)

Rate of item as per schedule=X

Rate to be considered for payment= $(X/1.2127) \times (100 \pm \text{Quoted Percentage Rate})$
100

For item No.50&51 rate shown in SOQ only shall be considered for payment

Percentage rate applicable over DSR 2023 items and additional items 1 to 53 except item no.50&51 is 3.12% below (Three point Twelve below only)


 प्रवीण.के/PRAVEEN.K.
 सहायक महाप्रबंधक (इंजी-सिविल)
 Asst. Gen. Manager [Engg-C]
 भा वि प्रा, कालीकट अंतराष्ट्रीय हवाई अड्डा
 AAI, Calicut International Airport