



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संख्या : ए. ए. आई/ कोल/ इंजीनियरिंग (सी) / बी दीवार ऑप्स/2024/ 833
No.: A. A. I/Kol/Engg(C)/B Wall Ops/2024/ 833

दिनांक : 19/08/2024
Date : 19/08/2024

To,
मेसर्स ए.एस.ट्रेडर्स
M/s. A. S. Traders
No. 2 Airport Gate,
P. O. – Rajbari, Motilal Colony,
Kolkata - 700081

कार्य का नाम : - "एनएससीबीआई हवाई अड्डे, कोलकाता पर पुराने घरेलू टर्मिनल भवन को परिचालन क्षेत्र से अलग करने के लिए परिचालन सीमा दीवार का निर्माण।"

Name of Work:- Construction of Operational Boundary Wall to segregate the old domestic terminal building from operational area at NSCBI Airport, Kolkata.

Ref. :- Your e-tender no. 2024_AAI_195348_1 opened on dated 18/07/2024

महोदय / Dear Sir(s),

1. उपरोक्त उल्लिखित कार्य के लिए आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत वस्तु दरों पर कुल रु. 68,14,180.00 (रुपये अड़सठ लाख चौदह हजार एक सौ अस्सी रुपये मात्र) जीएसटी को छोड़कर, जो कि निविदा में लगाई गई अनुमानित लागत 1,13,16,000/- जीएसटी छोड़कर से 39.78 प्रतिशत कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 68,14,180.00 (Rupees Sixty-Eight Lakh Fourteen Thousand One Hundred Eighty Only) excluding GST which is 39.78% below the Estimated cost put to tender of Rs. 1,13,16,000/- excluding GST.

2. वरिष्ठ प्रबंधक (अभि. - सि.), भा.वि.प्रा., नेताजी सुभाष चंद्र बोस अंतर्राष्ट्रीय हवाई अड्डे, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि अनुबंध पर हस्ताक्षर करने और उसे पूरा करने के लिए वरिष्ठ प्रबंधक (अभि. - सि.), भा.वि.प्रा., परिचालन कार्यालय, एनएससीबीआई एयरपोर्ट, कोलकाता - 700052 के कार्यालय में 30/08/2024 तक उपस्थित हों। अनुबंध करारनामे मूल्य 100/- (रुपए एक सौ केवल) के गैर-न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Senior Mgr. Engg.(C), AAI, Netaji Subhash Chandra Bose International Airport, Kolkata shall be the Engineer-in-charge of the work. You are requested to attend the office of Senior Manager Engg. (C), AAI, Operational Office, NSCBI Airport, Kolkata – 700052 by 30/08/2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा राशि के रूप में 6,81,418.00 रुपए (छह लाख इक्कासी हजार चार सौ अठारह रुपए मात्र) जमा करें, ऐसा न करने पर, निविदा दस्तावेज के पृष्ठ संख्या 35 पर खंड 1ए के अनुसार चालू बिल से राशि काट ली जाएगी।

Contd. P/2....

Please deposit Rs. 6,81,418.00 (Rupees Six Lakh Eighty-One Thousand Four Hundred Eighteen only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from the running bill as per Clause 1A on Page No. 35 of the tender document.

4. आपको अधिनियम 1970 अनुबंध श्रम (विनियमन और उन्मूलन) के प्रावधान का अनुपालन करने का अनुरोध किया जाता है और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 बाल श्रम (निषेध और नियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार नियमन और सेवा की स्थिति) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, केंद्र और राज्य सरकार के निविदा और नियमों का जीसीसी 19 खंड के अनुसार पृष्ठ नंबर 71 पर जैसा बताया गया।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no 71 of GCC of tender and rules of Central and State Government.

5. आपको वरिष्ठ प्रबन्धक (अभि. - सि.), भा.वि.प्रा, परिचालन कार्यालय, एनएससीबीआई एयरपोर्ट, कोलकाता - 700052 से संपर्क करने का भी निर्देश दिया जाता है, जो तुरंत आपको निर्माण-स्थान सौंपने की व्यवस्था करेंगे।

You are also directed to contact Senior Mgr. Engg. (C), Airports Authority of India, Operational Office, NSCBI Airport, Kolkata - 700052 immediately who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि कार्य करने के लिए 6 (छह) महीने का समय दिया जाएगा, जिसमें 2 महीने बारिश के लिए भी शामिल होंगे तथा इसकी गणना इस पत्र के जारी होने के 10वें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be 6 (Six) months including 2 months considered for rains and same shall be reckoned from the 10th day after the issue of this letter.

7. अनुबंध के संबंध में कोई और पत्राचार आम तौर पर प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.

8. कृपया पावती भेजें और स्वीकृति के तौर पर संलग्नित प्रतिलिपि पत्र पर हस्ताक्षर करके उस प्रतिलिपि पत्र को अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


9. यदि अंग्रेजी और हिंदी के बीच कोई विसंगति है तो अंग्रेजी में निकाले गए अर्थ को वरियता दी जाएगी।

If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

आपको धन्यवाद।

Thanking you.

आपका निष्ठापूर्वक / Yours faithfully,


19.08.2024

(प्रहल्लाद भोई)

वरिष्ठ प्रबन्धक (अभि - सिविल)

भा. वि. प्रा., ने. सु. च. ब. अ. विमानपत्तन, कोलकाता-52
(भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष के लिए और उनकी ओर से)

संलग्न -

I. बिल अनुसूची / BOQ

II. प्रपत्र-III / From - III

प्रहल्लाद भोई

Prahallad Bhoi

वरिष्ठ प्रबंधक (अभि- सिविल)

Senior Manager (Engg.-Civil)

भा.वि.प्रा., ने.सु.च.ब.अ. हवाई अड्डा, कोलकाता-52.
AAI, NSCB Airport, Kolkata-52.

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: AGM (Engg-Civil), Airports Authority of India, NSCB Airport, Kolkata - 700052

Name of Work: Construction of Operational Boundary Wall to segregate the old domestic terminal building from operational area at NSCB Airport, Kolkata.

Contract No: 2024_AAI_195348

Name of the Bidder/ Bidding Firm / Company :	A S TRADERS							
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding Service Tax, VAT, GST etc) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	9	10
1	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material within airport premises, as per direction of Engineer-in-charge.	item1	64.00	Cum	450.00	28800.00	28800.00	INR Twenty Eight Thousand Eight Hundred Only
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - Charge. a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	item2	150.00	Cum	375.00	56250.00	56250.00	INR Fifty Six Thousand Two Hundred & Fifty Only
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within airport premises as per direction of Engineer - in - charge. (b) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	item3	40.00	Cum	260.00	10400.00	10400.00	INR Ten Thousand Four Hundred Only
4	Demolishing dry brick pitching in floors, drains etc including stacking of serviceable material and disposal of unserviceable material within airport premises.	item4	40.00	Cum	230.00	9200.00	9200.00	INR Nine Thousand Two Hundred Only



17.08.2024

प्रहल्लाद भोई
Prahallad Bhoi

वरिष्ठ प्रबंधक (अभि०-सिविल)

Senior Manager (Engg.-Civil)

भा.वि.प्र., ने.सु.प.व.अ. हवाई अड्डा, कोलकाता-52.
AAI, NSCB Airport, Kolkata-52.

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding Service Tax, VAT, GST etc) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	9	10
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (a) All kinds of soil	item5	530.00	Cum	150.00	79500.00	79500.00	INR Seventy Nine Thousand Five Hundred Only
6	Credit item for taking away excavated earth (mixed with dismantled pavement rubbish) obtained during execution of work as per direction of Engineer In Charge.	item6	430.00	Cum	-2000.00	-860000.00	-860000.00	INR Minus Eight Lakh Sixty Thousand Only
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, for all leads and lifts within airport premises as directed by Engineer-in-charge.	item7	400.00	Cum	20.00	8000.00	8000.00	INR Eight Thousand Only
8	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	item8	160.00	Cum	1800.00	288000.00	288000.00	INR Two Lakh Eighty Eight Thousand Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth level. (a) 1:5:10 (1 cement: 5 coarse sand :10 graded stone aggregate 40mm nominal size)	item9	80.00	Cum	5000.00	400000.00	400000.00	INR Four Lakh Only
10	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level (a) 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	item10	190.00	Cum	6500.00	1235000.00	1235000.00	INR Twelve Lakh Thirty Five Thousand Only
11	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and	item11	30.00	Cum	7000.00	210000.00	210000.00	INR Two Lakh Ten Thousand Only

प्रहल्लाद भोई
19.08.2024

प्रहल्लाद भोई
Prahallad Bhoi
वरिष्ठ प्रबंधक (अभि.-सिविल)
Senior Manager (Engg.-Civil)
भा.वि.प्रा., नै.सु.व.व.अ. हवाई अड्डा, कोलकाता-52.
AAI, NSCB Airport, Kolkata-52.

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder (Excluding Service Tax, VAT, GST etc) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	9	10
12	Centring and shuttering including strutting, propping etc. and removal of form for:(a) Foundations, Footings, bases of columns etc. for mass concrete.	item12	211.00	Sqm	250.00	52750.00	52750.00	INR Fifty Two Thousand Seven Hundred & Fifty Only
13	Centring and shuttering including strutting, propping etc. and removal of form for:(b) Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	item13	530.00	Sqm	250.00	132500.00	132500.00	INR One Lakh Thirty Two Thousand Five Hundred Only
14	Centring and shuttering including strutting, propping etc. and removal of form for:(c) Lintels, beams, plinth beams, girders, bressumers and cantilevers.	item14	162.00	Sqm	140.00	22680.00	22680.00	INR Twenty Two Thousand Six Hundred & Eighty Only
15	Centring and shuttering including strutting, propping etc. and removal of form for:(c) Columns, Pillars, Piers, Abutments, Posts and Struts.	item15	143.00	Sqm	200.00	28600.00	28600.00	INR Twenty Eight Thousand Six Hundred Only
16	Reinforcement for R.C.C.work including straightening, cutting, bending, placing in position and binding all complete. (a) Thermo Mechanically treated Bars of Grade Fe 500.	item16	42900.00	Kg	75.00	3217500.00	3217500.00	INR Thirty Two Lakh Seventeen Thousand Five Hundred Only
17	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300 mm thick AAC blocks in super structure above ground level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for separately).	item17	180.00	Cum	6200.00	1116000.00	1116000.00	INR Eleven Lakh Sixteen Thousand Only
18	12 mm cement plaster of mix: 1 : 6 (1 cement : 6 fine sand)	item18	1700.00	Sqm	250.00	425000.00	425000.00	INR Four Lakh Twenty Five Thousand Only
19	Finishing walls with Acrylic Smooth exterior paint of required shade : (a) New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm).	item19	1700.00	Sqm	60.00	102000.00	102000.00	INR One Lakh Two Thousand Only

Prahallad Bhoi

17.08.2024

प्रेहल्लाद भोई
Prahallad Bhoi

वरिष्ठ प्रबंधक (अभियंता-सिविल)
Senior Manager (Engg.-Civil)

आ.वि.प्र., नै.सू.स.य.अ. हवाई अड्डा, कोलकाता-52.
AAI, NSCB Airport Kolkata-52.

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding Service Tax, VAT, GST etc) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	9	10
20	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : (a) Two or more coats on new work.	item20	60.00	Sqm	70.00	4200.00	4200.00	INR Four Thousand Two Hundred Only
21	Steel work welded in built up section/frame work including cutting, hoisting, making necessary holes for fixing barbed wire and concertina coil if required, fixing in position and applying a priming coat of approved steel primer using structural steel etc.as required. (a) In grating,frames,guard bar,ladders,railing brackets,gates and similar works.	item21	1310.00	Kg	80.00	104800.00	104800.00	INR One Lakh Four Thousand Eight Hundred Only
22	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m) having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron all complete as per direction of Engineer-in-charge with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	item22	350.00	Mtr.	380.00	133000.00	133000.00	INR One Lakh Thirty Three Thousand Only
23	Providing and Fixing in position for expansion joint, 25mm thick pre cut Synthetic joint filler board of approved make conforming to IS:1838 complete as per directions of Engineer-in-charge. (Note: Mode of measurement shall be length of joint multiplied by width of filler board).	item23	10.00	sqm	1000.00	10000.00	10000.00	INR Ten Thousand Only
Total in Figures						6814180.00	6814180.00	INR Sixty Eight Lakh Fourteen Thousand One Hundred & Eighty Only
Quoted Rate in Words		INR Sixty Eight Lakh Fourteen Thousand One Hundred & Eighty Only						

Prabhakar
19.08.2024

प्रहल्लाद भोई
Prahallad Bhoi
वरिष्ठ प्रबंधक (अभि- सिविल)
Senior Manager (Engg.-Civil)
भा.वि.प्र., ने.रा.ए.व.अ. हवाई अड्डा, कोलकाता-52.
AAI, NSCB Airport, Kolkata-52.