



75
आज़ादी का
अमृत महोत्सव

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.: एएआई/आरएचक्यू-एनआर/एनएटीएस/इंजी-सिविल/जीएसई एरिया/आईएफ/हिंडोन/2024/65
No.: AAI/RHQ-NR/NATS/E-C/GSE Area/IAF/Hindon/2024

दिनांक : 05.08.2024
Dated : 05.08.2024

सेवा में,

To,

मैसर्स दर्शन कंस्ट्रक्शन
176, जीएफ-4, शक्ति खंड-II,
इंदिरापुरम, गाजियाबाद (यूपी)- 201005

M/s Darshan Construction
176, GF-4, Shakti Khand-II,
Indirapuram, Ghaziabad (U.P.)- 201005

विषय : जीएसई क्षेत्र का निर्माण, लिंक रोड, भारतीय वायु सेना (आईएफ), हिंडोन, गाजियाबाद के
अंदर परिधि सड़क का चौड़ीकरण।

Sub : Construction of GSE Area, Link road, widening of perimeter road inside Indian
Air Force (IAF), Hindon, Ghaziabad.

निविदा आईडी : 2024_एएआई_197390_1
Tender ID : 2024_AAI_197390_1

महोदय/ Sir,

- 1) अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण द्वारा आपके ई-टेंडर को ऊपर दर्शाय गए कार्य के लिए आपके द्वारा दिए गए उद्धृत मद दरो पर जोकि कुल रूपए 1,63,64,400/- (रूपए एक करोड़ तिरसठ लाख चौसठ हजार चार सौ मात्र) (जीएसटी के बगैर) है जोकि निविदा के लिए लगाई गई अनुमानित लागत रूपए Rs.2,40,36,779/- से 31.92% कम है (जीएसटी के बगैर) पर स्वीकार किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 1,63,64,400/- (Rupees One Crore Sixty Three Lacs Sixty Four Thousand Four Hundred only) (excluding GST) which is 31.92% below the estimated cost put to tender of Rs.2,40,36,779/- (excluding GST).

- 2) सहायक महाप्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उत्तरी क्षेत्र, तृतीय तल, एनएटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, नई दिल्ली-110037, इस कार्य के लिए प्रभारी अभियंता होंगे। आपसे निवेदन है कि अनुबंध करार को पूरा करने के लिए आप दिनांक 20.08.2024 तक सहायक महाप्रबंधक (अभि.-सिविल), क्षेत्रीय मुख्यालय, उत्तरी क्षेत्र, एनएटीएस कॉम्प्लेक्स के कार्यालय में उपस्थित हो। अनुबंध करार 100 (सौ) रूपए के गैर-न्यायिक स्टॉप पेपर पर होगा और स्टॉप पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asstt. General Manager (Engg.-Civil), AAI, Regional Headquarters, Northern Region, 3rd Floor, NATS Complex, IGI Airport, New Delhi-110037, shall be the Engineer-In-Charge of the work. You are requested to attend the office of AGM (Engg.-Civil), RHQ-NR, NATS Complex by 20.08.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100 - (Rupees: One Hundred only) and the cost of the stamp paper shall be borne by you.

Contd....2

ANIL PRAKASH
25/08/24
अनिल प्रकाश

- 3) कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूति जमा के रूप में रु 16,36,440/- (रुपये सोलह लाख छत्तीस हजार चार सौ चालीस मात्र) की सुरक्षा जमा राशि के रूप में जमा कराएं अन्यथा संविदा दस्तावेज के पेज जीसीसी-16 पर क्लॉज़ 1 (ए) की शर्त के मुताबिक इसकी कटौती की जाएगी।

Please deposit Rs. 16,36,440/- (Rupees Sixteen Lacs Thirty Six Thousand Four Hundred Forty only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause 1 (A) on page GCC-16 of the contract document part.

- 4) निवेदन है कि आप श्रम अनुबंध (विनियम और उन्मूलन) अधिनियम 1970 और श्रम अनुबंध (विनियम और उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (विनियम और निषेध) अधिनियम 1986, निर्माण मजदूर (रोजगार विनियम और सेवा शर्त) अधिनियम 1996, भवन और अन्य निर्माण मजदूर कल्याण अधिनियम 1996 का पालन करेंगे, जोकि केंद्र और राज्य सरकार के टेंडर के पृष्ठ संख्या-48, जीसीसी के अनुच्छेद-19 पर दर्शाए गए हैं।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 48 of GCC of tender and rules of Central and State Government.

- 5) आपको निर्देश दिए जाते हैं कि आप शीघ्रातिशीघ्र सहायक प्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, एनएटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, नई दिल्ली से संपर्क करें जोकि आपको साइट को सौंपने का प्रबंध करेंगे।

You are also directed to contact Asstt. Manager (Engg.-Civil), AAI, RHQ-NR, NATS Complex, IGI Airport, New Delhi immediately who will arrange to hand over the site to you.

- 6) कृपया ध्यान दें कि कार्य को पूरा करने का समय **02 (दो)** महीने होगा जोकि इस पत्र के जारी होने के 10 वें दिन से माना जाएगा या साइट को सौंपने की तारीख के बाद भी यह माना जाएगा।

Please note that the time allowed for carrying out the work shall be **02 (Two) months** and same shall be reckoned from the 10th day after issue of this letter or the date of handing over of site which ever is earlier.

- 7) इस करार के संबंध में भविष्य में होने वाले सभी पत्राचार प्रभारी अभियंता को संबोधित किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

- 8) कृपया इस पत्र की पावती भेजे और संलग्न प्रतिलिपि पर हस्ताक्षर करके स्वीकृति के प्रमाणस्वरूप अधोहस्ताक्षरी को वापिस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Contd....3


ANIL PRAKASH
सहायक महाप्रबंधक
Asstt. General Manager
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

(3)

9) किसी भी विवाद की स्थिति में संस्करण का अंग्रेजी रूप मान्य होगा ।

In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद,

Thanking you,

संलग्न:-मात्राओं की अनुसूची (02 पृष्ठ)

Encl :- Schedule of Quantities (02 pages)

भवदीय/yours faithfully


05/08/24
अनिल प्रकाश

अनिल प्रकाश/ ANIL PRAKASH

सहायक महाप्रबंधक, अभि. (सिविल)/AGM-Engg-Civil

अध्यक्ष, ए.ए.आई. की ओर से तथा उनके लिए/For and on behalf of the Chairman, AAI

सहायक महाप्रबंधक
अभि. (सिविल) / AGM-Engg-Civil
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

Name of Work: Construction of GSE Area, Link road, widening of perimeter road inside Indian Air Force (IAF), Hindon, Ghaziabad.

Tender ID: 2024_AAI_197390_1

SCHEDULE OF QUANTITIES (SOQ)

Sl. No	Description	Units	Qty	Rate (in Rs.)	Amount (in Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	Cum	1870.00	100	187000.00
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	Sqm	7220.00	100.00	722000.00
3	Filling available excavated earth (excluding rock) in embankments, depression etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by watering and ramming with 0.5 tonne roller and every 3rd and topmost layer with 8-10 tonne vibratory roller etc. complete as per the directions of Engineer-in-charge.	Cum	940.00	120.00	112800.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	700.00	3800.00	2660000.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	1460.00	5300.00	7738000.00
6	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	270.00	700.00	189000.00
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	15.00	6000.00	90000.00
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	1500.00	70.00	105000.00
9	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	Sqm	1040.00	300.00	312000.00

Sl. No	Description	Units	Qty	Rate (in Rs.)	Amount (in Rs.)
10	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete: 600 mm dia RCC pipes	Metre	10.00	300.00	3000.00
11	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-35 grade with approved colour design and pattern	Sqm	7220.00	580.00	4187600.00
12	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Metre	200.00	10.00	2000.00
13	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Sqm	350.00	10.00	3500.00
14	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	Sqm	350.00	150.00	52500.00
Total without GST = Rs.					16364400.00

(Rupees One Crore Sixty Three Lacs Sixty Four Thousand Four Hundred only)


 05/06/24
 आनिल प्रकाश
 AGM (Engg-Civil)
 AAI, RHQ-NR, NAFS Complex, IGIA
 Asstt. General Manager
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India

Signature Not Verified

Digitally signed by DHARAM CHAND MEENA
 Date: 2024.11.27 11:24:25 IST
 Location: eProcurement System for Central PSUs