

भाविप्रा/कोल्हापुर/उप.म.प्र.(अभि.-सि)/डब्ल्यू-03/2024-25/ 100/
AAI/Kolhapur/Dy.GM (Engg.-C)/W-03/2024-25/ 100/

दिनांक: 30/08/2024
Date: 30/08/2024

सेवा मे,
मेसर्स श्री लक्ष्मीनारायण कन्स्ट्रक्शन
सिद्धई, 96/2, 'अ' वार्ड, दुधाली,
कोल्हापुर - 416012,
महाराष्ट्र।

To,
M/s. Shri Laxminarayan Constructions,
Siddhai, 96/2, 'A' Ward, Dudhali,
Kolhapur - 416012,
Maharashtra.

विषय :- कोल्हापुर हवाई अड्डे पर नए एटीसी टावर के सामने पार्किंग शेड का निर्माण।

Subject: - Construction of Parking Shed in Front of New ATC Tower at Kolhapur Airport.

संदर्भ:- दिनांक 16/08/2024 को खोला गया आपका ई-टेंडर 2024_AAI_198788_1 (वित्तीय लिफाफा)।

Ref: - Your e-tender no. 2024_AAI_198788_1 (financial bid) opened on 16/08/2024.

महोदय/Sir,

1. उपरोक्त कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दर पर कुल रु. 26,14,500/- (रु. छब्बीस लाख चौदह हजार पांच सौ, मात्र) (GST के बीना) पर स्वीकृत की जाती है जो की निविदा में रखी गयी अनुमानित लागत रु. 40,06,000/- (रु. चालीस लाख छह हजार, मात्र) से 34.74% नीचे है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 26,14,500/- (Rs. Twenty-Six Lakhs Fourteen Thousand Five hundred, only) (Excluding GST) which is 34.74% below the estimated cost put to tender of Rs. 40,06,000/- (Rs. Forty Lakhs Six Thousand, only).

2. वरिष्ठ प्रबंधक (इंजी.-सिविल), भारतीय विमानपत्तन प्राधिकरण, कोल्हापुर विमानक्षेत्र, कोल्हापुर कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 13/09/2024 तक वरिष्ठ प्रबंधक (इंजी.-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 300/- (रु. तीन सौ मात्र) के नोन-ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Senior Manager (Engg.- Civil), Airports Authority of India, Kolhapur Airport, Kolhapur shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Senior Manager (Engg.- Civil), AAI, Kolhapur Airport by 13/09/2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

3. बयाना राशि जमा रु. 80,120/- (अस्सी हजार एक सौ बीस रुपये, केवल) आपके मूल खाते में तभी वापस किए जाएंगे जब आपकी सुरक्षा जमा राशि आरएआर बिल में कटौती की गई राशि रुपये 80,120/- से अधिक हो जाएगी। कृपया, प्रतिभूति निक्षेप राशि रु. 2,61,450/- (रु. दो लाख इकसठ हजार चार

Handwritten signature and date: 30/8/24

सौ पचास, मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त 1A पृष्ठ क्रमांक GCC-16 के अनुसार की जाएगी।

The earnest money deposit of Rs. 80,120/- (Rs. Eighty Thousand One Hundred & Twenty, Only) will be refunded back to your original account only after your security deposit deducted amount in RAR Bill will comes to more than Rs. 80,120/-. Please deposit Rs. 2,61,450/- (Rupees Two Lakhs Sixty-One Thousand Four Hundred & Fifty, only), towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per condition of GCC Clause no. 1A at page 16 of GCC of tender document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 50 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 50 of GCC of tender & minimum wage act and rules of Central and state government.

5. आपको निर्देश दिया जाता है कि आप तुरंत वरिष्ठ प्रबंधक (इंजी.-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय 03 (तीन) महीना है जोकि इस पत्र के जारी करने के दसवे दिन से यानी दिनांक 09/09/2024 से गिना जायेगा।

You are also directed to contact Senior Manager (Engg.-Civil), AAI, Kolhapur Airport immediately who will arrange to hand over site to you. Please note that, the time allowed for carrying out the work is 03 (Three) Months which shall be reckoned from the tenth day issue of this letter i.e. date 09/09/2024.

6. इस ठेके के संबंध में आगे की कोई भी पत्राचार वरिष्ठ प्रबंधक (इंजी.-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र, कोल्हापुर, 416004 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Senior Manager (Engg.-Civil), AAI, Kolhapur Airport, Kolhapur - 416004.

7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall form part of contract.

8. उपरोक्त कार्य के लिए त्रुटि दायित्व की अवधि 12 (बारह) महीने होगी।

The defects liability period for the above-mentioned work is 12 (Twelve) months.

9. यदि ठेकेदार को किसी भी सुरक्षा नियम का उल्लंघन करते हुए पाया जाता है, तो वह ब्लैक लिस्टेड हो जाएगा और अन्य कानूनी कार्यवाही के लिए जिम्मेदार होगा।

If Contractor is found violate any of Security Regulations, he shall be Black listed and will be responsible subjected to other Legal Proceedings.

Handwritten signature
Sm (FC)

10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा.

In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully

Handwritten signature
30/8/2024

वरिष्ठ प्रबंधक (अभि.-सिविल),

भाविप्रा, कोल्हापुर हवाईअड्डा, कोल्हापुर

कृते तथा अध्यक्ष की ओर से, भारतीय विमानपत्तन प्राधिकरण

Senior Manager (Engg.-Civil),

AAI, Kolhapur Airport, Kolhapur

For & on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <SM (Engg.-Civil), AAI, Kolhapur Airport >

Name of Work: <Construction of Parking Shed in front of new ATC Tower at Kolhapur Airport.>

Contract No: <2024_AAI_198788_1>

Name of the Bidder/
Bidding Firm /

shrilaxminarayan constructions .

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	12	7	8	10
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Ordinary rock	item1	70.000	cum	INR	200.00	14000.00	INR Fourteen Thousand Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	item2	5.000	cum	INR	5000.00	25000.00	INR Twenty Five Thousand Only
3	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	item3	13.000	sqm	INR	300.00	3900.00	INR Three Thousand Nine Hundred Only
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	item4	400.000	kg	INR	90.00	36000.00	INR Thirty Six Thousand Only
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	item5	15000.000	kg	INR	105.00	1575000.00	INR Fifteen Lakh Seventy Five Thousand Only
6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	item6	370.000	sqm	INR	680.00	251600.00	INR Two Lakh Fifty One Thousand Six Hundred Only
7	12mm cement plaster of mix: 1:6 (1 cement : 6 fine sand)	item7	170.000	sqm	INR	300.00	51000.00	INR Fifty One Thousand Only

Handwritten signature
30/8/2024
SM/EC

8	Finishing with Acrylic smooth exterior paint of required shade: New work (two or more coat applied @ 1.67 ltr./10 sqm over and including priming coat of exterior primer applied @ 90 ltr./10 sqm)	item8	170.000	sqm	INR	120.00	20400.00	INR Twenty Thousand Four Hundred Only
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	item9	330.000	sqm	INR	180.00	59400.00	INR Fifty Nine Thousand Four Hundred Only
10	Brickwork with fly ash size bricks of class designation 50 in foundation and plinth in : Cement Mortar 1:6 (1 Cement : 6 Coarse sand)	item10	46.000	cum	INR	5500.00	253000.00	INR Two Lakh Fifty Three Thousand Only
11	Pooviding and fixing of Hilti M20X180 5.8 grade Anchor with RE 500V4 Chemical having minimum anchor depth of 100 mm, complete as per directions of Engineering Incharge. Rate includes all components such as making holes in existing floor, cleaning holes with blower, providing and supplying of Anchor bolts of specific grade, injecting chemicals with HILTI machine and finishing all complete as per directions of Engineer incharge. The Bolts should be installed only after checking and verification in a location directed by Engineer Incharge.	item11	40.000	Each	INR	1800.00	72000.00	INR Seventy Two Thousand Only
12	Wiring for light point/ fan point/ exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	item12	10.000	Point	INR	1400.00	14000.00	INR Fourteen Thousand Only
13	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	item13	40.000	Point	INR	1000.00	40000.00	INR Forty Thousand Only
14	Wiring for light/ power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 2 Nos. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	item14	20.000	Mtr	INR	500.00	10000.00	INR Ten Thousand Only
15	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	item15	80.000	Mtr	INR	350.00	28000.00	INR Twenty Eight Thousand Only
16	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	item16	5.000	Each	INR	500.00	2500.00	INR Two Thousand Five Hundred Only
17	Supply of 20 watts LED tubelight fixture, suitable for operation at 230V, 50Hz AC supply as per list of approved makes etc complete as required.(Philips 20w stellar bright TLED or equivalent)	item17	50.000	Nos.	INR	350.00	17500.00	INR Seventeen Thousand Five Hundred Only
18	Installation,Testing, Commissioning of wall bracket /ceiling fittings of all sizes and shapes containing upto two GLS/CFL/LED lamps per fitting, complete with all accessories including connections etc. as required.	item18	40.000	Job	INR	100.00	4000.00	INR Four Thousand Only
19	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 8 way, Double door	item19	2.000	Job	INR	8500.00	17000.00	INR Seventeen Thousand Only

Handwritten signature
30/8/2024
SM/EC

20	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole.	item20	4.000	Job	INR	1000.00	4000.00	INR Four Thousand Only
21	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole.	item21	12.000	Job	INR	300.00	3600.00	INR Three Thousand Six Hundred Only
22	Supply of 1.1 KV grade aluminium conductor & XLPE insulated and PVC sheathed armoured cable of following sizes conforming to IS:1554(Part 1)1988 / IS:7098 (Part 1) with up to date amendments. 4c X 16 sq.mm	item22	250.000	Mtr	INR	300.00	75000.00	INR Seventy Five Thousand Only
23	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (80 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia	item23	150.000	Mtr	INR	130.00	19500.00	INR Nineteen Thousand Five Hundred Only
24	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm.	item24	50.000	Mtr	INR	40.00	2000.00	INR Two Thousand Only
25	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC / HUME / METAL / HDPE pipe as required. 35 Upto 35 sq. mm	item25	200.000	Mtr	INR	30.00	6000.00	INR Six Thousand Only
26	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 16 sq. mm	item26	4.000	Each	INR	25.00	100.00	INR One Hundred Only
27	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing cable as required	item27	250.000	Mtr	INR	40.00	10000.00	INR Ten Thousand Only
Total in Figures							2614500.00	INR Twenty Six Lakh Fourteen Thousand Five Hundred Only
Quoted Rate in Words							INR Twenty Six Lakh Fourteen Thousand Five Hundred Only	


 30/8/2024
 S.M.F.E.2