

सं: एएआई/सिल/अभि.- वि./केबल/व.ओ - 07/2024-25/836-846

दिनांक: 23.09.2024

Ref: AAI/SIL/ENGG-E/CABLE/W.O-07/2024-25/

Date: 23.09.2024

सेवा,
एम/एस. अवस्थी इलेक्ट्रिक वर्क्स,
107/265, ब्रह्मा नगर,
कानपुर - 208012.

To,
M/s Awasthi Electric Works,
107/265, Brahma Nagar,
Kanpur-208012

कार्य का नाम :- प्रोविसन ऑफ़ स्टैंडबाई पॉवर सप्लाई केबल फ्रॉम सबस्टेशन टो टर्मिनल बिल्डिंग एट सिलचर एयरपोर्ट।

Name of Work: - Provision of Standby power supply cable from substation to terminal building at Silchar Airport.

(Tender ID: 2024_AAI_200332_2)

प्रिय महोदय / Dear Sir (s),

- उपरोक्त कार्य के लिए आपका ई-टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धरित मद दर जिसकी कुल राशि रु. 58,34,325/- जीएसटी के बिना (अठ्ठावन लाख चौतीस हजार तीन सौ पच्चीस केवल) लागत रु 1,07,03,640/- से 45.49 % कम है, स्वीकृत किया जाता है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 58,34,325/-** excluding GST (**Rupees: Fifty-Eight Lakh Thirty-Four Thousand Three Hundred and Twenty-Five Only**) which is 45.49% Below the Justified cost of Rs. 1,07,03,640/-.

- वरिष्ठ प्रबंधक (अभि.-वि.)** कार्य के लिए **प्रभारी इंजीनियर** होंगे। आपसे अनुरोध है कि आप अपना प्रत्यायित प्रतिनिधि जिसे कि आप की ओर से संविदा करार पर हस्ताक्षर करने की शक्ति दी गई है। **वरिष्ठ प्रबंधक (अभि.-वि.), भा.वि.प्रा., शिलचर हवाई अड्डा** के कार्यालय में करार पर हस्ताक्षर करने के लिए दिनांक **07.10.2024** को तैनात करें। (संविदा करार रु.100/- के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको ही वहन करनी होगी।)

Senior Manager (Engg.-Elect.), AAI, Silchar Airport, Silchar shall be the **Engineer-in-Charge** for the work. You are requested to attend the **O/o Senior Manager (Engg.-Elect.), AAI, Silchar Airport by 07.10.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/- (Rupees Hundred only)** and the cost of the stamp paper shall be borne by you.

- कृपया इस कार्य - आदेश के जारी होने के 10 दिन में सुरक्षा जमा के लिए रु. 5,83,433/- (जीएसटी के बिना) जमा करवा दें, ऐसा नहीं करने पर संविदा दस्तावेज की शर्त के अनुसार आपके रनिंग बिल से काट ली जाएगी।

Please deposit Rs. 5,83,433/- (excluding GST) towards security deposit within 10 (Ten) days from the date of issue of this work order, failing which, the same will be deducted as per condition of the Contract document.

- आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की स्थिति) के प्रावधानों का अनुपालन करें। अधिनियम 1996, भवन एवं अन्य सन्निर्माण कर्मकार कल्याण उपकर अधिनियम 1996 केन्द्र एवं राज्य सरकार के नियमानुसार।

You are requested to comply with provision of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as per rules of Central and State Government.

- आपको निर्देश दिए जाते हैं कि आप वरिष्ठ प्रबंधक (अभि.-वि.) से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपुर्दकरने कि व्यवस्था करेंगे।

You are also directed to contact **Sr. Manager (Engg-E)**, AAI, Silchar Airport immediately who will arrange to hand over the site to you.

- कृपया यह नोट कर लें कि काम करने का समय **04 (चार) महीने** होगा और इसकी गणना **1st अक्टूबर 2024** से की जाएगी।


Please note that the time allowed for carrying out the work shall be **04 (Four) months** and same shall be reckoned from **1st October' 2024**.

7. संविदा के संबंध में आगे किया जाने वाला पत्राचार समान्यतः उप महाप्रबंधक (अभि.-वि.) भा.वि.प्रा.,सिलचर हवाई अड्डा से किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. कार्य की दोष दायित्व अवधि कार्य पूरा होने की वास्तविक तिथि से 12 महीने होगी।
The defects liability period of the work shall be **12 Month** from the actual date of completion of the work.
9. कृपया इस पत्र प्राप्ति की सूचना दे तथा इसके साथ अनुलगन अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
10. यदि हिंदी और अंग्रेजी संस्करण के बीच कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण को सही माना जाएगा।
In case any discrepancy is found between Hindi and English version, then English version will be taken as correct.

धन्यवाद/ Thanking you.

भवदीय / Yours faithfully

Encl: 1. Schedule of Quantities
अनुलानक : 1. अनुसूची की मात्रा


एस. के. मजूमदार (S. K. Mazumder)
वरिष्ठ प्रबंधक (अभि.-वि.)
Senior Manager (Engg.-Elect.)
भा.वि.प्रा.,सिलचर हवाई अड्डा
AAI, Silchar Airport

SCHEDULE OF QUANTITIES

Name of Work : Provision of Standby power supply cable from substation to terminal building at Silchar Airport.

Name of Agency : M/s Awasthi Electric Works

Tender ID: 2024_AAI_200332_2

BOQ Item No.	Description of Items	Qty.	Unit	Rate per Month (Including GST)	Amount (Including GST)
A	B	C	D	E	F= C*E*12
1	Supplying of 3.5 core, 300 sqmm. size of 1.1kv grade multistand aluminium conductor XLPE insulated PVC sheathed armoured Heavy duty power cable (as per IS: 7098:1988 with upto date amendments) complete as required as per specifications.	3500	METER	1,350.00	47,25,000.00
2	Supplying of 4.0 core, 16 sqmm. size of 1.1kv grade multistand aluminium conductor XLPE insulated PVC sheathed armoured Heavy duty power cable (as per IS: 7098:1988 with upto date amendments) complete as required as per specifications.	500	METER	140.00	70,000.00
3	Supplying of 2.0 core, 10 sqmm. size of 1.1kv grade multistand aluminium conductor XLPE insulated PVC sheathed armoured Heavy duty power cable (as per IS: 7098:1988 with upto date amendments) complete as required as per specifications.	500	METER	93.00	46,500.00
4	Supplying and laying of 120 mm dia (OD-120 mm & ID-103 mm nominal) size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	2650	METER	165.00	4,37,250.00
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. (i) Above 185 sq. mm and upto 400 sq. mm	150	METER	350.00	52,500.00
6	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe/ DWC pipe as required. (i) Above 185 sq. mm and upto 400 sq. mm	2650	METER	120.00	3,18,000.00
7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required: (i) Above 185 sq. mm and upto 400 sq. mm	150	METER	100.00	15,000.00
8	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. (Clamped with 40X3mm MS flat clamp) (i) Above 185 sq. mm and upto 400 sq. mm	200	METER	165.00	33,000.00
9	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. (i) Upto 35 sq. mm	220	METER	300.00	66,000.00
10	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required. (i)Upto 35 sq. mm	25	METER	40.00	1,000.00
11	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required: (i)Upto 35 sq. mm	25	METER	35.00	875.00
12	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. (i)Upto 35 sq. mm	30	METER	150.00	4,500.00
13	Supplying and making end termination with brass compression gland and aluminium lugs for 3½ X 300 sq. mm (70mm) size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	16	SET	1,350.00	21,600.00

एच.के. मजूमदार
S K MAZUMDER

वरिष्ठ प्रबंधक (अभि.-विद्युत)

Sr. Manager (Engg.-Elect.)

भारतीय विमानपत्तन प्राधिकरण, सिलचर

BOQ Item No.	Description of Items	Qty.	Unit	Rate per Month (Including GST)	Amount (Including GST)
A	B	C	D	E	F= C*E*12
14	Supplying and making end termination with brass compression gland and aluminium lugs for 4 X 16 sq. mm (28mm) size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	10	SET	250.00	2,500.00
15	Supplying and making end termination with brass compression gland and aluminium lugs for 2 X 10 sq. mm (19mm) size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	10	SET	190.00	1,900.00
16	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 3½ X 300 sq. mm size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	4	SET	7,800.00	31,200.00
17	Excavation of the cable trenches in hard rock not exceeding 1.5 meters in width, and lift upto 1.5 meters, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 meters.	5	Cum	1,500.00	7,500.00
Total Amount Rs. (Excluding GST)					58,34,325.00

Sr. Manager (Engg-E)
AAI, Silchar Airport

एस. के. मजूमदार
S K MAZUMDER

वरिष्ठ प्रबंधक (अभि.-विद्युत)
Sr. Manager (Engg.-Elect.)

भारतीय विमानपत्तन प्राधिकरण, सिलचर
AIRPORTS AUTHORITY OF INDIA, SILCHAR