



(पंजीकृत डाक)

भा.वि.प्रा./आरपीआर/व.प्र.(अभि-सि)/जॉइंट_रिपेयर/2024/ 1675-86

दिनांक: 18.09.2024

सेवा में,
मेसर्स एस. के. कंस्ट्रक्शन
विलेज - बरेमा, पोस्ट - रामेश्वर,
वाराणसी (उ.प्र.) - 221405

To,
M/s S.K. Construction
Village - Barema, Post - Rameshwar,
Varanasi (UP) - 221405

विषय:- स्वामी विवेकानन्द हवाई अड्डा, रायपुर में एप्रन और रनवे पेवमेंट क्षेत्र के जॉइंट्स का सीलिंग कंपाउंड से मरम्मत।

Sub:- Repairing of joints with sealing compound for Apron & Runway pavement area at S.V. Airport, Raipur.

Tender ID:- 2024_AAI_202527_1

संदर्भ :- आपकी ई-निविदा जो दिनांक 03.09.2024 को खोली गयी।

Ref:- Your E-tender opened on 03.09.2024

महोदय/Sir,

1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त कार्य के लिए आपकी निविदा स्वीकार की जाती है आपके द्वारा उद्धृत राशि रु 20,41,776.00 (रुपये बीस लाख इकतालीस सात सौ छिहत्तर मात्र) (जी.एस.टी. छोड़कर) जो कि अनुमानित लागत रु. 28,07,000/- (रुपये अट्ठाईस लाख सात हजार मात्र) (जी.एस.टी. छोड़कर) से 27.26% कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs 20,41,776.00 (Rupees Twenty Lakhs Forty-One Thousand Seven Hundred Seventy-Six Only) (Excluding GST) which is 27.26% below the estimated cost put to tender of Rs. 28,07,000/- (Rupees Twenty-Eight Lakhs Seven Thousand Only) (Excluding GST).


2. वरिष्ठ प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि कृपया दिनांक 13.10.2024 तक स्वामी विवेकानन्द हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार पर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

Senior Manager (Engg-Civil), AAI, Swami Vivekananda Airport, Raipur shall be the Engineer-In-charge of the work. You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 13.10.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर 16 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 56,140/- (रुपये छप्पन हजार एक सौ चालीस मात्र) को जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा। कृपया इस कार्यदिश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये 1,48,038/- (रुपये एक लाख अड़तालीस हजार अड़तीस मात्र) इस कार्यालय में जमा कराये अन्यथा यह कांटेक्ट डॉक्यूमेंट के पेज नंबर 16 पर धारा नं 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. 56,140/- (Rupees Fifty-Six Thousand One Hundred Forty Only) received along with your tender will be treated and converted as part of security

Signature
18.09.24



deposit as per Clause no. 1A on Page 16 of contract document. Please deposit Rs. 1,48,038/- (Rupees One Lakh Forty-Eight Thousand Thirty-Eight Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page 16 of contract document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर 52 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करे, साथ ही ठेका श्रमिक (विनियमन एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 तथा केंद्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 52 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ईएसआई अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ईएसआई पंजीकरण काम के वास्तविक समापन तक वैध रहे।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप वरिष्ठ प्रबंधक (अभि-सि.), स्वामी विवेकानंद हवाई अड्डा, रायपुर से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Sr. Manager (Engg.-Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि कार्य पूरा करने के लिए आपको 04 (चार) महीने का समय प्रदान किया जाता है जो इस पत्र के जारी होने के बाद दसवे दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 04 (Four) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी भी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

BHAW
29/05/24



Note: किसी भी विसंगति की स्थिति में अंग्रेजी संस्करण/पाठ मान्य होगा।

In case any discrepancy the English version/ text shall prevail.

सधन्यवाद !

भवदीय,

संलग्न :- अनुसूची - अ

sd

(भावेश पी मेहता)

वरिष्ठ प्रबंधक (अभि.-सि.)

भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

मूलप्रति में नहीं

प्रतिलिपि:

1. क्षेत्रीय कार्यपालक निदेशक, पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
2. महाप्रबंधक (इंजी), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
4. उपमहाप्रबंधक (सतकर्ता), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
5. सहायक श्रम आयुक्त (सी), डी -6, आदर्श सोसाइटी, सेक्टर - 1, अवंती विहार, रायपुर।
6. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक - डी, स्कीम नं - 32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.) - 492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
2. उपमहाप्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
3. उपमहाप्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
4. सहायक महाप्रबंधक (अभि-विद्युत्), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
5. मुख्य सुरक्षा अधिकारी, भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।

B. Mehta
18.09.24

(भावेश पी मेहता)

वरिष्ठ प्रबंधक (अभि.-सि.)

Received

Deepak Kumar Yadav

Schedule-A

NAME OF WORK :- Repairing of joints with sealing compound for Apron & Runway pavement area at S.V. Airport, Raipur.

Sl. No.	BOQ Item No.	Description	Unit	M/s S.K. Construction		
				Qty.	Rate	Amount
1	1	Demolishing cement concrete pavement manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	30.00	1250.00	37500.00
2	2	Removal of existing sealant by raking out with the help of a metal raker such that most of the sealant is removed. and re sealing of contraction, longitudinal or expansion joints in concrete pavement with fresh sealant material. Any spalls of the joint shall be made good by epoxy mortar (epoxy mortar shall be paid separately) as per morth clause 3005.2 and technical specification all complete as per direction of Engineer-in-Charge. (Fresh sealant shall be paid separately)	Mtr	8410.00	8.00	67280.00
3	3	Providing and laying in position Polysulphide sealant of approved make conforming to BS-5212-1990 or IS: 11433 1995 in expansion/ construction/dummy joints including raking out joints and preparing the surface, rounding off edges, applying 2 coats of approved primer compatible with the brand of Polysulphide and preparing the surface and applying masking tape along the edge of joint to prevent accidental spillage of sealant on top surface and to give neat finish to the sealant and removing the masking tape after application of sealant etc. complete as per direction of Engineer in- Charge & particular specifications. [Note: For purpose of payment, quantity (Length x Width x Depth) of Polysulphide sealant only will be measured.] i) Expansion Joints of size 25 mm wide and 10 mm deep over 30 mm dia closed-cell Polyethylene foam back-up rod (manufacturers specifications) and as per sketch. ii) Construction Joints of size 10 mm wide and 10 mm deep over 12 dia closed-cell Polyethylene foam back-up rod(manufacturers specifications) and as per sketch. iii) Dummy Joints of size 10 mm wide and 10 mm deep over 12 mm dia closed-cell Polyethylene foam back-up rod (manufacturers specifications) and as per sketch.	Cucm	1287820.00	0.90	1159038.00
4	4	Patching of damaged concrete surface with polymerized elastomeric concrete (ShaliPatch EC or equivalent) with excellent adhesion to substrate for repair of concrete pavement including cutting of the existing loose ,damaged and worn out concrete pavement in a geometrical shape, the edge of the chipped out portion to be given a vertical / acute angled cut of at least 50mm depth, removal of debris, cleaning the surface thoroughly with air jet to make it free from loose and dust particles, priming the cleaned surface with a polyurethane primer (like ShaliPrime PUM or equivalent) to act as a bond coat for further rendering and laying the material in position etc complete as per technical specification the direction and satisfaction of the Engineer-in-charge.	Sqm	34.36	8250.00	283470.00
5	5	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.)	Kg	200.44	1450.00	290638.00
6	6	Applying epoxy mortar (ShailFix FRM 40 or equivalent) over leached, honey combed, pot holes and spalled concrete surface as per morth clause 2804.2 and Technical Specification. all complete as per direction of Engineer-in-Charge.	Sqm	65.00	1360.00	88400.00
7	7	Making joint/ groove cutting by saw machine over the existing CC pavement all complete as per direction of Engineer-in-Charge.	Mtr	150.00	150.00	22500.00
8	8	Providing and laying Pavement Quality Concrete (PQC) produced in a batching plant having a Characteristic flexural strength i.e. minimum flexural strength of 4.1 MPa at 28 days using 400 Kg of Portland Pozzolana Cement / Portland Slag Cement fine aggregate, graded stone aggregates of 40 mm nominal size in appropriate proportion as per specification and job mix formula, laid in panels as per drawings/design as approved by the Engineer-In-Charge using Fixed form paver/ Manual method including making necessary provision for expansion joint, curing, etc. complete as per direction of Engineer-in-Charge and particular specifications. The item for execution shall also include the following operations: (i) Polyethylene sheet (White in color) of thickness 400 micron conforming to IS: 2508 with 6mm thick fine sand layer. Note: (i) The quantity of cement, type of cement and super plasticizer for one Cum. of finished concrete specified are for tendering purpose only. The contractor shall quote his rates assuming quantity of 400 Kg/ cum of Portland Pozzolana Cement/ Portland Slag cement. In addition, approved mix designs of PQC of previous project are available at the Airport, the same shall be followed provided meeting the test parameters of gradation, strength etc.	Cum	13.00	7150.00	92950.00
				Total Amount		2041776.00

(Rupees - Twenty Lakhs Forty-One Thousand Seven Hundred Seventy-Six Only Excl. @18% GST)


 (Bhavesh P Mehta)
 SM(E-C)
 AAI, S.V. Airport, Raipur