



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं:- भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर-03/2024-25/26

दिनांक:- 11/10/2024

सेवा में,

मैसर्स सोगानी इलेक्ट्रिकल्स,
753, आचार्यो का रास्ता,
किशनपोल बाजार,
जयपुर - 302003
ई-मेल - sele753@yahoo.in

M/s Sogani Electricals,
753, Achariyon Ka Rasta,
Kishanpole Bazar,
Jaipur -302003
E-mail :- sele753@yahoo.in

विषय :- प्रोविसन ऑफ़ वीआईपी रूम इन डिपार्चर ऑफ़ टर्मिनल बिल्डिंग एट किशनगढ़ एअरपोर्ट, अजमेर । इलेक्ट्रिकल वर्क फॉर सिफ्टिंग ऑफ़ इक्विपमेंट्स ।

Subject :- Provision of VIP room in Departure of Terminal Building at Kishangarh Airport, Ajmer. - Electrical work for shifting of Equipments.

संदर्भ:- दिनांक 19/09/2024 को खोली गई आपकी टेण्डर आई डी.-2024_AAI_203191_1 (वित्तीय बिड)।

Ref:- Your Tender ID: 2024_AAI_203191_1 (Financial Bid) opened on dated 19/09/2024.

महोदय,

1. उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल **रु. 8,89,110.00** (अक्षरे आठ लाख नवासी हजार एक सौ दस रुपये मात्र) **(जी.एस.टी. रहित)** की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत **रु. 10,02,038.00 (जी.एस.टी. रहित)** से **11.27% नीचे** हैं।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 8,89,110.00** (Rupees Eight Lakh Eighty Nine Thousand One Hundred Ten only) **(Excluding GST)** which is **11.27% below** the estimated cost of **Rs. 10,02,038.00 (Excluding GST)**.

2. सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **06/11/2024** तक सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हो। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन-ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा तथा स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-E) AAI, Kishangarh Airport, Ajmer by **06/11/2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of **Rs. 100/-** (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. सुरक्षा राशि **रु. 88,911.00** (अक्षरे अठ्ठासी हजार नौ सौ ग्यारह रुपये मात्र) को 10 दिन के भीतर जमा करें अन्यथा इस राशि की कटौति संविदा कागजात के पृष्ठ 33 पर खण्ड-1 ए के अनुसार आपके चालू बिलों से की जाएगी।

Security deposit **Rs. 88,911.00** (Rupees Eighty Eight Thousand Nine Hundred Eleven only) within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no.- 1A, page no. -33 of tender/contract document.

4. आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970, संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध एवं उन्मूलन) अधिनियम 1986, निर्माण श्रमिकों (सेवा के शर्त और नियमन) अधिनियम 1986 और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जो कि निविदा दस्तावेज के जी.सी.सी. के प्रावधानों का और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970, Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.

5. आपको प्रबन्धक (अभियांत्रिकी-विद्युत), भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।

You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको **03 माह** का समय प्रदान किया जाता है जो कि इस पत्र के जारी होने की तिथि से 10 दिन बाद से प्रभावी होगी।

Please note that the time allowed for carrying out the work shall be **03 Months** & shall be reckoned from 10th day after the date of issue this letter.

7. दोष दायित्व अवधि **एक (01) वर्ष** होगी, जो कार्य के पुरा होने की वास्तविक दर्ज तिथि से प्रभावी होगी।

The defects liability period shall be **One (01) Years**, which will be effective from the actual recorded date of completion of the work.

8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-इन-चार्ज के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया पत्र की पावती भेजें।

Please acknowledge the receipt.

10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In case any discrepancy is found, then English version will be taken as correct.

Enclosure :- BOQ Page-01 to 03

भवदीय / Yours Faithfully,

सहायक महाप्रबंधक (अभि०-वि०) / Asstt. Gen. Mgr. (Engg.-E)
कृते तथा ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

11/10/24

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:-Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work:-Provision of VIP room in Departure of Terminal Building at Kishangarh Airport, Ajmer. - Electrical work for shifting of Equipments.

Contract No:-2024_AAI_203191_1

Name of the Bidder/ Bidding Firm / Company :	M/S SOGANI ELECTRICALS, JAIPUR
--	--------------------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Dismantling, shifting, re-Installation, Testing & Commissioning of 2.0 ton (Make-Voltas) VRV Airconditioners indoor from existing location to new location, including fixing of drain pipe, copper pipe, PVC conduit, T-joint and solvent material, 10 mm fastener, 10 mm ss rod & nut bolt, supporting ss rod & clamp, soldering & brazing, complete as per site requirement. (Excluding the cost of supply of Copper Pipe, Draine Pipe, Insulation & Control wiring)	3	Job	7550.00	22650.00	INR Twenty Two Thousand Six Hundred & Fifty Only
2	Testing and Commissioning of outdoor of VRV Airconditioner system of capacity 20 HP (Make-Voltas) including leakage test in the refrigerant pipe line with nitrogen, vaccummising in the VRV system, refrigerant recharge, connecting the indoor & outdoor communication cable and making the Airconditioners in perfect working conditions as per site requirement. (Excluding the cost of supply of refrigerant R-410)	2	Job	4330.00	8660.00	INR Eight Thousand Six Hundred & Sixty Only
3	Dismantling, Shifting, re-Installation, testing & commissioning of indoor of 03 TR Tower AC (Make-Voltas) including supply & recharge refrigerant, fixing of drain pipe, copper pipe, PVC conduit, T-joint, soldering & brazing, etc. complete as per site requirement. (Excluding the cost of supply of Copper Pipe, Drain pipe, insulation & Control wiring)	1	Job	8900.00	8900.00	INR Eight Thousand Nine Hundred Only
4	Supply of refrigerant R-410 suitable for recharging the VRV Air Conditioning System complete as required.	140	Kg	1350.00	189000.00	INR One Lakh Eighty Nine Thousand Only
5	Supply of copper refrigerant pipe size 3/8" with suitable nitrile rubber pipe insulation complete as required.	36	Meter	270.00	9720.00	INR Nine Thousand Seven Hundred & Twenty Only
6	Supply of copper refrigerant pipe size 5/8" with suitable nitrile rubber pipe insulation complete as required.	36	Meter	400.00	14400.00	INR Fourteen Thousand Four Hundred Only
7	Supply of 25mm PVC Drain Pipe with elbow/socket and suitable nitrile rubber pipe insulation etc. complete as required.	38	Meter	80.00	3040.00	INR Three Thousand & Forty Only
8	Supply of 20mm PVC Conduit with elbow/socket for wiring complete as required.	32	Meter	25.00	800.00	INR Eight Hundred Only
9	Supply of 2 Core 1.5 Sqmm copper communication wire for connection between indoor and outdoor of Air Conditioning System complete as required.	40	Meter	85.00	3400.00	INR Three Thousand Four Hundred Only
10	Supply of 3 X 2.5 Sqmm size PVC insulated un sheathed bright anneales Copper Conductor cable suitable to work upto 1100V, AC Supply confirming to IS:694 upto date amendments etc complete as required.	36	Meter	160.00	5760.00	INR Five Thousand Seven Hundred & Sixty Only
11	Supply, Installation, Testing and Commissioning of 8 way (8 + 24), Double door, horizontal type three pole and neutral, sheet steel, IP-43, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including arthing etc. as required. (But without MCB/RCCB/Isolator)	3	Each	6770.00	20310.00	INR Twenty Thousand Three Hundred & Ten Only
12	Supplying and fixing of 8 way (4 + 24), Double door surface/ recess mounting, vertical type, 415 volts, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.)	1	Each	8282.00	8282.00	INR Eight Thousand Two Hundred & Eighty Two Only
13	Supplying and fixing 4 way (4 + 12), Double door, horizontal type three pole and neutral, sheet steel, IP-43, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).	1	Each	4170.00	4170.00	INR Four Thousand One Hundred & Seventy Only

97

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
14	Supplying and fixing of 20mm size of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.	37	Mtr	170.00	6290.00	INR Six Thousand Two Hundred & Ninety Only
15	Supplying and fixing of 25mm size of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.	41	Mtr	195.00	7995.00	INR Seven Thousand Nine Hundred & Ninety Five Only
16	Supplying and drawing 3 x 4 sq.mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	37	Mtr	160.00	5920.00	INR Five Thousand Nine Hundred & Twenty Only
17	Supplying and drawing 6 x 4 sq.mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	43	Mtr	320.00	13760.00	INR Thirteen Thousand Seven Hundred & Sixty Only
18	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	24	Each	450.00	10800.00	INR Ten Thousand Eight Hundred Only
19	Supply of 4C x 16 Sqmm, 1.1 KV grade, Armoured, XLPE insulated, PVC sheathed, Multicore, Copper conductor cable conforming to IS: 7098 (Part -1) 1988 amended upto date.	200	Mtr	1010.00	202000.00	INR Two Lakh Two Thousand Only
20	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade Upto 35 sq. mm size in the existing masonry open duct as required.	160	Mtr	18.00	2880.00	INR Two Thousand Eight Hundred & Eighty Only
21	Laying and fixing of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of Upto 35 sq. mm (clamped with 1mm thick saddle) size on wall surface as required.	40	Mtr	40.00	1600.00	INR One Thousand Six Hundred Only
22	Supplying and making end termination with brass compression gland and copper lugs for 4 X 16 sq. mm (28mm) size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required.	10	Each	280.00	2800.00	INR Two Thousand Eight Hundred Only
23	SITC of High Wall single phase, 5-Star inverter type 2.0 TR capacity split type airconditioner unit, minimum 20500 BTU/hr, fitted with hermetically sealed rotary compressor operating on refrigerant R-32/green gas suitable for single phase, 230V, 50Hz, including standard length of copper refrigerant pipe, copper cable and all other accessories as per OEM, capable of performing the functions as cooling, dehumidifying, air circulating and filtering, including fixing of extra copper refrigerant pipe, drain pipe and holes in wall etc. etc. complete as required.	2	Each	52100.00	104200.00	INR One Lakh Four Thousand Two Hundred Only
24	SITC of High Wall single phase, 5-Star inverter type 1.5 TR capacity split type airconditioner unit, minimum 16500 BTU/hr, fitted with hermetically sealed rotary compressor operating on refrigerant R-32/green gas suitable for single phase, 230V, 50Hz, including standard length of copper refrigerant pipe, copper cable and all other accessories as per OEM specifications capable of performing the functions as cooling, dehumidifying, air circulating and filtering, including fixing of extra copper refrigerant pipe, drain pipe and holes in wall etc. complete as required.	1	Each	39200.00	39200.00	INR Thirty Nine Thousand Two Hundred Only
25	Supply of copper refrigerant pipe size 1/2" (12.5mm) with suitable nitrile rubber pipe insulation complete as required.	5	Meter	340.00	1700.00	INR One Thousand Seven Hundred Only
26	Supply of copper refrigerant pipe size 1/4" (6.25mm) with suitable nitrile rubber pipe insulation complete as required.	5	Meter	190.00	950.00	INR Nine Hundred & Fifty Only
27	Supply and fitting of appropriate size and thickness of MS Stand / L-Chair for fixing 1.5/2.0 TR split AC outdoor unit or condensing units along with necessary vibration pads, anchor fastener/bolt & nuts etc on concrete/brick wall or floor etc. as required.	3	Each	786.00	2358.00	INR Two Thousand Three Hundred & Fifty Eight Only
28	Supplying and fixing 6 A to 32 A rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single Pole	8	Each	275.00	2200.00	INR Two Thousand Two Hundred Only
29	Supplying and fixing 6 A to 32 A rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double Pole	13	Each	780.00	10140.00	INR Ten Thousand One Hundred & Forty Only

97

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
30	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet and complete with connections, testing and commissioning etc. as required.	3	Each	2100.00	6300.00	INR Six Thousand Three Hundred Only
31	Supplying and fixing of 40 A, Four Pole MCB, 10 KA rating, "C" curve, miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	5	Each	2325.00	11625.00	INR Eleven Thousand Six Hundred & Twenty Five Only
32	Supplying and fixing of 63A, Four Pole MCB, 10 KA rating, "C" curve, miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	5	Each	3300.00	16500.00	INR Sixteen Thousand Five Hundred Only
33	Supplying and fixing of 100A, Four Pole MCB, 15 KA rating, "C" curve, miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	3	Each	9600.00	28800.00	INR Twenty Eight Thousand Eight Hundred Only
34	Supply, Installation, Testing & Commissioning of 125 Amp, 3 phase, 4 pole, enclosed Automatic Transfer Switch panel with fixing on wall, connections etc. complete as required. Make/ Model:- L&T/ Enclosed ATS, Frame 2, 125A or Havells/Instaline ATS IHYFCDE125 or equivalent.	2	Job	56000.00	112000.00	INR One Lakh Twelve Thousand Only
Total in Figures					889110.00	INR Eight Lakh Eighty Nine Thousand One Hundred & Ten Only
Quoted Rate in Words		INR Eight Lakh Eighty Nine Thousand One Hundred & Ten Only				


 11/10/24
 AGM (E-2)

Signature Not Verified

Digitally signed by TANSUKH
 Date: 2024.10.25 18:25:19 IST
 Location: eProcurement System for
 Central PSUs