



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
मैसूरु हवाई अड्डा / MYSURU AIRPORT
(A Public Sector Undertaking Miniratna Category-1)

No. AAI/MYS/ ENGG(E)/CW-02/2024-25 / 19/10/24

Date: 07.10.2024

To

M/s Awasthi Electric Works,
107/265 Brahma Nagar,
Kanpur - 208012
Email id: aewknp@gmail.com

कार्य का नाम/Name of work: डबल गेट सुरक्षा प्रणाली का निर्माण मैसूरु में परिसर की दीवार, बोलाड सुरक्षा बूथ आदि शामिल हैं एयरपोर्ट। एसएच: इलेक्ट्रिकल वर्क्स / "Construction of double gate security system including compound wall, bollard security booth etc, at Mysuru Airport. SH: Electrical Works."

संदर्भ / Ref : आपकी ई-निविदा संख्या: 2024_AAI_203370_1 /

Your e-tender no.: 2024_AAI_203370_1

आपकी ई-निविदा दिनांक 23.08.2024 को खुली /

Your Tender opened on 23.08.2023

महोदय / Dear Sir (s),

- उपर्युक्त कार्य के लिए आपका ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है, आपके द्वारा उद्धृत वस्तु दरें कुल रु. 15,67,162.00 (मात्र पन्द्रह लाख सड़सठ हजार एक सौ बासठ रुपये) (जीएसटी को छोड़कर) जो रुपये की निविदा में लगाई गई उचित लागत से 22.32% कम है। 20,17,389.00 (जीएसटी को छोड़कर)। / Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, item rates quoted by you totaling to Rs. 15,67,162.00 (Rupees Fifteen Lakhs Sixty Seven Thousand One Hundred and Sixty Two Only) (Excl. GST) which is 22.32% below the justified cost put to tender of Rs. 20,17,389.00 (Excl. GST).
- सहा. महाप्रबंधक (इंजीनियरिंग-ई), एएआई, मैसूरु हवाई अड्डा, मैसूरु, कार्य के प्रभारी अभियंता होंगे। आपसे अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए 16.10.2024 के भीतर एजीएम (इंजीनियरिंग-ई), एएआई, मैसूरु के कार्यालय में उपस्थित होने का अनुरोध किया जाता है। अनुबंध अनुबंध रुपये के मूल्य के गैर-न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा। 100/- (रुपए-सौ मात्र) और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी। / Asst. General Manager (Engg-E), AAI, Mysuru Airport, Mysuru, shall be the Engineer-in-charge of the work. You are requested to attend the office of AGM (Engg-E), AAI, Mysuru within 16.10.2024 to sign and complete the contract agreement. The Contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees- hundred only) and the cost of stamp paper shall be borne by you.

Contd...2

3. कृपया रुपये जमा करें इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में **1,56,716/-** (मात्र एक लाख छप्पन हजार सात सौ सोलह रुपये) जमा करने में विफल रहने पर, जीसीसी क्लॉज 1 (ए) की शर्त के अनुसार इसे काट लिया जाएगा।) पृष्ठ सं। अनुबंध दस्तावेज़ के 21 | / Please deposit Rs. **1,56,716/-** (Rupees One Lakh Fifty Six Thousand Seven Hundred and Sixteen only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of GCC Clause 1 (a) page no. 21 of contract document.
4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम १९७० और अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम १९७१ बाल श्रम (निषेध और विनियमन) अधिनियम १९८६, निर्माण श्रमिकों (रोजगार और सेवा की स्थिति का विनियमन) अधिनियम के प्रावधानों का अनुपालन करें। १९९६, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम १९९६ जैसा कि खंड संख्या में निर्दिष्ट है। पृष्ठ संख्या १९ पर। निविदा के जीसीसी के ६२ और केंद्रीय और राज्य सरकार के न्यूनतम मजदूरी अधिनियम और उसके नियम केंद्रीय और राज्य सरकारों के नियम। / You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Act 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and condition of Service) Act 1996, building and other construction workers welfare Cess Act 1996 as specified in Clause no. 19 on page no. 62 of GCC of Tender and rules of central and state Government minimum wages act & Rules thereof central and state Governments.
2. कार्य के प्रभारी अभियंता अपने निर्णय के अनुसार निष्पादित कार्य को स्वीकार या अस्वीकार करेंगे। / Engineer in charge of the work will accept or reject the work executed according to his judgment.
5. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय 04 महीने होगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन से की जाएगी।/ Please note that the time allowed for carrying out the work shall be 04 Months and same shall be reckoned from 10th day of issue of this letter.
6. अनुबंध के संबंध में कोई भी आगे का पत्राचार आम तौर पर प्रभारी अभियंता, भारतीय विमानपत्तन प्राधिकरण, मैसूरु हवाई अड्डा, मैसूरु को संबोधित किया जाना चाहिए।/ Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge, Airports Authority of India, Mysuru Airport, Mysuru.

7. कृपया पावती और स्वीकृति की निशानी के रूप में अधोहस्ताक्षरी को यह प्राप्त करने के बाद इसके साथ संलग्न इस पत्र की दूसरी प्रति, हस्ताक्षर कर अधोहस्ताक्षरी को वापस भेजें।

Please acknowledge receipt and return the duplicate copy of this letter enclosed herewith after signing it to the under signed as a token of acceptance.

Thanking you

Encls: Schedule of Quantities

भवदीय/Yours faithfully,

सहायक महाप्रबंधक, इंजीनियरी (इलेक्ट्रिकल),

Asst. General Manager (Engg-E)

अध्यक्ष, भाविप्रा के लिए एवं उनकी ओर से

For and on behalf of the Chairman
Airports Authority of India.

सहायक महाप्रबंधक (इंजी-वि)
Asst. General Manager (Engg - Elect)

प्रतिलिपि/Copy To :

1. एयरपोर्ट डायरेक्टर, एएआई, मैसूर एयरपोर्ट
Airport Director, AAI, Mysuru Airport
2. उप। महाप्रबंधक (इंजीनियरिंग-ई), एएआई, आरएचक्यू, एसआर, चेन्नई।
Dy. General Manager (Engg-E), AAI, RHQ, SR, Chennai.
3. मैनेजर (इंजीनियरिंग-ई), एएआई, मैसूर एयरपोर्ट।
Manager (Engg-E), AAI, Mysuru Airport.
4. वर्क ऑर्डर फाइल। / Work order file.
5. समझौते की फाइल। / Agreement file.

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Asst. General Manager (E-E), Airports Authority of India, Mysuru.

Name of Work: Construction of double gate security system including compound wall, bollard security booth etc, at Mysuru Airport. SH: Electrical Works.

Contract No: 2024_AAL_203370_1

Name of the Bidder/ Bidding Firm / Company : AWASTHI ELECTRIC WORKS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLSH PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C	29	EACH	1800.00	52200.00	INR Fifty Two Thousand Two Hundred Only	
2	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc as required. Group C	4	EACH	1050.00	4200.00	INR Four Thousand Two Hundred Only	

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	30	Meter	350.00	10500.00	INR Ten Thousand Five Hundred Only
4	Wiring for light/ power plug with 2X4 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	240	METER	310.00	74400.00	INR Seventy Four Thousand Four Hundred Only
5	Wiring for light/ power plug with 4X4 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 2 Nos 4 sq. mm FR PVC insulated copper conductor single core cable for loop earthing as required.	60	METER	520.00	31200.00	INR Thirty One Thousand Two Hundred Only
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	16	EACH	550.00	8800.00	INR Eight Thousand Eight Hundred Only
7	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. 6 Module (200mmX75mm)	4	EACH	380.00	1520.00	INR One Thousand Five Hundred & Twenty Only
8	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 15/16 A SWITCH	8	EACH	150.00	1200.00	INR One Thousand Two Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
9	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 6 pin 15/16 A socket outlet	8	EACH	1800.00	14400.00	INR Fourteen Thousand Four Hundred Only
10	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 Volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing and suitable cable end box etc. as required. (But without MCB/RCCB/Isolator) 8 way (8+24) Double door	1	EACH	7500.00	7500.00	INR Seven Thousand Five Hundred Only
11	Supplying and fixing following ways surface/recess mounting, vertical type 415 Volts, TPN MCB Distribution Board in sheet steel, dust protected, duly powder painted, inclusive of tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB s, cable end box (but without MCB s and Incomer) as required. 6 way (8+18) Double door	1	EACH	11600.00	11600.00	INR Eleven Thousand Six Hundred Only
12	Supplying and fixing following rating Triple Pole and Neutral, 415 volts, C curve, miniature circuit breaker in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 AMPS	2.00	EACH	1670.00	3340.00	INR Three Thousand Three Hundred & Forty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
13	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 AMPS	2	EACH	3050.00	6100.00	INR Six Thousand One Hundred Only
14	Supplying and fixing 5 to 32 amps rating 240/415 Volts, 10 KA, C curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple Pole 25 Amps	3	EACH	850.00	2550.00	INR Two Thousand Five Hundred & Fifty Only
15	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, C curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	27	EACH	160.00	4320.00	INR Four Thousand Three Hundred & Twenty Only
16	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	6	EACH	22.00	132.00	INR One Hundred & Thirty Two Only
17	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. 1 or 2 Module (75mmX75mm)	6	EACH	225.00	1350.00	INR One Thousand Three Hundred & Fifty Only
18	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. Telephone socket outlet RJ 11	6	EACH	145.00	870.00	INR Eight Hundred & Seventy Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
19	Supply of 1400 mm sweep BLDC Ceiling fan, 5 star rated with double ball bearing, standard down rod and other standard accessories suitable for 230 V, 50 Hz, single phase AC supply as required.	5	EACH	3750.00	18750.00	INR Eighteen Thousand Seven Hundred & Fifty Only
20	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	5	EACH	550.00	2750.00	INR Two Thousand Seven Hundred & Fifty Only
21	Supply of 300 mm dia single phase 900 RPM Heavy Duty Industrial Exhaust fan suitable for 230 V, 50 Hz, single phase AC supply including all accessories etc as required.	1	EACH	2870.00	2870.00	INR Two Thousand Eight Hundred & Seventy Only
22	Supply of 400 mm sweep BLDC wall fan, 5 star rated suitable for 230 V, 50 Hz, single phase AC supply as required.	2	EACH	4350.00	8700.00	INR Eight Thousand Seven Hundred Only
23	Supply of 20 W surface mounted extruded aluminium LED batten (4 feet) with opal diffuser along with all accessories like heat sink, constant current output driver, reflector, cover etc. complete suitable for operating at 230 V, 50 Hz, single phase AC supply as per specifications.	16	EACH	350.00	5600.00	INR Five Thousand Six Hundred Only
24	Supply of 15 W surface mounted LED downlight luminaire with white powder coated pressure die cast aluminium housing and diffuser along with all accessories like heat sink, constant current output driver, reflector, cover etc. complete suitable for operating at 230 V, 50 Hz, single phase AC supply as per specifications.	4	EACH	790.00	3160.00	INR Three Thousand One Hundred & Sixty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
25	Supply of Integral 45 Watts LED Street Light Luminaire with pressure die cast aluminium housing with IP 66 protection along with all accessories like heat sink, constant current output driver, reflector, glass cover etc. complete suitable for operating at 230 V, 50 Hz, single phase AC supply as per specifications.	40	EACH	1690.00	67600.00	INR Sixty Seven Thousand Six Hundred Only
26	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLSH PVC insulated, copper conductor, single core cable etc. as required.	5	EACH	250.00	1250.00	INR One Thousand Two Hundred & Fifty Only
27	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	1	EACH	400.00	400.00	INR Four Hundred Only
28	Installation of wall fan on surface including connections, testing, commissioning etc. as required.	2	EACH	250.00	500.00	INR Five Hundred Only
29	Installation, testing and commissioning of pre-wired, LED fitting of all types, complete with all accessories directly on ceiling/wall, including connections with 1.5 sq. mm FRLSH PVC insulated, copper conductor, single core cable and earthing etc. as required.	20	EACH	200.00	4000.00	INR Four Thousand Only
30	ITC of Street Light Luminaire on wall with suitable Medium class GI pipe bent to shape including wiring the pipe, making connections etc. complete as required.	4	EACH	600.00	2400.00	INR Two Thousand Four Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
31	Supply of aluminium conductor XLPE insulated, PVC inner sheathed, armoured power cable of 1.1 KV grade conforming to IS-7098 Part I(1988) amended up to date. 3.5 X 50 sq mm	100	Meter	335.00	33500.00	INR Thirty Three Thousand Five Hundred Only
32	Supply of XLPE insulated, PVC inner sheathed, armoured copper conductor power cable of 1.1 KV grade conforming to IS-7098 Part I(1988) amended up to date. 4 X 6 sq mm	200	Meter	360.00	72000.00	INR Seventy Two Thousand Only
33	Supply of aluminium conductor XLPE insulated, PVC inner sheathed, armoured power cable of 1.1 KV grade conforming to IS-7098 Part I(1988) amended up to date. 4 X 16 sq mm	600	Meter	170.00	102000.00	INR One Lakh Two Thousand Only
34	Supplying and laying of following size HDPE pipe of PE 80 grade PN 8 pressure rating conforming to IS 4984 -2016 along with all accessories complete with fitting and cutting, jointing etc. in the existing trench, complete as required. 63 mm OD	70	Meter	290.00	20300.00	INR Twenty Thousand Three Hundred Only
35	Supplying and laying of following size HDPE pipe of PE 80 grade PN 8 pressure rating conforming to IS 4984 -2016 along with all accessories complete with fitting and cutting, jointing etc. in the existing trench, complete as required. 50 mm OD	800	Meter	240.00	192000.00	INR One Lakh Ninety Two Thousand Only
36	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/META/HDPEL pipe as required. Upto 35 sq. mm	800	Meter	40.00	32000.00	INR Thirty Two Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
37	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/METAL/HDPE pipe as required. Above 35 sq. mm and up to 95 sq. mm	70	Meter	60.00	4200.00	INR Four Thousand Two Hundred Only
38	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 35 sq. mm and upto 95 sq. mm	15	Meter	50.00	750.00	INR Seven Hundred & Fifty Only
39	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	15	Meter	420.00	2250.00	INR Two Thousand Two Hundred & Fifty Only
40	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 3.5x50 sq mm	2.00	Set	190.00	840.00	INR Eight Hundred & Forty Only
41	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 4 core x 6 sq. mm	4	Set	210.00	760.00	INR Seven Hundred & Sixty Only
42	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 4X16 sq mm	50	Set		10500.00	INR Ten Thousand Five Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
43	Supplying and fixing 4 pole, Load Break Switch in Sheet Steel Enclosure of following rating conforms to IEC 947-3 AC-23A, Front operated suitable for 415V, 50Hz AC supply as required. 100 Amps	1	EACH	11900.00	11900.00	INR Eleven Thousand Nine Hundred Only
44	Supplying and fixing Three Phase & Neutral, 200 Amps, 4 Way Busbar chamber suitable for 415Volt 3 phase, 50Hz AC supply fabricated out of sheet steel (CRCA) and epoxy powder coated. The bus bar sections are made of ETP grade copper & tin plated and the bus bar supports are made of DMC. The bus bar chamber shall conforms to IEC-61439-3/IS-8623 & IEC-60529 /IS-2147	1.00	EACH	27500.00	27500.00	INR Twenty Seven Thousand Five Hundred Only
45	Providing and fixing following rating and breaking capacity MCCB with thermomagnetic release and terminal spreaders and rotary handle in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 100 A 25 KA, 4 Pole	1	EACH	9500.00	9500.00	INR Nine Thousand Five Hundred Only
46	Interconnection between existing Four Pole Busbar System/MCCB/Load Break Switch/TPN MCB DB etc. with 4 x 16 sqmm Single Core HRFR PVC Insulated Industrial Grade Copper Conductor (Unsheathed) Flexible Cables, 1100 Volt Conforming to IS 694, copper lugs complete with connections, testing and commissioning etc. as required.	2	EACH	5000.00	10000.00	INR Ten Thousand Only
47	Earthing with copper Earth plate 600mm x 600mm x 3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	2	Set	22000.00	44000.00	INR Forty Four Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
48	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and refilling etc. as required.	10.00	Meter	1850.00	18500.00	INR Eighteen Thousand Five Hundred Only
49	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	20	Meter	1450.00	29000.00	INR Twenty Nine Thousand Only
50	Jointing copper / G.I. tape (with another copper/ G I tape, base of the final or any other metallic object) by riveting / nut bolting, sweating and soldering etc as required.	6	EACH	700.00	4200.00	INR Four Thousand Two Hundred Only
51	Supply, Installation, Testing and Commissioning of 1.5 TR (nominal capacity), High wall mounted, Inverter Split type Air-conditioner with BEE star rating 5, consisting of non-ductable type indoor units (fan coil) with cord less remote control and one number out door unit comprising of compressor, cooling fan, copper condensing coil suitable for operation on single phase, 230 +/- 10% volts, 50 HZ, AC supply including installing the indoor (fan coil) unit and outdoor unit on wall on suitable stand, providing and fixing insulated copper piping (suction and discharge) and electrical connections with flexible copper cable of suitable size as per manufacturer's recommendations, between the indoor and outdoor units up to a length of 3 (three) meters, wrapping the insulated refrigerant line with white wrapping tape, providing drain piping (up to 3 meter length), drilling the hole on wall, making good the opening after installation including first charge of refrigerant etc. complete as required	3.00	EACH	52000.00	156000.00	INR One Lakh Fifty Six Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
52	Supply, Installation, Testing and Commissioning of Voltage stabilizer with initial time delay, high and low voltage cut off suitable for 1.5 TR Inverter type split AC units	3	EACH	4500.00	13500.00	INR Thirteen Thousand Five Hundred Only
53	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm and disposal of surplus excavated soil as directed, within a lead of 50 metres.	228	Cum	600.00	136800.00	INR One Lakh Thirty Six Thousand Eight Hundred Only
54	Supply, Installation, Testing and Commissioning of 3 mtr Hot Dip Galvanized Street Light Pole, Top dia 70mm bottom dia 130 mm with 1 meter single arm on R C C foundation including providing RCC foundation as per Manufacturer's recommendation, opening for cable entry, including foundation bolts, 1 meter single arm, junction box etc. installation of 45 W street light LED fitting (supply of fitting not included) complete as per specification and as required	25	EACH	11000.00	275000.00	INR Two Lakh Seventy Five Thousand Only
55	Supplying and drawing 2 Core x 1.5 sq.mm PVC insulated and PVC Round Sheathed, Multicore Annealed Bare Copper Conductor (flexible) industrial cable for Voltage Grade 1100 Volt, Conforming to IS 694 : 2010 in street light poles from junction box to fittings as required.	100.00	Meter	60.00	6000.00	INR Six Thousand Only
Total in Figures					1567162.00	INR Fifteen Lakh Sixty Seven Thousand One Hundred & Sixty Two Only
Quoted Rate in Words						INR Fifteen Lakh Sixty Seven Thousand One Hundred & Sixty Two Only

Signature Not Verified

Digitally signed by JAYAM J
Date: 2025.04.28 16:46:57 IST
Location: eProcurement System for Central PSUs

राष्ट्रीय महाप्रबंधक (इंजी-वि)
Asst. General Manager (Engg - Elect)