



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.- भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर-05/2024-25/45

दिनांक:- 07/11/2024

सेवा में,

मैसर्स सुभम इलेक्ट्रिकल,
संगम टॉवर, चेम्बर नं.-13,
कोर्ट रोड, सीकर (राजस्थान),
पिन कोड - 332001
ई-मेल- Subhamelectricalsikar@gmail.com

M/s Subham Electrical,
Sangam Tower, Chamber No.13,
Court Road, Sikar (Rajasthan),
Pin Code - 332001,
E-mail: Subhamelectricalsikar@gmail.com

विषय :- प्रोविजन ऑफ 02 नंबरस बोरवेल एट किशनगढ़ एयरपोर्ट, अजमेर । (सबहेड :- इलेक्ट्रिकल वर्क)।

Subject:- Provision of 02 Nos. Borewell at Kishangarh Airport, Ajmer. (SH Electrical Work).

संदर्भ:- दिनांक 18/09/2024 को खोली गई आपकी जेम-बोली (वित्तीय बिड)।

Ref:- Your GeM-Bid (Financial Bid) opened on dated 18/09/2024.

महोदय,

- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल **रु. 7,84,150.00** (अक्षरे सात लाख चौरासी हजार एक सौ पचास रुपये मात्र) (जी.एस.टी रहित) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत **रु. 8,74,154.00** (जी.एस.टी. रहित) से **10.30% नीचे** हैं।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 7,84,150.00** (Rupees Seven Lakh Eighty Four Thousand One Hundred Fifty only) (**Excluding GST**) which is **10.30% below** the estimated cost of **Rs. 8,74,154.00 (Excluding GST)**.

- सहायक महाप्रबंधक (अभियांत्रिकी-विधुत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **02.12.2024** तक सहायक महाप्रबंधक (अभियांत्रिकी-विधुत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हो। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन-ज्युडिशियल) स्टांप पेपर पर बनाया जाएगा तथा स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-E) AAI, Kishangarh Airport, Ajmer by **02.12.2024** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- सुरक्षा राशि **रु. 78,415.00** (अक्षरे अठत्तर हजार चार सौ पन्द्रह रुपये मात्र) को 10 दिन के भीतर जमा करें अन्यथा इस राशि की कटौति संविदा कागजात के पृष्ठ 33 पर खण्ड-1 ए के अनुसार आपके चालू बिलों से की जाएगी।

Security deposit Rs. 78,415.00 (Rupees Seventy Eight Thousand Four Hundred Fifteen only) within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no.- 1A, page no. -33 of tender/contract document.

- आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970, संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध एवं उन्मूलन) अधिनियम 1986, निमार्ण श्रमिकों (सेवा के शर्त और नियमन) अधिनियम 1986 और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जो कि निविदा दस्तावेज के जी.सी.सी. के प्रावधानों का और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970, Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.




भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

5. आपको प्रबन्धक (अभियांत्रिकी-विद्युत), भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।
You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.
6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको **03 माह** का समय प्रदान किया जाता है जो कि इस पत्र के जारी होने की तिथि के दसवें दिन के बाद से प्रभावी होंगी।
Please note that the time allowed for carrying out the work shall be **03 Months** & shall be reckoned from 10th day after the date of issue this letter
7. दोष दायित्व अवधि **एक (01) वर्ष होगी**, जो कार्य के पुरा होने की वास्तविक दर्ज तिथि से प्रभावी होगी।
The defects liability period shall be **One (01) Years**, which will be effective from the actual recorded date of completion of the work.
8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-इन-चार्ज के नाम से किया जाएगा।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
9. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.
10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।
In case any discrepancy is found, then English version will be taken as correct.

Enclosure :- BOQ Page 01 to 02

भवदीय / Yours Faithfully,


सहायक महाप्रबंधक (अभि०-वि०) / Asstt. Gen. Mgr. (Engg-E)
कृते तथा ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:-Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work:-Provision of 02 Nos. Borewell at Kishangarh Airport, Ajmer. (SH:- Electrical Work).

Contract No:-2024_AAI_203864_1

Name of the Bidder/
Bidding Firm /
Company : **RANDHEER SINGH MS SUBHAM ELECTRICALS**

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of 5.5KW/7.5HP (Discharge capacity min 80 LPM at Head of 170 m) multistage, submersible pump set suitable for 200 mm diameter borewell with stainless steel casing, stainless steel shaft & Impeller and built in non return valve coupled with water filled submersible squirrel cage motors suitable for 415v +10% volts, 3phase, 50 Hz, AC supply, sand protection etc. complete as required. (Make :- KSB/Kirloskar/Havells/Crompton or equivalent)	2	Each	42400.00	84800.00	INR Eighty Four Thousand Eight Hundred Only
2	Supply of 50mm dia, medium class GI pipe of standard length with suitable flange having 2 Nos. open cut for accommodation of safety rope & submersible cable, nut, bolts, rubber.gaskets etc. complete as required.	250	Mtr	425.00	106250.00	INR One Lakh Six Thousand Two Hundred & Fifty Only
3	Installation and Lowering of 5.5KW/7.5HP submersible pump set along with 50 mm dia medium class GI pipe of standard length connected with motor & pump set in the borewell, each G.I. Pipe length should be coupled with threaded & welded flanges with 4 nos. suitable size nut bolts, rubber gasket including lowering & clamping submersible cables (clamping with nylon clamp near the flanges) bends, Socket and Testing & Commissioning etc complete as required.	2	Job	4000.00	8000.00	INR Eight Thousand Only
4	Design, fabrication, supply, installation, testing and commissioning of vermin proof, dust proof, outdoor LT starter panel with canopy, made out of 2 mm thick CRCA sheet duly rust inhibited, powder coated paint, lockable arrangement etc. including necessary stand with four legs each of 01 mtr length made of 40mm x 40mm x 5mm MS angle, control wiring, with arrangement of DOL/SD starter suitable for operation of 3 phase 7.5 hp submersible pump set, fixing the panel in cement concrete upto depth of 0.5 mtr & CC up to depth of 100mm all around the panel in 01 mtr etc. and having following accessories. INCOMER 1 Nos. 63A 4P MCCB (Ics=Icu=30 KA) with thermal magnetic release having following items:- 01 set of Digital multifunction meter suitable to measure V, A, KWH, PF etc. with suitable range CTs. 01 Set of Indication Lamps, LED type, R,Y,B and MCCB 'ON', lamps with protection MCBs. 01 Set terminal spreader. BUS BAR 01 Set of 100A TPN Busbars of aluminium alloy. AT OUTGOING 2 Nos. 32A 4P MCCB (Ics=Icu=30 KA) with thermal magnetic release.	3	Job	23000.00	69000.00	INR Sixty Nine Thousand Only
5	Supply of 4C x 25 Sqmm, 1.1 KV grade, Armoured,XLPE insulated, PVC sheathed, Aluminium conductor cable confirming to IS: 7098 (Part -1) 1988 amended upto date.	220	Mtr	215.00	47300.00	INR Forty Seven Thousand Three Hundred Only
6	Supply of 3C x 6 Sqmm PVC insulated & PVC sheathed flat submersible copper conductor cable of 1.1 KV grade confirming to IS : 694/1990 as required.	400	Mtr	175.00	70000.00	INR Seventy Thousand Only
7	Supplying and making end termination with brass compression gland and aluminium lugs for 4C X 25 sqmm, PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	2	Job	200.00	400.00	INR Four Hundred Only
8	Supplying and making end termination with brass compression gland and copper lugs for 3C X 6 Sqmm PVC insulated & PVC sheathed flat submersible copper conductor cable of 1.1 KV grade as required.	2	Job	100.00	200.00	INR Two Hundred Only
9	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of upto 35 sq. mm in the existing RCC/ HUME/ METAL/HDPE/DWC pipe as required.	320	Mtr	10.00	3200.00	INR Three Thousand Two Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
10	Supplying and laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required.	290	Mtr	200.00	58000.00	INR Fifty Eight Thousand Only
11	Cutting/excavation of PCC surface/road with help of cutting/breaking machine depth up to 300 mm etc. complete as required.	1.2	Cum	4000.00	4800.00	INR Four Thousand Eight Hundred Only
12	Making/repairing the of PCC surface/road with Cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) up to minimum depth of 300 mm, curing with water etc complete as required.	1.2	Cum	6000.00	7200.00	INR Seven Thousand Two Hundred Only
13	Design, fabrication, supply, installation, testing and commissioning of vermin proof, dust proof, front operated, cubicle type, outdoor LT feeder panel with canopy, made out of 2 mm thick CRCA sheet duly rust inhibited, powder coated paint, complete with double hinged front door with lockable arrangement etc. including necessary stand with four legs each of 01 mtr length made of 40mm x 40mm x 5mm MS angle, control wiring, fixing the panel in cement concrete upto depth of 0.5 mtr & CC up to depth of 100mm all around the panel in 01 mtr etc. and having following accessories. INCOMER 2 Nos. 125A 4P MCCB (Ics=Icu=30 KA) with thermal magnetic release. Each Incomer shall have one set of the following items: 01 set of Digital multifunction meter suitable to measure V, A, KWH, PF etc. with suitable range CT's. 1 Set of Indication Lamps, LED type, R,Y,B and MCCB 'ON', lamps with protection MCB's and terminal spreader. BUS BAR 1 Set of 300A TPN Busbars of aluminium alloy. BUS COUPLER 1 Nos. 125A 4P MCCB (Ics=Icu=30 KA) with thermal magnetic release and mechanical interlocking. MCCB 'ON', lamps with protection MCB and 01 Set terminal spreader. OUTGOING 4 Nos. 63 A FP MCCB (Ics=Icu=30 KA) with thermal magnetic release. 4 Sets (1 Set for each outgoing) LED type 'ON' Indication Lamps with protection MCBs. 4 Sets of terminal spreader for 63A FP MCCB's.	2	Job	75000.00	150000.00	INR One Lakh Fifty Thousand Only
14	Design, fabrication, supply, installation, testing and commissioning of vermin proof, dust proof, front operated, cubicle type, outdoor LT feeder panel with canopy, made out of 2 mm thick CRCA sheet duly rust inhibited, powder coated paint, complete with double hinged front door with lockable arrangement etc. including necessary stand made of 40mm x 40mm x 5mm MS angle, control wiring, fixing the panel on surface with CC or on wall having following accessories.. INCOMER 2 Nos. 250A 4P MCCB (Ics=Icu=50 KA) with thermal magnetic release. Each Incomer shall have one set of the following items: 01 set of Digital multifunction meter suitable to measure V, A, KWH, PF etc. with suitable range CT's. 1 Set of Indication Lamps, LED type, R,Y,B and MCCB 'ON', lamps with protection MCB's and terminal spreader. BUS BAR 1 Set of 600A TPN Busbars of aluminium alloy. BUS COUPLER 1 Nos. 250A 4P MCCB (Ics=Icu=50 KA) with thermal magnetic release and mechanical interlocking. MCCB 'ON', lamps with protection MCB and terminal spreader OUTGOING 10 Nos. 63 A FP MCCB (Ics=Icu=30 KA) with thermal magnetic release. 10 Sets (1 Set for each outgoing) LED type 'ON' Indication Lamps with protection MCBs. 10 Sets of terminal spreader for 63A FP MCCB's.	1	Job	175000.00	175000.00	INR One Lakh Seventy Five Thousand Only
Total in Figures					784150.00	INR Seven Lakh Eighty Four Thousand One Hundred &
Quoted Rate in Words						INR Seven Lakh Eighty Four Thousand One Hundred & Fifty Only

Signature Not Verified

Digitally signed by TANSUKH

Date: 2024.11.28 11:02:51 IST

Location: eProcurement System for Central PSUs

AGM (E.S.)