



DHOLERA INTERNATIONAL AIRPORT COMPANY LTD.

(A Joint Venture of Airports Authority of India-Government of Gujarat-
National Industrial Corridor Development & Implementation Trust)

CIN : U62100GJ2012SGC068709

REF: - DIACL/GM(P)/DHOLERA/ASR-MSSR/2024-25/50-132

DATE: 22.11.2024

कार्य आदेश / Work Order

सेवा में / To,

मेसर्स सौम्या कंस्ट्रक्शन,
शांतिकुंज, 2nd फ्लोर,
धनलक्ष्मी कॉम्प्लेक्स के पास,
ठक्कर नगर बीआरटीएस बस स्टैंड के सामने,
एन.एच.नं. 8, ठक्करनगर,
अहमदाबाद - 382350
फोन: 9825073718 / 9998155596
ई-मेल:
saumyaconstruction69@gmail.com

M/s Saumya Construction,
Shantikunj, 2nd Floor,
Near Dhanlaxmi Complex,
Opp. Thakkar Nagar BRTS Bus Stand,
N.H.No.8, Thakkarnagar,
Ahmedabad - 382350.
Phone: 9825073718 / 9998155596
Email:saumyaconstruction69@gmail.com

कार्य का नाम: डेवलपमेंट ऑफ न्यू ग्रीनफील्ड एयरपोर्ट एट धोलेरा, अहमदाबाद (गुजरात). फेज 1.
उप शीर्ष: धोलेरा हवाई अड्डा, धोलेरा पर एंटीना टॉवर के साथ एसआर-एमएसएसआर (रडार)
भवन का निर्माण और अन्य संबंधित कार्य.

(निविदा नंबर: 2024_AAI_206523_1)

Name of Work: Development of New Greenfield Airport at Dholera, Ahmedabad (Gujarat). Phase-1

SH: Construction of ASR-MSSR (Radar) building with Antenna Tower and other associated works at Dholera Airport, Dholera.
(Tender ID: 2024_AAI_206523_1)

प्रिय महोदय /Dear Sir(s),

- उपर्युक्त कार्य के लिए आपकी ई-निविदा के अनुसार आपके द्वारा उद्धृत राशि **रुपया 18,98,80,385.00 (रुपया अठ्ठारह करोड़ अठ्ठानवे लाख अस्सी हजार तीन सौ पचासी मात्र) जीएसटी को छोड़कर**, अध्यक्ष, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड (डीआईएसीएल) की ओर से स्वीकार की जाती है जो की निविदा में रखी गयी अनुमानित लागत **रुपया 19.05 करोड़ (जीएसटी को छोड़कर) से 0.33% नीचे** है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Dholera International Airport Company Limited (DIACL), at the amount quoted by you totalling to **INR 18,98,80,385.00 (INR Eighteen Crore Ninety Eight Lakh Eighty Thousand Three Hundred Eighty Five only) Excluding GST** which is **0.33%** below the estimated cost put to tender of **INR 19.05 Crore. (Excluding GST)**

D. M. Dholera

2. उपमहाप्रबंधक (अभि.-सिविल)-IV, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड (डीआईएसीएल), गांधीनगर, इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि अनुबंध करार को पूरा करने एवं हस्ताक्षर करने के लिए आप इस पत्र के जारी होने के 15 दिनों के भीतर उपमहाप्रबंधक (अभि.-सिविल)-IV, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड (डीआईएसीएल), ब्लॉक-1, तीसरी मंजिल, ए2 विंग, कर्मयोगी भवन, सेक्टर 10ए, गांधीनगर-382010, गुजरात के कार्यालय में उपस्थित होने का कष्ट करे। अनुबंध करार **रुपए 300/- (₹: तीन सौ केवल)** मूल्य के गैर-न्यायिक स्टांप पेपर पर निष्पादित किया जाएगा और स्टांप पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Dy. General Manager (Engg-Civil)-IV, Dholera International Airport Company Limited (DIACL), Gandhinagar, shall be the Engineer-in-charge of the work. You are requested to attend the office of Dy.General Manager (Engg-Civil)-IV, Dholera International Airport Company Limited (DIACL), Block-1, 3rd Floor, A2 Wing, Karmayogi Bhavan, Sector 10A, Gandhinagar-382010, Gujarat within 15 days of issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **INR 300/- (INR Three Hundred only)** and the cost of the stamp paper shall be borne by you.

3. आपको संलग्न बीओक्यू के अंतर्गत कार्य आरंभ करने का निर्देश दिया जाता है। कार्य निविदा लिखित नियम व शर्तों के अनुसार किया जाना तय है।

You are directed to start the work as per BOQ attached. The work shall be executed as per terms and conditions of Tender Document.

4. कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर **रुपया 94,94,020.00 (रुपया चौारानबे लाख चौारानबे हजार बीस मात्र)** की राशि प्रतिभूति जमा राशि के रूप में जमा कराये, ऐसा न करने पर निविदा दस्तावेज के अनुबंध की सामान्य शर्तों के, खंड न. 1ए के अनुसार कटौती की जाएगी।

Please deposit an amount of **INR 94,94,020.00 (INR Ninety Four Lakh Ninety Four Thousand Twenty only)** towards security deposit within 15 days from the date of issue of this letter failing which, the same will be deducted as per Clause No. 1A of General Condition of Contract of tender document.

5. इस कार्य आदेश जारी होने के 30 दिनों के भीतर, आप धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर को निविदा दस्तावेज के पृष्ठ संख्या GCC-15 पर खंड संख्या 1 के अनुसार एक अपरिवर्तनीय परफोरमेस गारंटी **रुपया 94,94,020.00 (रुपया चौारानबे लाख चौारानबे हजार बीस मात्र)** बैंक गारंटी के रूप में, राष्ट्रीयकृत / अनुसूचित भारतीय बैंक से लेकिन किसी भी सहकारी या ग्रामीण बैंक से नहीं, निविदा दस्तावेज में संलग्न प्रोफोर्मा में प्रस्तुत करें।


Dy. Gen. Mgr
Dholera

Within 30 days of issue of this work order, you shall submit to Dholera International Airport Company Limited, Gandhinagar, an irrevocable Performance Guarantee as per Clause No. 1 on page no. GCC-15 of tender document, for an amount **INR 94,94,020.00 (INR Ninety Four Lakh Ninety Four Thousand Twenty only)** in the form of Bank Guarantee from a Nationalized/Scheduled Indian Bank but not from any Co-operative or Garmin Bank in proforma appended in the tender document.

6. आपसे अनुरोध है कि आप निविदा दस्तावेज के अनुबंध की शर्तों के अनुसार श्रम अनुबंध (विनियमन एवं उन्मूलन) अधिनियम 1970 और श्रम अनुबंध (विनियमन एवं उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध व नियमन) कानून 1986, भवन और अन्य सन्निर्माण कर्मकार (नियोजन तथा सेवा-शर्त विनियमन) अधिनियम 1996, भवन और अन्य सन्निर्माण कर्मकार कल्याण उपकर अधिनियम, 1996 और न्यूनतम मजदूरी अधिनियम और उसके बाद केंद्र और राज्य सरकारों के नियमों के प्रावधानों का पालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, provisions of the Child Labour (Prohibition and Regulation) Act, 1986, the provisions of the building and other construction workers (Regulation of Employment & Conditions of Service) Act, 1996 and the building and other Construction Workers Welfare Cess Act, 1996 and minimum wages act & rules thereof Central and State Governments as specified in the tender document.

7. आपको निर्देश दिया जाता है कि आप शीघ्रातिशीघ्र वरिष्ठ प्रबंधक (अभि.- सिविल)-II, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर से सम्पर्क करें जोकि आपको कार्यस्थल को सौंपने का प्रबंध करेंगे।

You are also directed to contact Senior Manager (Engg-Civil)-II, Dholera International Airport Company Limited, Gandhinagar, immediately who will arrange to hand over the site to you.

8. कृपया ध्यान दे कि आपको कार्य पूरा करने कि लिए ०६ (छः) महीने का समय प्रदान किया जाता है जोकि इस पत्र के जारी होने के बाद दसवे दिन से प्रारम्भ माना जायेगा।

Please note that the time allowed for carrying out the work shall be 06 (six) Months and same shall be reckoned from the 10th day after the date of issue of this letter.

9. ई-टेंडरिंग प्रक्रिया के दौरान उठाए गए सभी प्री बीड/पोस्ट बीड शुद्धिपत्र, प्रश्न, स्पष्टीकरण आदि और उपरोक्त वर्णित पत्रों सहित उत्तर भी अनुबंध का हिस्सा होंगे।

All Pre bid/Post bid corrigendum, queries, clarifications etc. raised during e-tendering process and replies thereof including the letters referred above shall also form part of the agreement.

Handwritten signature:
Dholera
DMS

10. भविष्य में, अनुबंध के सम्बन्ध में कोई भी पत्राचार, सामान्य रूप से प्रभारी अभियंता को सम्बोधित किया जाना चाहिये।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

11. कृपया इस पत्र की पावती भेजें एवं सलग्न प्रतिलिपि पर हस्ताक्षर करके कार्य की स्वीकृति के प्रमाणस्वरूप अधोहस्ताक्षरी को वापिस भेजें।


Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance of work.

12. यदि कोई विसंगति पायी जाती है तो अंग्रेजी संस्करण को ही सही माना जाएगा ।

In case of any discrepancy is found, then the English version will be considered as correct.

संलग्नक / Enclosure: ऊपर दिए अनुसार / As above.

भवदीय / Yours faithfully,



(राकेश सी. धामणस्कर / **Rakesh C. Dhamanaskar**)

उप महाप्रबंधक (अभि.- सिविल)-IV / Dy.GM (Engg-Civil)-IV

प्रभारी अभियंता / Engineer-In-charge

डीआईएसीएल, गांधीनगर / DIACL, Gandhinagar

अध्यक्ष, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड के लिए व उनकी ओर से

For and on behalf of the Chairman, Dholera International Airport Company Ltd.

प्रतिलिपि / Copy to : संलग्न पत्र के अनुसार

NOO - प्रतिलिपि /Copy to: सूचनार्थ/ For information

1. प्रबंध निदेशक, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर।
2. श्रम आयुक्त, अहमदाबाद।
3. क्षेत्रीय भविष्य निधि आयुक्त , अहमदाबाद।

अंतर विभागीय / Inter Departmental

1. मुख्य प्रचालन अधिकारी, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर ।
2. महाप्रबंधक (अभि.- सिविल), धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर ।
3. मुख्य वित्तीय अधिकारी, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर ।
4. संयुक्त महाप्रबंधक (अभि.- विद्युत), धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर ।
5. उपमहाप्रबंधक (अभि.- सिविल) II धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर ।
6. सहायक महाप्रबंधक (अभि.- विद्युत), धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर।
7. वरिष्ठ प्रबंधक (अभि.- सिविल) I/II, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर।
8. वरिष्ठ प्रबंधक (अभि.- विद्युत) II, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर।
9. कंपनी सचिव, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड, गांधीनगर।
10. करारनामा प्रतिलिपि / कार्यालय प्रतिलिपि ।

(राकेश सी. धामणस्कर / **Rakesh C. Dhamanaskar**)

उप महाप्रबंधक (अभि.- सिविल)-IV/ Dy.GM (Engg-Civil)-IV

प्रभारी अभियंता / Engineer-In-charge

डीआईएसिएल, गांधीनगर / DIACL, Gandhinagar

अध्यक्ष, धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड के लिए व उनकी ओर से

For and on behalf of the Chairman, Dholera International Airport Company Ltd.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg-C), Dholera International Airport Company Limited, Gandhinagar

Name of Work: Development of New Greenfield Airport at Dholera, Ahmedabad (Gujarat). Phase-1. SH: Construction of ASR-MSSR (Radar) building with Antenna Tower and other associated works at Dholera Airport, Dholera.

Contract No: 2024_AAI_206523_1

Name of the
Bidder/ Bidding
Firm / Company
:

SAUMYA CONSTRUCTION

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.50m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. a) All kinds of soil	120.000 ✓	Cum ✓	130.00	15600.00	INR Fifteen Thousand Six Hundred Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.50m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.(a) All kinds of soil	100.000 ✓	Cum ✓	130.00	13000.00	INR Thirteen Thousand Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	100.000 ✓	Cum ✓	100.00	10000.00	INR Ten Thousand Only
4	Supplying and filling in plinth with Fine sand under floors, including watering, ramming, consolidating and dressing complete.	223.000 ✓	Cum ✓	1850.00	412550.00	INR Four Lakh Twelve Thousand Five Hundred & Fifty Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - (a)All work up to plinth level : (i)1:4:8 (1cement : 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)..	90.000 ✓	Cum ✓	5800.00	522000.00	INR Five Lakh Twenty Two Thousand Only
6	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor,etc., up to floor five level, excluding the cost of centering, shuttering and finishing : (a) 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	10.000 ✓	Cum ✓	7200.00	72000.00	INR Seventy Two Thousand Only
7	Centering and shattering including strutting, propping etc. and removal of form for : (i)Foundation footing bases of coloumn, etc for mass concrete.	300.000 ✓	Sqm ✓	650.00	195000.00	INR One Lakh Ninety Five Thousand Only
8	Centering and shuttering including strutting, propping etc. and removal of form for : a) Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	470.000 ✓	Sqm ✓	900.00	423000.00	INR Four Lakh Twenty Three Thousand Only




Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
9	Centering and shattering including strutting, propping etc. and removal of form for : (i) Suspended floors, roofs, landing, balconies and access platform.	1310.000 ✓	Sqm ✓	800.00	1048000.00	INR Ten Lakh Forty Eight Thousand Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : (i) Lintles, beam plinth beams girders, bressumers and cantilevers.	2518.000 ✓	Sqm ✓	800.00	2014400.00	INR Twenty Lakh Fourteen Thousand Four Hundred Only
11	Centering and shuttering including strutting, propping etc. and removal of form for : (i) Columns, pliers, piers, abutments, post and struts.	1453.000 ✓	Sqm ✓	800.00	1162400.00	INR Eleven Lakh Sixty Two Thousand Four Hundred Only
12	Centering and shuttering including strutting, propping etc. and removal of form for : (i) Stairs (excluding landings) except spiral staircases etc..	104.000 ✓	Sqm ✓	800.00	83200.00	INR Eighty Three Thousand Two Hundred Only
13	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc. including cost of de-shuttering and decentering at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured) (a) Suspended floors, roofs, landing, beams and balconies (Plan area to be measured).	1009.000 ✓	Sqm ✓	550.00	554950.00	INR Five Lakh Fifty Four Thousand Nine Hundred & Fifty Only
14	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the Engineer-in-charge; for the following grades of concrete. (i) All works upto plinth level Concrete of M30 grade with minimum cement content of 350 kg /cum Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.	693.000 ✓	Cum ✓	7200.00	4989600.00	INR Forty Nine Lakh Eighty Nine Thousand Six Hundred Only
15	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the Engineer-in-charge; for the following grades of concrete. (i) All works above plinth level upto floor V level Concrete of M30 grade with minimum cement content of 350 kg /cum. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.	658.000 ✓	Cum ✓	8000.00	5264000.00	INR Fifty Two Lakh Sixty Four Thousand Only
16	Extra for R.C.C./ B.M.C/ R.M.C. work above floor V level for each four floors or part thereof.	50.000 ✓	Cum ✓	450.00	22500.00	INR Twenty Two Thousand Five Hundred Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (i)Thermo- Mechanically Treated bars of grade Fe-500D or more	84000.000 ✓	Kg ✓	79.00	6636000.00	INR Sixty Six Lakh Thirty Six Thousand Only
18	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. (i)Thermo- Mechanically Treated bars of grade Fe-500 D or more.	90000.000 ✓	Kg	80.00	7200000.00	INR Seventy Two Lakh Only
19	Brick work with common burnt clay F.P.S. bricks (non-modular) of class designation 50 in foundation and plinth in : (i)Cement mortar 1:6 (1 cement : 6 coarse sand)	111.000 ✓	Cum ✓	6800.00	754800.00	INR Seven Lakh Fifty Four Thousand Eight Hundred Only
20	Brick work with common burnt clay F.P.S. bricks (non-modular) of class designation 50 in superstructure above plinth level upto floor five level in all shapes and sizes in : (i)Cement mortar 1:6 (1 cement : 6 coarse sand)	483.000 ✓	Cum ✓	7200.00	3477600.00	INR Thirty Four Lakh Seventy Seven Thousand Six Hundred Only
21	Half brick masonry with 7cm thick common burnt clay FPS(non-modular) bricks of class designation 50 in superstructure above plinth. in : (i)Cement mortar 1:4 (1 Cement : 4 coarse sand)	658.000 ✓	Sqm ✓	1100.00	723800.00	INR Seven Lakh Twenty Three Thousand Eight Hundred Only
22	Extra for providing and placing in position 2 Nos. 6mm dia. M.S.bars at every third course of half brick masonry (with F.P.S. bricks).	658.000 ✓	Sqm	150.00	98700.00	INR Ninety Eight Thousand Seven Hundred Only
23	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position : (i)Sal wood	1.500 ✓	Cum ✓	120000.00	180000.00	INR One Lakh Eighty Thousand Only
24	Providing and fixing ISI marked flush door shutters decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. (i)35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	33.000 ✓	Sqm ✓	5500.00	181500.00	INR One Lakh Eighty One Thousand Five Hundred Only
25	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete : (i)300x16 mm	31.000 ✓	Each ✓	250.00	7750.00	INR Seven Thousand Seven Hundred & Fifty Only
26	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete (a) 250x10 mm	31.000 ✓	Each ✓	250.00	7750.00	INR Seven Thousand Seven Hundred & Fifty Only
27	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : a) 125 mm	62.000 ✓	Each ✓	250.00	15500.00	INR Fifteen Thousand Five Hundred Only

22/11/24
Dhruv

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
28	Providing and fixing aluminium hanging floor door stopper ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc. complete.(i)Single rubber stopper	25.000 ✓	Each ✓	250.00	6250.00	INR Six Thousand Two Hundred & Fifty Only
29	Providing and fixing IS : 3564 marked Aluminium die cast body tubular type universal hydraulic door closer, (having brand logo embossed on the body ,door weight upto 35Kg and door width upto 1.0m) with necessary accessories and screws etc. complete.	25.000 ✓	Each	1800.00	45000.00	INR Forty Five Thousand Only
30	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. all complete.(a)Fixed to openings / wooden frames with rawl plugs (designation 10 No.) etc., all complete	720.000 ✓	Kg ✓	120.00	86400.00	INR Eighty Six Thousand Four Hundred Only
31	Steel work welded in built up sections/framed work including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc.as required.(i) In gratings, frames, guard bar, ladders, railings, brackets, gates & similar works.(using various type MS solid ,plates,flats,IS sections,hollow tube sections etc.)	1800.000 ✓	Kg ✓	130.00	234000.00	INR Two Lakh Thirty Four Thousand Only
32	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 — part 1 and M.S. top cover of required thickness for rolling shutters. (i)80x1.20 mm M.S. laths with 1.20 mm thick top cover.	32.000 ✓	Sqm ✓	6500.00	208000.00	INR Two Lakh Eight Thousand Only
33	Extra for providing mechanical device chain and crank operation for operating rolling shutters.(i)Exceeding 10.00 sqm and upto 16.80 sqm in the area ✓	32.000 ✓	Sqm ✓	1200.00	38400.00	INR Thirty Eight Thousand Four Hundred Only
34	Providing and fixing ball bearing for rolling shutters.	6.000 ✓	Each ✓	1200.00	7200.00	INR Seven Thousand Two Hundred Only
35	Extra for providing grilled rolling shutters manufactured out of 8 mm dia M.S. bar instead of laths as per design approved by Engineer-in- charge, (area of grill to be measured).	6.000 ✓	Sqm ✓	1200.00	7200.00	INR Seven Thousand Two Hundred Only
36	52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, .hardening compound mixed @ 2 litre per 50kg of cement or as per manufacturers specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	300.000 ✓	Sqm ✓	390.00	117000.00	INR One Lakh Seventeen Thousand Only
37	Cement plaster skirting (upto 30 cm height) with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement. (i)18 mm thick	15.000 ✓	Sqm ✓	250.00	3750.00	INR Three Thousand Seven Hundred & Fifty Only
38	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : (a) 25 mm thick.	90.000 ✓	Sqm ✓	1450.00	130500.00	INR One Lakh Thirty Thousand Five Hundred Only



Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
39	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand' and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	31.000 ✓	Sqm ✓	1450.00	44950.00	INR Forty Four Thousand Nine Hundred & Fifty Only
40	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : IS 622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.(a) Size of Tile 600x600 mm or as required.	470.000 ✓	Sqm ✓	1150.00	540500.00	INR Five Lakh Forty Thousand Five Hundred Only
41	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. (i) Size of Tile 600x600 mm or as required.	145.000 ✓	Sqm ✓	1200.00	174000.00	INR One Lakh Seventy Four Thousand Only
42	Providing and fixing removable raised/false access flooring with system and its components of approved make for different plenum height with possible height adjustment upto 50 mm, comprising of modular load bearing floor panels supported on G.I. rectangular stinger frame work and G.I. Pedestal etc. all complete, as per the architectural drawings, as specified and as directed by Engineer-in-charge consisting of : a) Providing at required spacing to form modular framework, pedestals made out of GI tube of thickness minimum 2 mm and 25 mm outer diameter, fully welded on to the G.I. Base plate of size 100mmx100mmx3mm at the bottom of the pedestal tube, G.I. pedestal head of size 75mmx75mmx3.5 mm welded with GI fully threaded stud 16mm outer diameter with two GI Check nuts screwed on the stud for level adjustment upto 50mm, locking and stabilizing the pedestal head in position at the required level. The pedestals shall be fixed to the subfloor (base) through base plate using epoxy based adhesive of approved make or the machine screw with rawl plug.b) Stringers system in all steel construction hot dipped galvanized of rectangular size 570x20x30x0.80mm thick having holes at both ends for securing the stringers on to the pedestal head using fully threaded screws ensuring maximum lateral stability in all directions, the grid formed by the pedestal and stringer assembly shall receive the floor panel, this system shall provide adequate solid, rigid support for access floor panel, the system shall provide a minimum clear uninterrupted clearance between the bottom of the floor for electrical conduits and wiring etc. all complete as per the architectural drawings, as specified and as directed by the Engineer-in-charge. c) Providing and fixing Access Floor panel of 600x600x32 mm medium grade Filled Steel anti static high pressure Lamination of 800H grade (FS800H). Access Floor panel shall be steel welded construction with an enclosed bottom pan with uniform pattern of 64 hemispherical cones. The top and bottom plates of Steel Gauges: top 0.6 mm and bottom 0.7 mm fused spot welded together (minimum 64 welds in each dome and 20 welds along each flange). The panel should be Corroresist epoxy coated for lifetime rust protection and cavity formed by the top and bottom plate is filled with Pyrogrip noncombustible Portland cementitious core mixed with lightweight foaming compound. The access floor shall be factory finished with Anti-static High Pressure laminate with Non Warp technology upto 1mm thickness for superior adhesion and Surface flatness within 0.75mm.The panel is to withstand a Concentrated Load of 363 kgs applied on area 25mm x 25mm without collapse in the centre of the panel which is placed on four steel blocks. The panel will withstand and Uniformly Distributed Load (UDL) minimum 1250 kg/sqm and an impact load of 50kg all complete as per the approved manufacturers specification and as per the direction of Engineer-in-charge. All specification must be printed on the side of the panel to ensure the quality of the product,(i) 300 mm Finished Floor Height (FFH).	140.000 ✓	Sqm ✓	4800.00	672000.00	INR Six Lakh Seventy Two Thousand Only
43	Providing and fixing 18mm thick mirror polished, machine cut for kitchen platforms, vanity counters facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 Cement : 4 coarse sand) with joints treated with white cement ,mixed with matching pigment, epoxy touch ups, including rubbing ,curing etc. complete at all levels. (i)Granite Black (Over 0.5 sqm but upto 1.0 sqm)	20.000 ✓	Sqm ✓	5500.00	110000.00	INR One Lakh Ten Thousand Only

24/11/24
Dumus

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
44	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep.(e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. "All above operations to be done in order and as directed and specified by the Engineer-in-Charge":(i)With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	752.000 ✓	Sqm ✓	600.00	451200.00	INR Four Lakh Fifty One Thousand Two Hundred Only
45	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1mx1mx400micron, finished with 12mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	28.000 ✓	Each ✓	300.00	8400.00	INR Eight Thousand Four Hundred Only
46	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.(i) Single socketed pipes.(a) 110 mm diameter	260.000 ✓	Mtr ✓	650.00	169000.00	INR One Lakh Sixty Nine Thousand Only
47	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i)Single tee without door.(a)110x110x110 mm	28.000 ✓	Each ✓	650.00	18200.00	INR Eighteen Thousand Two Hundred Only
48	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i)Shoe (Plain). (a)110 mm Shoe.	28.000 ✓	Each ✓	650.00	18200.00	INR Eighteen Thousand Two Hundred Only

22/11/24
Dymus

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
49	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : (i)12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) : 2011 (Board with BIS certification marks)	236.000 ✓	Sqm ✓	1100.00	259600.00	INR Two Lakh Fifty Nine Thousand Six Hundred Only
50	Providing and fixing thermal insulation of ceiling (under deck insulation) with Resin Bonded Rockwool conforming to IS: 8183,density 48 kg/ m3, 50 mm thick, wrapped in 200 G Virgin Polythene bags fixed to ceiling with metallic cleats (50x50x3 mm) @ 60 cm and wire mesh of 12.5mm x 24 gauge wire mesh, for top most ceiling of building.	236.000 ✓	Sqm ✓	350.00	82600.00	INR Eighty Two Thousand Six Hundred Only
51	12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	2418.000 ✓	Sqm ✓	470.00	1136460.00	INR Eleven Lakh Thirty Six Thousand Four Hundred & Sixty Only
52	15 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	2654.000 ✓	Sqm ✓	480.00	1273920.00	INR Twelve Lakh Seventy Three Thousand Nine Hundred & Twenty Only
53	6 mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	952.000 ✓	Sqm ✓	450.00	428400.00	INR Four Lakh Twenty Eight Thousand Four Hundred Only
54	White washing with lime to give an even shade: New work (three or more coats)	752.000 ✓	Sqm ✓	65.00	48880.00	INR Forty Eight Thousand Eight Hundred & Eighty Only
55	Finishing walls with Acrylic Smooth exterior emulsion paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	1950.000 ✓	Sqm ✓	125.00	243750.00	INR Two Lakh Forty Three Thousand Seven Hundred & Fifty Only
56	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. : (i)Two coats	2654.000 ✓	Sqm ✓	140.00	371560.00	INR Three Lakh Seventy One Thousand Five Hundred & Sixty Only
57	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture..	257.000 ✓	Sqm ✓	150.00	38550.00	INR Thirty Eight Thousand Five Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
58	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material etc. complete in all respect in accordance with Specification for Road and Bridge Works, Ministry of Road Transport & Highways, Section no 200, Section 201 and as per the directions of Engineer In charge.	30080.000 ✓	Sqm ✓	3.00	90240.00	INR Ninety Thousand Two Hundred & Forty Only
59	Construction of embankment with approved soil/earth material (having soil parameters (a).Free Swell Index is less than 15 % (Test as per IS-2911 Part 3-1980) and, (b).Soaked CBR is more than 5 (Test as per IS-2720 Part 16) and (c).Unconfined Compressive strength is more than 1.5 Kg/cm2 (Test as per IS-2720 Part- 10) for the sample compacted at 97% of the Maximum Dry Density of heavy compaction (Modified proctor)) obtained from approved identified borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2 and as per the directions of Engineer Incharge..	642000.000 ✓	Cum ✓	158.00	101436000.00	INR Ten Crore Fourteen Lakh Thirty Six Thousand Only
60	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge. (Note:Length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	27.000 ✓	Cum ✓	7500.00	202500.00	INR Two Lakh Two Thousand Five Hundred Only
61	Providing and laying Pavement Quality Concrete (PQC) produced in a batching and mixing plant having a Characteristic flexural strength i.e. flexural strength of 4.1 MPa at 28 days using Ordinary Portland cement of 43/53 grade or Portland Pozzolana Cement or Portland Slag cement conforming as per relevant IS codes, to be mixed at site, with 0.5% Super plasticizer by mass of cementitious material, fine aggregate, graded stone aggregates of 40 mm nominal size in appropriate proportion as per specification and job mix formula, laid in panels as per drawings/design as approved by the Engineer-In-Charge using Slip Form Paver or Fixed form paver including anti friction layer, joint filler board, making necessary provision for expansion, dummy and construction joint including filling with Polysulphide sealant of approved make, curing and making profile, complete as per direction of Engineer-in-Charge and specifications. The item for execution shall include all operations making pavement for intended use but not limited to following: (i) Polyethylene sheet (White in color) of thickness 400 micron conforming to IS: 2508 with 6mm thick fine sand layer. (ii) Providing and laying in position for expansion joint, 25mm thick pre-cut Synthetic joint filler board of approved make conforming to IS:1838(part 3)-2011, 45 mm from top (to be removed at the time of filling of Polysulphide sealant). (iii) Mechanically cutting dummy joints 3mm wide x 1/3rd thickness of slab which is subsequently widened to 10mm for the top 25mm depth and construction joints 10mm wide x 25mm deep as per specification. (iv) Providing and laying in position Polysulphide sealant of approved make conforming to BS-5212-1990 or IS: 11433-1995 in expansion/ construction / dummy joints including rounding off edges, applying 2 coats of approved primer compatible with the brand of Polysulphide and preparing the surface and applying masking tape along the edge of joint to prevent accidental spillage of sealant on top surface and to give neat finish to the sealant and removing the masking tape after application of sealant etc. as per the details below: (a) Expansion Joints of size 25 mm wide and 10 mm deep over 30mm dia expanded closed-cell Polyethylene foam back-up/backer rod of minimum density 22 Kg/Cum, as per manufacturer's specifications and sketch at Appendix-'A'. (b) Construction Joints of size 10 mm wide and 10 mm deep over 12mm dia expanded closed-cell Polyethylene foam back-up/backer rod of minimum density 22 Kg/Cum, as per manufacturer's specifications and sketch at Appendix-'A'. (c) Dummy Joints of size 10 mm wide and 10 mm deep over 12 mm dia expanded closed-cell Polyethylene foam back-up/backer rod of minimum density 22 Kg/Cum, as per manufacturer's specifications and sketch at Appendix-'A'. (v) Making profile as per DGCA CAR, panel drawing showing dummy, construction, expansion joints location. Note:-(i) Areas inaccessible to paving equipment shall be constructed by manual/hand guided method. Areas in which manual/hand guided methods of construction become indispensable shall be got approved by the Engineer-in-Charge in writing in advance. (ii) The quantity of cement, type of cement and super plasticizer for one Cum. Of finished concrete specified are for tendering purpose only. The contractor shall quote his rates assuming quantity of OPC Cement as 360 Kg/Cum or 400 Kg of Portland Pozzolana Cement/ Portland Slag cement. In addition, if the actual quantity of cement & super plasticizer required as per laboratory mix design varies from the quantity assumed above, necessary cost adjustment for deviation in the quantity of cement and super plasticizer as per mix design, if any, shall be done as per the rate of cement and super plasticizer in actual supply voucher from manufacturer/authorized dealer at the time of execution. In the case of authorized distributor, the rate may be authenticated by the manufacturer. The rate of cement and super plasticizer exclusive of GST shall only be considered for payment.	1963.000 ✓	Cum ✓	8000.00	15704000.00	INR One Crore Fifty Seven Lakh Four Thousand Only

Q
22/11/24
Dumma

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
62	Preparation of granular sub-base by providing close graded material, conforming to specifications mixing in a mechanical mix plant at OMC, carriage of mixed material by mechanical transport to work site, for all leads and lifts, spreading in uniform layers of specified thickness with mechanical means including neatly leveling & dressing on prepared surface and compacting with vibratory power roller to achieve the desired density, complete and as per direction of Engineer-in-charge.	1612.000 ✓	Cum ✓	2200.00	3546400.00	INR Thirty Five Lakh Forty Six Thousand Four Hundred Only
63	Construction of subgrade with mixture stones/rock dust and with earth in required proportion but not less than 75% stones/rock dust and 25% of earth to meet out the CBR (min. field soaked CBR not less than 20), MDD and other requirements of subgrade layer as per MoRTH specification including preparing the surface to the required camber, rolling, testing as per required frequency, finishing etc. complete in all respect as per direction of Engineer-In-Charge.	6400.000 ✓	Cum ✓	1700.00	10880000.00	INR One Crore Eight Lakh Eighty Thousand Only
64	Boring, providing and installation bored cast-in-situ reinforced cement concrete piles of grade M-25 of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by percussion drilling using Direct mud circulation (DMC) or Bailer and chisel technique by tripod and mechanical Winch Machine all complete, including removal of excavated earth with all its lifts and leads (length of pile for payment shall be measured up to bottom of pile cap). (i) 600 mm dia piles	864.000 ✓	Mtrs ✓	3500.00	3024000.00	INR Thirty Lakh Twenty Four Thousand Only
65	Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform by Kentledge/Anchor piles method and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer in-charge. Note: 1. Initial and Routine Load Test shall not be carried out by Dynamic method of testing. Note: 2. Testing agency shall submit the design of loading platform for the approval of Engineer-in-charge. (i) Single pile above 50 tonne and upto 100 tonne Safe capacity. (a) Initial test (Test Load 2.5 times the Safe capacity)	2.000 ✓	Each ✓	100000.00	200000.00	INR Two Lakh Only
66	Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform by Kentledge/Anchor piles method and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer in-charge. Note: 1. Initial and Routine Load Test shall not be carried out by Dynamic method of testing. Note: 2. Testing agency shall submit the design of loading platform for the approval of Engineer-in-charge. (i) Single pile above 50 tonne and upto 100 tonne Safe capacity.. (a) Routine test (Test Load 1.5 times the Safe capacity)	2.000 ✓	Each ✓	100000.00	200000.00	INR Two Lakh Only

D. Miller Duran


Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
67	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : (i) For fixed portion..(a)Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	891.000 ✓	Kg ✓	550.00	490050.00	INR Four Lakh Ninety Thousand & Fifty Only
68	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : (i) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). (a)Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	760.000 ✓	Kg ✓	600.00	456000.00	INR Four Lakh Fifty Six Thousand Only
69	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. (i) Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side..	37.000 ✓	Sqm ✓	1200.00	44400.00	INR Forty Four Thousand Four Hundred Only
70	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): (i)With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	87.000 ✓	Sqm ✓	1400.00	121800.00	INR One Lakh Twenty One Thousand Eight Hundred Only
71	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete. (i)Upto 5 mm depth and 5 mm width...	312.000 ✓	Mtr ✓	120.00	37440.00	INR Thirty Seven Thousand Four Hundred & Forty Only
72	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in-charge..(i) Anodized (AC 15) aluminium..	30.000 ✓	Each ✓	1500.00	45000.00	INR Forty Five Thousand Only

D. Miley Dinesh

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
73	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 63IS, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg., for doors, including cost of cutting floors , embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. (a) With stainless steel cover plate minimum 1.25 mm thickness.	10.000 ✓	Each ✓	4500.00	45000.00	INR Forty Five Thousand Only
74	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: (i) White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	3.000 ✓	Each ✓	7500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
75	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : (i)W.C. pan with ISI marked black solid plastic seat and lid..	3.000 ✓	Each ✓	7500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
76	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass including painting of fittings and cutting and making good the walls and floors wherever required : (i)Single half stall urinal with 5 litre P.V.C. automatic flushing cistern.	6.000 ✓	Each ✓	7500.00	45000.00	INR Forty Five Thousand Only
77	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : (i)White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap.	6.000 ✓	Each ✓	6500.00	39000.00	INR Thirty Nine Thousand Only
78	Providing and fixing toilet paper holder : a) C.P. Brass	6.000 ✓	Each ✓	1500.00	9000.00	INR Nine Thousand Only
79	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - (i)Exposed on wall. :(a)15 mm dia. nominal bore	30.000 ✓	Mtr ✓	600.00	18000.00	INR Eighteen Thousand Only
80	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - (i)Exposed on wall. :(a)20 mm dia. nominal bore	30.000 ✓	Mtr ✓	600.00	18000.00	INR Eighteen Thousand Only
81	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - (i)Exposed on wall. :(a)40 mm dia. nominal bore	40.000 ✓	Mtr ✓	850.00	34000.00	INR Thirty Four Thousand Only
82	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps i/c making good the walls etc. concealed pipe including painting with anti corrosive bitumastic paint, cutting chases and making good the wall: (i)15 mm dia nominal bore	30.000 ✓	Mtr ✓	600.00	18000.00	INR Eighteen Thousand Only
83	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.i) External work a) 40 mm dia. nominal bore	1400.000 ✓	Mtr ✓	950.00	1330000.00	INR Thirteen Lakh Thirty Thousand Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
95	Preparation and submission of detailed architectural and structural design of proposed (i)ASR-MSSR (Radar) Building (apprx height 6.00m & antenna tower apprx.height of 25.00 Metre approximate height,Mini Substation cum stores building of of min 5.0m height , all MEP services drawings & design, drawing for RCC structure ,drainage connectivity including conducting necessary soil tests etc. complete. Rate of items including following stages. 1. Prepartion of Preliminary drawings ,working out the quantity of RCC & Reinforcement, BBS based on soil investigation report etc.for proposed the buildings to be submitted for approval of Engineer-in-charge. 2. After finalization of prelimnary drawings. Submission of vetted " Good for construction" drawings in six sets & soft copy . 3. Structural analysis & design of all buildings as specified including reinforcement detailing etc with relevent IS codes with uptodate corrections. 4.All structural drawings & designs of buildings along with design report shall be vetted by any NIT/IIT Engg college and to be submitted in 6 sets,soil reports(min 03nos copies) along with soft copy. 5.Consultant to be appointed with prior approval of Engineer-in-Charge i.e. registered architect with council of architecture.Visit of consultant during each stage & as and when desired by EIC during the time of execution of work.	1.000 ✓	per Job	1000000.00	1000000.00	INR Ten Lakh Only
96	Providing and Fixing Non-Reflective Film of make Garware or equivalent (thickness not less than 50 microns) on glass including cleaning the surface as required as per direction of Engineer Incharge.	50.000 ✓	Sqm ✓	600.00	30000.00	INR Thirty Thousand Only
97	Providing and laying dry lean cement concrete with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not exceed 15:1, aggregate gradation after blending to be as per specification, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 MPa at 7 days, mixed in a batching plant as per mix design, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonne vibratory roller, finishing and curing etc complete as per specification and direction of the Engineer-Incharge.	1058.000 ✓	Cum ✓	5500.00	5819000.00	INR Fifty Eight Lakh Nineteen Thousand Only
98	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required - Group C	82 ✓	Point ✓	2200.00	180400.00	INR One Lakh Eighty Thousand Four Hundred Only
99	Wiring for group controlled (looped) light point/ fan point/exhaust fan point/call bell point (without independent switch etc.) with 1.5 sqmm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit and earthing the point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable etc as required. - Group C ✓	40 ✓	Point ✓	2050.00	82000.00	INR Eighty Two Thousand Only
100	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit along with 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	180 ✓	Meter ✓	850.00	153000.00	INR One Lakh Fifty Three Thousand Only
101	Wiring for light/ power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit along with 2 Nos 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	125 ✓	Meter ✓	1050.00	131250.00	INR One Lakh Thirty One Thousand Two Hundred & Fifty Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
102	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.					
102.01	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	65 ✓	Meter ✓	145.00	9425.00	INR Nine Thousand Four Hundred & Twenty Five Only
102.02	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	270 ✓	Meter ✓	215.00	58050.00	INR Fifty Eight Thousand & Fifty Only
102.03	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	100 ✓	Meter ✓	425.00	42500.00	INR Forty Two Thousand Five Hundred Only
102.04	2 X 6 sq. mm + 1 X 6 sq. mm earth wire	270 ✓	Meter ✓	600.00	162000.00	INR One Lakh Sixty Two Thousand Only
102.05	2 X 10 sq. mm + 1 X 6 sq. mm earth wire	50 ✓	Meter ✓	450.00	22500.00	INR Twenty Two Thousand Five Hundred Only
103	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					
103.01	3 x 1.5 sq. mm	50 ✓	Meter ✓	145.00	7250.00	INR Seven Thousand Two Hundred & Fifty Only
103.02	3 x 2.5 sq. mm	40 ✓	Meter ✓	225.00	9000.00	INR Nine Thousand Only
103.03	3 x 4 sq. mm	30 ✓	Meter ✓	350.00	10500.00	INR Ten Thousand Five Hundred Only
103.04	3 x 6 sq. mm	30 ✓	Meter ✓	600.00	18000.00	INR Eighteen Thousand Only
104	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmoured telephone cable in the existing surface/ recessed steel/ PVC conduit as required - 4 Pair	100 ✓	Meter ✓	80.00	8000.00	INR Eight Thousand Only
105	Supplying and drawing of UTP-4 pair CAT-6 24-AWG LAN cable in the existing surface/ recessed steel / PVC conduit as required. - 1 Run of Cable	90 ✓	Meter ✓	85.00	7650.00	INR Seven Thousand Six Hundred & Fifty Only
106	Supplying and fixing of following sizes of steel conduit along with accessories in surface/ recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required					
106.01	20 mm	50 ✓	Meter ✓	300.00	15000.00	INR Fifteen Thousand Only
106.02	25 mm	50 ✓	Meter ✓	350.00	17500.00	INR Seventeen Thousand Five Hundred Only
107	Supplying and fixing 3 pin, 5A ceiling rose on the existing junction box/ wooden block including connection etc as required.	15 ✓	Each ✓	250.00	3750.00	INR Three Thousand Seven Hundred & Fifty Only
108	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (The make and Model should be same as those for BOQ item no. 1)					
108.01	5/6 A Switch	27 ✓	Each ✓	250.00	6750.00	INR Six Thousand Seven Hundred & Fifty Only



Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
108.02	15/16 A switch	29 ✓	Each ✓	350.00	10150.00	INR Ten Thousand One Hundred & Fifty Only
108.03	3 pin 5/6 A socket outlet	27 ✓	Each ✓	450.00	12150.00	INR Twelve Thousand One Hundred & Fifty Only
108.04	6 pin 15/16 A socket outlet	29 ✓	Each ✓	650.00	18850.00	INR Eighteen Thousand Eight Hundred & Fifty Only
108.05	Telephone socket outlet	6 ✓	Each ✓	325.00	1950.00	INR One Thousand Nine Hundred & Fifty Only
108.06	Bell Push	3 ✓	Each ✓	220.00	660.00	INR Six Hundred & Sixty Only
109	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate as required. (The make and Model should be same as those for BOQ item no. 1)	16 ✓	Each ✓	1400.00	22400.00	INR Twenty Two Thousand Four Hundred Only
110	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.					
110.01	1 or 2 Module (75mmX75 mm)	20 ✓	Each ✓	650.00	13000.00	INR Thirteen Thousand Only
110.02	3 Module (100 mmX75 mm)	10 ✓	Each ✓	700.00	7000.00	INR Seven Thousand Only
110.03	4 Module (125mmX75mm)	10 ✓	Each ✓	700.00	7000.00	INR Seven Thousand Only
110.04	6 Module (200mmX75mm)	10 ✓	Each ✓	800.00	8000.00	INR Eight Thousand Only
110.05	8 Module (125mmX125mm)	5 ✓	Each ✓	900.00	4500.00	INR Four Thousand Five Hundred Only
110.06	12 Module (200mmX150mm)	5 ✓	Each ✓	900.00	4500.00	INR Four Thousand Five Hundred Only
111	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connection etc. as required.	6 ✓	Each ✓	1900.00	11400.00	INR Eleven Thousand Four Hundred Only
112	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 2 nos, 3 pin 5/6 A modular socket outlets and 2 nos 5/6 A modular switches, connection etc. as required. (For light plugs to be use in non residential buildings)	6 ✓	Each ✓	2600.00	15600.00	INR Fifteen Thousand Six Hundred Only
113 ✓	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connection etc. as required.	12 ✓	Each ✓	2800.00	33600.00	INR Thirty Three Thousand Six Hundred Only
114	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess i/c providing and fixing 25 A modular socket outlet and 25 A modular SP MCB, "C" curve including connection, painting etc. as required.	15 ✓	Each ✓	3500.00	52500.00	INR Fifty Two Thousand Five Hundred Only
115	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, IP43 MCB distribution board, 415 volts, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 6 way (4 + 18), Double door	2 ✓	Each ✓	25000.00	50000.00	INR Fifty Thousand Only


 M. M. M. M. M.
 D. M. M.

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
116	Supplying and fixing of following ways surface/recess mounting, vertical type, 415 volts, IP43 TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 As tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required. (Note: Vertical type MCB TPDB is normally used where 3 phase outlets are required.) - 8 way (4 + 24), Double door	2 ✓	Each	26000.00	52000.00	INR Fifty Two Thousand Only
117	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
117.01	Single pole	66 ✓	Each	350.00	23100.00	INR Twenty Three Thousand One Hundred Only
117.02	Triple Pole	6 ✓	Each	2100.00	12600.00	INR Twelve Thousand Six Hundred Only
118	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, 'A' type (or 'Adi' type) residual current circuit breaker (RCCB) with Added immunity against pulsating DC currents, having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
118.01	40A	2 ✓	Each	3000.00	6000.00	INR Six Thousand Only
118.02	63A	2 ✓	Each	3000.00	6000.00	INR Six Thousand Only
Total in Figures					189880385.00	INR Eighteen Crore Ninety Eight Lakh Eighty Thousand Three Hundred & Eighty Five Only
Quoted Rate in Words		INR Eighteen Crore Ninety Eight Lakh Eighty Thousand Three Hundred & Eighty Five Only				


DGM US
21/11/2024

उप महाप्रबंधक (अभि.-सिविल)
Dy. General Manager (Engg-Civil)
धोलेरा इंटरनेशनल एयरपोर्ट कंपनी लिमिटेड
Dholera International Airport Company Ltd.
(A Joint Venture of AAI-GOG-NICDIT)
गांधीनगर/Gandhinagar-382010