



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या: भा.वि.प्रा./ राजमुंदरी/ एफएसओएचटी और स्टेटिकटैंक /2024-25 /1246-1249
Ref.No. AAI/RJY/Engg-Civil/ FSOHT&STATICTANK /2024-25

दिनांक:22.10.2024
Date:22.10.2024

सेवा में
श्री कार्तिकेय इंटरप्राइजेज,
9-49/1, सूर्यराव पेटा,
एयरटेल टावर के पास, वेमागिरी,
पूर्वी गोदावरी,
आंध्र प्रदेश - 533 125

To
SRI KARTHIKEYA ENTERPRISES,
9-49/1, SURYARAO PETA,
NEAR AIRTEL TOWER, VEMAGIRI,
EAST GODAVARI,
ANDHRA PRADESH - 533 125.

कार्य का नाम : राजमुंदरी हवाई अड्डे पर अग्निशमन प्रणाली की श्रेणी VI के लिए ओवरहेड वॉटर टैंक, स्टेटिक टैंक का निर्माण और ओएचटी, स्टेटिक टैंक और पूर्व-निर्धारित बिंदु के आसपास हार्ड स्टैंड का प्रावधान।

Name of Work: Construction Overhead Water Tank, Static Tank and provision of Hard stand around OHT, Static Tank & Pre-Determined Point for Category VI of Firefighting system at Rajahmundry Airport.

संदर्भ : ई-निविदा क्रमांक 2024_AAI_206564_1 के संदर्भ में विषयागत कार्य हेतु 03.10.2024 को खोली गई आपकी वित्तीय निविदा।

Ref : Your financial bid for the subject work in reference to Tender ID - 2024_AAI_206564_1, opened on 03.10.2024.

महोदय/Dear Sir,

- उपर्युक्त कार्य के लिए आपका ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत कुल रु. 52,42,865.00 (रुपये बावन लाख बयालीस हजार आठ सौ पैंसठ मात्र) (जीएसटी को छोड़कर) की दर पर स्वीकार किया जाता है जो कि निविदा में रखी गई अनुमानित लागत रु.63,35,894.00 से 17.25% कम है।

Your E-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the items rate quoted by you totalling to Rs. 52,42,865.00 (Rupees Fifty two lakh forty two thousand eight hundred sixty five only) (Excl. GST) which is 17.25% below estimated cost put to tender of Rs. 63,35,894.00.

- सहायक महाप्रबंधक (इंजीनियरिंग-सिविल), एएआई राजमुंदरी हवाई अड्डा कार्य का प्रभारी इंजीनियर होगा। आपसे अनुरोध है कि समझौते पर हस्ताक्षर करने और पूरा करने के लिए 05.11.2024 तक सहायक महाप्रबंधक (इंजीनियरिंग-सिविल), एएआई, राजमुंदरी हवाई अड्डे के कार्यालय में उपस्थित हों। अनुबंध 100/- रुपये मूल्य के गैर-न्यायिक स्टांप पेपर पर निष्पादित किया जाएगा और स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-Civil), AAI Rajahmundry Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Assistant General

विमानपत्तन निदेशक का कार्यालय, राजमुंदरी हवाई अड्डा, मधुरपूडि (पोस्ट), राजमुंदरी - 533 102

O/o The Airport Director, Rajahmundry Airport, Madhurapudi (Post), Rajahmundry - 533 102 (इंजीनियरिंग)

दूरभाष / Phone: 0883 - 2007838, फैक्स / FAX: 0883 - 2487852 Asst. Gen Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण/AAI



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

Manager (Engg-Civil), AAI, Rajahmundry Airport by 05.11.2024 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100/- and the cost of the stamp paper shall be borne by you.

3. इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के रूप में रुपये 5,24,287/- (मात्र पांच लाख चौबीस हजार दो सौ सत्तासी रुपये) कृपया जमा करें, ऐसा न करने पर, अनुबंध दस्तावेज़ के पृष्ठ GCC-17 पर खंड 1A की शर्त के अनुसार कटौती की जाएगी।

Please deposit Rs. 5,24,287/- (Rupees five lakh twenty-four thousand two hundred eighty-seven only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1A on Page GCC-17 of the Contract Document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और शर्त) के प्रावधानों का अनुपालन करें। सेवा अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड संख्या में निर्दिष्ट है। 19 पेज नं. केंद्र और राज्य सरकारों की निविदा और उसके नियमों की जीसीसी की धारा 45।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition and Regulation) Act 1986, Construction Workers (Regulation of Employment and condition of Service) Act 1996, Building and other construction workers Welfare cess Act 1996 as specified in clause no. 19 at page no. 45 of GCC of tender and rules thereof Central and State Governments.

5. आपको तुरंत एएआई राजमुंदरी हवाई अड्डे के सहायक महाप्रबंधक (इंजीनियरिंग-सिविल) से संपर्क करने का भी निर्देश दिया जाता है, जो आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. General Manager (Engg-Civil), AAI Rajahmundry Airport immediately who will arrange to handover the site to you.

6. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय 12 (बारह) महीने होगा जिसकी गणना इस पत्र के जारी होने के दसवें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be 12 (Twelve) Months which shall be reckoned from tenth day after issue of this letter.

7. इस अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with this contract should normally be addressed to the Engineer-in-Charge.


22/10/24

विमानपत्तन निदेशक का कार्यालय, राजमुंदरी हवाई अड्डा, मधुरपूडि (पोस्ट), राजमुंदरी

O/o The Airport Director, Rajahmundry Airport, Madhurapudi (Post), Rajahmundry - 533 102

दूरभाष / Phone: 0883 - 2007838, फैक्स / FAX: 0883 - 2487852

महाप्रबंधक (इंजीनियरिंग)

Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण / AAI

राजमुंदरी हवाई अड्डा / RAJAHMUNDY AIRPORT

RAJAHMUNDY-533 102.




भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

8. कृपया पावती भेजें तथा इसके साथ संलग्नित इस पत्र की दूसरी प्रति पर विधिवत हस्ताक्षर करने के उपरान्त प्राप्ति के प्रमाणस्वरूप में इसे अधोहस्ताक्षरी को वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

भवदीय / Yours faithfully,


22/10/24

(के कनकराज) / (K. KANAKARAJ)

सहायक महाप्रबंधक (अभि-सि.), / Asst. General Manager (Engg-Civil)
भा.वि.प्रा. राजमंड्री हवाई अड्डा, / AAI Rajahmundry Airport
अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के लिए राजमंड्री हवाई अड्डा
For and on Behalf of the Chairman, Airports Authority of India

संलग्न/Encl.: अनुसूची ऐ /Schedule A

NOO: -

सेवा प्रतिलिपि: / Copy to:

बाहरी /External

1. महाप्रबंधक (वित्त) भा.वि.प्रा. एस/अर, चेन्नई हवाई अड्डा, चेन्नई
General Manager (Finance), AAI, S/R, Chennai Airport, Chennai.
2. संयुक्त महाप्रबंधक (जागरूकता) भा.वि.प्रा. एस/अर, चेन्नई हवाई अड्डा, चेन्नई
Jt. General Manager (Vigilance), AAI, S/R, Chennai Airport, Chennai.
3. श्रम प्रवर्तन अधिकारी (केंद्रीय), वरि. एस ई /टेली. बिल्डिंग रेलवे स्टेशन प्रेमिसेस राजहमुंद्री ई.जी.डीटी. 533 101.
The Labour Enforcement Officer (Central), Sr. SE/Tele. Building, Railway Station Premises, Rajahmundry, East Godavari District, 533101 along with Form - VII.

अंदर का/ Internal:

1. विमानपत्तन निदेशक/Airport Director.
2. उप महाप्रबंधक (अभि-सि.)/Dy. General Manager (Engg-Civil)-II.
3. उप महाप्रबंधक (ए टी एम)/Dy. General Manager (ATM).
4. मुख्य सुरक्षा अधिकारी /Chief Security Officer
5. प्रबंधक (अग्निशमन)/Manager (Fire).
6. सहायक प्रबंधक (वित्त.)/Asst. Manager (Finance).
7. टर्मिनल प्रबंधक /Terminal Manager.
8. कार्य फ़ाइल/Work File.
9. भा.वि.प्रा.वेबसाइट/AAI website.


22/10/24

सहायक महा प्रबंधक (इंजीनियरिंग)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंड्री हवाई अड्डा / RAJAHMUNDRI AIRPORT
राजमंड्री/ RAJAHMUNDRI-533 102.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. Gen. Manger (Engg-C), AAI, Rajahmundry Airport

Name of Work: Construction Overhead Water Tank, Static Tank and provision of Hard stand around OHT, Static Tank & Pre-Determined Point for Category VI of Firefighting system at Rajahmundry Airport

Contract No: 2024_AAI_205564_1

Name of the Bidder/ Bidding Firm / Company : SRI KARTHIKEYA ENTERPRISES

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT in Words without GST.		
1	2	3	4	5	6	7	8		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge. All kinds of soil.	532.00	cum	INR	180.00	95760.00	INR Ninety Five Thousand Seven Hundred & Sixty Only		
2	Carriage of materials by mechanical transport including loading, unloading and stacking : lead upto 1.0 km for earth.	266.00	cum	INR	200.00	53200.00	INR Fifty Three Thousand Two Hundred Only		
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidation each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	48.00	cum	INR	250.00	12000.00	INR Twelve Thousand Only		
4	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil.	106.00	cum	INR	100.00	10600.00	INR Ten Thousand Six Hundred Only		
5	Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	8.00	cum	INR	1800.00	14400.00	INR Fourteen Thousand Four Hundred Only		

22/10/24

महायुक्त महा प्रबंधक (इंजीनियरिंग)

Asst. Gen Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण / AAI

राजमंड्री हवाई अड्डा / RAJAHMUNDARY AIRPORT

राजमंड्री / RAJAHMUNDARY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. p	TOTAL AMOUNT Without GST in Rs. p	TOTAL AMOUNT In Words without GST.			
1	2	3	4	5	6	7	8			
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size).	8.00	cum	INR	5000.00	40000.00	INR Forty Thousand Only			
7	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	91.00	sqm	INR	400.00	36400.00	INR Thirty Six Thousand Four Hundred Only			
8	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	244.00	sqm	INR	800.00	195200.00	INR One Lakh Ninety Five Thousand Two Hundred Only			
9	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform.	59.00	sqm	INR	1000.00	59000.00	INR Fifty Nine Thousand Only			
10	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers.	87.00	sqm	INR	900.00	78300.00	INR Seventy Eight Thousand Three Hundred Only			
11	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts.	108.00	sqm	INR	950.00	102600.00	INR One Lakh Two Thousand Six Hundred Only			
12	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Under 20 cm wide	44.00	mtr	INR	200.00	8800.00	INR Eight Thousand Eight Hundred Only			
13	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Above 20 cm wide	6.00	sqm	INR	900.00	5400.00	INR Five Thousand Four Hundred Only			
14	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentering at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured).Suspended floors, roofs, landing, beams and balconies (Plan area to be measured).	96.00	sqm	INR	400.00	38400.00	INR Thirty Eight Thousand Four Hundred Only			

Signature
22/10/24

महाक मना प्रबंधक (इंजीनियरिंग)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
राजमंडी/ RAJAHMUNDRY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder	TOTAL AMOUNT Without GST in Rs.	TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars.	5500.00	kgs	INR	90.00	495000.00	INR Four Lakh Ninety Five Thousand Only
16	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars.	5900.00	kgs	INR	90.00	531000.00	INR Five Lakh Thirty One Thousand Only
17	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. All works upto plinth level. Concrete of M25 grade with minimum cement content of 330 kg / cum. Extra cement above the minimum specified cement content in design mix shall be payable separately as per approved mix design.	45.00	cum	INR	6200.00	279000.00	INR Two Lakh Seventy Nine Thousand Only

BeauRaj
22/10/24

सहायक महा प्रबंधक (इंजीनियरिंग)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण / AAI
राजमुंदरी हवाई अड्डा / RAJAHMUNDRI AIRPORT
गजपतपुर / RAJAHMUNDRI-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder	TOTAL AMOUNT Without GST in Rs.	TOTAL AMOUNT In Words without GST.		
1	2	3	4	5	6	7	8		
18	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. All works above plinth level upto floor V level. Concrete of M25 grade with minimum cement content of 330 kg /cum Extra cement above the minimum specified cement content in design mix shall be payable separately as per approved mix design.	59.00	cum	INR	7600.00	448400.00	INR Four Lakh Forty Eight Thousand Four Hundred Only		
19	Add for using extra cement in the items of design mix over and above the specified cement content therein.	10.00	qtl	INR	700.00	7000.00	INR Seven Thousand Only		
20	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	800.00	kgs	INR	180.00	144000.00	INR One Lakh Forty Four Thousand Only		
21	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm2), counter sunk head, comprising of 10 mm dia polyamide PA 6 grade sleeve, including drilling of hole in frame , concrete/ masonry, etc. as per direction of Engineer-in-charge. 10 x 160 mm.	50.00	nos	INR	300.00	15000.00	INR Fifteen Thousand Only		
22	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand).	270.00	sqm	INR	225.00	60750.00	INR Sixty Thousand Seven Hundred & Fifty Only		
23	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	270.00	sqm	INR	120.00	32400.00	INR Thirty Two Thousand Four Hundred Only		


 22/10/24
 महाक म्हा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण / AAI
 राजमंडरी / RAJAHMUNDRY AIRPORT
 राजमंडरी / RAJAHMUNDRY 33 102

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder	TOTAL AMOUNT Without GST in Rs.	TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
24	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work.	100.00	sqm	INR	120.00	12000.00	INR Twelve Thousand Only
25	Cement concrete in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Concrete of M25 grade with minimum cement content of 330 kg /cum. Extra cement above the minimum specified cement content in design mix shall be payable separately as per approved mix design.	230.00	cum	INR	5100.00	1173000.00	INR Eleven Lakh Seventy Three Thousand Only
26	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the engineer in charge.	400.00	per cm depth per cm width per metre length	INR	11.00	4400.00	INR Four Thousand Four Hundred Only
27	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motorgrader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20.	183.00	cum	INR	1650.00	301950.00	INR Three Lakh One Thousand Nine Hundred & Fifty Only
28	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	138.00	cum	INR	1650.00	227700.00	INR Two Lakh Twenty Seven Thousand Seven Hundred Only


 22.10.24
 महायुक्त महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
 राजमंडी/ RAJAHMUNDRY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder	TOTAL AMOUNT Without GST In Rs.	TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
29	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 50 mm nominal dia Pipes.	150.00	mtr	INR	1000.00	150000.00	INR One Lakh Fifty Thousand Only
30	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. 50 mm dia. Nominal bore.	20.00	mtr	INR	1000.00	20000.00	INR Twenty Thousand Only
31	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :50 to 80 mm nominal bore.	1.00	nos	INR	1650.00	1650.00	INR One Thousand Six Hundred & Fifty Only
32	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) 50 mm nominal bore.	2.00	nos	INR	500.00	1000.00	INR One Thousand Only
33	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation,refilling the earth or cutting of wall and making good the same complete wherever required : 50mm nominal bore.	2.00	nos	INR	1450.00	2900.00	INR Two Thousand Nine Hundred Only
34	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality. H D - 20. Circular shape 560 mm internal diameter.	8.00	nos	INR	1550.00	12400.00	INR Twelve Thousand Four Hundred Only


 महाप्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानन प्राधिकरण/AAI
 राजमंडी स्टाई अड्डा / RAJAHMUNDY AIRPORT
 राजमंडी / RAJAHMUNDY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
35	Providing and mixing integral crystalline admixture for water proofing treatment to RCC structures like basement raft, retaining walls, reservoir, sewage & water treatment plant, tunnels/subway and bridge deck etc. at the time of transporting of concrete into the drum of the ready-mix truck, using integral crystalline admixture @0.80% (minimum) to the weight of cement content per cubic meter of concrete or higher as recommended by the manufacturer's specification in reinforced cement concrete at site of work. The material shall meet the requirements as specified in ACI-212-3R-2010 ie., by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure. The crystalline admixture shall be capable of self healing of cracks upto a width of 0.50mm. the work shall be carried out all complete as per specification and the direction of the Engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage.(Treated finished area will be measured for payment)	300.00	kgs	INR	400.00	120000.00	INR One Lakh Twenty Thousand Only

22/10/24


सहायक महा प्रबंधक (इंजी-सिविल)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंड्री हवाई अड्डा / RAJAHMUNDRI AIRPORT
राजमंड्री/ RAJAHMUNDRI-533 102.

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	TEXT # Quoted Currency y in INR / Other Currency	NUMBER # RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. p	NUMBER # TOTAL AMOUNT Without GST in Rs. p	TEXT # TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
36	Water proofing of Static Tank inner and outer surface. The method consists of application of 2 coats of Dr. Fixit Fastflex (or equivalent) a two component cementitious waterproofing system. Operation 1: Base preparation of cleaning, brushing and removal of flaky materials etc, Operation 2: Opening the construction joints, corner of the wall and slab, Cracks in 'V' groove up to 20mm depth and width. providing hunching to the corner of the slab with Cement mortar mixed with Dr. Fixit Pidicrete URP (or equivalent) @ 1.5kg/bag of cement. After completing the above all the given treatment, Applying & supplying of a two component of Dr. Fixit Fastflex (or equivalent) acrylic cementitious coating system @ 2.1 kg/sqm in 2 coats.. At the time of second coat sand will be sprinkled over the coated surface to get proper bonding for Protective plastering, The coating to be extended in the wall up to 450mm height from Finished floor level. Plastering of 20 mm thickness over the applied waterproofing membrane with CM 1:4 (1Cement : 4 M. sand)) to be mixed with Intergeral waterproofing compound Dr. Fixit Pidiproof LW+ (or equivalent) at a dosage of 200ml/50 kg bag of cement compound. (Treated finished area will be measured for payment)	179.00	sqm	INR	1000.00	179000.00	INR One Lakh Seventy Nine Thousand Only

Asst. Gen Manager
22/10/24

सहायक महा प्रबंधक (इंजीनियरिंग)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंड्री हवाई अड्डा / RAJAHMUNDRY AIRPORT
राजमंड्री/RAJAHMUNDRY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	4	5	6	7	8
37	Waterproofing of Over head water tank inner surface. The method consists of application of 2 coats of Dr.Fixit Fastflex(or equivalent) a two component cementitious waterproofing system. Operation 1: Base preparation of cleaning, brushing and removal of flaky materials etc, Operation 2: Opening the construction joints, corner of the wall and slab, Cracks in 'V' groove up to 20mm depth and width. providing hunching to the corner of the slab with Cement mortar mixed with Dr.Fixit Pidicrete URP(or equivalent) @ 1.5Kg/bag of cement .After completing the above all the given treatment, Applying & supplying of a two component of Dr.Fixit Fastflex(or equivalent) acrylic cementitious coating system @ 2.1 kg/sqm in 2 coats.. At the time of second coat sand will be sprinkled over the coated surface to get proper bonding for Protective plastering , The coating to be extened in the wall up to 450mm height from Finished floor level. Plastering of 20 mm thickness over the applied waterproofing membrane with CM 1:4 (1Cement : 4 M .sand)) to be mixed with Intergeral waterproofing compound Dr.Fixit Pidiproof LW+(or equivalent) at a dosage of 200ml/50 kg bag of cement compound.	74.00	sqm	INR	1000.00	74000.00	INR Seventy Four Thousand Only
38	Providing and laying polythene sheet 400 micron thick confirming to IS 2508 anti friction layer on the surface course complete as per specifications with specified overlaps between adjacent and transverse strips, only plan area will be measured for payment, as directed by the engineer in charge.	915.00	sqm	INR	69.00	63135.00	INR Sixty Three Thousand One Hundred & Thirty Five Only
39	Providing and fixing brass gate valve of ZOLOTO or equivalent in water supply line, all complete as per direction of Engineer-in-Charge. 50 mm nominal bore.	2.00	nos	INR	2600.00	5200.00	INR Five Thousand Two Hundred Only
40	Providing and fixing PVC foot step reinforced with 12mm dia MS rod having length 165mm width 170mm, thickness 25mm for UG sump tank or overhead water tank etc.	25.00	nos	INR	400.00	10000.00	INR Ten Thousand Only
41	Compacting original ground supporting sub-grade Loosening, leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Table 300-2 for embankment construction.	915.00	Sqm	INR	48.00	43920.00	INR Forty Three Thousand Nine Hundred & Twenty Only


 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
 राजमंडी/ RAJAHMUNDRY-533 102.

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (Inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.	
1	2	3	4	5	6	7	8	
42	Carrying out Structural design of elevated (Around 10 mtr) Rectangular Over Head Tank of capacity 50000 litres and Rectangular UG sump of capacity 100000 litres for the given SBC by AAI and submission of detailed structural design and drawings etc complete as per the direction of Engineer-in-Charge. The design and drawing shall be vetted by any Government Engineering college or university.	1.00	job	INR	78000.00	78000.00	INR Seventy Eight Thousand Only	
Total In Figures						5242865.00	INR Fifty Two Lakh Forty Two Thousand Eight Hundred & Sixty Five Only	
Quoted Rate in Words						INR Fifty Two Lakh Forty Two Thousand Eight Hundred & Sixty Five Only		

Signature
22/10/24

महापंक महा प्रबंधक (इंजीनियरिंग)
Asst. Gen Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
राजमंडी/ RAJAHMUNDRY-533 102.