



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

By Hand/E-mail

Date: 15.10.2024

F.No. AAI/BLY/Engg(C)/24/Pits-Tiles/717

सेवा में,

M/s. G. R. ENGINEERS AND CONTRACTOR
11A/2, PRATAP NAGAR WEST,
MAHOLI ROAD, MATHURA,
UTTAR PRADESH-281004

मैसर्स जी० आर० इंजीनियर्स एण्ड कंन्ट्रैक्टर
11ए/2, प्रताप नगर पश्चिम,
मोहाली रोड, मथुरा,
उत्तर प्रदेश-281004

Subject: Repair and recharge of rain water harvesting pits and tile repair work at Bareilly Airport.

संदर्भ : आपकी ई-निविदा आई.डी. AAI_2024_206822_1 जो दिनांक 07.10.2024 को खोली गई

Ref: Your E- Tender ID: AAI_2024_206822_1 Opened on Dated: 07.10.2024.

प्रिय महोदय,

Dear sir,

- 1) आपके उपरोक्त कार्य की ₹ 7,48,110/- (जीएसटी रहित) (रु० सात लाख अड़तालीस हजार एक सौ दस मात्र) की मदद से ई-निविदा जो कि उक्त कार्य की अनुमानित लागत ₹ 9,94,495/- (जीएसटी रहित) (रु० नौ लाख चौरानवे हजार चार सौ पचियानवे मात्र) से 24.77% कम है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling to ₹ 7,48,110/- (excluding GST) (Rupees seven lakhs forty-eight thousand one hundred ten only) which is 24.77% below the estimated cost put to tender of ₹ 9,94,495/- (excluding GST) (Rupees nine lakhs ninety-four thousand four hundred ninety-five only).

- 2) सहायक महाप्रबंधक (अभि-सिविल), भा०वि०प्रा०, सिविल एन्क्लेव, बरेली इस कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि दिनांक: 07.11.2024 तक सहायक महाप्रबंधक, (अभि-सिविल) भा०वि०प्रा०, सिविल एन्क्लेव, बरेली एयरपोर्ट के कार्यालय में उपस्थित होकर ठेका संविदा को हस्ताक्षरित कर पूर्ण करें। ठेका रु 100/- (रुपये एक सौ मात्र) के न्यायिकोत्तर मुद्रांक पत्र पर सम्पादित किया जाएगा एवं मुद्रांक पत्र की कीमत आपके द्वारा वहन की जाएगी।

Asst. General Manager (Engg.Civil), AAI, Civil Enclave, Bareilly shall be the Engineer-in-charge of this work. You are requested to attend the office of Asst. General Manager (Engg.Civil), AAI, Civil Enclave, Bareilly by dated: 07.11.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-Judicial stamp paper of value Rs. 100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

- 3) आपसे अनुरोध है कि संविदा मूल्य के 10% की दर से सुरक्षा जमा राशि जमा करें जो कि किसी भी अनुसूचित बैंक की बैंक गारंटी के रूप में हो सकता है लेकिन सहकारी या ग्रामीण बैंक नहीं हो। यदि आप जमानत राशि जमा करने में विफल रहते हैं, तो इसे प्रत्येक आर.ए. बिल से उक्त आर.ए. बिल राशि के 10% की दर से सुरक्षा जमा की पूरी राशि की वसूली तक परिस्थितियों के अनुसार एवं प्रभारी अभियन्ता से निकासी प्रमाण पत्र प्रदान करने उपरान्त अंतिम बिल में समायोजित/निपटान करने के लिए वसूल किया जाएगा।

You are requested to deposit the security deposit @ 10% of the contract value which can be in the form of bank guarantee of any scheduled bank but not Co-Operative or Gramin Bank. If you fail to deposit security deposit, the same shall be recovered from each RA bill @ 10% of the said RA bill amount till realization of full amount of security deposit, to be adjusted/settled in the final bill as per the circumstances and on providing clearance certificate from Engineer-in-charge.

- 4) आपसे अनुरोध है कि 1970 के अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, भवन और अन्य निर्माण श्रमिकों (रोजगार का विनियमन) के प्रावधानों का अनुपालन करें। सेवा की शर्तों अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, न्यूनतम मजदूरी अधिनियम 1948, ईपीएफ अधिनियम -1952, ईएसआई अधिनियम -1948, और केंद्र और राज्य सरकार के अन्य नियम।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Building and other Construction Workers (Regulation of Employment of Conditions of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996, Minimum Wages Act 1948, EPF Act-1952, ESI Act-1948, and other rules there of central and state Government.

- 5) ठेकेदार नियमित तथा प्रभावी पर्यवेक्षण को सुनिश्चित करेगा और उनके द्वारा तैनात किये गये कार्मिक पर नियंत्रण एवं ठेके के दायित्वों को पूरा करने के लिए उपयुक्त निर्देश देगा।

सिविल एन्क्लेव, बरेली, पीलीभीत रोड, मुडिया अहमद नगर (मयूर वन चेतना केन्द्र के पास), बरेली, उत्तर प्रदेश -243122

Civil Enclave, Bareilly, Pilibhit Road, Mudiya Ahmed Nagar (Near Mayur Van Chetna Kendra), Bareilly, Uttar Pradesh -243122

Handwritten signature and date 15/10/24

The contractor shall ensure regular and effective supervision and control of the personnel deployed by him and gives suitable direction for undertaking the contractual obligations.

- 6) आपको निर्देशित किया जाता है कि तुरन्त प्रभाव से सहायक प्रबन्धक (इंजी-सिविल) सिविल एन्क्लेव, बरेली को संपर्क करें जो कि आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asstt Manager (Engg- Civil), Civil Enclave, Bareilly immediately who will arrange to hand over the site to you.

- 7) कार्य करने का निर्धारित समय **02 माह** है, जो कि इस पत्र के निर्गत होने की तिथि के **दसवें दिन** से माना जाएगा।

Please note that time allowed for carrying out the work shall be **02 Months** and same shall be reckoned from the **10th day** from the date of issue of this letter.

- 8) संविदा के संदर्भ में सामान्यतः कोई भी पत्राचार कार्य प्रभारी अभियन्ता को सम्बोधित करते हुए किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.

- 9) नागरिक उड्डयन सुरक्षा ब्यूरो (बीसीएस) के निर्देशानुसार एयरोड्रोम एंट्री परमिट (ईपी) जारी करने के लिए संबंधित एजेंसी के ई-सहज पोर्टल से सुरक्षा मंजूरी और बीसीएस द्वारा अनुमोदित सुरक्षा कार्यक्रम अनिवार्य है। अतः आपको निर्देशित किया जाता है कि उपरोक्त कार्य के लिए प्रतिनियुक्त कैजुअल लेबर, प्रोपराइटर, इंजीनियर्स का सुरक्षा क्लीयरेंस एवं पुलिस वेरीफिकेशन प्राप्त करें।

Security Clearance from the e-Sahaj portal of the concerned agency and security programme approved by BCAS is mandatory for issuance of Aerodrome Entry Permit (AEP) as per the instruction of Civil Aviation Security Bureau (BCAS). Hence, you are directed to get security clearance and Police Verification of Casual Labours, Proprietor, Engineers deputed for the above-mentioned work.

- 10) ठेके की त्रुटि दायित्व अवधि **बारह महीने** है जो कि कार्य समाप्ति की तिथि से गिना जाएगा।

The defect liability period of the contract is **Twelve Months** which shall be reckoned from the actual date of completion of work.

- 11) कृपया प्राप्ति की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

नोट: यदि हिंदी और अंग्रेजी संस्करण में कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण का पालन किया जाएगा।

Note: If any discrepancy is observed in Hindi and English version, then English version will be followed.

भवदीय,
Yours faithfully,


15/10/24
(अवधेश अग्रवाल)

(Avdhesh Aggarwal)

सहायक महाप्रबन्धक (इंजी०-सि०)

Asst. General Manager (Engg. -Civil)

भा०वि०प्रा०, सिविल एन्क्लेव, बरेली

AAI, Civil Enclave, Bareilly

अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के लिए व उनकी तरफ से

For & on behalf of the Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

Encl: Price Schedule

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Asstt. General Manager (Engg-Civil), AAI, Civil Enclave, Bareilly

Name of Work:- Repair and recharge of rain water harvesting pits and tile repair work at Bareilly Airport.

Contract No: 2024_AAI_206822

Name of the Bidder/ Bidding Firm / Company : M/s G. R. Engineers & Contractors

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	Sl. No.	TEXT # Item Description	TEXT # Item Code / Make	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures To be entered by the Bidder excluding GST Rs. P	NUMBER # TOTAL AMOUNT	TEXT # TOTAL AMOUNT In Words
1	1	2 Cleaning of whole filter media of rain water harvesting pit by removing the complete existing layers of coarse sand, gravel and coarse graded aggregate and washing with clear water and segregating each layer, including opening of covers and replacing complete as per satisfaction and direction of engineer in-charge.	3	4	5	7	8	10
2	2	Filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, 5 mm to 10mm & 1.50 mm to 2 mm etc. , in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge (Cleaned stone boulders, gravels, coarse sand etc. shall be supply by AAI fee of cost).	Item No.2	15.00	cum	200.00	3000.00	INR Three Thousand Only
3	3	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	Item No.3	10.00	cum	1,700.00	17000.00	INR Seventeen Thousand Only
4	4	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	Item No.4	15.00	cum	1,750.00	26250.00	INR Twenty Six Thousand Two Hundred & Fifty Only
5	5	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer - in-charge.	Item No.5	20.00	cum	1,400.00	28000.00	INR Twenty Eight Thousand Only
6	6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Item No.6	21.00	cum	6,400.00	134400.00	INR One Lakh Thirty Four Thousand Four Hundred Only
7	7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Item No.7	1575.00	kg	77.00	121275.00	INR One Lakh Twenty One Thousand Two Hundred & Seventy Five Only
8	8	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Item No.8	281.00	sqm	45.00	12645.00	INR Twelve Thousand Six Hundred & Forty Five Only
9	9	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	Item No.9	281.00	sqm	280.00	78680.00	INR Seventy Eight Thousand Six Hundred & Eighty Only
10	10	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Item No.10	344.00	sqm	60.00	20640.00	INR Twenty Thousand Six Hundred & Forty Only
11	11	Disposal of building rubbish/ malha/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Item No.11	58.00	cum	240.00	13920.00	INR Thirteen Thousand Nine Hundred & Twenty Only

15/11/24

12	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in dado upto 3 m height, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, including grouting of joints with white cement and matching pigments etc. complete. Size of Tile 600x300 mm	Item No.12	344.00	sqm	800.00	275200.00	INR Two Lakh Seventy Five Thousand Two Hundred Only
13	Deduct for taking away of reinforced steel scrapped from dismantled RCC. The material so received shall be the property of contractor after dismantling, duly weighed/measured before removing from the site as per the satisfaction of Engineer-in-charge.	Item No.13	1575.00	kg	12.00	-189000.00	INR Minus Eighteen Thousand Nine Hundred Only
Total in Figures						7,48,110.00	
Quoted Rate in Words							
INR Seven Lakh Forty Eight Thousand One Hundred & Ten Only							

1575 x 12 =
 18900
 AGM/EC

Signature Not Verified

Digitally signed by AVDHESH AGGARWAL

Date: 2025.09.10 15:34:02 IST

Location: eProcurement System for Central PSUs