



भारतीय विमानपत्तन प्राधिकरण, कडपा हवाई अड्डा.
AIRPORTS AUTHORITY OF INDIA
KADAPA AIRPORT- 516003.

Ref.No.:AAI/Kadapa/Engg-C/Perimeter Road/WO/2024-25/ 911

Date: 06.02.2025

To,

M/s. NSC PROJECTS Pvt. Ltd,
#L-87, Street no.7C, Mahipalpur Extension,
New Delhi - 110037.
Ph. No. (Office): 0124-4222541, 42
Mobile: +91-9811012499
Email ID: narbirsingh07@gmail.com

Name of Work: Construction of Perimeter road, Emergency Access road, RCC Storm water drain, Security Watch Towers, Boundary wall for part of newly acquired land at Runway 29 at Kadapa Airport.

Ref: Your tender for the subject work opened on 15.01.2025 in CPP portal (Tender ID: 2024_AAI_207871_1).

Dear Sir (s),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs.6,86,67,232/- (Rupees Six Crore Eighty Six Lakhs Sixty Seven Thousand Two Hundred and Thirty Two only) (Excluding GST)** which is 30.29% below the estimated cost put to tender of Rs.9,85,00,000/-.
2. Asst. General Manager (Engg-Civil)-I, AAI, Kadapa Airport shall be the Engineer-in-Charge of the work. You are requested to attend the office of the **Asst. General Manager (Engg-Civil)-I, AAI, Kadapa Airport by 01.03.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.
3. The Earnest money amount of Rs.19,70,000/- (Rupees Nineteen Lakh Seventy Thousand Only) received in the form of bank guarantee along with your e-tender will be treated and converted as part of Security Deposit as per conditions of clause 1A at page no. 15 of the General Conditions of Contract of tender document. Please deposit **Rs.14,63,362/- (Rupees Fourteen Lakh Sixty Three Thousand Three Hundred and Sixty Two only) as Security Deposit** within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per conditions of clause 1A at page 15 of the General Conditions of Contract of tender document.
4. Within 30 days of issue of this letter, you shall submit to AAI, an irrevocable performance guarantee for an amount **Rs.34,33,362/- (Rupees Thirty Four Lakh Thirty Three Thousand Three Hundred and Sixty Two only)** in the form of irrevocable Bank Guarantee as per condition of Clause -1 on GCC at page no. 14 of the Tender Document, on the proforma Appendix-I on GCC at page no. 81 of the Tender Document.

Ronunt
A. K. Singh

Pg. 1 of 2

5. You are directed to apply for Security Clearance through BCAS portal, followed with Security Programme for obtaining entry permit into Terminal Building & Operational area for labours, and vehicles for carrying out the contract work.
6. You are requested to comply with the provision of contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central Rules 1971 and minimum wages act and rules there of central and state Governments.
7. You are also directed to contact Manager (Engg-Civil), Airports Authority of India immediately who will arrange to handover the site to you.
8. Please note that the time allowed for carrying out the work shall be **15 (Fifteen) Months** (Including two months considered for rain), which shall be reckoned from the 10th day from the date of issue of this letter.
9. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Item Rate BOQ (10 Pages).

Yours faithfully,

H. Kumar
06/04/2015
Asst. General Manager (Engg-Civil)-I,
AAI, Kadapa Airport.
For and on behalf of Chairman,
Airports Authority of India.

सहायक महाप्रबंधक (ई-सी)/Asst. General Manager (Engg-C)-I
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India
कडप्पा हवाई अड्डा / Kadapa Airport
कडपा / Kadapa-516003.

Validate

Print

Help

Item Rate BoQ**Tender Inviting Authority: Asst. General Manager (E-C), AIRPORTS AUTHORITY OF INDIA, Kadapa Airport.****Name of Work: Construction of Perimeter road, Emergency Access road, RCC Storm water drain, Security Watch Towers, Boundary wall for part of newly acquired land at Runway 29 at Kadapa Airport****TENDER ID: 2024_AAI_207871_1**

Name of the Bidder/ Bidding Firm / Company :	NSC Projects Pvt Ltd						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
1	2	3	4	5	7	8	10
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth within airport premises as directed by Engineer-incharge. All kinds of soil	Item No.1	5940.00	Cum	120.00	712800.00	INR Seven Lakh Twelve Thousand Eight Hundred Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil within airport premises as per direction of Engineer in charge. All kinds of soil.	Item No.2	2031.00	Cum	120.00	243720.00	INR Two Lakh Forty Three Thousand Seven Hundred & Twenty Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and for all leads & Lifts	Item No.3	2165.00	Cum	60.00	129900.00	INR One Lakh Twenty Nine Thousand Nine Hundred Only
4	Supplying and filling in plinth with local sand/ M sand under floors, including watering, ramming, consolidating and dressing complete.	Item No.4	225.00	Cum	1200.00	270000.00	INR Two Lakh Seventy Thousand Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering All work upto plinth level. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregated 20mm nominal size)	Item No.5	646.00	Cum	4500.00	2907000.00	INR Twenty Nine Lakh Seven Thousand Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering All work upto plinth level. 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregated 40mm nominal size derived from natural sources)	Item No.6	620.00	Cum	3200.00	1984000.00	INR Nineteen Lakh Eighty Four Thousand Only
7	Centering and shuttering including strutting,propping etc. and removal of form for Foundations, footing bases of columns, etc. For mass concrete	Item No.7	2972.00	Sqm	300.00	891600.00	INR Eight Lakh Ninety One Thousand Six Hundred Only
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement-All work up to plinth level: 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	Item No.8	1673.00	Cum	5100.00	8532300.00	INR Eighty Five Lakh Thirty Two Thousand Three Hundred Only
9	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :	Item No.9	29.00	Cum	5500.00	159500.00	INR One Lakh Fifty Nine Thousand Five Hundred Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Item No.10	4973.00	Sqm	350.00	1740550.00	INR Seventeen Lakh Forty Thousand Five Hundred & Fifty Only
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (a) Thermo-Mechanically Treated bars or more	Item No.11	102338.00	Kg	78.00	7982364.00	INR Seventy Nine Lakh Eighty Two Thousand Three Hundred & Sixty Four Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. (a) Thermo-Mechanically Treated bars or more	Item No.12	5316.00	Kg	78.00	414648.00	INR Four Lakh Fourteen Thousand Six Hundred & Forty Eight Only
13	Centering and shuttering including strutting,propping etc. and removal of form for Lintels,beams,plinth beams,griders,bressumers and cantilevers	Item No.13	337.00	Sqm	400.00	134800.00	INR One Lakh Thirty Four Thousand Eight Hundred Only
14	Centering and shuttering including strutting,propping etc. and removal of form for Columns,pillars, piers, Abuments,posts and struts	Item No.14	671.00	Sqm	400.00	268400.00	INR Two Lakh Sixty Eight Thousand Four Hundred Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
15	Providing and fixing ISI marked aluminium butt hinges anodised (anodiccoating not less than grade AC 10 as per IS: 1868) transparent or dyedto required colour or shade with necessary screws etc. complete: 100x75x4 mm	Item No.15	12.00	Each	200.00	2400.00	INR Two Thousand Four Hundred Only
16	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868),transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm	Item No.16	12.00	Each	300.00	3600.00	INR Three Thousand Six Hundred Only
17	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodiccoating not less than grade AC 10 as per IS : 1868) transparent or dyedto required colour or shade, with necessary screws etc. complete : 250x10 mm	Item No.17	8.00	Each	250.00	2000.00	INR Two Thousand Only
18	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete	Item No.18	4.00	Each	2000.00	8000.00	INR Eight Thousand Only
19	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	Item No.19	8.00	Each	150.00	1200.00	INR One Thousand Two Hundred Only
20	Providing and fixing aluminium hanging floor door stopper, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868)transparent or dyed to required colour and shade, with necessary screwsetc. complete. Twin rubber stopper	Item No.19	4.00	Each	150.00	600.00	INR Six Hundred Only
21	Providing and fixing bright finished brass 100 mm mortice latch and lock, ISI marked, with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles of approved quality with necessary screws etc. complete.	Item No.19	4.00	Each	2000.00	8000.00	INR Eight Thousand Only
22	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Item No.19	1330.00	Kg	110.00	146300.00	INR One Lakh Forty Six Thousand Three Hundred Only
23	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	Item No.19	8014.00	Kg	120.00	961680.00	INR Nine Lakh Sixty One Thousand Six Hundred & Eighty Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
24	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	Item No.19	1569.00	Kg	110.00	172590.00	INR One Lakh Seventy Two Thousand Five Hundred & Ninety Only
25	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5 x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Item No.19	80.00	Sqm	1000.00	80000.00	INR Eighty Thousand Only
26	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws complete: Ridges plain (500 - 600mm)	Item No.19	56.00	meter	750.00	42000.00	INR Forty Two Thousand Only
27	Extra for providing and fixing wind ties of 40x 6 mm flat iron section	Item No.19	152.00	meter	200.00	30400.00	INR Thirty Thousand Four Hundred Only
28	6 mm cement plaster of mix : (a) 1:3 (1 cement: 3 fine sand)	Item No.19	487.00	Sqm	300.00	146100.00	INR One Lakh Forty Six Thousand One Hundred Only
29	12 mm cement plaster of mix : (a) 1:6 (1 cement: 6 fine sand)	Item No.19	1173.00	Sqm	300.00	351900.00	INR Three Lakh Fifty One Thousand Nine Hundred Only
30	15 mm cement plaster on rough side of single : 1:6 (1 cement: 6 fine sand)	Item No.19	1173.00	Sqm	300.00	351900.00	INR Three Lakh Fifty One Thousand Nine Hundred Only
31	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Item No.19	2756.00	Sqm	120.00	330720.00	INR Three Lakh Thirty Thousand Seven Hundred & Twenty Only
32	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Item No.19	376.00	Sqm	120.00	45120.00	INR Forty Five Thousand One Hundred & Twenty Only
33	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on pavement surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. New work (Two or more coats)	Item No.19	645.00	Sqm	150.00	96750.00	INR Ninety Six Thousand Seven Hundred & Fifty Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
34	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, on any height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer- in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle shall be paid separately)	Item No.19	330.00	meter	550.00	181500.00	INR One Lakh Eighty One Thousand Five Hundred Only
35	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tipplers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. a) With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	Item No.19	4204.00	Cum	1900.00	7987600.00	INR Seventy Nine Lakh Eighty Seven Thousand Six Hundred Only
36	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineerin- charge.	Item No.19	1727.00	Cum	3200.00	5526400.00	INR Fifty Five Lakh Twenty Six Thousand Four Hundred Only
37	Providing and laying factory made chamfered edge Cement Concrete paver blocks in drive ways etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. a) 80 mm thick C.C. paver block of M-40 grade with approved color design and pattern.	Item No.19	11316.00	Sqm	750.00	8487000.00	INR Eighty Four Lakh Eighty Seven Thousand Only
38	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes.	Item No.19	90.00	meter	2500.00	225000.00	INR Two Lakh Twenty Five Thousand Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
39	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 600 mm dia RCC pipes.	Item No.19	90.00	meter	3500.00	315000.00	INR Three Lakh Fifteen Thousand Only
40	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia RCC pipes.	Item No.19	98.00	meter	4500.00	441000.00	INR Four Lakh Forty One Thousand Only
41	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	Item No.19	248.00	Kg	500.00	124000.00	INR One Lakh Twenty Four Thousand Only
42	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	Item No.19	52.00	Kg	600.00	31200.00	INR Thirty One Thousand Two Hundred Only
43	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness.	Item No.19	25.00	Sqm	1700.00	42500.00	INR Forty Two Thousand Five Hundred Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
44	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level. All types of soil 300mm dia	Item No.19	150.00	meter	600.00	90000.00	INR Ninety Thousand Only
45	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 200 mm nominal size dia	Item No.19	150.00	meter	2500.00	375000.00	INR Three Lakh Seventy Five Thousand Only
46	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	Item No.19	9.00	Cum	1900.00	17100.00	INR Seventeen Thousand One Hundred Only
47	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	Item No.19	9.00	Cum	1900.00	17100.00	INR Seventeen Thousand One Hundred Only
48	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer -in-charge.	Item No.19	9.00	Cum	1900.00	17100.00	INR Seventeen Thousand One Hundred Only
49	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer-in-charge.	Item No.19	11.00	Cum	1900.00	20900.00	INR Twenty Thousand Nine Hundred Only
50	Supplying and installation of moisture resistant/fire resistant cement board as per standard sizes fixed with self-drilling / taping screws. Screws shall be of counter sunk rib head of 1.60mm to 4 mm thick or 8 to 10 gauge of length varying from 25 to 45 mm. a)Cement Bonded particle board 8 mm thick (Termite,Fire & Moisture Resistance),as per IS:14276 : 1995	Item No.19	40.00	Sqm	1000.00	40000.00	INR Forty Thousand Only
51	Demolishing R.C.C. work manually/ by mechanical means and disposal of unserviceable material as per the direction of engineer-in-charge.	Item No.19	52.00	Cum	1000.00	52000.00	INR Fifty Two Thousand Only
52	Demolishing brick work manually/ by mechanical means, and disposal of unserviceable materials as per the direction of Engineer-in-charge. In cement mortar	Item No.19	227.00	Cum	500.00	113500.00	INR One Lakh Thirteen Thousand Five Hundred Only
53	Dismantling steel work in single sections including dismembering, and disposal of unserviceable materials as per the direction of Engineer-in-charge. Channels, angles, tees and flats	Item No.19	1224.00	Kg	15.00	18360.00	INR Eighteen Thousand Three Hundred & Sixty Only
54	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within airport premises as per direction of the Engineer-in-Charge.	Item No.19	3554.00	Kg	15.00	53310.00	INR Fifty Three Thousand Three Hundred & Ten Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
55	Dismantling baricading sheet and stacking the material within airport premises as per direction of the Engineer-in-Charge. A) G.S. Sheet	Item No.19	604.00	Sqm	100.00	60400.00	INR Sixty Thousand Four Hundred Only
56	Dismantling RBT & Concertina coil or flexible wire rope in fencing including making rolls and stacking within airport premises as per direction of the Engineer-in-Charge.	Item No.19	2940.00	kg	15.00	44100.00	INR Forty Four Thousand One Hundred Only
57	Providing and fixing 110 mm dia PVC Pipes of 300 mm length of approved make in brick wall at specified location and spacing as directed by the Engineer-in-charge.	Item No.19	600.00	Each	100.00	60000.00	INR Sixty Thousand Only
58	Providing and laying in position for expansion joint, 20mm thick pre-cut Synthetic joint/Expansion filler board, complete as per particular technical specifications and directions of Engineer-in-charge.	Item No.19	23.00	Sqm	2500.00	57500.00	INR Fifty Seven Thousand Five Hundred Only
59	Providing and installing modular toilet(Size: 4'x4'x7') of FRP (Fiber reinforced plastic) body with bio digestive system, an over head tank of at least 250 Litres capacity, water closet, health faucet, flushing system and at least one bib cock inside the toilet including all necessary fittings/fixtures etc. complete.	Item No.19	15.00	Each	60000.00	900000.00	INR Nine Lakh Only
60	Clearing and grubbing the site including uprooting rank vegetation, grass, bushes, shrubs, saplings and tress girth upto 300 mm including removal and disposal of stumps of cut trees, top soil not exceeding 200 mm and other unserviceable materials with in airport premises by mechanical means all inclusive as per direction of engineer-in-charge	Item No.19	22.00	Hector	16000.00	352000.00	INR Three Lakh Fifty Two Thousand Only
61	Rolling with power road roller on the ground over which pavement will be constructed as per directions of the Engineer in charge.	Item No.19	16150.00	sqm	5.00	80750.00	INR Eighty Thousand Seven Hundred & Fifty Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
62	Construction of embankment with soil obtained within the airport premises/from excavation items after mixing the soil with Sand/ M sand brought from outside in 1:1 ratio (1 Soil:1 Sand/M-sand) i/c all lifts, leads and transporting sand/M-sand to site including spreading, grading and consolidation with vibratory roller 8-10 tonne capacity including making good the undulations etc as per technical specifications and drawings to required slope as per the direction of Engineer-in-charge.	Item No.19	2160.00	Cum	800.00	1728000.00	INR Seventeen Lakh Twenty Eight Thousand Only
63	Construction of subgrade with approved soil brought from outside including the cost of earth with all lifts & leads, transporting to site, spreading, grading and consolidating with vibratory roller 8-10 tonne capacity including making good the undulation etc, as per technical specifications and drawings complete as per the directions of Engineer-in-charge.	Item No.19	19420.00	Cum	495.00	9612900.00	INR Ninety Six Lakh Twelve Thousand Nine Hundred Only
64	Brick work with cement concrete blocks, confirming to IS :2185 with min. avg. compressive strength of 5 Mpa in all shapes and sizes in foundation and plinth in : Cement mortar 1:6 (1 Cement: 6 coarse sand)	Item No.19	126.00	Cum	5500.00	693000.00	INR Six Lakh Ninety Three Thousand Only
65	Brick work with cement concrete blocks, confirming to IS :2185 with min. avg. compressive strength of 5 Mpa in all shapes and sizes in superstructure above plinth level up to floor V level in : Cement mortar 1:6 (1 Cement: 6 coarse sand)	Item No.19	118.00	Cum	5800.00	684400.00	INR Six Lakh Eighty Four Thousand Four Hundred Only
66	Conducting CBR test and providing soaked, unsoaked CBR values, proctor density values including collection of soil samples at the locations within airport premises as directed by Engineer-in-charge.	Item No.19	8.00	Each	20000.00	160000.00	INR One Lakh Sixty Thousand Only
67	Topographic survey of approximately 50 Acres of land including taking levels and providing the alignment and geometric design of roads and drains as required and submission of two sets of hard copies and one soft copy of the topographic survey and geometric design inclusive of longitudinal alignment and corss section, as directed by the Engineer in charge.	Item No.19	1.00	job	150000.00	150000.00	INR One Lakh Fifty Thousand Only
68	Providing Technical services to Engineering office by deploying appropriate Graduate Civil Engineer for assisting AAI Engineer in execution and quality control of Project works. The job includes assisting in Marking, Surveying, testing of samples, measurements of items, preparation drawings, documents and ensuring safety arrangements at work site etc., complete as directed by the Engineer-in-charge. The unit of this item is 'JOB'. One 'JOB' denotes providing services for One month.	Item No.19	15.00	job	40000.00	600000.00	INR Six Lakh Only

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excluding GST) Rs. P	TOTAL AMOUNT (without GST) in Rs. P	TOTAL AMOUNT (With out GST) In Words
69	Provision of Data processing services to Engineering Section by deploying person having computer knowledge for assisting AAI Civil Engineers in preparation of bills, maintenance of office records & files, registers, preparations of progress report, all types of computer / clerical works and other related works / duties etc., as directed by Engineer-In-Charge. The unit of this item is 'JOB'. One 'JOB' denotes providing services for One month.	Item No.19	15.00	job	24000.00	360000.00	INR Three Lakh Sixty Thousand Only
70	Credit item for Taking away materials like TMT bars recovered from each cubic meter of RCC demolished from AAI premises as per the directions of Engineer in charge. The measurement quantity for this item shall be same as demolishing of RCC Item no.51	Item No.70	52.00	Cum	500.00	-26000.00	INR Twenty Six Thousand Only
71	Credit item for Taking away bricks recovered from each cubic meter of brick work demolished from AAI premises as per the directions of Engineer in charge. The measurement quantity for this item shall be same as demolishing of brick work Item no. 52	Item No.71	227.00	Cum	300.00	-68100.00	INR Sixty Eight Thousand One Hundred Only
72	Credit item for Taking away steel materials recovered from dismantling of Steel from AAI premises as per the directions of Engineer in charge. The measurement quantity for this item shall be same as dismantling of Steel Item No.53 & Item no.54	Item No.72	4778.00	Kg	15.00	-71670.00	INR Seventy One Thousand Six Hundred & Seventy Only
73	Credit item for G.S sheet recovered from dismantling of baricading sheet from AAI Premises as per the directions of Engineer in charge. The measurement quantity for this item shall be same as dismantling baricading sheet item no.55	Item No.73	604.00	Sqm	15.00	-9060.00	INR Nine Thousand & Sixty Only
74	Credit item for Taking away R.B.T wire / Concertina coil recovered form dismantling of R.B.T wire / Concertina coil from AAI premises as per the directions of Engineer in charge. The measurement quantity for this item shall be same as dismantling of R.B.T wire/concertina coil Item no. 56	Item No.74	2940.00	kg	10.00	-29400.00	INR Twenty Nine Thousand Four Hundred Only
Total in Figures						68667232.00	INR Six Crore Eighty Six Lakh Sixty Seven Thousand Two Hundred & Thirty Two Only
Quoted Rate in Words			INR Six Crore Eighty Six Lakh Sixty Seven Thousand Two Hundred & Thirty Two Only				

Signature Not Verified

Digitally signed by SHOWJENDRA KUMARREDDY VENTHURLA
Date: 2025.04.11 17:39:28 IST
Location: eProcurement System for Central PSUs

